


O'REILLY®

Covers iOS 15,  
Xcode 13, and Swift 5.5

# iOS 15 Programming Fundamentals with Swift

Swift, Xcode, and Cocoa Basics



Matt Neuburg

# iOS 15 Programming Fundamentals with Swift

Move into iOS development by getting a firm grasp of its fundamentals, including the Xcode 13 IDE, Cocoa Touch, and the latest version of Apple's acclaimed programming language, Swift 5.5. With this thoroughly updated guide, you'll learn the Swift language, understand Apple's Xcode development tools, and discover the Cocoa framework.

- Explore Swift's object-oriented concepts
- Become familiar with built-in Swift types
- Dive deep into Swift objects, protocols, and generics
- Tour the life cycle of an Xcode project
- Learn how nibs are loaded
- Understand Cocoa's event-driven design
- Communicate with C and Objective-C

In this edition, catch up on the latest iOS programming features:

- Structured concurrency: `async/await`, tasks, and actors
- Swift-native formatters and attributed strings
- Lazy locals and throwing getters
- Enhanced collections with the Swift Algorithms and Collections packages
- Xcode tweaks: column breakpoints, package collections, and Info.plist build settings
- Improvements in Git integration, localization, unit testing, documentation, and distribution

And more!

"Neuburg is my favorite programming book writer, period."

—John Gruber  
Daring Fireball

Matt Neuburg has a PhD in Classics and has taught at many colleges and universities. A former editor of *MacTech* magazine and contributing editor for *TidBITS*, he's written many macOS and iOS applications and several books, including *AppleScript: The Definitive Guide* and *REALbasic: The Definitive Guide* (both from O'Reilly).

IOS DEVELOPMENT

US \$59.99

CAN \$79.99

ISBN: 978-1-098-11850-1



9

Twitter: @oreillymedia  
facebook.com/oreilly

EIGHTH EDITION

---

# iOS 15 Programming Fundamentals with Swift

*Swift, Xcode, and Cocoa Basics*

*Matt Neuburg*

Beijing • Boston • Farnham • Sebastopol • Tokyo

**O'REILLY®**

# iOS 15 Programming Fundamentals with Swift, Eighth Edition

by Matt Neuburg

Copyright © 2022 Matt Neuburg. All rights reserved.

Printed in the United States of America.

Published by O'Reilly Media, Inc., 1005 Gravenstein Highway North, Sebastopol, CA 95472.

O'Reilly books may be purchased for educational, business, or sales promotional use. Online editions are also available for most titles (<http://oreilly.com>). For more information, contact our corporate/institutional sales department: 800-998-9938 or [corporate@oreilly.com](mailto:corporate@oreilly.com).

**Editor:** Suzanne McQuade

**Production Editor:** Kristen Brown

**Proofreader:** O'Reilly Production Services

**Illustrator:** Matt Neuburg

**Indexer:** Matt Neuburg

**Cover Designer:** Karen Montgomery

**Interior Designer:** David Futato

April 2015:	First Edition
October 2015:	Second Edition
October 2016:	Third Edition
October 2017:	Fourth Edition
September 2018:	Fifth Edition
October 2019:	Sixth Edition
October 2020:	Seventh Edition
October 2021:	Eighth Edition

## Revision History for the Eighth Edition

2021-10-01: First Release

See <http://oreilly.com/catalog/errata.csp?isbn=9781098118501> for release details.

The O'Reilly logo is a registered trademark of O'Reilly Media, Inc. *iOS 15 Programming Fundamentals with Swift*, the image of a harp seal, and related trade dress are trademarks of O'Reilly Media, Inc.

The views expressed in this work are those of the author, and do not represent the publisher's views. While the publisher and the author have used good faith efforts to ensure that the information and instructions contained in this work are accurate, the publisher and the author disclaim all responsibility for errors or omissions, including without limitation responsibility for damages resulting from the use of or reliance on this work. Use of the information and instructions contained in this work is at your own risk. If any code samples or other technology this work contains or describes is subject to open source licenses or the intellectual property rights of others, it is your responsibility to ensure that your use thereof complies with such licenses and/or rights.

ISBN: 978-1-098-11850-1

[LSI]

---

# Table of Contents

<b>Preface.....</b>	<b>xv</b>
---------------------	-----------

---

## **Part I. Language**

<b>1. The Architecture of Swift.....</b>	<b>3</b>
Ground of Being	3
Everything Is an Object?	4
Three Flavors of Object Type	6
Variables	6
Functions	8
The Structure of a Swift File	9
Scope and Lifetime	12
Object Members	13
Namespaces	13
Modules	14
Instances	15
Why Instances?	17
The Keyword self	19
Privacy	20
Design	22
<b>2. Functions.....</b>	<b>25</b>
Function Parameters and Return Value	25
Void Return Type and Parameters	29
Function Signature	30
External Parameter Names	30
Overloading	32

Default Parameter Values	33
Variadic Parameters	34
Ignored Parameters	35
Modifiable Parameters	36
Calling Objective-C with Modifiable Parameters	37
Called by Objective-C with Modifiable Parameters	38
Reference Type Modifiable Parameters	39
Function in Function	40
Recursion	40
Function as Value	41
Anonymous Functions	44
Using Anonymous Functions Inline	45
Anonymous Function Abbreviated Syntax	46
Define-and-Call	50
Closures	51
How Closures Improve Code	53
Function Returning Function	54
Closure Setting a Captured Variable	57
Closure Preserving Captured Environment	58
Escaping Closures	59
Capture Lists	60
Curried Functions	62
Function References and Selectors	63
Function Reference Scope	65
Selectors	67
<b>3. Variables and Simple Types.....</b>	<b>71</b>
Variable Scope and Lifetime	71
Variable Declaration	73
Computed Variable Initialization	77
Computed Variables	78
Computed Properties	79
Property Wrappers	81
Setter Observers	82
Lazy Initialization	83
Singleton	84
Lazy Initialization of Instance Properties	85
Built-In Simple Types	85
Bool	85
Numbers	88

String	96
Character and String Index	102
Range	106
Tuple	108
Optional	111
<b>4. Object Types.....</b>	<b>125</b>
Object Type Declarations and Features	125
Initializers	127
Properties	133
Methods	136
Subscripts	139
Nested Object Types	141
Enums	142
Raw Values	143
Associated Values	145
Enum Case Iteration	147
Enum Initializers	148
Enum Properties	149
Enum Methods	150
Why Enums?	152
Structs	153
Struct Initializers	153
Struct Properties	154
Struct Methods	155
Classes	156
Value Types and Reference Types	157
Subclass and Superclass	162
Class Initializers	168
Class Deinitializer	176
Class Properties	176
Static/Class Members	177
Polymorphism	178
Casting	182
Casting Down	183
Type Testing and Casting Down Safely	183
Type Testing and Casting Optionals	185
Bridging to Objective-C	186
Type References	187
From Instance to Type	187

From self to Type	187
Type as Value	191
Summary of Type Terminology	192
Comparing Types	192
Protocols	193
Why Protocols?	194
Adopting a Library Protocol	195
Protocol Type Testing and Casting	197
Declaring a Protocol	197
Protocol Composition	198
Class Protocols	199
Optional Protocol Members	200
Implicitly Required Initializers	202
Expressible by Literal	204
Generics	205
Generic Declarations	208
Type Constraints	210
Explicit Specialization	212
Generic Types and Covariance	213
Associated Type Chains	215
Where Clauses	217
Extensions	220
Extending Protocols	222
Extending Generics	225
Umbrella Types	227
Any	227
AnyObject	229
AnyClass	231
Collection Types	232
Array	232
Dictionary	251
Set	258
OrderedSet and OrderedDictionary	263
<b>5. Flow Control and More.....</b>	<b>269</b>
Flow Control	269
Branching	270
Loops	282
Jumping	288
Privacy	305



Private and Fileprivate	306
Public and Open	308
Privacy Rules	309
Introspection	309
Operators	310
Memory Management	313
Memory Management of Reference Types	314
Exclusive Access to Value Types	321
Miscellaneous Swift Language Features	323
Synthesized Protocol Implementations	323
Key Paths	326
Instance as Function	329
Dynamic Membership	330
Property Wrappers	332
Custom String Interpolation	337
Reverse Generics	339
Result Builders	341
Result	341
<b>6. Structured Concurrency.....</b>	<b>343</b>
Multithreading	344
The Main Thread	344
Background Threads	345
Asynchronous Code	347
Structured Concurrency Syntax	353
async/await	354
Async Contexts	355
Tasks	356
Wrapping a Completion Handler	357
Multiple Concurrent Tasks	361
async let	362
Task Groups	363
Asynchronous Sequences	367
Built-in Asynchronous Sequences	368
Making an Asynchronous Sequence	369
Asynchronous Sequence Methods	370
Actors	370
Actor Isolation	371
Actor Serialization	372
The Main Actor	372

Context Switching	374
Implicit Context Switching	374
Explicit Context Switching	375
More About Tasks	377
Task Priority	377
The Current Task	378
Sleeping	378
Yielding	379
Cancellation	380
More About Actors	386
Reentrancy	386
The Keyword nonisolated	387
The Keyword isolated	388
Global Actors	389
Sendable	390

---

## Part II. IDE

<b>7. Anatomy of an Xcode Project.....</b>	<b>395</b>
New Project	395
The Project Window	397
The Navigator Pane	399
The Inspector Pane	404
The Editor	405
Project File and Dependents	408
Contents of the Project Folder	409
Groups	410
The Target	411
Build Phases	411
Build Settings	413
Configurations	414
Schemes and Destinations	416
From Project to Built App	418
Build Settings	420
Property List Settings	420
Nib Files	421
Resources	421
Code Files	423
Frameworks and SDKs	424

Swift Packages	425
The App Launch Process	429
The Entry Point	429
How an App Gets Going	431
App Without a Storyboard	433
Renaming Parts of a Project	434
<b>8. Nib Files.....</b>	<b>437</b>
The Nib Editor Interface	438
Document Outline	439
Canvas	442
Inspectors	443
Loading a Nib	444
Loading a View Controller Nib	445
Loading a Main View Nib	446
Loading a View Nib Manually	447
Connections	448
Outlets	449
The Nib Owner	450
Automatically Configured Nibs	454
Misconfigured Outlets	455
Deleting an Outlet	457
More Ways to Create Outlets	457
Outlet Collections	460
Action Connections	461
More Ways to Create Actions	463
Misconfigured Actions	464
Connections Between Nibs — Not!	465
Additional Configuration of Nib-Based Instances	466
<b>9. Documentation.....</b>	<b>471</b>
The Documentation Window	471
Class Documentation Pages	473
Quick Help	476
Documenting Frameworks and Packages	479
Symbol Declarations	482
Header Files	483
Sample Code	484
Internet Resources	484

<b>10. Life Cycle of a Project.....</b>	<b>487</b>
Environmental Dependencies	487
Conditional Compilation	488
Build Action	489
Permissible Runtime Environment	490
Backward Compatibility	491
Device Type	492
Arguments and Environment Variables	494
Version Control	495
Editing and Navigating Your Code	498
Text Editing Preferences	499
Multiple Selection	500
Code Completion and Placeholders	501
Snippets	502
Refactoring and Code Actions	503
Fix-it and Live Syntax Checking	505
Navigation	506
Finding	509
Running in the Simulator	510
Debugging	512
Caveman Debugging	512
The Xcode Debugger	516
Testing	524
Unit Tests	527
Interface Tests	531
Test Plans	533
Massaging the Report	535
Clean	536
Running on a Device	537
Obtaining a Developer Program Membership	537
Signing an App	538
Automatic Signing	539
Manual Signing	541
Running the App	542
Managing Development Certificates and Devices	543
Profiling	543
Gauges	544
Memory Debugging	544
Instruments	546
Localization	548

Creating Localized Content	548
Testing Localization	553
Distribution	554
Making an Archive	555
The Distribution Certificate	556
The Distribution Profile	557
Distribution for Testing	558
Final App Preparations	560
Screenshots and Video Previews	562
Property List Settings	563
Submission to the App Store	565

---

## Part III. Cocoa

<b>11. Cocoa Classes.....</b>	<b>571</b>
Subclassing	571
Categories and Extensions	574
How Swift Uses Extensions	574
How You Use Extensions	574
How Cocoa Uses Categories	575
Protocols	576
Optional Members	577
Informal Protocols	580
Some Foundation Classes	580
NSRange	581
NSNotFound	583
NSString and Friends	584
NSDate and Friends	587
NSNumber	590
NSValue	592
NSData	593
NSMeasurement and Friends	594
Equality, Hashability, and Comparison	595
NSArray and NSMutableArray	598
NSDictionary and NSMutableDictionary	600
NSSet and Friends	601
NSIndexSet	602
NSNull	603
Immutable and Mutable	603

Property Lists	604
Codable	605
Accessors, Properties, and Key–Value Coding	609
Swift Accessors	610
Key–Value Coding	611
How Outlets Work	612
Cocoa Key Paths	613
Uses of Key–Value Coding	614
KeyPath Notation	615
The Secret Life of NSObject	616
<b>12. Cocoa Events.....</b>	<b>619</b>
Reasons for Events	619
Subclassing	620
Notifications	621
Receiving a Notification	623
Unregistering	625
Subscribing to a Notification	626
Posting a Notification	628
Timer	629
Delegation	631
Cocoa Delegation	632
Implementing Delegation	633
Data Sources	635
Actions	636
The Responder Chain	639
Nil-Targeted Actions	640
Key–Value Observing	642
Registration and Notification	643
Unregistering	644
Key–Value Observing Example	645
Swamped by Events	647
Delayed Performance	649
<b>13. Memory Management.....</b>	<b>653</b>
Principles of Cocoa Memory Management	653
Rules of Cocoa Memory Management	654
What ARC Is and What It Does	655
How Cocoa Objects Manage Memory	656
Autorelease Pool	657

Memory Management of Instance Properties	659
Retain Cycles and Weak References	660
Unusual Memory Management Situations	662
Notification Observers	663
KVO Observers	664
Timers	665
Other Unusual Situations	666
Memory Management of CTypeRefs	666
Property Memory Management Policies	668
Debugging Memory Management Mistakes	671
<b>14. Communication Between Objects.....</b>	<b>673</b>
Visibility Through an Instance Property	673
Visibility by Instantiation	674
Getting a Reference	676
Visibility by Relationship	677
Global Visibility	677
Notifications and Key–Value Observing	679
The Combine Framework	680
Alternative Architectures	687
Model–View–Controller	687
Router and Data Space	687
Model–View–Presenter	688
Protocols and Reactive Programming	689
SwiftUI	690
Result Builders and Modifiers	691
State Properties	692
Bindings	694
Passing Data Downhill	694
Passing Data Uphill	696
Custom State Objects	697
<b>Appendix. C, Objective-C, and Swift.....</b>	<b>701</b>
<b>Index.....</b>	<b>739</b>





---

# Preface

In July of 2010, Chris Lattner created a folder on his computer called *Shiny*, and a new computer language was born. Four years later, in 2014, that language, renamed Swift, was introduced to the public, and was greeted with a mixture of surprise and excitement — and skepticism.

Prior to that moment, Cocoa programming, on iOS and before that on Mac OS, had always been done chiefly in Objective-C. The Cocoa frameworks that give an iOS app its functionality are based on Objective-C; they expect to be spoken to in Objective-C. The tradition of using Objective-C was long and deeply ingrained. For all its faults, Objective-C was the language we had learned to live with as the price of programming Cocoa. Could Cocoa be spoken to in a whole new language? Could this new language replace Objective-C as the iOS developer’s language of choice?

No one knew. I certainly didn’t know! So the first thing I did, as an experiment, was to try translating my own existing iOS apps into Swift. Not only was I able to do it, but I found the new Swift versions easier to understand and maintain than their Objective-C originals. From that moment, I was convinced that the vast majority of new iOS programmers would hitherto adopt Swift. I was right.

Swift is a superb language to learn, even (perhaps especially) if you’ve never programmed before, and is the easiest and clearest way to program iOS. It has these salient features:

## *Object-orientation*

Swift is a modern, object-oriented language. It is *purely* object-oriented: “Everything is an object.”

## *Clarity*

Swift is easy to read and easy to write. Its syntax is clear, consistent, and explicit, with few hidden shortcuts and minimal syntactic trickery.

### *Safety*

Swift enforces strong typing to ensure that it knows, and that you know, what the type of every object reference is at every moment.

### *Economy*

Swift is a fairly small language, providing some basic types and functionalities and no more. The rest must be provided by your code, or by libraries of code that you use — such as Cocoa.

### *Memory management*

Swift manages memory automatically. You will rarely have to concern yourself with memory management.

### *Cocoa compatibility*

The Cocoa APIs are written primarily in C and Objective-C. Swift is explicitly designed to interface with most of the Cocoa APIs.

Earlier editions of this book, before 2014, taught the reader Objective-C. After 2014, they teach Swift. This edition is geared to Swift 5.5. The Swift language has reached a high state of maturity. It has achieved ABI stability, which means that the Swift language has become part of the system. Swift apps are smaller and faster than ever.

The Foundation and Cocoa APIs, however, are still written in C and Objective-C. To interact with them, you might have to know what those languages would expect. Therefore in this book I describe Objective-C in enough detail to allow you to read it when you encounter it in the documentation and on the internet, and I occasionally show some Objective-C code. **Part III**, on Cocoa, is largely about learning to think the way Objective-C thinks — because the structure and behavior of the Cocoa APIs are fundamentally based on Objective-C. And the book ends with an appendix that details how Swift and Objective-C communicate with one another, as well as explaining how your app can be written partly in Swift and partly in Objective-C.

## The Scope of This Book

This book doesn't teach you how to write any practical iOS programs. It's about the fundamental underpinnings of iOS programming, the basics that you need to understand from the outset in order to get started. If writing an iOS program is like building a house of bricks, this book teaches you what a brick is and how to handle it; actually assembling the bricks comes later. In this book, you'll learn all about:

- The programming *language* you'll be writing in (Swift).
- The *milieu* in which you'll be writing, editing, running, testing, and generally developing (Xcode).
- The *framework* you'll be communicating with as your app runs (Cocoa).

When you have read this book, you'll know about Swift, Xcode, and the nature of the Cocoa framework, and you will be ready to proceed to learn about real-life iOS app components such as views and view controllers. And even though the book doesn't show how to write any particularly interesting iOS apps, it does constantly use my own real apps and real programming situations to illustrate and motivate its explanations, as it teaches you the underlying basis of iOS programming.

The book has three parts:

- **Part I** introduces the Swift language, from the ground up — I do not assume that you know any other programming languages. My way of teaching Swift is different from other treatments, such as Apple's; it is systematic and Euclidean, with pedagogical building blocks piled on one another in what I regard as the most helpful order. At the same time, I have tried to confine myself to the essentials. Swift is not a big language, but it has some subtle and unusual corners that you probably don't need to know about. Also, I never mention Swift playgrounds or the REPL. My focus here is real-life iOS programming, and my explanation of Swift concentrates on the practical aspects of the language that actually come into play in the course of programming iOS.
- **Part II** turns to Xcode, the world in which all iOS programming ultimately takes place. It explains what an Xcode project is and how it is transformed into an app, and how to work comfortably and nimbly with Xcode to consult the documentation and to write, navigate, and debug code, as well as how to bring your app through the subsequent stages of running on a device and submission to the App Store. There is also a chapter on nibs and the nib editor (Interface Builder), including outlets and actions as well as the mechanics of nib loading.
- **Part III** introduces the Cocoa Touch framework. The Foundation and UIKit frameworks, and other frameworks that they entail, constitute Cocoa, which provides the underlying functionality that any iOS app needs to have. To use a framework effectively, you have to think the way the framework thinks, put your code where the framework expects it, and fulfill many obligations imposed on you by the framework. Also, Cocoa uses Objective-C, so you need to know how your Swift code will interface with Cocoa's features and behaviors. Cocoa provides important foundational classes and adds linguistic and architectural devices such as categories, protocols, delegation, and notifications, as well as the pervasive responsibilities of memory management. Key-value coding and key-value observing are also discussed here.

The last chapter of **Part III** is about the general problem of how objects can refer to one another in an iOS program. In addition to the traditional Cocoa-based solutions, I also discuss the Swift Combine framework. Also, in June of 2019, Apple introduced SwiftUI. It constitutes an alternative to UIKit and Cocoa, with a completely different programming paradigm for constructing apps. I do not

teach SwiftUI in this book — that would require another entire book — but I do explain its chief linguistic features, and I talk about its solutions to the problem of communicating between objects within an iOS app and how they differ from Cocoa patterns.

## From the Preface to the First Edition (Programming iOS 4)

The popularity of the iPhone, with its largely free or very inexpensive apps, and the subsequent popularity of the iPad, have brought and will continue to bring into the fold many new programmers who see programming for these devices as worthwhile and doable, even though they may not have felt the same way about OS X. Apple’s own annual WWDC developer conventions have reflected this trend, with their emphasis shifted from OS X to iOS instruction.

The widespread eagerness to program iOS, however, though delightful on the one hand, has also fostered a certain tendency to try to run without first learning to walk. iOS gives the programmer mighty powers that can seem as limitless as imagination itself, but it also has fundamentals. I often see questions online from programmers who are evidently deep into the creation of some interesting app, but who are stymied in a way that reveals quite clearly that they are unfamiliar with the basics of the very world in which they are so happily cavorting.

It is this state of affairs that has motivated me to write this book, which is intended to ground the reader in the fundamentals of iOS. Here I have attempted to marshal and expound, in what I hope is a pedagogically helpful and instructive yet ruthlessly Euclidean and logical order, the principles and elements on which sound iOS programming rests. My hope, as with my previous books, is that you will both read this book cover to cover (learning something new often enough to keep you turning the pages) and keep it by you as a handy reference.

This book is not intended to disparage Apple’s own documentation and example projects. They are wonderful resources and have become more wonderful as time goes on. I have depended heavily on them in the preparation of this book. But I also find that they don’t fulfill the same function as a reasoned, ordered presentation of the facts. The online documentation must make assumptions as to how much you already know; it can’t guarantee that you’ll approach it in a given order. And online documentation is more suitable to reference than to instruction. A fully written example, no matter how well commented, is difficult to follow; it demonstrates, but it does not teach.

A book, on the other hand, has numbered chapters and sequential pages; I can assume you know views before you know view controllers for the simple reason that Part I precedes Part II. And along with facts, I also bring to the table a degree of experience, which I try to communicate to you. Throughout this book you'll find me referring to “common beginner mistakes”; in most cases, these are mistakes that I have made myself, in addition to seeing others make them. I try to tell you what the pitfalls are because I assume that, in the course of things, you will otherwise fall into them just as naturally as I did as I was learning. You'll also see me construct many examples piece by piece or extract and explain just one tiny portion of a larger app. It is not a massive finished program that teaches programming, but an exposition of the thought process that developed that program. It is this thought process, more than anything else, that I hope you will gain from reading this book.

## Versions

This book is geared to Swift 5.5, iOS 15, and Xcode 13.

In general, only very minimal attention is given to earlier versions of iOS and Xcode. Earlier versions can be very different from the current version, and it would be impossible to go into detail about all that has changed over the years. Besides, that information is readily and compendiously available in my earlier books. Recent innovations are called out clearly. The book does contain some advice about backward compatibility (especially in [Chapter 10](#)).

I generally give method names in Swift, in the style of a function reference (as described in [Chapter 2](#)) — that is, the name plus parentheses containing the parameter labels followed by colon. Now and then, if a method is already under discussion and there is no ambiguity, I'll use the bare name. In a few places, such as the [Appendix](#), where the Objective-C language is explicitly under discussion, I use Objective-C method names.

I have tried to keep my code up-to-date right up to the moment when the manuscript left my hands; but if, at some future time, a new version of Xcode is released along with a new version of Swift, some of the code in this book, and even some information about Swift itself, might be slightly incorrect. Please make allowances, and be prepared to compensate.

Screenshots of Xcode were taken using Xcode 13 under macOS 11 Big Sur. I have waited until the last moment before publication to take these screenshots; I don't expect the interface to have changed significantly by the time you read this, and if it does, the difference shouldn't cause any confusion.

# Acknowledgments

This book was written with the aid of some wonderful software:

- Git (<http://git-scm.com>)
- Sourcetree (<http://www.sourcetreeapp.com>)
- TextMate (<http://macromates.com>)
- AsciiDoc (<https://asciidoc-py.github.io>)
- AsciiDoctor (<http://asciidoctor.org>)
- BBEdit (<http://barebones.com/products/bbedit>)
- EasyFind (<https://www.devontechnologies.com/support/download>)
- GraphicConverter (<http://www.lemkesoft.com>)
- OmniGraffle (<http://www.omnigroup.com>)
- GoodReader (<http://goodreader.com>)

At O'Reilly Media, many people have made writing this book fun and easy; particular thanks go to Kristen Brown, Rachel Roumeliotis, Suzanne McQuade, Dan Fauxsmith, Adam Witwer, Nick Adams, Heather Scherer, Melanie Yarbrough, Sarah Schneider, and Sanders Kleinfeld. My first editor was Brian Jepson; his influence is present throughout.

Finally, a special thanks to all my readers for their support, encouragement, suggestions, and wonderfully detailed errata submissions.

## Conventions Used in This Book

The following typographical conventions are used in this book:

### *Italic*

Indicates new terms, URLs, email addresses, filenames, and file extensions.

### Constant width

Used for program listings, as well as within paragraphs to refer to program elements such as variable or function names, databases, data types, environment variables, statements, and keywords.

### **Constant width bold**

Shows commands or other text that should be typed literally by the user.

### *Constant width italic*

Shows text that should be replaced with user-supplied values or by values determined by context.



This element signifies a tip or suggestion.



This element signifies a general note.



This element indicates a warning or caution.

## Using Code Examples

Supplemental material (code examples, exercises, etc.) is available for download at <http://github.com/mattneub/Programming-iOS-Book-Examples>.

This book is here to help you get your job done. In general, if example code is offered with this book, you may use it in your programs and documentation. You do not need to contact us for permission unless you're reproducing a significant portion of the code. For example, writing a program that uses several chunks of code from this book does not require permission. Selling or distributing a CD-ROM of examples from O'Reilly books does require permission. Answering a question by citing this book and quoting example code does not require permission. Incorporating a significant amount of example code from this book into your product's documentation does require permission.

We appreciate, but do not require, attribution. An attribution usually includes the title, author, publisher, and ISBN. For example: “*iOS 15 Programming Fundamentals with Swift* by Matt Neuburg (O'Reilly). Copyright 2022 Matt Neuburg, 978-1-098-11850-1.”

If you feel your use of code examples falls outside fair use or the permission given above, feel free to contact us at [permissions@oreilly.com](mailto:permissions@oreilly.com).

## O'Reilly Online Learning



For almost 40 years, *O'Reilly Media* has provided technology and business training, knowledge, and insight to help companies succeed.

Our unique network of experts and innovators share their knowledge and expertise through books, articles, and our online learning platform. O'Reilly's online learning platform gives you on-demand access to live training courses, in-depth learning paths, interactive coding environments, and a vast collection of text and video from

O'Reilly and 200+ other publishers. For more information, please visit <http://oreilly.com>.

## How to Contact Us

Please address comments and questions concerning this book to the publisher:

O'Reilly Media, Inc.  
1005 Gravenstein Highway North  
Sebastopol, CA 95472  
800-998-9938 (in the United States or Canada)  
707-829-0515 (international or local)  
707-829-0104 (fax)

We have a web page for this book, where we list errata, examples, and any additional information. You can access this page at <https://oreil.ly/ios15-prog-fundamentals>.

To comment or ask technical questions about this book, email [bookquestions@oreilly.com](mailto:bookquestions@oreilly.com).

For news and more information about our books and courses, see our website at <http://oreilly.com>.

Find us on Facebook: <http://facebook.com/oreilly>

Follow us on Twitter: <http://twitter.com/oreillymedia>

Watch us on YouTube: <http://youtube.com/oreillymedia>



---

# Language

This part of the book teaches the Swift language, from the ground up. The description is rigorous and orderly. Here you'll become sufficiently conversant with Swift to be comfortable with it, so that you can proceed to the practical business of actual programming.

- **Chapter 1** surveys the structure of a Swift program, both physically and conceptually. You'll learn how Swift code files are organized, and you'll be introduced to the most important underlying concepts of the object-oriented Swift language: variables and functions, scopes and namespaces, object types and their instances.
- **Chapter 2** explores Swift functions. We start with the basics of how functions are declared and called; then we discuss parameters — external parameter names, default parameters, and variadic parameters. Then we dive deep into the power of Swift functions, with an explanation of functions inside functions, functions as first-class values, anonymous functions, functions as closures, curried functions, and function references and selectors.
- **Chapter 3** starts with Swift variables — their scope and lifetime, and how they are declared and initialized, along with features such as computed variables and setter observers. Then some important built-in Swift types are introduced, including Booleans, numbers, strings, ranges, tuples, and Optionals.
- **Chapter 4** is all about Swift object types — classes, structs, and enums. It explains how these three object types work, and how you declare, instantiate, and use them. Then it proceeds to polymorphism and casting, protocols, generics, and extensions. The chapter concludes with a discussion of Swift's umbrella types,

such as Any and AnyObject, and collection types — Array, Dictionary, and Set (including option sets).

- **Chapter 5** is a miscellany. We start with Swift’s flow control structures for branching, looping, and jumping, including error handling. Then I describe Swift access control (privacy), introspection (reflection), and how to create your own operators. Next I talk about Swift memory management. The chapter ends with a survey of some recently added Swift language features: synthesized protocol implementations, key paths, instances as functions, dynamic members, property wrappers, custom string interpolation, reverse generics, result builders, and Result.
- **Chapter 6** describes a major new Swift 5.5 feature: support for multithreaded and asynchronous code. First, there’s an explanation of multithreading and concurrency, and we review an older way of expressing asynchronous code (completion handlers). Then we meet the new asynchronous syntax, along with tasks, concurrent subtasks, asynchronous sequences, and an additional Swift object type — actors. The chapter concludes by diving deeper into such topics as task cancellation and actor reentrancy, along with the Sendable protocol.

---

# The Architecture of Swift

It will be useful at the outset for you to have a general sense of how the Swift language is constructed and what a Swift-based iOS program looks like. This chapter will survey the overall architecture and nature of the Swift language. Subsequent chapters will fill in the details.

## Ground of Being

A complete Swift command is a *statement*. A Swift text file consists of multiple *lines* of text. Line breaks are meaningful. The typical layout of a program is one statement, one line:

```
print("hello")
print("world")
```

(The `print` command provides instant feedback in the Xcode console.)

You can combine more than one statement on a line, but then you need to put a semicolon between them:

```
print("hello"); print("world")
```

You are free to put a semicolon at the end of a statement that is last or alone on its line, but no one ever does (except out of habit, because C and Objective-C *require* the semicolon):

```
print("hello");
print("world");
```

Conversely, a single statement can be broken into multiple lines, to prevent long statements from becoming long lines. But you should try to do this at sensible places so as not to confuse Swift. After an opening parenthesis is a good place:

```
print(  
    "world")
```

Comments are everything after two slashes in a line (so-called C++-style comments):

```
print("world") // this is a comment, so Swift ignores it
```

You can also enclose comments in `/*...*/`, as in C. Unlike C, C-style comments can be nested.

Many constructs in Swift use curly braces as delimiters:

```
class Dog {  
    func bark() {  
        print("woof")  
    }  
}
```

By convention, the contents of curly braces are preceded and followed by line breaks and are indented for clarity, as shown in the preceding code. Xcode will help impose this convention, but the truth is that Swift doesn't care, and layouts like this are legal (and are sometimes more convenient):

```
class Dog { func bark() { print("woof") } }
```

Swift is a *compiled* language. This means that your code must *build* — passing through the compiler and being turned from text into some lower-level form that a computer can understand — before it can *run* and actually do the things it says to do. The Swift compiler is very strict; in the course of writing a program, you will often try to build and run, only to discover that you can't even build in the first place, because the compiler will flag some *error*, which you will have to fix if you want the code to run. Less often, the compiler will let you off with a *warning*; the code can run, but in general you should take warnings seriously and fix whatever they are telling you about. The strictness of the compiler is one of Swift's greatest strengths, and provides your code with a large measure of audited correctness even before it ever runs.

The Swift compiler's error and warning messages range from the insightful to the obtuse to the downright misleading. You will sometimes know that *something* is wrong with a line of code, but the Swift compiler might not be telling you clearly exactly *what* is wrong or even *where* in the line to focus your attention. My advice in these situations is to pull the line apart into several lines of simpler code until you reach a point where you can work out what the issue is. Try to love the compiler even when its messages seem mysterious; remember, it knows more than you do.

## Everything Is an Object?

In Swift, “everything is an object.” That’s a boast common to various modern object-oriented languages, but what does it mean? Well, that depends on what you mean by “object” — and what you mean by “everything.”

Let's start by stipulating that an object, roughly speaking, is something you can send a message to. A message, roughly speaking, is an imperative instruction. For example, you can give commands to a dog: "Bark!" "Sit!" In this analogy, those phrases are messages, and the dog is the object to which you are sending those messages.

In Swift, the syntax of message-sending is *dot-notation*. We start with the object; then there's a dot (a period); then there's the message. (Some messages are also followed by parentheses, but ignore them for now; the full syntax of message-sending is one of those details we'll be filling in later.) This is valid Swift syntax:

```
fido.bark()
rover.sit()
```

By the way, a dot is also another good place to break up a long line (*before* the dot):

```
fido
    .bark()
```

The idea of *everything* being an object is a way of suggesting that even "primitive" linguistic entities can be sent messages. Take, for example, 1. It appears to be a literal digit and no more. It will not surprise you, if you've ever used any programming language, that you can say things like this in Swift:

```
let sum = 1 + 2
```

But it *is* surprising to find that 1 can be followed by a dot and a message. This is legal and meaningful in Swift (don't worry about what it actually means):

```
let s = 1.description
```

But we can go further. Return to that innocent-looking `1 + 2` from our earlier code. It turns out that this is actually a kind of syntactic trickery, a convenient way of expressing and hiding what's really going on. Just as 1 is actually an object, + is actually a message; but it's a message with special syntax (*operator syntax*). In Swift, every noun is an object, and every verb is a message.

Perhaps the ultimate acid test for whether something is an object in Swift is whether you can modify it. An object type can be *extended* in Swift, meaning that you can define your own messages on that type. For example, you can't normally send the say-Hello message to a number, but you can change a number type so that you can:

```
extension Int {
    func sayHello() {
        print("Hello, I'm \(self)")
    }
}
1.sayHello() // outputs: "Hello, I'm 1"
```

In Swift, then, 1 is an object. In some languages, such as Objective-C, it clearly is not; it is a "primitive" or *scalar* built-in data type. So the distinction being drawn here is between object types on the one hand and scalars on the other. In Swift, there are no

scalars; *all* types are ultimately object types. That’s what “everything is an object” really means.

## Three Flavors of Object Type

If you know Objective-C or some other object-oriented language, you may be surprised by Swift’s notion of what *kind* of object 1 is. In many languages, such as Objective-C, an object is a *class* or an instance of a class (I’ll explain later what an instance is). Swift has classes, but 1 in Swift is not a class or an instance of a class: the type of 1, namely *Int*, is a *struct*, and 1 is an instance of a struct. And Swift has yet another kind of thing you can send messages to, called an *enum*.

So Swift has three kinds of object type: classes, structs, and enums. I like to refer to these as the three *flavors* of object type. Exactly how they differ from one another will emerge in due course. But they are all very definitely object types, and their similarities to one another are far stronger than their differences. For now, just bear in mind that these three flavors exist.

(Okay, I lied. New in Swift 5.5, there is actually a fourth flavor, *actors*. Actors are highly specialized and I’ll tell you about them later. Until then, just pretend there are three flavors.)

The fact that a struct or enum is an object type in Swift will surprise you particularly if you know Objective-C. Objective-C has structs and enums, but they are not objects. Swift structs, in particular, are much more important and pervasive than Objective-C structs. This difference between how Swift views structs and enums and how Objective-C views them can matter when you are talking to Cocoa.

## Variables

A variable is a *name* for an object. Technically, it *refers* to an object; it is an object *reference*. Nontechnically, you can think of it as a shoebox into which an object is placed. The object may undergo changes, or it may be replaced inside the shoebox by another object, but the name has an integrity all its own. The object to which the variable refers is the variable’s *value*.

In Swift, no variable comes implicitly into existence; all variables must be *declared*. If you need a name for something, you must say “I’m creating a name.” You do this with one of two keywords: *let* or *var*. In Swift, declaration is usually accompanied by *initialization* — you use an equal sign to give the variable a value immediately, as part of the declaration. These are both variable declarations (and initializations):

```
let one = 1
var two = 2
```

Once the name exists, you are free to use it. We can change the value of `two` to be the same as the value of `one`:

```
let one = 1
var two = 2
two = one
```

The last line of that code uses both the name `one` and the name `two` declared in the first two lines: the name `one`, on the right side of the equal sign, is used merely to *refer* to the value inside the shoebox `one` (namely 1); but the name `two`, on the left side of the equal sign, is used to *replace* the value inside the shoebox `two`. Before saying `two = one`, the value of `two` was 2; afterward, it is 1.

A statement with a variable name on the left side of an equal sign is called an *assignment*, and the equal sign is the *assignment operator*. The equal sign is not an assertion of equality, as it might be in an algebraic formula; it is a command. It means: “Get the value of what’s on the right side of me, and use it to replace the value of what’s on the left side of me.”

The two kinds of variable declaration differ in that a name declared with `let` *cannot have its initial value replaced*. A variable declared with `let` is a *constant*; its value is assigned once and stays. This won’t even compile:

```
let one = 1
var two = 2
one = two // compile error
```

It is always possible to declare a name with `var` to give yourself the most flexibility, but if you know you’re never going to replace the initial value of a variable, it’s better to use `let`, as this permits Swift to behave more efficiently. In fact, the Swift compiler will call your attention to any case of your using `var` where you could have used `let`, offering to change it for you.

Variables also have a *type*. This type is established when the variable is declared and *can never change*. This won’t compile:

```
var two = 2
two = "hello" // compile error
```

Once `two` is declared and initialized as 2, it is a number (properly speaking, an `Int`) and it must always be so. You can replace its value with 1 because that’s also an `Int`, but you can’t replace its value with “hello” because that’s a string (properly speaking, a `String`) — and a `String` is not an `Int`.

Variables literally have a life of their own — more accurately, a *lifetime* of their own. As long as a variable exists, it keeps its value alive. Thus, a variable can be not only a way of conveniently *naming* something, but also a way of *preserving* it. I’ll have more to say about that later.



By convention, type names such as `String` or `Int` (or `Dog`) start with a capital letter; variable names start with a small letter. *Do not violate this convention.* If you do, your code might still compile and run just fine, but I will personally send agents to your house to remove your kneecaps in the dead of night.

## Functions

Executable code, like `fido.bark()` or `one = two` or `print("hello")`, cannot go just anywhere in your program. Failure to appreciate this fact is a common beginner mistake, and can result in a mysterious compile error message such as “Expected declaration.”

In general, executable code must live inside the body of a *function*. A function is a batch of code that can be told, as a batch, to run. Its body is delimited by curly braces. Typically, a function has a name, and it gets that name through a function declaration. Function declaration syntax is another of those details that will be filled in later, but here’s an example:

```
func go() {  
    let one = 1  
    var two = 2  
    two = one  
}
```

That describes a sequence of things to do — declare `one`, declare `two`, change the value of `two` to match the value of `one` — and it gives that sequence a *name*, `go`; but it doesn’t *perform* the sequence. The sequence is performed when someone *calls* the function. Thus, we might say, elsewhere:

```
go()
```

That is a command to the `go` function that it should actually run. But again, that command is itself executable code, so it cannot live on its own either. It might live in the body of a different function:

```
func doGo() {  
    go()  
}
```

But wait! This is getting a little nutty. That, too, is just a function declaration; to run it, someone must call `doGo` by saying `doGo()` — and that’s executable code too. This seems like some kind of infinite regression; it looks like none of our code will *ever* run. If all executable code has to live in a function, who will tell *any* function to run? The initial impetus must come from somewhere.

In real life, fortunately, this regression problem doesn’t arise. Remember that your goal is ultimately to write an iOS app. Your app will be run on an iOS device (or the Simulator) by a runtime that already wants to call certain functions. So you start by



writing special functions that you know the runtime itself will call. That gives your app a way to get started and gives you places to put functions that will be called by the runtime at key moments.



Swift also has a special rule that a file called *main.swift*, exceptionally, *can* have executable code at its top level, outside any function body, and this is the code that actually runs when the program runs. You can construct your app with a *main.swift* file, but in general you won't need to. In the rest of this chapter I'll assume that we are not in a *main.swift* file.

## The Structure of a Swift File

A Swift program can consist of one file or many files. In Swift, a file is a meaningful unit, and there are definite rules about the structure of the Swift code that can go inside it. Only certain things can go at the top level of a Swift file — chiefly the following:

### *Module import statements*

A module is an even higher-level unit than a file. A module can consist of multiple files, and these can all see each other automatically. Your app's files belong to a single module and can see each other. But a module can't see another module without an `import` statement. That is how you are able to talk to Cocoa in an iOS program: the first line of your file says `import UIKit`.

### *Variable declarations*

A variable declared at the top level of a file is a *global* variable: all code in any file will be able to see and access it, without explicitly sending a message to any object.

### *Function declarations*

A function declared at the top level of a file is a *global* function: all code in any file will be able to see and call it, without explicitly sending a message to any object.

### *Object type declarations*

The declaration for a class, a struct, or an enum.

This is a legal Swift file containing at its top level (just to demonstrate that it can be done) an `import` statement, a variable declaration, a function declaration, a class declaration, a struct declaration, and an enum declaration:

```
import UIKit
var one = 1
func changeOne() {
}
class Manny {
}
```

```

struct Moe {
}
enum Jack {
}

```

That's a very silly and mostly empty example, but remember, our goal is to survey the parts of the language and the structure of a file, and the example shows them.

So much for the top level of a file. But now let's talk about what can go inside the curly braces that we see in our example. It turns out that they, too, can all have variable declarations, function declarations, and object type declarations within them! Indeed, *any* structural curly braces can contain such declarations.

But what about executable code? You'll notice that I did *not* say that executable code can go at the top level of a file. That's because it can't! *Only a function body can contain executable code*. A statement like `one = two` or `print("hello")` is executable code, and can't go at the top level of a file. But in our previous example, `func changeOne()` is a function declaration, so executable code *can* go inside its curly braces, because they constitute a function body:

```

var one = 1
// executable code can't go here!
func changeOne() {
    let two = 2 // executable code
    one = two   // executable code
}

```

Similarly, executable code can't go directly inside the curly braces that accompany the `class Manny` declaration; that's the top level of a class declaration, not a function body. But a class declaration can contain a function declaration, and that function declaration *can* contain executable code:

```

class Manny {
    let name = "manny"
    // executable code can't go here!
    func sayName() {
        print(name) // executable code
    }
}

```

To sum up, **Example 1-1** is a legal Swift file, schematically illustrating the structural possibilities. (Ignore the hanky-panky with the `name` variable declaration inside the enum declaration for Jack; enum top-level variables have some special rules that I'll explain later.)

*Example 1-1. Schematic structure of a legal Swift file*

```
import UIKit
var one = 1
func changeOne() {
    let two = 2
    func sayTwo() {
        print(two)
    }
    class Klass {}
    struct Struct {}
    enum Enum {}
    one = two
}
class Manny {
    let name = "manny"
    func sayName() {
        print(name)
    }
    class Klass {}
    struct Struct {}
    enum Enum {}
}
struct Moe {
    let name = "moe"
    func sayName() {
        print(name)
    }
    class Klass {}
    struct Struct {}
    enum Enum {}
}
enum Jack {
    var name : String {
        return "jack"
    }
    func sayName() {
        print(name)
    }
    class Klass {}
    struct Struct {}
    enum Enum {}
}
```

Obviously, we can recurse down as far we like: we could have a class declaration containing a class declaration containing a class declaration, and so on. But I'm sure you have the idea by now, so there's no point illustrating further.

# Scope and Lifetime

In a Swift program, things have a *scope*. This refers to their ability to be seen by other things. Things are nested inside of other things, making a nested hierarchy of things. The rule is that things can see things *at their own level and at a higher level containing them*. The levels are:

- A module is a scope.
- A file is a scope.
- Curly braces are a scope.

When something is declared, it is declared at some level within that hierarchy. Its place in the hierarchy — its scope — determines whether it can be seen by other things.

Look again at [Example 1-1](#). Inside the declaration of Manny is a `name` variable declaration and a `sayName` function declaration; the code *inside* `sayName`'s curly braces can see things *outside* those curly braces *at a higher containing level*, and can therefore see the `name` variable. Similarly, the code inside the body of the `changeOne` function can see the `one` variable declared at the top level of the file; indeed, *everything* throughout this file can see the `one` variable declared at the top level of the file.

Scope is thus a very important way of *sharing information*. Two different functions declared inside Manny would *both* be able to see the `name` declared at Manny's top level. Code inside Jack and code inside Moe can *both* see the `one` declared at the file's top level.

Things also have a *lifetime*, which is effectively equivalent to their scope. A thing lives as long as its surrounding scope lives. In [Example 1-1](#), the variable `one` lives as long as the file lives — namely, as long the program runs. It is global *and persistent*. But the variable `name` declared at the top level of Manny exists only so long as a Manny instance exists (I'll talk in a moment about what that means).

Things declared at a deeper level live even shorter lifetimes. Consider this code:

```
func silly() {  
    if true {  
        class Cat {}  
        var one = 1  
        one = one + 1  
    }  
}
```

That code is silly, but it's legal: remember, I said that variable declarations, function declarations, and object type declarations can appear in *any* structural curly braces. In that code, the class `Cat` and the variable `one` will not even come into existence until someone calls the `silly` function, and even then they will exist only during the brief

instant that the path of code execution passes through the `if` construct. Suppose the function `silly` is called; the path of execution then enters the `if` construct. Here, `Cat` is declared and comes into existence; then `one` is declared and comes into existence; then the executable line `one = one + 1` is executed; and then the scope ends — and both `Cat` and `one` vanish in a puff of smoke. And throughout their brief lives, `Cat` and `one` were completely invisible to the rest of the program. (Do you see why?)

## Object Members

Inside the three object types (class, struct, and enum), things declared at the top level have special names, mostly for historical reasons. Let's use the `Manny` class as an example:

```
class Manny {
    let name = "manny"
    func sayName() {
        print(name)
    }
}
```

In that code:

- `name` is a variable declared at the top level of an object declaration, so it is called a *property* of that object.
- `sayName` is a function declared at the top level of an object declaration, so it is called a *method* of that object.

Things declared at the top level of an object declaration — properties, methods, and any objects declared at that level — are collectively the *members* of that object. Members have a special significance, because they define the *messages* you are allowed to send to that object!

## Namespaces

A *namespace* is a named region of a program. The names of things inside a namespace cannot be reached by things outside it without somehow first passing through the barrier of *saying* that region's name. This is a good thing because it allows the same name to be used in different places without a conflict. Clearly, namespaces and scopes are closely related notions.

Namespaces help to explain the significance of declaring an object at the top level of an object, like this:

```
class Manny {
    class Klass {}
}
```

This way of declaring `Klass` makes `Klass` a *nested type*. It effectively “hides” `Klass` inside `Manny`. `Manny` is a namespace! Code *inside* `Manny` can see (and say) `Klass` directly. But code outside `Manny` can’t do that. It has to specify the namespace *explicitly* in order to pass through the barrier that the namespace represents. To do so, it must say `Manny’s` name first, followed by a dot, followed by the term `Klass`. In short, it has to say `Manny.Klass`.

The namespace does not, of itself, provide secrecy or privacy; it’s a convenience. In **Example 1-1**, I gave `Manny` a `Klass` class, and I also gave `Moe` a `Klass` class. But they don’t conflict, because they are in different namespaces, and I can differentiate them, if necessary, as `Manny.Klass` and `Moe.Klass`.

It will not have escaped your attention that the syntax for diving explicitly into a namespace is the message-sending dot-notation syntax. They are, in fact, the same thing.

In effect, message-sending allows you to see into scopes you can’t see into otherwise. Code inside `Moe` can’t *automatically* see the `Klass` declared inside `Manny`, but it *can* see it by taking one easy extra step, namely by speaking of `Manny.Klass`. It can do *that* because it *can* see `Manny` (because `Manny` is declared at a level that code inside `Moe` can see).

## Modules

The top-level namespaces are *modules*. Your app is a module and hence a namespace; that namespace’s name is, by default, the name of the app. If my app is called `MyApp`, then if I declare a class `Manny` at the top level of a file, that class’s *real* name is `MyApp.Manny`. But I don’t usually need to use that real name, because my code is already inside the same namespace, and can see the name `Manny` directly.

When you import a module, all the top-level declarations of *that* module become visible to your code as well, without your having to use the module’s namespace explicitly to refer to them. For example, Cocoa’s Foundation framework, where `NSString` lives, is a module. When you program iOS, you will say `import Foundation` (or, more likely, you’ll say `import UIKit`, which itself imports `Foundation`), allowing you to speak of `NSString` without saying `Foundation.NSString`.

Swift itself is defined in a module — the Swift module. But you don’t have to import it, because your code *always implicitly imports the Swift module*. You could make this explicit by starting a file with the line `import Swift`; there is no need to do this, but it does no harm either.

That fact is important, because it solves a major mystery: where do things like `print` come from, and why is it possible to use them outside of any message to any object? `print` is in fact a function declared at the top level of the Swift module, and your code

can see the Swift module's top-level declarations because it imports Swift. The `print` function becomes, as far as your code is concerned, an ordinary top-level function like any other; it is global to your code, and your code can speak of it without specifying its namespace. You *can* specify its namespace — it is perfectly legal to say things like `Swift.print("hello")` — but you probably never will, because you won't need to.

Your own app module, however, *overshadows* any modules you import. That means that if you declare a term identical to an imported term, you lose the magical ability to use the imported term without specifying the namespace. If you were to declare a `print` function of your own, it would effectively hide the Swift `print` function; you can still call the Swift `print` function, but now you *have* to use the namespaced `Swift.print` explicitly. Similarly, if you were to declare your own `String` type, all code that refers to Swift's `String` type would require you to say `Swift.String`. Nearly always, that sort of thing is accidental and you will prefer that your own terms not conflict with any imported terms.



You can actually *see* the Swift top-level declarations and read and study them, and this can be a useful thing to do. For example, to see the declaration of `print`, Command-Control-click the term `print` in your code. Behold, there are some Swift top-level declarations! You won't see any executable Swift *code* here, but you will see the declarations for various available Swift terms, including `print`.

## Instances

Object types — class, struct, and enum — have an important feature in common: they can be *instantiated*. In effect, when you declare an object type, you are only defining a *type*. To instantiate a type is to make a thing — an *instance* — of that type.

For example, I can declare a `Dog` class, and I can give my class a method:

```
class Dog {  
    func bark() {  
        print("woof")  
    }  
}
```

But I don't actually have any `Dog` objects in my program yet. I have merely described the *type* of thing a `Dog` *would* be if I had one. To get an actual `Dog`, I have to *make* one. The process of making an actual `Dog` object whose type is the `Dog` class is the process of instantiating `Dog`. The result is a new object — a `Dog` instance.

In Swift, instances can be created by using the object type's name as a function name and calling the function. This involves using parentheses. When you append parentheses to the name of an object type, you are sending a very special kind of message to that object type: *Instantiate yourself!*




Figure 1-1. Making an instance and calling an instance method

So now I'm going to make a Dog instance:

```
let fido = Dog()
```

There's a lot going on in that code! I did two things. I instantiated Dog, causing me to end up with a Dog instance. I also put that Dog instance into a shoebox called *fido* — I declared a variable and initialized the variable by assigning my new Dog instance to it. Now *fido is a Dog instance*. (Moreover, because I used *let*, *fido* will always be this same Dog instance. I could have used *var* instead, but even then, initializing *fido* as a Dog instance would mean *fido* could only be some Dog instance after that.)

Now that I have a Dog instance, I can send *instance messages* to it. And what do you suppose they are? They are Dog's properties and methods! For example:

```
let fido = Dog()
fido.bark()
```

That code is legal. Not only that, it is effective: it actually does cause "woof" to appear in the console. I made a Dog and I made it bark! (See [Figure 1-1](#).)

There's an important lesson here, so let me pause to emphasize it. By default, properties and methods are *instance* properties and methods. You can't use them as messages to the object type itself; you have to have an *instance* to send those messages to. As things stand, this is illegal and won't compile:

```
Dog.bark() // compile error
```

It is possible to declare a function *bark* in such a way that saying *Dog.bark()* is legal, but that would be a different kind of function — a *class* function or a *static* function — and you would need to say so when you declare it.



The same thing is true of properties. To illustrate, let's give Dog a name property:

```
class Dog {  
    var name = ""  
}
```

That allows me to set a Dog's name, but it needs to be an *instance* of Dog:

```
let fido = Dog()  
fido.name = "Fido"
```

It is possible to declare a property name in such a way that saying `Dog.name` is legal, but that would be a different kind of property — a *class* property or a *static* property — and you would need to say so when you declare it.

## Why Instances?

Even if there were no such thing as an instance, an object type is itself an object. We know this because it is possible to send a message to an object type (the phrase `Manny.Klass` is a case in point). Why, then, do instances exist at all?

The answer has mostly to do with the nature of instance properties. The *value* of an instance property is defined with respect to *a particular instance*. This is where instances get their real usefulness and power.

Consider again our Dog class. I'll give it a name property and a bark method; remember, these are an instance property and an instance method:

```
class Dog {  
    var name = ""  
    func bark() {  
        print("woof")  
    }  
}
```

A Dog instance comes into existence with a blank name (an empty string). But its name property is a *var*, so once we have any Dog instance, we can assign to its name a new String value:

```
let dog1 = Dog()  
dog1.name = "Fido"
```

We can also ask for a Dog instance's name:

```
let dog1 = Dog()  
dog1.name = "Fido"  
print(dog1.name) // "Fido"
```

The important thing is that we can make more than one Dog instance, and that two different Dog instances can have two different name property values ([Figure 1-2](#)):




Figure 1-2. Two dogs with different property values

```
let dog1 = Dog()
dog1.name = "Fido"
let dog2 = Dog()
dog2.name = "Rover"
print(dog1.name) // "Fido"
print(dog2.name) // "Rover"
```

Note that a Dog instance's name property has nothing to do with the name of the variable to which a Dog instance is assigned. The variable is just a shoebox. You can pass an instance from one shoebox to another. But the instance itself maintains its own internal integrity:

```
let dog1 = Dog()
dog1.name = "Fido"
var dog2 = Dog()
dog2.name = "Rover"
print(dog1.name) // "Fido"
print(dog2.name) // "Rover"
dog2 = dog1
print(dog2.name) // "Fido"
```

That code didn't change Rover's name; it changed which dog was inside the dog2 shoebox, replacing Rover with Fido.

The full power of object-based programming has now emerged. There is a Dog object type which defines *what it is to be a Dog*. Our declaration of Dog says that any and every Dog instance has a name property and a bark method. But each Dog instance

can have its own `name` property *value*. So multiple instances of the same object type behave alike — both Fido and Rover can bark, and will do so when they are sent the bark message — but they are different instances and can have different property values: Fido's name is "Fido" while Rover's name is "Rover".

An instance is responsible not only for the values but also for the *lifetimes* of its properties. Suppose we bring a Dog instance into existence and assign to its `name` property the value "Fido". Then this Dog instance is keeping the string "Fido" alive just so long as we do not replace the value of its `name` with some other value — and just so long as this instance lives.

In short, an instance is both code and data. The code it gets from its type and in a sense is shared with all other instances of that type, but the data belong to it alone. The data can persist as long as the instance persists. The instance has, at every moment, a *state* — the complete collection of its own personal property values. An instance is a device for *maintaining state*. It's a box for storage of data.

## The Keyword `self`

An instance is an object, and an object is the recipient of messages. Thus, an instance needs a way of sending a message to itself. This is made possible by the keyword `self`. This word can be used wherever an instance of the appropriate type is expected.

Let's say I want to keep the thing that a Dog says when it barks, such as "woof", in a property. Then in my implementation of `bark` I need to refer to that property. I can do it like this:

```
class Dog {
    var name = ""
    var whatADogSays = "woof"
    func bark() {
        print(self.whatADogSays)
    }
}
```

Similarly, let's say I want to write an instance method `speak` which is merely a synonym for `bark`. My `speak` implementation can consist of simply calling my own `bark` method. I can do it like this:

```
class Dog {
    var name = ""
    var whatADogSays = "woof"
    func bark() {
        print(self.whatADogSays)
    }
}
```

```

    func speak() {
        self.bark()
    }
}

```

Observe that the term `self` in that example appears only in instance methods. When an instance's code says `self`, it is referring to *this* instance. If the expression `self.name` appears in a `Dog` instance method's code, it means the name of *this* `Dog` instance, the one whose code is running at that moment.

It turns out that every use of the word `self` I've just illustrated is optional. You can omit it and all the same things will happen:

```

class Dog {
    var name = ""
    var whatADogSays = "woof"
    func bark() {
        print(whatADogSays)
    }
    func speak() {
        bark()
    }
}

```

The reason is that if you omit the message recipient and the message you're sending can be sent to `self`, the compiler supplies `self` as the message's recipient under the hood. However, I never do that (except by mistake). As a matter of style, I like to be explicit in my use of `self`. I find code that omits `self` harder to read and understand. And there are situations where you *must* say `self`, so I prefer to use it whenever I'm allowed to.

## Privacy

Earlier, I said that a namespace is not, of itself, an insuperable barrier to accessing the names inside it. But such a barrier is sometimes desirable. Not all data stored by an instance is intended for alteration by, or even visibility to, another instance. And not every instance method is intended to be called by other instances. Any decent object-based programming language needs a way to endow its object members with *privacy* — a way of making it harder for other objects to see those members if they are not supposed to be seen.

Consider, for example:

```

class Dog {
    var name = ""
    var whatADogSays = "woof"
    func bark() {
        print(self.whatADogSays)
    }
}

```

```

    func speak() {
        print(self.whatADogSays)
    }
}

```

Here, other objects can come along and change my property `whatADogSays`. Since that property is used by both `bark` and `speak`, we could easily end up with a `Dog` that, when told to `bark`, says "meow". That seems somehow undesirable:

```

let fido = Dog()
fido.whatADogSays = "meow"
fido.bark() // meow

```

You might reply: Well, silly, why did you declare `whatADogSays` with `var`? Declare it with `let` instead. Make it a constant! Now no one can change it:

```

class Dog {
    var name = ""
    let whatADogSays = "woof"
    func bark() {
        print(self.whatADogSays)
    }
    func speak() {
        print(self.whatADogSays)
    }
}

```

That is a good answer, but it is not quite good enough. There are two problems. Suppose I want a `Dog` instance *itself* to be able to change *its own* `whatADogSays` — by assigning to `self.whatADogSays`. Then `whatADogSays` *has* to be a `var`; otherwise, even the instance itself can't change it. Also, suppose I don't want any other object to *know* what this `Dog` says, except by calling `bark` or `speak`. Even when declared with `let`, other objects can still *read* the value of `whatADogSays`. Maybe I don't like that.

To solve this problem, Swift provides the `private` keyword. I'll talk later about all the ramifications of this keyword, but for now it's enough to know that it exists:

```

class Dog {
    var name = ""
    private var whatADogSays = "woof"
    func bark() {
        print(self.whatADogSays)
    }
    func speak() {
        print(self.whatADogSays)
    }
}

```

Now `name` is a public property, but `whatADogSays` is a private property: it can't be seen by other types of object. A `Dog` instance can say `self.whatADogSays`, but a `Cat` instance with a reference to a `Dog` instance as `fido` can't say `fido.whatADogSays`:

## Reserved Words

Certain terms, like `class` and `func` and `var` and `let` and `if` and `private` and `import`, are *reserved* in Swift; they are part of the language. That means you can't use them as *identifiers* — such as the name of a class, a function, or a variable. If you try to do so, you'll get a compile error.

To force a reserved word to be an identifier, surround it by backticks (```). This (extraordinarily confusing) code is legal:

```
class `func` {  
    func `if`() {  
        let `class` = 1  
    }  
}
```

```
class Cat {  
    func tryToChangeWhatADogSays() {  
        let fido = Dog()  
        fido.whatADogSays = "meow" // compile error  
    }  
}
```

The important lesson here is that object members are public by default, and if you want privacy, you have to ask for it.

To sum up: A class declaration defines a namespace. This namespace requires that other objects use an extra level of dot-notation to refer to what's inside the namespace, but other objects *can* still refer to what's inside the namespace; the namespace does not, in and of itself, close any doors of visibility. The `private` keyword lets you close those doors.

## Design

Instances do not come into being by magic. You have to instantiate a type in order to obtain an instance. Much of the action of your program, therefore, will consist of instantiating types. And of course you will want those instances to persist, so you will also assign each newly created instance to a variable as a shoebox to hold it, name it, and give it a lifetime. The instance will *persist* according to the lifetime of the variable that refers to it. And the instance will be *visible* to other instances according to the scope of the variable that refers to it.

Much of the art of object-based programming involves giving instances a sufficient lifetime and making them visible to one another. You will often put an instance into a particular shoebox — assigning it to a particular variable, declared at a certain scope — exactly so that, thanks to the rules of variable lifetime and scope, this instance will

*persist* long enough to keep being useful to your program while it will still be needed, and so that other code can *get a reference* to this instance and talk to it later.

Planning how you're going to create instances, and working out the lifetimes and communication between those instances, may sound daunting. Fortunately, in real life, when you're programming iOS, the framework will provide scaffolding for you. Before you write a single line of code, the framework ensures that your app, as it launches, is given some instances that will persist for the lifetime of the app, providing the basis of your app's visible interface and giving you an initial place to put your own instances and give them sufficiently long lifetimes.

What about the question of what object types your program will need in the first place, and what methods and properties they should have? This is not as much of a worry as you might suppose. Swift itself supplies a library of powerful and useful object types. Moreover, much of your code when you're programming iOS will be focused on the details of real-world interface objects, such as labels and buttons that the user can see and tap, and the framework will make it clear what object types and facilities it offers for this purpose, and will provide ways to ensure the appropriate persistence and visibility of the associated instances.

What the framework cannot tell you is how to design the underlying business logic of whatever your app does behind the scenes. This is where you will have the most freedom — and the most difficulty arriving at an appropriate architecture of object types, functionalities, and relationships. These will not be easy decisions, and there are no clear-cut answers. Object-based programming is an art; and allowing your program (and your thinking) to evolve as you write code, discovering new needs and issues, is an art within that art, which I call *growing a program*. All individuals and teams develop their own way of meeting the long-term challenges involved.





---

# Functions

Nothing is so characteristic of Swift syntax as the way you declare and call functions. Probably nothing is so important, either! As I said in [Chapter 1](#), all your executable code is going to be in functions; they are where the action is.

## Function Parameters and Return Value

Remember those imaginary machines for processing miscellaneous stuff that you drew in your math textbook in elementary school? You know the ones I mean: with a funnel-like “hopper” at the top, and then a bunch of gears and cranks, and then a tube at the bottom where something is produced. A function works like that: you feed some stuff in, the stuff is processed in accordance with what this particular machine does, and something is produced. The stuff that goes in is the input; what comes out is the output. More technically, a function that expects input has *parameters*; a function that produces output has a *result*.

Here’s the declaration for a silly but valid function that expects two Int values, adds them together, and produces that sum:

```
func sum (_ x:Int, _ y:Int) -> Int {  
    let result = x + y  
    return result  
}
```

The syntax here is very strict and well-defined, and you can’t use Swift unless you understand it perfectly. Let’s pause to appreciate it in full detail. I’ll break the first line into pieces so that I can call them out individually:

```

func sum                                ❶
  (_ x:Int, _ y:Int)                   ❷❸
  -> Int {                             ❹❺
    let result = x + y                ❻
    return result                     ❼
  }

```

- ❶ The declaration starts with the keyword `func`, followed by the *name* of this function; here, it's `sum`. This is the name that must be used in order to *call* the function — that is, in order to run the code that the function contains.
- ❷ The name of the function is followed by its *parameter list*. It consists, minimally, of parentheses. If this function takes parameters (input), they are listed inside the parentheses, separated by a comma. Each parameter has a strict format: the *name* of the parameter, a colon, and the *type* of the parameter.
- ❸ This particular function declaration also has an underscore (`_`) and a space before each parameter name in the parameter list. I'm not going to explain that underscore yet, but I need it for the example, so just trust me for now.
- ❹ If the function is to return a value, then after the parentheses is an arrow operator (`->`) followed by the *type* of value that this function will return.
- ❺ Then we have curly braces enclosing the *body* of the function — its actual code.
- ❻ Within the curly braces, in the function body, the variables defined as the parameter names have sprung to life, with the types specified in the parameter list.
- ❼ If the function is to return a value, it must do so with the keyword `return` followed by that value. And, not surprisingly, the type of that value must match the type declared earlier for the return value (after the arrow operator).

Here are some further points to note about the parameters and return type of our function:

### Parameters

Our `sum` function expects two parameters — an `Int`, to which it gives the name `x`, and another `Int`, to which it gives the name `y`. The function body code won't run unless code elsewhere calls this function and actually passes values of the specified types for its parameters. If I try to call this function *without* providing a value for each of these two parameters, or if either of the values I provide is *not* an `Int`, the compiler will stop me with an error.

In the body of the function, therefore, we can confidently use those values, referring to them by those names, certain that they will exist as specified by our parameter list. The parameter names `x` and `y`, indeed, are defined just so that the

parameter values *can* be referred to within the function body. The parameter declaration is thus a kind of variable declaration: we are declaring variables `x` and `y` for use inside this function. With regard to their scope, these variables are local (*internal*) to the function; *only* the function body can see them, and they are different from any other `x` and `y` that may be used in other functions or at a higher level of scope.

### *Return type*

The last statement of our `sum` function's body returns the value of a variable called `result`; this variable was created by adding two `Int` values together, so it is an `Int`, which is what this function is supposed to produce. If I try to return a `String` (`return "howdy"`), or if I omit the return statement altogether, the compiler will stop me with an error.

The keyword `return` actually does *two* things. It *returns* the accompanying value, and it also *halts* execution of the function. It is permitted for more lines of code to follow a return statement, but the compiler will warn if this means that those lines can never be executed.

A function that returns a value must contain a return statement, so if its body consists of just a single statement, it must *be* the return statement. The keyword `return` can be omitted in that situation. This is mostly to facilitate the SwiftUI domain-specific language, and in general I like to say `return` explicitly, but in some situations it does feel more elegant to omit it.

You can view the function declaration before the curly braces as a *contract* about what kinds of values will be used as input and about what kind of output will be produced. According to this contract, the function *expects* a certain number of parameters, each of a certain type, and *yields* a certain type of result. Everything must correspond to this contract. The function body, inside the curly braces, can use the parameters as local variables. The returned value must match the declared return type.

The same contract applies to code elsewhere that *calls* this function. Here's some code that calls our `sum` function:

```
let z = sum(4,5)
```

Focus your attention on the right side of the equal sign — `sum(4,5)`. That's the function call. How is it constructed? It uses the *name* of the function; that name is followed by *parentheses*; and inside those parentheses, separated by a comma, are the *values* to be passed to each of the function's parameters. Technically, these values are called *arguments*. Here, I'm using literal `Int` values, but I'm perfectly free to use `Int` variables instead; the only requirement is that I use things that have the correct type:

```
let x = 4
let y = 5
let z = sum(y,x)
```

In that code, I purposely used the names `x` and `y` for the variables whose values are passed as arguments, and I purposely reversed them in the call, to emphasize that these names have *nothing to do* with the names `x` and `y` inside the function parameter list and the function body. Argument names do not magically make their way to the function. Their *values* are all that matter; their values are the arguments.

What about the value returned by the function? That value is magically *substituted* for the function call, at the point where the function call is made. It happens that in the preceding code, the result is 9. So the last line is exactly as if I had said:

```
let z = 9
```

The programmer and the compiler both know what type of thing this function returns, so they also know where it is and isn't legal to call this function. It's fine to call this function as the initialization part of the declaration of the variable `z`, just as it would be to use 9 as the initialization part of that declaration: in both cases, we have an `Int`, and so `z` ends up being declared as an `Int`. But it would not be legal to write this:

```
let z = sum(4,5) + "howdy" // compile error
```

Because `sum` returns an `Int`, that's the same as trying to add an `Int` to a `String` — and by default, you can't do that in Swift.

Observe that it is legal to ignore the value returned from a function call:

```
sum(4,5)
```

That code is rather silly in this particular situation, because we have made our `sum` function go to all the trouble of adding 4 and 5 for us and we have then thrown away the answer without capturing or using it. The compiler knows this, and will warn that we are failing to use the result of our function call. Nevertheless, a warning is not an error; that code is legal. There are, in fact, lots of situations where it is perfectly reasonable to ignore the value returned from a function call; in particular, the function may do other things (technically called *side effects*) in addition to returning a value, and the purpose of your call to that function may be those other things.



If you're ignoring a function call result deliberately, you can silence the compiler warning by assigning the function call to `_` (a variable without a name) — for example, `_ = sum(4,5)`. Alternatively, if the function being called is your own, you can prevent the warning by marking the function declaration with `@discardableResult`.

If you can call `sum` wherever you can use an `Int`, and if the parameters of `sum` have to be `Int` values, doesn't that mean you can call `sum` inside a call to `sum`? Of course it does! This is perfectly legal (and reasonable):

```
let z = sum(4,sum(5,6))
```

The only arguments against writing code like that are that you might confuse yourself and that it might make things harder to debug later. But technically it's legal and quite normal.

## Void Return Type and Parameters

Let's return to our function declaration. With regard to a function's parameters and return type, there are two degenerate cases that allow us to express a function declaration more briefly:

### *A function without a return type*

No law says that a function *must* return a value. A function may be declared to return *no* value. In that case, there are three ways to write the declaration: you can write it as returning `Void`; you can write it as returning `()`, an empty pair of parentheses; or you can omit the arrow operator and the return type entirely. These are all legal:

```
func say1(_ s:String) -> Void { print(s) }
func say2(_ s:String) -> () { print(s) }
func say3(_ s:String) { print(s) }
```

If a function returns no value, then its body need not contain a return statement. If it does contain a return statement, it will consist of the word `return` alone, and its purpose will be purely to end execution of the function at that point.

A call to a function that returns no value is made purely for the function's side effects; it has no useful return value that can be made part of a larger expression, so the statement that calls the function will usually consist of the function call and nothing else.

### *A function without any parameters*

No law says that a function *must* take any parameters. If it doesn't, the parameter list in the function declaration can be completely empty. But you can't omit the parameter list parentheses themselves! They will be present in the function declaration, after the function's name:

```
func greet() -> String { return "howdy" }
```

Just as you cannot omit the parentheses (the parameter list) from a function *declaration*, you cannot omit the parentheses from a function *call*. Those parentheses will be empty if the function takes no parameters, but they must be present:

```
let greeting = greet()
```

Notice the parentheses!

A function can lack both a return value and parameters; these are all ways of expressing the same thing:

```
func greet1() -> Void { print("howdy") }  
func greet2() -> () { print("howdy") }  
func greet3() { print("howdy") }
```

## Function Signature

If we ignore the parameter names in the function declaration, we can completely characterize a function by the *types* of its inputs and its output. To do so, we write the parameter types in parentheses, followed by the arrow operator and the output type, like this:

```
(Int, Int) -> Int
```

That is a legal expression in Swift; it is the *signature* of a function. In this case, it's the signature of a function that takes two `Int` parameters and returns an `Int`. In fact, it's the signature of our `sum` function! Of course, there can be other functions that take two `Int` parameters and return an `Int` — and that's just the point. This signature characterizes *all* functions that have this number of parameters, of these types, and that return a result of this type. A function's signature is, in effect, *its* type — the type *of the function*. The fact that functions have types will be of great importance later on.

The signature of a function must include both the parameter list (without parameter names) and the return type, even if one or both of those is empty; the signature of a function that takes no parameters and returns no value may be written `() -> Void` or `() -> ()`.

## External Parameter Names

A function can *externalize* the names of its parameters. The external parameter names become part of the function's name, and must appear in a call to the function as *labels* to the arguments. There are several reasons why this is a good thing:

- It clarifies the purpose of each argument; an argument label can give a clue as to how that argument contributes to the behavior of the function.
- It distinguishes one function from another; two functions with the same name before the parentheses and the same signature, but with different external parameter names, are two distinct functions.
- It helps Swift to interface with Objective-C and Cocoa, where method parameters nearly always have external names.



It will be useful to have a term for the part of a function's name that precedes the parentheses, so I don't have to keep calling it "the name before the parentheses" to distinguish it from the external parameter names. Let's call it the function's *base name*.

External parameter names are so standard in Swift that there's a rule: by default, *all* parameter names are externalized *automatically*, using the internal name as the external name. If you want a parameter name to be externalized, and if you want the external name to be the same as the internal name, *do nothing* — that will happen all by itself.

If you want to depart from the default behavior, you can do either of the following in your function declaration:

#### *Change the name of an external parameter*

If you want the external name of a parameter to be different from its internal name, precede the internal name with the external name and a space.

#### *Suppress the externalization of a parameter*

To suppress a parameter's external name, precede the internal name with an underscore and a space.

That explains my declaration `func sum (_ x:Int, _ y:Int) -> Int` at the start of this chapter: I was suppressing the externalization of the parameter names, so as not to have to explain argument labels at the outset.

Here's the declaration for a function that concatenates a string with itself a given number of times:

```
func echoString(_ s:String, times:Int) -> String {
    var result = ""
    for _ in 1...times { result += s }
    return result
}
```

That function's first parameter has an internal name only, but its second parameter has an external name, which will be the same as its internal name, namely `times`. And here's how to call it:

```
let s = echoString("hi", times:3)
```

In the call, as you can see, the external name precedes the argument as a label, separated by a colon.

Now let's say that in our `echoString` function we prefer to use `times` purely as an external name for the second parameter, with a different name — say, `n` — as the internal name. And let's strip the `string` off the function's base name and make it the external name of the first parameter. Then the declaration would look like this:

```
func echo(string s:String, times n:Int) -> String {
    var result = ""
    for _ in 1...n { result += s }
    return result
}
```

In the body of that function, there is now no `times` variable available; `times` is purely an external name, for use as a label in the call. The internal name is `n`, and that's the name the code refers to. And here's how to call it:

```
let s = echo(string:"hi", times:3)
```



The existence of external names doesn't mean that the call can use a different parameter order from the declaration. Our `echo(string:times:)` expects a `String` parameter and an `Int` parameter, *in that order*. The order can't be different in the call, even though the label might appear to disambiguate which argument goes with which parameter.

## Overloading

In Swift, function *overloading* is legal (and common). This means that two functions with exactly the same name, *including* their external parameter names, can coexist as long as they have different signatures. (Two functions with the same base name but *different* external parameter names do *not* constitute a case of overloading; they are simply two different functions with two different names.) These two functions can coexist:

```
func say (_ what:String) {
}
func say (_ what:Int) {
}
```

The reason overloading works is that Swift has strict typing. A `String` parameter is not an `Int` parameter. Swift can tell them apart both in the declaration and in a function call. So Swift knows unambiguously that `say("what")` is different from `say(1)`, and it knows *which* say function each is calling.

Overloading works for the return type as well. Two functions with the same name and parameter types can have different return types. But the context of the call must disambiguate; that is, it must be clear what return type the caller is expecting.

For example, these two functions can coexist:

```
func say() -> String {
    return "one"
}
func say() -> Int {
    return 1
}
```



But now you can't call `say` like this:

```
let result = say() // compile error
```

The call is ambiguous, and the compiler tells you so. The call must be used in a context where the expected return type is clear. One solution, as I'll describe in [Chapter 3](#), is to state the problematic type explicitly (rather than relying on type inference):

```
let result: String = say()
```

Alternatively, the context itself might disambiguate. Suppose we have another function that is not overloaded, and that expects a `String` parameter:

```
func giveMeAString(_ s:String) {  
    print("thanks!")  
}
```

Then `giveMeAString(say())` is legal, because only a `String` can go in this spot, so we must be calling the `say` that returns a `String`. Similarly:

```
let result = say() + "two"
```

Only a `String` can be “added” to a `String`, so this must be the `say` that returns a `String`.

You can also disambiguate explicitly between overloads in a method call using the name of the method, the keyword `as`, and the signature of the desired method. The syntax is a little odd, because the entire expression must be enclosed in parentheses, followed immediately by the parentheses signifying that this is a method call:

```
let result = (say as () -> String)()
```

## Default Parameter Values

A parameter can have a default value. This means that the caller can omit the parameter entirely, supplying no argument for it; the value will then be the default.

To specify a default value in a function declaration, append `=` and the default value after the parameter type:

```
class Dog {  
    func say(_ s:String, times:Int = 1) {  
        for _ in 1...times {  
            print(s)  
        }  
    }  
}
```

In effect, there are now *two* functions, one with a single unlabeled parameter, the other with an additional `times:` parameter. If you just want to say something once, you can call the `say` that takes a single unlabeled argument:

```
let d = Dog()
d.say("woof") // same as d.say("woof", times:1)
```

If you want repetition, call the `say` that takes a `times:` parameter:

```
let d = Dog()
d.say("woof", times:3)
```

## Variadic Parameters

A parameter can be *variadic*. This means that the caller can supply as many argument values of this parameter's type as desired, separated by a comma; the function body will receive these values as an array.

To indicate in a function declaration that a parameter is variadic, follow it with three dots, like this:

```
func sayStrings(_ array:String ...) {
    for s in array { print(s) }
}
```

And here's how to call it:

```
sayStrings("hey", "ho", "nonny nonny no")
```

Another parameter may follow a variadic parameter, but it must have an external label to show where the variadic arguments end in the call. The global `print` function works like that. It takes a variadic first parameter, so that you can output multiple values with a single command; the remaining parameters have default values and can be omitted:

```
print("Manny", 3, true) // Manny 3 true
```

The `print` function's remaining parameters dictate further details of the output. The default `separator:` (for when you provide multiple values) is a space, and the default `terminator:` is a newline; you can change either or both:

```
print("Manny", "Moe", separator:", ", terminator:", ")
print("Jack")
// output is "Manny, Moe, Jack" on one line
```

In Swift 5.3 and before, a function can declare a maximum of one variadic parameter. Starting in Swift 5.4, that restriction has been lifted. Even two variadic parameters in a row are now legal, though you still need an external label on the second one:

```
func sayStrings(_ array:String ..., and array2:String ...) {
    for s in array { print(s) }
    for s in array2 { print(s) }
}
```

A second variadic parameter that isn't adjacent to the first variadic parameter doesn't require an external label:

## Initializers Are Functions

In [Chapter 1](#), I declared a `Dog` class and instantiated it, creating a `Dog` instance, by saying `Dog()`. When you do this, you are actually calling a function — a special function called an *initializer*. This particular initializer function takes no parameters; hence the parentheses are empty. But an initializer is a function like any other, so it can have parameters, external parameter names, default parameter values, overloading, and so forth. And the syntax for calling an initializer (and thus for creating an instance) is the same as the syntax for any other function call. What's special is only that the parentheses follow the name of the type we're instantiating.

I'll explain how initializers are declared and implemented later ([Chapter 4](#)). Swift built-in types tend to have multiple initializers. For example, here I'll initialize two `String` objects:

```
let s1 = String(42)
let s2 = String(repeating: "ho", count: 2)
```

After that, `s1` is the string `"42"` and `s2` is the string `"hoho"`. And there are many other `String` initializers, each providing a different way to make a `String`.

```
func sayStrings(_ array:String ..., other:String, _ array2:String ...) {
    for s in array { print(s) }
    print(other)
    for s in array2 { print(s) }
}
```

Arguably, that function declaration is silly, as it results in a confusing call:

```
sayStrings("Manny", "Moe", "Jack", other: "Matt", "Groucho", "Harpo", "Chico")
```

In that call, `"Matt"` is a parameter on its own, while `"Groucho"` and the rest are the arguments to an additional (variadic) parameter. But there's no indication of that, so a human being might think that `other:` is a variadic. Nevertheless, the compiler isn't confused, so it's legal!



Unfortunately, there's a hole in the Swift language: there's no way to convert an array into a comma-separated list of arguments (comparable to splatting in Ruby). If what you're starting with is an array of some type, you can't use it where a variadic of that type is expected.

## Ignored Parameters

A parameter whose local name is an underscore is ignored. The caller must supply an argument, but it has no name within the function body and cannot be referred to there. For example:

```
func say(_ s:String, times:Int, loudly _:Bool) {
```

No `loudly` parameter makes its way into the function body, but the caller must still provide it:

```
say("hi", times:3, loudly:true)
```

What’s the purpose of this feature? It isn’t to satisfy the compiler, because the compiler doesn’t complain if a parameter is never referred to in the function body. I use it primarily as a kind of note to myself, a way of saying, “Yes, I know there is a parameter here, and I am deliberately not using it for anything.”

## Modifiable Parameters

In the body of a function, a parameter is essentially a local variable. By default, it’s a variable implicitly declared with `let`. You can’t assign to it:

```
func say(_ s:String, times:Int, loudly:Bool) {  
    loudly = true // compile error  
}
```

If your code needs to assign to a parameter name within the body of a function, declare a `var` local variable inside the function body and assign the parameter value to it; your local variable can even have the same name as the parameter:

```
func say(_ s:String, times:Int, loudly:Bool) {  
    var loudly = loudly  
    loudly = true // no problem  
}
```

In that code, `loudly` is a local variable; assigning to it doesn’t change the value of any variable outside the function body. However, it is also possible to configure a parameter in such a way that assigning to it *does* modify the value of a variable outside the function body! One typical use case is that you want your function to return more than one result. Here I’ll write a rather advanced function that removes all occurrences of a given character from a given string and returns the number of occurrences that were removed:

```
func removeCharacter(_ c:Character, from s:String) -> Int {  
    var s = s  
    var howMany = 0  
    while let ix = s.firstIndex(of:c) {  
        s.remove(at:ix)  
        howMany += 1  
    }  
    return howMany  
}
```

And you call it like this:

```
let s = "hello"
let result = removeCharacter("l", from:s) // 2
```

That's nice, but the *original* string, *s*, is still "hello"! In the function body, we removed all occurrences of the character from the *local* copy of the String parameter.

If we want a function to alter the *original* value of an argument passed to it, we must do the following:

- The type of the parameter we intend to modify must be declared *inout*.
- When we call the function, the variable holding the value to be modified must be declared with *var*, not *let*.
- Instead of passing the variable as an argument, we must pass its *address*. This is done by preceding its name with an ampersand (&).

Our `removeCharacter(_:from:)` now looks like this:

```
func removeCharacter(_ c:Character, from s: inout String) -> Int {
    var howMany = 0
    while let ix = s.firstIndex(of:c) {
        s.remove(at:ix)
        howMany += 1
    }
    return howMany
}
```

And our call to `removeCharacter(_:from:)` now looks like this:

```
var s = "hello"
let result = removeCharacter("l", from:&s)
```

After the call, *result* is 2 and *s* is "heo". Notice the ampersand before the name *s* when we pass it as the *from:* argument. It is required; if you omit it, the compiler will stop you. I like this requirement, because it forces us to acknowledge explicitly to the compiler, and to ourselves, that we're about to do something potentially dangerous: we're letting this function, as a side effect, modify a value outside of itself.



When a function with an *inout* parameter is called, the variable whose address was passed as argument to that parameter is *always* set, even if the function makes no changes to that parameter.

## Calling Objective-C with Modifiable Parameters

You may encounter variations on that pattern when you're using Cocoa. The Cocoa APIs are written in C and Objective-C, so instead of the Swift term *inout*, you'll probably see some mysterious type such as `UnsafeMutablePointer`. From your point of view as the caller, however, it's the same thing: you'll prepare a *var* variable and pass its address.

For instance, consider the problem of learning a `UIColor`'s RGBA components. There are four such components: the color's red, green, blue, and alpha values. A function that, given a `UIColor`, returned the components of that color, would need to return four values at once — and that is something that Objective-C cannot do. So a different strategy is used. The `UIColor` method `getRed(_:green:blue:alpha:)` returns only a `Bool` reporting whether the component extraction succeeded. Instead of returning the actual components, it says: “You hand me four `CGFloat`s *as arguments*, and I will *modify* them for you so that they are the results of this operation.” Here's roughly how the declaration for `getRed(_:green:blue:alpha:)` appears in Swift:

```
func getRed(_ red: UnsafeMutablePointer<CGFloat>,
            green: UnsafeMutablePointer<CGFloat>,
            blue: UnsafeMutablePointer<CGFloat>,
            alpha: UnsafeMutablePointer<CGFloat>) -> Bool
```

How would you call this function? The parameters are each an `UnsafeMutablePointer` to a `CGFloat`. You'll create four `var CGFloat` variables beforehand, giving them each some value even though that value will be replaced when you call `getRed(_:green:blue:alpha:)`. The arguments you'll pass will be the *addresses* of those variables. Those variables are where the component values will be after the call; and you'll probably be so sure that the component extraction will succeed, that you won't even bother to capture the call's actual result:

```
let c = UIColor.purple
var r : CGFloat = 0
var g : CGFloat = 0
var b : CGFloat = 0
var a : CGFloat = 0
c.getRed(&r, green: &g, blue: &b, alpha: &a)
// now r, g, b, a are 0.5, 0.0, 0.5, 1.0
```

## Called by Objective-C with Modifiable Parameters

Sometimes, Cocoa will call *your* function with an `UnsafeMutablePointer` parameter, and *you* will want to change its value. To do this, you cannot assign directly to it, as we did earlier with the `inout` parameter `s` that we declared in our implementation of `remove(from:character:)`. You're talking to Objective-C, not to Swift, and this is an `UnsafeMutablePointer`, not an `inout` parameter. The technique here is to assign to the `UnsafeMutablePointer`'s `pointee` property. Here (without further explanation) is an example from my own code:

```
func popoverPresentationController(
    _ popoverPresentationController: UIPopoverPresentationController,
    willRepositionPopoverTo rect: UnsafeMutablePointer<CGRect>,
    in view: AutoreleasingUnsafeMutablePointer<UIView>) {
    view.pointee = self.button2
    rect.pointee = self.button2.bounds
}
```

## Reference Type Modifiable Parameters

There is one very common situation where your function can modify a parameter *without* declaring it as `inout` — namely, when the parameter is an *instance of a class*. This is a special feature of classes, as opposed to the other two object type flavors, `enum` and `struct`. `String` isn't a class; it's a `struct`. That's why we had to use `inout` in order to modify a `String` parameter. So I'll illustrate by declaring a `Dog` class with a `name` property:

```
class Dog {
    var name = ""
}
```

Here's a function that takes a `Dog` instance parameter and a `String`, and sets that `Dog` instance's `name` to that `String`. Notice that no `inout` is involved:

```
func changeName(of d:Dog, to newName:String) {
    d.name = newName
}
```

Here's how to call it. We pass a `Dog` instance *directly*:

```
let d = Dog()
d.name = "Fido"
print(d.name) // "Fido"
changeName(of:d, to:"Rover")
print(d.name) // "Rover"
```

We were able to change a property of our `Dog` instance `d`, even though it wasn't passed as an `inout` parameter, and even though it was declared originally with `let`, not `var`. This appears to be an exception to the rules about modifying parameters — but it isn't. It's a feature of class instances, namely that they are themselves mutable. In `changeName(of:to:)`, we didn't actually attempt to assign *a different `Dog` instance* to the parameter. To do that, the `Dog` parameter *would* need to be declared `inout` (and `d` would have to be declared with `var` and we would have to pass its address as argument).

Technically, we say that classes are *reference types*, whereas the other object type flavors are *value types*. When you pass an instance of a `struct` as an argument to a function, you effectively wind up with a *separate copy* of the `struct` instance. But when you pass an instance of a class as an argument to a function, you pass a reference to the

class instance *itself*. I'll discuss this topic in more detail later (“Value Types and Reference Types” on page 157).

## Function in Function

A function can be declared anywhere, including inside the body of a function. A function declared in the body of a function (also called a *local function*) is available to be called by later code within the same scope, but is completely invisible elsewhere.

This feature is an elegant architecture for functions whose sole purpose is to assist another function. If only function A ever needs to call function B, function B might as well be packaged inside function A.

Here's a typical example from one of my apps (I've omitted everything except the structure):

```
func checkPair(_ p1:Piece, and p2:Piece) -> Path? {  
    // ...  
    func addPathIfValid(_ midpt1:Point, _ midpt2:Point) {  
        // ...  
    }  
    for y in -1..._yct {  
        addPathIfValid((pt1.x,y),(pt2.x,y))  
    }  
    for x in -1..._xct {  
        addPathIfValid((x,pt1.y),(x,pt2.y))  
    }  
    // ...  
}
```

What I'm doing in the first for loop (for *y*) and what I'm doing in the second for loop (for *x*) are the same — but with a different set of starting values. We could write out the functionality in full inside each for loop, but that would be an unnecessary and confusing repetition. (Such a repetition would violate the principle often referred to as *DRY*, for “Don't Repeat Yourself.”) To prevent that repetition, we could refactor the repeated code into an instance method to be called by both for loops, but that exposes this functionality more broadly than we need, as it is called *only* by these two for loops inside *checkPair*. A local function is the perfect compromise.

## Recursion

A function can call itself. This is called *recursion*. Recursion seems a little scary, rather like jumping off a cliff, because of the danger of creating an infinite loop; but if you write the function correctly, you will always have a “stopper” condition that handles the degenerate case and prevents the loop from being infinite:



```
func countdownFrom(_ ix:Int) {
    print(ix)
    if ix > 0 { // stopper
        countdownFrom(ix-1) // recurse!
    }
}
countdownFrom(5) // 5, 4, 3, 2, 1, 0
```

## Function as Value

If you've never used a programming language where functions are first-class citizens, perhaps you'd better sit down now, because what I'm about to tell you might make you feel a little faint: In Swift, a function *is* a first-class citizen. This means that a function can be used wherever a value can be used. A function can be assigned to a variable; a function can be passed as an argument in a function call; a function can be returned as the result of a function.

Swift has strict typing. You can assign a value to a variable or pass a value into or out of a function only if it is the right *type* of value. In order for a function to be used as a value, the function needs to *have* a type. And indeed it does: a function's *signature* is its type.

The chief purpose of using a function as a value is so that this function can later be called without a definite knowledge of *what* function it is. Here's the world's simplest (and silliest) example, just to show the syntax and structure:

```
func doThis(_ f:() -> ()) {
    f()
}
```

That is a function `doThis` that takes one parameter (and returns no value). The parameter, `f`, is itself a function! How do we know? Well, look at its type (after the colon): it is `() -> ()`. That's a function signature; in particular, it is the signature of a function that takes no parameters and returns no value.

The function `doThis`, then, expects as its parameter a function, which it names `f`. Then, within its body, `doThis` *calls* the function `f` that it received as its parameter, by saying `f()`. So `doThis` is merely a function that trivially calls another function. But it does this without knowing in advance *what* function it is going to call. That's the power of functions being first-class citizens.

Having declared the function `doThis`, how would you call it? You'd need to pass it a function as argument. Here's one way to do that:

```
func doThis(_ f:() -> ()) {
    f()
}
func whatToDo() { ❶
    print("I did it")
}
doThis(whatToDo) ❷
```

- ❶ First, we declare a function (`whatToDo`) *of the proper type* — a function that takes no parameters and returns no value.
- ❷ Then, we call `doThis`, passing as argument a *function reference* — in effect, the bare name of the function. Notice that we are not *calling* `whatToDo` here; we are *passing* it.

Sure enough, this works: we pass `whatToDo` as argument to `doThis`; `doThis` calls the function that it receives as its parameter; and the string "I did it" appears in the console.

Obviously, that example, while demonstrating a remarkable ability of the Swift language, is far from compelling, because the outcome in practice is no different from what would have happened if we had simply called `whatToDo` directly. But in real life, encapsulating function-calling in a function can reduce repetition and opportunity for error. Moreover, a function may call its parameter function in some special way; it might call it after doing other things, or at some later time.

Here's a case from my own code. A common thing to do in Cocoa is to draw an image, directly, in code. One way of doing this involves four steps:

```
let size = CGSize(width:45, height:20)
UIGraphicsBeginImageContextWithOptions(size, false, 0) ❶
let p = UIBezierPath(
    roundedRect: CGRect(x:0, y:0, width:45, height:20), cornerRadius: 8)
p.stroke() ❷
let result = UIGraphicsGetImageFromCurrentImageContext()! ❸
UIGraphicsEndImageContext() ❹
```

- ❶ Open an image context.
- ❷ Draw into the context.
- ❸ Extract the image.
- ❹ Close the image context.

That works — in this case, it generates an image of a rounded rectangle — but it's ugly. The sole purpose of all that code is to obtain `result`, the image; but that purpose is buried in all the other code. At the same time, everything except for the two lines involving the `UIBezierPath` `p` (step 2) is boilerplate; every time I do this in any

app, step 1, step 3, and step 4 are exactly the same. Moreover, I live in mortal fear of forgetting a step; if I were to omit step 4 by mistake, the universe would explode.

Since the only thing that's different every time I draw is step 2, step 2 is the only part I should have to write out! The entire problem is solved by writing a utility function expressing the boilerplate:

```
func imageOfSize(_ size:CGSize, _ whatToDraw:() -> ()) -> UIImage {
    UIGraphicsBeginImageContextWithOptions(size, false, 0)
    whatToDraw()
    let result = UIGraphicsGetImageFromCurrentImageContext()!
    UIGraphicsEndImageContext()
    return result
}
```

My `imageOfSize` utility is so useful that I declare it at the top level of a file, where all my files can see it. To make an image, I can perform step 2 (the actual drawing) in a function and pass that function as argument to the `imageOfSize` utility:

```
func drawing() {
    let p = UIBezierPath(
        roundedRect: CGRect(x:0, y:0, width:45, height:20),
        cornerRadius: 8)
    p.stroke()
}
let image = imageOfSize(CGSize(width:45, height:20), drawing)
```

Now *that* is a beautifully expressive and clear way to turn drawing instructions into an image.

The Cocoa API is full of situations where you'll pass a function to be called by the runtime in some special way or at some later time. Some common Cocoa situations even involve passing *two* functions. For instance, when you perform view animation, you'll often pass one function prescribing the action to be animated and another function saying what to do afterward:

```
func whatToAnimate() { // self.myButton is a button in the interface
    self.myButton.frame.origin.y += 20
}
func whatToDoLater(finished:Bool) {
    print("finished: \(finished)")
}
UIView.animate(withDuration:0.4,
    animations: whatToAnimate, completion: whatToDoLater)
```

That means: Change the frame origin (that is, the position) of this button in the interface, but do it over time (four-tenths of a second); and then, when that's finished, print a log message in the console saying whether the animation was performed or not.

## Type Aliases Can Clarify Function Types

To make function type specifiers clearer, we can take advantage of Swift's type alias feature to give a function type a name. The name can be descriptive, and the possibly confusing arrow operator notation is avoided:

```
typealias VoidVoidFunction = () -> ()
func dothis(_ f:VoidVoidFunction) {
    f()
}
```



The Cocoa documentation will often describe a function to be passed in this way as a *handler*, and will refer to it as a *block*, because that's the Objective-C syntactic construct needed here. In Swift, it's a function.

## Anonymous Functions

Consider once again this example:

```
func whatToAnimate() { // self.myButton is a button in the interface
    self.myButton.frame.origin.y += 20
}
func whatToDoLater(finished:Bool) {
    print("finished: \(finished)")
}
UIView.animate(withDuration:0.4,
    animations: whatToAnimate, completion: whatToDoLater)
```

There's a slight bit of ugliness in that code. I'm declaring functions `whatToAnimate` and `whatToDoLater`, just because I want to pass those functions in the last line. But I don't really need the *names* `whatToAnimate` and `whatToDoLater` for anything, except to refer to them in the last line; neither the names nor the functions will ever be used again. In my call to `UIView.animate(withDuration:animations:completion:)`, it would be nice to be able to pass just the *body* of those functions *without* a declared name.

We can do that. A nameless function body is called an *anonymous* function, and is legal and common in Swift. To form an anonymous function, you do two things:

1. Create the function body itself, including the surrounding curly braces, but with no function declaration.
2. If necessary, express the function's parameter list and return type as the first thing *inside* the curly braces, followed by the keyword `in`.

Let's practice by transforming our named function declarations into anonymous functions. Here's the named function declaration for `whatToAnimate`:

```
func whatToAnimate() {
    self.myButton.frame.origin.y += 20
}
```

Here's an anonymous function that does the same thing. Notice how I've moved the parameter list and return type inside the curly braces:

```
{
    () -> () in
    self.myButton.frame.origin.y += 20
}
```

Here's the named function declaration for `whatToDoLater`:

```
func whatToDoLater(finished:Bool) {
    print("finished: \(finished)")
}
```

Here's an anonymous function that does the same thing:

```
{
    (finished:Bool) -> () in
    print("finished: \(finished)")
}
```

## Using Anonymous Functions Inline

Now that we know how to make anonymous functions, let's use them. The point where we need the functions is the point where we're passing the second and third arguments to `animate(withDuration:animations:completion:)`. We can create and pass anonymous functions *right at that point*, like this:

```
UIView.animate(withDuration:0.4,
    animations: {
        () -> () in
        self.myButton.frame.origin.y += 20
    },
    completion: {
        (finished:Bool) -> () in
        print("finished: \(finished)")
    }
)
```

We can make the same improvement in the way we call the `imageOfSize` function from the preceding section. Earlier, we called that function like this:

```
func drawing() {
    let p = UIBezierPath(
        roundedRect: CGRect(x:0, y:0, width:45, height:20),
        cornerRadius: 8)
    p.stroke()
}
let image = imageOfSize(CGSize(width:45, height:20), drawing)
```

We now know, however, that we don't need to declare the drawing function separately. We can call `imageOfSize` with an anonymous function:

```
let image = imageOfSize(CGSize(width:45, height:20), {
    () -> () in
    let p = UIBezierPath(
        roundedRect: CGRect(x:0, y:0, width:45, height:20),
        cornerRadius: 8)
    p.stroke()
})
```

Anonymous functions are very commonly used in Swift, so make sure you can read and write that code!

## Anonymous Function Abbreviated Syntax

Anonymous functions are so common and so important in Swift that some shortcuts for writing them are provided:

### *Omission of the return type*

If the anonymous function's return type is already known to the compiler, you can omit the arrow operator and the specification of the return type:

```
UIView.animate(withDuration:0.4,
    animations: {
        () in // *
        self.myButton.frame.origin.y += 20
    }, completion: {
        (finished:Bool) in // *
        print("finished: \(finished)")
    })
```

(Occasionally the compiler will fail to infer the anonymous function's return type, even though you think it should be obvious, and will give a compile error. If that happens, just don't use this shortcut: supply an `in` expression with an explicit return type.)

### *Omission of the in expression when there are no parameters*

If the anonymous function takes no parameters, and if the return type can be omitted, the `in` expression itself can be omitted:

```
UIView.animate(withDuration:0.4,
    animations: { // *
        self.myButton.frame.origin.y += 20
    }, completion: {
        (finished:Bool) in
        print("finished: \(finished)")
    })
```

### *Omission of the parameter types*

If the anonymous function takes parameters and their types are already known to the compiler, the types can be omitted:

```
UIView.animate(withDuration:0.4,
  animations: {
    self.myButton.frame.origin.y += 20
  }, completion: {
    (finished) in // *
    print("finished: \(finished)")
  })
```

### *Omission of the parentheses*

If the parameter types are omitted, the parentheses around the parameter list can be omitted:

```
UIView.animate(withDuration:0.4,
  animations: {
    self.myButton.frame.origin.y += 20
  }, completion: {
    finished in // *
    print("finished: \(finished)")
  })
```

### *Omission of the in expression even when there are parameters*

If the return type can be omitted, and if the parameter types are already known to the compiler, you can omit the `in` expression and refer to the parameters directly within the body of the anonymous function by using the magic names `$0`, `$1`, and so on, in order:

```
UIView.animate(withDuration:0.4,
  animations: {
    self.myButton.frame.origin.y += 20
  }, completion: {
    print("finished: \( $0)") // *
  })
```

### *Omission of the parameter names*

If the anonymous function body doesn't need to refer to a parameter, you can substitute an underscore for its name in the parameter list in the `in` expression:

```
UIView.animate(withDuration:0.4,
  animations: {
    self.myButton.frame.origin.y += 20
  }, completion: {
    _ in // *
    print("finished!")
  })
```



If an anonymous function takes parameters, you *must* acknowledge them somehow. You can omit the `in` expression and use the parameters by the magic names `$0` and so on. Or you can keep the `in` expression and give the parameters names or ignore them with underscores. But you can't omit the `in` expression and *not* use the parameters' magic names! If you do, your code won't compile.

#### *Omission of the function argument label*

If your anonymous function is the last argument being passed in this function call — which will just about always be the case — you can close the function call with a right parenthesis *before* this last argument, and then put just the anonymous function body *without a label*. This is called *trailing closure syntax* (I'll explain in a moment what a closure is):

```
UIView.animate(withDuration:0.4,
  animations: {
    self.myButton.frame.origin.y += 20
  }) { // *
    _ in
    print("finished!")
  }
```

In that code, the `completion:` parameter is last, so the call can pass the anonymous function argument outside the call's parentheses, using trailing closure syntax with no label.

But there's a curious asymmetry in that particular example, because this is a method that takes *two* function parameters. The `animations:` parameter is an anonymous function too, but it still sits inside the parentheses. A Swift 5.3 innovation resolved that asymmetry: now, *multiple* anonymous function arguments can be expressed using trailing closure syntax. When you do that, the *first* anonymous function takes no label; the remaining functions *do* each have their labels, with *no comma*:

```
UIView.animate(withDuration:0.4) { // *
  self.myButton3.frame.origin.y += 20
} completion: { // *
  _ in
  print("finished")
}
```

#### *Omission of the calling function parentheses*

If you use a trailing closure, and if the function you are calling takes no parameters other than the function you are passing to it, you can omit the empty parentheses from the call. This is the *only* situation in which you can omit the parentheses from a function call! To illustrate, I'll declare and call a different function:



```

func doThis(_ f:() -> ()) {
    f()
}
doThis { // no parentheses!
    print("Howdy")
}

```

### *Omission of the keyword return*

If the anonymous function body consists of exactly one statement consisting of returning a value with the keyword `return`, the keyword `return` can be omitted (and in this situation, I like to do so):

```

func greeting() -> String {
    return "Howdy"
}
func performAndPrint(_ f:()->String) {
    let s = f()
    print(s)
}
performAndPrint {
    greeting() // meaning: return greeting()
}

```

When writing anonymous functions, you will frequently find yourself taking advantage of all the omissions you are permitted. In addition, you'll sometimes shorten the *layout* of the code (though not the code itself) by putting the whole anonymous function together with the function call *on one line*. Thus, Swift code involving anonymous functions can be extremely compact.

Here's a typical example. We start with an array of `Int` values and generate a new array consisting of all those values multiplied by 2, by calling the `map(_:)` instance method. The `map(_:)` method of an array takes a function. That function takes one parameter of the same type as the array's elements and returns a new value; here, our array is made of `Int` values, and we are passing to the `map(_:)` method a function that takes one `Int` parameter and returns an `Int`. We could write out the whole function, like this:

```

let arr = [2, 4, 6, 8]
func doubleMe(i:Int) -> Int {
    return i*2
}
let arr2 = arr.map(doubleMe) // [4, 8, 12, 16]

```

That, however, is not very Swiftly. We don't need the name `doubleMe` for anything else, so this may as well be an anonymous function:

```
let arr = [2, 4, 6, 8]
let arr2 = arr.map ({
    (i:Int) -> Int in
    return i*2
})
```

Now let's abbreviate our anonymous function. Its parameter type is known in advance, so we don't need to specify that. Its return type is known by inspection of the function body, so we don't need to specify that. There's just one parameter and we are going to use it, so we don't need the `in` expression as long as we refer to the parameter as `$0`. Our function body consists of just one statement, and it is a return statement, so we can omit `return`. And `map(_:)` doesn't take any other parameters, so we can omit the parentheses and follow the name directly with a trailing closure:

```
let arr = [2, 4, 6, 8]
let arr2 = arr.map {$0*2}
```

It doesn't get any Swiftier than that!

## Define-and-Call

A pattern that's surprisingly common in Swift is to define an anonymous function and call it, all in one move:

```
{
    // ... code goes here
}()
```

Notice the parentheses after the curly braces! The curly braces *define* an anonymous function body; the parentheses *call* that anonymous function. I call this construct *define-and-call*.

Using define-and-call, an action can be taken at the point where it is needed, rather than in a series of preparatory steps. For instance, there's a common Cocoa situation where we create and configure an `NSMutableParagraphStyle` and then use it as an argument in a call to the `NSMutableAttributedString` method `addAttribute(_:value:range:)`, like this:

```
let para = NSMutableParagraphStyle()
para.headIndent = 10
para.firstLineHeadIndent = 10
// ... more configuration of para ...
content.addAttribute( // content is an NSMutableAttributedString
    .paragraphStyle,
    value:para,
    range:NSMakeRange(location:0, length:1))
```

I find that code ugly. We don't need `para` except to pass it as the `value:` argument within the call to `addAttribute(_:value:range:)`, so it would be much nicer to create and configure it right there within the call, as the `value:` argument itself. That

sounds like an anonymous function — except that the `value:` parameter is not a function, but an `NSMutableParagraphStyle` object.

We can solve the problem by providing, as the `value:` argument, an anonymous function that *produces* an `NSMutableParagraphStyle` object and calling it so that it *does* produce an `NSMutableParagraphStyle` object:

```
content.addAttribute(
    .paragraphStyle,
    value: {
        let para = NSMutableParagraphStyle()
        para.headIndent = 10
        para.firstLineHeadIndent = 10
        // ... more configuration of para ...
        return para
    }(),
    range:NSMakeRange(location:0, length:1))
```

I'll demonstrate some further uses of define-and-call in [Chapter 3](#).

## Closures

Swift functions are *closures*. This means they can *capture* references to external variables in scope within the body of the function. What do I mean by that? Well, recall from [Chapter 1](#) that code in curly braces constitutes a scope, and this code can “see” variables and functions declared in a surrounding scope. For example:

```
class Dog {
    var whatThisDogSays = "woof" ❶
    func bark() {
        print(self.whatThisDogSays) ❷
    }
}
```

In that code:

- ❶ The variable `whatThisDogSays` is *external* to the function: it is *declared outside* the body of the function, and yet is *in scope* for the body of the function, so that the code inside the body of the function can see it.
- ❷ The code inside the body of the function *refers* to the external variable `whatThisDogSays` — it says, explicitly, `whatThisDogSays`.

So far, so good; but we now know that the function `bark` can be passed as a value. In effect, it can travel from one environment to another. When it does, what happens to that reference to `whatThisDogSays`? Let's find out:

```

func doThis(_ f : () -> ()) {
    f()
}
let d = Dog()
d.whatThisDogSays = "arf"
let barkFunction = d.bark
doThis(barkFunction) // arf

```

We run that code, and "arf" appears in the console!

Perhaps that result doesn't seem very surprising to you. But think about it. We do not directly *call* `d.bark()`. We make a `Dog` instance and *pass* its bark function as a value into the function `doThis`. There, it is called. Now, `whatThisDogSays` is an instance property of a particular `Dog`. Inside the function `doThis` there is no `whatThisDogSays`. Indeed, inside the function `doThis` there is no `Dog` instance! Nevertheless the call `f()` still works. The function `d.bark`, as it is passed around, evidently *carries* the variable `whatThisDogSays` along with itself.

But there's more. I'll change the example by moving the line where we set `d.whatThisDogSays` to *after* we assign `d.bark` into our variable `barkFunction`:

```

func doThis(_ f : () -> ()) {
    f()
}
let d = Dog()
let barkFunction = d.bark      ❶
doThis(barkFunction) // woof  ❷
d.whatThisDogSays = "arf"     ❸
doThis(barkFunction) // arf   ❹

```

What just happened?

- ❶ We assigned `d.bark` to `barkFunction`, once and for all; after that, we never changed `barkFunction`.
- ❷ At that time, `d.whatThisDogSays` was "woof", so we passed `barkFunction` into `doThis` and got "woof".
- ❸ We then changed `d.whatThisDogSays` to "arf". We didn't change `barkFunction`.
- ❹ We passed `barkFunction` into `doThis` again, and this time we got "arf"!

After creating both `d` and `barkFunction`, changing a property of the `Dog` `d` changes the output of calling `barkFunction`! How can this be? Evidently, after step 1, when `d.bark` has been assigned to `barkFunction`, *both* our `Dog` variable `d` *and* the function `barkFunction` are holding references to the same `Dog` instance. This is because `d.bark`, which we assigned to `barkFunction`, refers to `self`, which *is* the `Dog`

instance. That's what we mean when we say that a function is a closure and that it *captures* external variables referred to in its body.

## How Closures Improve Code

You can use the fact that functions are closures to make your code more general, and hence more useful. To illustrate, here, once again, is my earlier example of a function that accepts drawing instructions and performs them to generate an image:

```
func imageOfSize(_ size:CGSize, _ whatToDraw:() -> ()) -> UIImage {
    UIGraphicsBeginImageContextWithOptions(size, false, 0)
    whatToDraw()
    let result = UIGraphicsGetImageFromCurrentImageContext()!
    UIGraphicsEndImageContext()
    return result
}
```

As you know, we can call `imageOfSize` with a trailing closure:

```
let image = imageOfSize(CGSize(width:45, height:20)) {
    let p = UIBezierPath(
        roundedRect: CGRect(x:0, y:0, width:45, height:20),
        cornerRadius: 8)
    p.stroke()
}
```

That code, however, contains an annoying repetition. This is a call to create an image of a given size consisting of a rounded rectangle of that size. We are repeating the size; the pair of numbers `45,20` appears twice. That's silly. Let's prevent the repetition by putting the size into a variable at the outset:

```
let sz = CGSize(width:45, height:20)
let image = imageOfSize(sz) {
    let p = UIBezierPath(
        roundedRect: CGRect(origin:CGPoint.zero, size:sz),
        cornerRadius: 8)
    p.stroke()
}
```

The variable `sz`, declared outside our anonymous function at a higher level, is visible inside it. Thus we can refer to it inside the anonymous function — and we do so. The anonymous function is just a function body; it won't be *executed* until `imageOfSize` calls it. Nevertheless, when we refer to `sz` from inside the function body in the expression `CGRect(origin:CGPoint.zero, size:sz)`, we capture its value *now*, because the function body is a closure. When `imageOfSize` calls `whatToDraw`, and `whatToDraw` turns out to be a function whose body refers to a variable `sz`, there's no problem, even though there is no `sz` anywhere in the neighborhood of `imageOfSize`.

Now let's go further. So far, we've been hard-coding the size of the desired rounded rectangle. Imagine, though, that creating images of rounded rectangles of various

sizes is something we do often. It would make sense to package this code up as a function, where `sz` is not a fixed value but a parameter; the function will then return the image:

```
func makeRoundedRectangle(_ sz:CGSize) -> UIImage {
    let image = imageOfSize(sz) {
        let p = UIBezierPath(
            roundedRect: CGRect(origin:CGPoint.zero, size:sz),
            cornerRadius: 8)
        p.stroke()
    }
    return image
}
```

Incredibly, that works! The parameter `sz` that arrives into `makeRoundedRectangle` is no longer a hard-coded value; we don't know what it will be. Nevertheless, when `makeRoundedRectangle` is called, `sz` *will* have a value, and the anonymous function captures `sz`, so when `imageOfSize` calls the anonymous function, `sz` inside that function will have the `sz` value that was passed to `makeRoundedRectangle`.

Our code is becoming beautifully compact. To call `makeRoundedRectangle`, supply a size; an image is returned. I can perform the call, obtain the image, and display that image, all in one move, like this (`self.iv` is a `UIImageView` in the interface):

```
self.iv.image = makeRoundedRectangle(CGSize(width:45, height:20))
```

## Function Returning Function

But now let's go even further! Instead of returning an image, our function can return *a function* that makes rounded rectangles *of the specified size*. If you've never seen a function returned as a value from a function, you may now be gasping for breath. But a function, after all, can be used as a value. We have already passed a function *into* a function as an argument in the function call; now we are going to receive a function *from* a function call as its result:

```
func makeRoundedRectangleMaker(_ sz:CGSize) -> () -> UIImage { ❶
    func f () -> UIImage { ❷
        let im = imageOfSize(sz) {
            let p = UIBezierPath(
                roundedRect: CGRect(origin:CGPoint.zero, size:sz),
                cornerRadius: 8)
            p.stroke()
        }
        return im
    }
    return f ❸
}
```

Let's analyze that code slowly:

- ❶ The declaration is the hardest part. What on earth is the type (signature) of this function `makeRoundedRectangleMaker`? It is `(CGSize) -> () -> UIImage`. That expression has *two* arrow operators. To understand it, keep in mind that everything after each arrow operator is the type of a returned value. So `makeRoundedRectangleMaker` is a function that takes a `CGSize` parameter and returns a `() -> UIImage`. Okay, and what's a `() -> UIImage`? We already know that: it's a function that takes no parameters and returns a `UIImage`. So `makeRoundedRectangleMaker` is a function that takes a `CGSize` parameter and returns a *function* — a function that itself, when called with *no* parameters, will return a `UIImage`.
- ❷ Now here we are in the body of the function `makeRoundedRectangleMaker`, and our first step is to declare a function (a function-in-function, or local function) of precisely the type we intend to return, namely, one that takes no parameters and returns a `UIImage`. Here, we're naming this function `f`. The way this function works is simple and familiar: it calls `imageOfSize`, passing it an anonymous function that makes an image of a rounded rectangle (`im`) — and then it returns the image.
- ❸ Finally, we *return* the function we just made (`f`). We have fulfilled our contract: we said we would return a function that takes no parameters and returns a `UIImage`, and we do so.

But perhaps you are still gazing open-mouthed at `makeRoundedRectangleMaker`, wondering how you would ever call it and what you would get if you did. Let's try it:

```
let maker = makeRoundedRectangleMaker(CGSize(width:45, height:20))
```

What is the variable `maker` after that code runs? It's a *function* — a function that takes no parameters and that, when called, produces the image of a rounded rectangle of size 45,20. You don't believe me? I'll prove it — by *calling* the function that is now the value of `maker`:

```
let maker = makeRoundedRectangleMaker(CGSize(width:45, height:20))
self.iv.image = maker()
```

Now that you've gotten over your stunned surprise at the notion of a function that produces a function as its result, turn your attention once again to the implementation of `makeRoundedRectangleMaker` and let's analyze it again, a different way. Remember, I didn't write that function to show you that a function can produce a function. I wrote it to illustrate closures! Let's think about how the environment gets captured:

```

func makeRoundedRectangleMaker(_ sz:CGSize) -> () -> UIImage {
    func f () -> UIImage {
        let im = imageOfSize(sz) { // *
            let p = UIBezierPath(
                roundedRect: CGRect(origin:CGPoint.zero, size:sz), // *
                cornerRadius: 8)
            p.stroke()
        }
        return im
    }
    return f
}

```

The function `f` takes no parameters. Yet, twice within the function body of `f` (I've marked the places with asterisk comments), there are references to a size value `sz`. The body of the function `f` can see `sz`, the parameter of the surrounding function `makeRoundedRectangleMaker`, because it is in a surrounding scope. The function `f` *captures* the reference to `sz` at the time `makeRoundedRectangleMaker` is called, and *keeps* that reference when `f` is returned and assigned to `maker`:

```
let maker = makeRoundedRectangleMaker(CGSize(width:45, height:20))
```

That is why `maker` is now a function that, when it is called, creates and returns an image of the particular size 45,20 even though it itself will be called *with no parameters*. The knowledge of what size of image to produce has been *baked into* the function referred to by `maker`. Looking at it another way, `makeRoundedRectangleMaker` is a *factory* for creating a whole family of functions similar to `maker`, each of which produces an image of one particular size. That's a dramatic illustration of the power of closures.

Before I leave `makeRoundedRectangleMaker`, I'd like to rewrite it in a Swiftier fashion. Within `f`, there is no need to create `im` and then return it; we can return the result of calling `imageOfSize` directly:

```

func makeRoundedRectangleMaker(_ sz:CGSize) -> () -> UIImage {
    func f () -> UIImage {
        return imageOfSize(sz) {
            let p = UIBezierPath(
                roundedRect: CGRect(origin:CGPoint.zero, size:sz),
                cornerRadius: 8)
            p.stroke()
        }
    }
    return f
}

```

But there is no need to declare `f` and then return it either; it can be an anonymous function and we can return it directly:



```
func makeRoundedRectangleMaker(_ sz:CGSize) -> () -> UIImage {
    return {
        return imageOfSize(sz) {
            let p = UIBezierPath(
                roundedRect: CGRect(origin:CGPoint.zero, size:sz),
                cornerRadius: 8)
            p.stroke()
        }
    }
}
```

But our anonymous function consists of nothing but a return statement; the anonymous function parameter to `imageOfSize` consists of multiple statements, but the `imageOfSize` call itself is still just one Swift statement. We can omit the keyword `return` (and we could omit the remaining `return` too, but I prefer not to):

```
func makeRoundedRectangleMaker(_ sz:CGSize) -> () -> UIImage {
    return {
        imageOfSize(sz) {
            let p = UIBezierPath(
                roundedRect: CGRect(origin:CGPoint.zero, size:sz),
                cornerRadius: 8)
            p.stroke()
        }
    }
}
```

## Closure Setting a Captured Variable

The power that a closure gets through its ability to capture its environment is even greater than I've shown so far. If a closure captures a reference to a variable outside itself, and if that variable is settable, then *the closure can set the variable*.

Let's say I've declared this simple function. All it does is to accept a function that takes an `Int` parameter, and to call that function with an argument of 100:

```
func pass100 (_ f:(Int) -> ()) {
    f(100)
}
```

Now, look closely at this code and try to guess what will happen when we run it:

```
var x = 0
print(x) // ?
func setX(newX:Int) {
    x = newX
}
pass100(setX)
print(x) // ?
```

The first `print(x)` call obviously produces 0. The second `print(x)` call produces 100! The `pass100` function has reached into my code and *changed* the value of my variable

x. That's because the function `setX` that I passed to `pass100` contains a reference to `x`; not only does it contain it, but it captures it; not only does it capture it, but it sets its value. That `x` is my `x`. The `pass100` function was able to set my `x` just as readily as I would have set it by calling `setX` directly.

## Closure Preserving Captured Environment

When a closure captures its environment, it *preserves* that environment *even if nothing else does*. Here's an example calculated to blow your mind — a function that modifies a function:

```
func countAdder(_ f: @escaping () -> ()) -> () -> () {
    var ct = 0
    return {
        ct = ct + 1
        print("count is \(ct)")
        f()
    }
}
```

The function `countAdder` accepts a function as its parameter and returns a function as its result. (I'll explain the `@escaping` attribute in the next section.) The function that it returns calls the function that it accepts, with a little bit added: it increments a variable and reports the result. So now try to guess what will happen when we run this code:

```
func greet () {
    print("howdy")
}
let countedGreet = countAdder(greet)
countedGreet() // ?
countedGreet() // ?
countedGreet() // ?
```

What we've done here is to take a function `greet`, which prints "howdy", and pass it through `countAdder`. What comes out the other side of `countAdder` is a new function, which we've named `countedGreet`. We then call `countedGreet` three times. Here's what appears in the console:

```
count is 1
howdy
count is 2
howdy
count is 3
howdy
```

Clearly, `countAdder` has added to the functionality of the function that was passed into it *the ability to report how many times it is called*. Now ask yourself: Where on earth is the variable that maintains this count? Inside `countAdder`, it was a local

variable `ct`. But it isn't declared inside the anonymous function that `countAdder` returns. That's deliberate! If it *were* declared inside the anonymous function, we would be setting `ct` to 0 every time `countedGreet` is called — we wouldn't be counting. Instead, `ct` is initialized to 0 once *and then captured* by the anonymous function. This variable is preserved as part of the *environment* of `countedGreet` — it is *outside* `countedGreet` in some mysterious environment-preserving world, so that it can be incremented every time `countedGreet` is called.

## Escaping Closures

If a function passed around as a value will be preserved for later execution, rather than being called directly, it is a closure that captures and preserves its environment *over time*. That's called an *escaping* closure. In some situations, the function's type must be explicitly marked `@escaping`. The compiler will detect violations of this rule, so if you find the rule confusing, don't worry about it; just let the compiler enforce it for you.

This function is legal because it receives a function and calls it directly:

```
func funcCaller(f:() -> ()) {  
    f()  
}
```

And this function is legal, even though it returns a function to be executed later, because it also *creates* that function internally. The function that it returns *is* an escaping closure, but the type of the function's returned value does not have to be marked as `@escaping`:

```
func funcMaker() -> () -> () {  
    return { print("hello world") }  
}
```

But this function is illegal. It receives a function as a parameter *and* returns that function to be executed later:

```
func funcPasser(f:() -> ()) -> () -> () { // compile error  
    return f  
}
```

The solution is to mark the type of the incoming parameter `f` as `@escaping`, and the compiler will prompt you to do so:

```
func funcPasser(f:@escaping () -> ()) -> () -> () {  
    return f  
}
```

A secondary feature of escaping closures is that, when you refer to a property or method of `self` within the function body, the compiler may insist that you say `self`

explicitly. That’s because such a reference *captures* `self`, and the compiler wants you to acknowledge this fact by *saying* `self`:

```
let f1 = funcPasser {
    print(view.bounds) // compile error, because self.view is implied
}
let f2 = funcPasser {
    print(self.view.bounds) // ok
}
```

I’ll say more about *why* you must acknowledge a captured `self` when I talk about memory management in [Chapter 5](#).

## Capture Lists

Sometimes, you might want a function to refer to a variable outside itself, just in order to get its value, but *without* capturing the variable. Swift provides an ingenious syntax for doing that — but only when the function is an anonymous function. At the start of the anonymous function body, you put square brackets containing a comma-separated list of references to variables in the surrounding environment. This is called a *capture list*.

If you have a capture list, you must follow it with the keyword `in` if there’s no `in` expression already. If there *is* an `in` expression already, the capture list precedes any parameter names.

The result is as if the value had been passed into the anonymous function *as a parameter* rather than by closure capture; like a parameter, it behaves as if it had been declared with `let` (“[Modifiable Parameters](#)” on page 36).

To illustrate, let’s start with a simple example that captures a reference in the usual way. Remember, I’m going to need an anonymous function here, so I’ll declare a variable and assign the anonymous function to it. Test yourself by guessing what the output is:

```
var x = 0
let f : () -> () = {
    print(x)
}
f() // ?
x = 1
f() // ?
```

The first call to `f()` prints 0. The second call to `f()` prints 1. That’s similar to the very first closure example I gave earlier. The variable `x` is declared outside the function `f`. The function `f` captures the variable `x` and prints it out. If we *change* the value of `x` and call `f`, it prints out the *new* value of `x`.

Now let’s see what happens if we include `x` in a capture list:

```

var x = 0
let f : () -> () = { [x] in // *
    print(x)
}
f()
x = 1
f()

```

This time, the call to `f()` prints out 0 — *both times*. We changed `x` to 1, but `f` doesn't care. Because of the capture list, `f` had already captured the *value* of `x` as 0 at the time it was declared. In effect, `x` behaves like an ordinary parameter passed into `f`; it's a constant. Another way to see this is that if `f` tries to set the value of `x`, the compiler will complain: "Cannot assign to value: `x` is an immutable capture."

It is also legal to assign a capture list expression to another name. For example, a capture list can say `[y=x]`; that's as if you were passing `x` into the anonymous function as a parameter, but now the parameter is called `y`. This is useful when there is something unfortunate about the original name, or when the value to be passed in is an expression that needs to be evaluated at the time of assignment. Here's an example from my own code (without explanation of the context):

```

self.undoer.registerUndo(withTarget: self) {
    [oldCenter = self.center] myself in
    myself.setCenterUndoably(oldCenter)
}

```

The anonymous function passed as a parameter to `registerUndo` is an escaping function. My capture list declares a constant `oldCenter` and sets its value to `self.center`. As a result, the value of `self.center` is evaluated *now*, when `registerUndo` is called, rather than later, when the anonymous function itself is called (at which time the value of `self.center` may have changed).

Another use of capture lists is to work around the requirement to say `self` explicitly in an escaping closure. Recall this example from the preceding section:

```

let f2 = funcPasser {
    print(self.view.bounds)
}

```

We are forced to say `self` explicitly because this is an escaping closure. But many people don't like saying `self` explicitly; and if this anonymous function implies `self` many times, it may be necessary to say `self` explicitly many times. Starting in Swift 5.3, there's a stylistic alternative: if you put `self` in the capture list, that satisfies the compiler, and you don't have to write `self` as the implicit target in the function body:

```

let f2 = funcPasser { [self] in
    print(view.bounds) // ok
}

```

# Curried Functions

Return once more to `makeRoundedRectangleMaker`:

```
func makeRoundedRectangleMaker(_ sz:CGSize) -> () -> UIImage {
    return {
        imageOfSize(sz) {
            let p = UIBezierPath(
                roundedRect: CGRect(origin:CGPoint.zero, size:sz),
                cornerRadius: 8)
            p.stroke()
        }
    }
}
```

There's something I still don't like about this method: the size of the rounded rectangle that it creates is a parameter (`sz`), but the `cornerRadius` of the rounded rectangle is hard-coded as 8. I'd like the ability to pass a value for the corner radius as part of the call. I can think of two ways to do that. One is to give `makeRoundedRectangleMaker` itself another parameter:

```
func makeRoundedRectangleMaker(_ sz:CGSize, _ r:CGFloat) -> () -> UIImage {
    return {
        imageOfSize(sz) {
            let p = UIBezierPath(
                roundedRect: CGRect(origin:CGPoint.zero, size:sz),
                cornerRadius: r)
            p.stroke()
        }
    }
}
```

And we would then call it like this:

```
let maker = makeRoundedRectangleMaker(CGSize(width:45, height:20), 8)
```

But there's another way. The function that we are returning from `makeRoundedRectangleMaker` takes no parameters. Instead, *it* could take the extra parameter:

```
func makeRoundedRectangleMaker(_ sz:CGSize) -> (CGFloat) -> UIImage {
    return { r in
        imageOfSize(sz) {
            let p = UIBezierPath(
                roundedRect: CGRect(origin:CGPoint.zero, size:sz),
                cornerRadius: r)
            p.stroke()
        }
    }
}
```

Now `makeRoundedRectangleMaker` returns a function that, itself, takes one parameter, so we must remember to supply that when we call it:

```
let maker = makeRoundedRectangleMaker(CGSize(width:45, height:20))
self.iv.image = maker(8)
```

If we don't need to conserve `maker` for anything, we can of course do all that in one line — a function call that yields a function which we immediately call to obtain our image:

```
self.iv.image = makeRoundedRectangleMaker(CGSize(width:45, height:20))(8)
```

When a function returns a function that takes a parameter in this way, it is called a *curried* function (after the computer scientist Haskell Curry).

## Function References and Selectors

When you want to refer to a function by name — perhaps in order to pass it as argument to another function — you can often use its bare name. That's what I've been doing throughout this chapter, in examples like this:

```
func whatToAnimate() { // self.myButton is a button in the interface
    self.myButton.frame.origin.y += 20
}
func whatToDoLater(finished:Bool) {
    print("finished: \(finished)")
}
UIView.animate(withDuration:0.4,
    animations: whatToAnimate, completion: whatToDoLater) // *
```

A bare name like `whatToAnimate` or `whatToDoLater` is a *function reference*. It consists of the base name alone, the part of the function's name that precedes the parentheses. The lack of parentheses makes it clear that this is a reference, not a call. Use of the bare name as a function reference is legal when it's unambiguous: in this particular context, there's only one function called `whatToDoLater` in scope, and I'm using its name as argument in a function call where the parameter type is known (namely, `(Bool) -> ()`).

But now consider the following situation. Just as I can pass a function as an argument, I can assign a function as a value to a variable. And suppose I have *two* functions with the same name, one that takes a parameter, and one that doesn't:

```
class Dog {
    func bark() {
        print("woof")
    }
    func bark(_ loudly:Bool) {
        if loudly {
            print("WOOF")
        } else {
            self.bark()
        }
    }
}
```

```

func test() {
    let barkFunction = bark // compile error
    // ...
}

```

That code won't compile, because the bare name `bark` is ambiguous in this context: which `bark` method does it refer to? To solve this problem, Swift provides a notation allowing you to refer to a function more precisely. This notation has two parts:

#### *Full name*

The full name of a Swift function is the base name along with parentheses containing the external names of its parameters, each followed by colon (and no commas or spaces). If the external name of a parameter is suppressed, we represent its external name as an underscore.

#### *Signature*

The signature of a Swift function may be appended to its bare name (or full name) with the keyword `as`.

So, for example:

```

func say(_ s:String, times:Int) {

```

That method has full name `say(_:times:)` but may be referred to using a bare name and signature as `say as (String, Int) -> ()`.

In our `bark` example, use of the full name solves the problem if the function to which we want a reference is the one that takes a parameter:

```

class Dog {
    func bark() {
        // ... as before ...
    }
    func bark(_ loudly:Bool) {
        // ... as before ...
    }
    func test() {
        let barkFunction = bark(_) // fine
    }
}

```

But use of the full name *doesn't* solve the problem if the function to which we want a reference is the one that takes *no* parameters, because in that case the full name is the bare name, which is exactly what's ambiguous in this context. Use of the signature solves the problem:

```

class Dog {
    func bark() {
        // ... as before ...
    }
}

```



```

func bark(_ loudly:Bool) {
    // ... as before ...
}
func test() {
    let barkFunction = bark as () -> () // fine
}
}

```

Obviously, an explicit signature is needed also when a function is *overloaded*:

```

class Dog {
    func bark() {
    }
    func bark(_ loudly:Bool) {
    }
    func bark(_ times:Int) {
    }
    func test() {
        let barkFunction = bark(_) // compile error
    }
}

```

Here, we have said that we want the bark that takes one parameter, but there are *two* such bark functions, one whose parameter is a Bool, the other whose parameter is an Int. The signature disambiguates (and we can use the bare name):

```

let barkFunction = bark as (Int) -> () // "times", not "loudly"

```

Here's an overloaded method where one overload has a default parameter:

```

class Dog {
    func bark(loudly:Bool = false) {
    }
    func bark(softly:Bool) {
    }
    func test() {
        self.bark() // fine
        let barkFunction = bark // compile error
    }
}

```

A *call* to `self.bark()` is resolved to the bark method with a default parameter, but a function *reference* `bark` is rejected as ambiguous; if the function reference means `bark(loudly:)`, it must say so.

## Function Reference Scope

In the foregoing examples of function references, there was no need to tell the compiler *where* the function is defined. That's because the function is already in scope at the point where the function reference appears. If you can *call* the function without supplying further information, you can form the function *reference* without supplying further information.

However, a function reference *can* supply further information about where a function is defined; and sometimes it *must* do so. This is done by prefixing an instance or class to the function reference, using dot-notation. There are situations where the compiler would force you to use `self` to call a function; in those situations, you will have to use `self` to refer to the function as well:

```
class Dog {
    func bark() {
    }
    func bark(_ loudly:Bool) {
    }
    func test() {
        let f = {
            return self.bark(_) // self required here
        }
    }
}
```

To form a function reference to an instance method of another type, you have two choices. If you have on hand an instance of that type, you can use dot-notation with a reference to that instance:

```
class Cat {
    func purr() {
    }
}
class Dog {
    let cat = Cat()
    func test() {
        let purrFunction = cat.purr
    }
}
```

The other possibility is to use *the type* with dot-notation (this works even if the function is an instance method):

```
class Cat {
    func purr() {
    }
}
class Dog {
    func bark() {
    }
    func test() {
        let barkFunction = Dog.bark // legal but not necessary
        let purrFunction = Cat.purr
    }
}
```

If you use the type with dot-notation and you need to disambiguate the function reference by giving its signature, the signature must describe the curried static/class version of the instance method (see [“The Secret Life of Instance Methods” on page 138](#)):

```

class Cat {
    func purr() {
    }
    func purr(_ loudly:Bool) {
    }
}
class Dog {
    func test() {
        let purrFunction = Cat.purr as (Cat) -> () -> Void
    }
}

```

## Selectors

In Objective-C, a selector is a kind of method reference. In iOS programming, you might have to call a Cocoa method that wants a selector as one of its parameters; typically, this parameter will be named either `selector:` or `action:`. Usually, such a method also requires that you provide a *target* (an object reference); the idea is that the runtime can later call the method by turning the selector into a message and sending that message to that target.

Unfortunately, this architecture can be extremely risky. The reason is that to form the selector, it is necessary to construct a string representing a method's Objective-C name. If you construct that string incorrectly, then when the time comes to send the message to the target, the runtime will find that the target can't handle that message, because it has no such method, and the app comes to a violent and premature halt, dumping into the console the dreaded phrase "unrecognized selector." Here's a typical recipe for failure:

```

class ViewController : UIViewController {
    @IBOutlet var button : UIButton!
    func viewDidLoad() {
        super.viewDidLoad()
        self.button.addTarget( // prepare to crash!
            self, action: "buttonPressed", for: .touchUpInside)
    }
    @objc func buttonPressed(_ sender: Any) {
        // ...
    }
}

```

In that code, `self.button` is a button in the interface, and we are configuring it by calling `addTarget(_:action:for:)`, so that when the button is tapped, our `buttonPressed` method will be called. But we are configuring it incorrectly! Unfortunately, "buttonPressed" is *not* the Objective-C name of our `buttonPressed` method; the correct name would have been "buttonPressed:", with a colon. (I'll explain why in the [Appendix](#).) Therefore, our app will crash when the user taps that button.

The point is that if you don't know the rules for forming a selector string — or even if you do, but you make a typing mistake — an “unrecognized selector” crash is likely to result. Humans are fallible, and therefore “unrecognized selector” crashes have historically been extremely common among iOS programmers. The Swift compiler, however, is *not* fallible in this way. Therefore, Swift provides a way to let the compiler form the selector for you, by means of `#selector` syntax.

To ask the compiler to form an Objective-C selector for you, you use `#selector(...)` with a function reference inside the parentheses. We would rewrite our button action example like this:

```
class ViewController : UIViewController {
    @IBOutlet var button : UIButton!
    func viewDidLoad() {
        super.viewDidLoad()
        self.button.addTarget(
            self, action: #selector(buttonPressed), for: .touchUpInside)
    }
    @objc func buttonPressed(_ sender: Any) {
        // ...
    }
}
```

When you use that notation, two wonderful things happen:

#### *The compiler validates the function reference*

If your function reference isn't valid, your code won't even compile. The compiler also checks that this function is exposed to Objective-C; there's no point forming a selector for a method that Objective-C can't see, as your app would crash if Objective-C were to try to call such a method. To ensure Objective-C visibility, the method may need to be marked with the `@objc` attribute; the compiler will enforce this requirement.

#### *The compiler forms the Objective-C selector for you*

If your code compiles, the actual selector that will be passed into this parameter is guaranteed to be correct. *You* might form the selector incorrectly, but the compiler won't! It is impossible that the resulting selector should fail to match the method, and there is no chance of an “unrecognized selector” crash.

Very rarely, you still might need to create a selector manually. To do so, you can use a string, or you can instantiate `Selector` with the string as argument — for example, `Selector("woohoo:")`.



You can still crash, even with `#selector` syntax, by sending an action message to the *wrong target*. In the preceding example, if you changed `self`, the first argument of the `addTarget` call, to `self.button`, you'd crash at runtime with “unrecognized selector” — because the `buttonPressed` method is declared in `ViewController`, not in `UIButton`. Unfortunately, the compiler won't help you with this kind of mistake.



---

# Variables and Simple Types

A variable is a named “shoebox” whose contained value must be of a single well-defined type. Every variable must be explicitly and formally declared. To put a value into the shoebox, causing the variable name to *refer* to that value, you *assign* the value to the variable. The variable name becomes a *reference* to that value.

This chapter goes into detail about declaration and initialization of variables. It then discusses all the primary built-in Swift simple types. (I mean “simple” as opposed to collections; the primary built-in collection types are discussed at the end of [Chapter 4](#).)

## Variable Scope and Lifetime

A variable not only gives its referent a name; it also, by virtue of *where* it is declared, endows its referent with a particular scope (visibility) and lifetime. (See [“Scope and Lifetime” on page 12](#).) Assigning a value to a variable is a way of ensuring that this value can be *seen* by code that needs to see it and that it *persists* long enough to serve its purpose. There are three distinct levels of variable scope and lifetime:

### *Global variables*

A global variable, or simply a *global*, is a variable declared at the top level of a Swift file. A global variable lives as long as the file lives, which is as long as the program runs. A global variable is visible everywhere (that’s what “global” means). It is visible to all code within the *same* file, because it is at top level; any other code in the same file is therefore at the same level or at a lower contained level of scope. Moreover, it is visible (by default) to all code within any *other* file in the same module, because Swift files in the same module can automatically see one another, and hence can see one another’s top levels:

```
// File1:
let globalVariable = "global"
class Dog {
    func printGlobal() {
        print(globalVariable) // *
    }
}
// File2:
class Cat {
    func printGlobal() {
        print(globalVariable) // *
    }
}
```

## Properties

A *property* is a variable declared at the top level of an object type declaration (an enum, struct, or class). There are two kinds of properties: instance properties and static/class properties.

### Instance properties

By default, a property is an *instance* property. Its value can differ for each instance of this object type, as I explained in [Chapter 1](#). Its lifetime is the same as the lifetime of the instance. An instance comes into existence through deliberate instantiation of an object type; the subsequent lifetime of the instance, and hence of its instance properties, depends primarily on the lifetime of the variable to which the instance *itself* is assigned.

### Static/class properties

A property is a static/class property if its declaration is preceded by the keyword `static` or `class`. (I'll go into detail about those terms in [Chapter 4](#).) Its lifetime is the same as the lifetime of the object type. If the object type is declared at the top level of a file, the property lives as long as the program runs.

A property is visible only by way of the object. An object's methods can see that object's properties directly; such code can refer to the property using dot-notation with `self`, and I always do this as a matter of style, but `self` can usually be omitted except for purposes of disambiguation. An instance property is also visible (by default) to other code, provided the other code has a reference to this instance; in that case, the property can be referred to through dot-notation with the instance reference. A static/class property is visible (by default) to other code that can see the name of this object type; in that case, it can be referred to through dot-notation with the object type:



```
// File1:
class Dog {
    static let staticProperty = "staticProperty"
    let instanceProperty = "instanceProperty"
    func printInstanceProperty() {
        print(self.instanceProperty) // *
    }
}
// File2:
class Cat {
    func printDogStaticProperty() {
        print(Dog.staticProperty) // *
    }
    func printDogInstanceProperty() {
        let d = Dog()
        print(d.instanceProperty) // *
    }
}
```

### *Local variables*

A local variable is a variable declared inside a function body. A local variable lives only as long as its surrounding curly-braces scope lives: it comes into existence when the path of execution passes into the scope and reaches the variable declaration, and it goes out of existence when the path of execution exits the scope. Local variables are sometimes called *automatic*, to signify that they come into and go out of existence automatically. A local variable can be seen only by subsequent code within the same scope (including a subsequent deeper scope within the same scope):

```
class Dog {
    func printLocalVariable() {
        let localVariable = "local"
        print(localVariable) // *
    }
}
```

## Variable Declaration

A variable is declared with `let` or `var`:

- With `let`, the variable becomes a *constant* — its value can never be changed after the first assignment of a value.
- With `var`, the variable is a true variable, and its value can be changed by subsequent assignment.

A variable declaration is usually accompanied by *initialization* — you use an equal sign to assign the variable a value, as part of the declaration. That, however, is not a requirement; it is legal to declare a variable without immediately initializing it.

What is *not* legal is to declare a variable without giving it a *type*. A variable *must* have a type from the outset, and that type can *never be changed*. A variable declared with `var` can have its *value* changed by subsequent assignment, but the new value must conform to the variable's fixed type.

You can give a variable a type explicitly or implicitly:

#### *Explicit variable type declaration*

After the variable's name in the declaration, add a colon and the name of the type:

```
var x : Int
```

#### *Implicit variable type by initialization*

If you initialize the variable as part of the declaration, and if you provide no explicit type, Swift will *infer* its type, based on the value with which it is initialized:

```
var x = 1 // and now x is an Int
```

It is perfectly possible to declare a variable's type explicitly *and* assign it an initial value, all in one move:

```
var x : Int = 1
```

In that example, the explicit type declaration is superfluous, because the type (`Int`) would have been inferred from the initial value. Sometimes, however, providing an explicit type, even while also assigning an initial value, is *not* superfluous. Here are the main situations where that's the case:

#### *Swift's inference would be wrong*

A very common case in my own code is when I want to provide the initial value as a numeric literal. Swift will infer either `Int` or `Double`, depending on whether the literal contains a decimal point. But there are a lot of other numeric types! When I mean one of those, I will provide the type explicitly, like this:

```
let value : Float = 2.0
```

#### *Swift can't infer the type*

Sometimes, the type of the initial value is completely unknown to the compiler unless you tell it. A very common case involves option sets (discussed in [Chapter 4](#)). This won't compile:

```
var opts = [.autoreverse, .repeat] // compile error
```

The problem is that Swift doesn't know the type of `.autoreverse` and `.repeat` unless we tell it:

```
let opts : UIView.AnimationOptions = [.autoreverse, .repeat]
```

### *The programmer can't infer the type*

I frequently include a superfluous explicit type declaration as a kind of note to myself. Here's an example from my own code:

```
let duration : CMTIME = track.timeRange.duration
```

In that code, `track` is an `AVAssetTrack`. Swift knows perfectly well that the `duration` property of an `AVAssetTrack`'s `timeRange` property is a `CMTIME`. But I don't! In order to remind myself of that fact, I've shown the type explicitly.



Even if the compiler can infer a variable's type correctly from its initial value, such inference takes time. You can reduce compilation times by providing your variable declarations with explicit types.

As I've already said, a variable doesn't have to be initialized when it is declared — even if the variable is a constant. It is legal to write this:

```
let x : Int
```

Now `x` is an empty shoebox — an `Int` variable without an initial value. You can assign this variable an initial value later. Since this particular variable is a constant, that initial value will be its only value from then on.

In the case of an instance property of an object (at the top level of an enum, struct, or class declaration), that sort of thing is quite normal, because the property can be initialized in the object's initializer function. (I'll have more to say about that in [Chapter 4](#).) For a local variable, however, such behavior is unusual, and I strongly urge you to avoid it. It isn't a disaster — the Swift compiler will stop you from trying to use a variable that has never been assigned a value — but it's not a good habit. A local variable should generally be initialized as part of its declaration.

The exception that proves the rule is what we might call *conditional initialization*. Sometimes, we don't *know* a variable's initial value until we've performed some sort of conditional test. The variable itself, however, can be declared only once; so it must be declared in advance and conditionally initialized afterward. This sort of thing is not unreasonable:

```
let timed : Bool
if val == 1 {
    timed = true
} else {
    timed = false
}
```

That particular example can arguably be better expressed in other ways (which I'll come to in [Chapter 5](#)), but there are situations where conditional initialization is the cleanest approach.

When a variable's *address* is to be passed as argument to a function, the variable must be declared *and initialized* beforehand, even if the initial value is fake. Recall this example from [Chapter 2](#):

```
var r : CGFloat = 0
var g : CGFloat = 0
var b : CGFloat = 0
var a : CGFloat = 0
c.getRed(&r, green: &g, blue: &b, alpha: &a)
```

After that code runs, our four CGFloat 0 values will have been replaced; they were just momentary placeholders, to satisfy the compiler.

On rare occasions, you'll want to call a Cocoa method that returns a value immediately and later uses that value in a function passed to that same method. For example, Cocoa has a UIApplication instance method declared like this:

```
func beginBackgroundTask(expirationHandler handler: (() -> Void)? = nil)
    -> UIBackgroundTaskIdentifier
```

`beginBackgroundTask(expirationHandler:)` returns an identifier object, and will later call the `expirationHandler:` function passed to it — a function in which you will want to *use* the identifier object that was returned at the outset. Swift's safety rules won't let you declare the variable that holds this identifier and use it in an anonymous function all in the same statement:

```
let bti = UIApplication.shared.beginBackgroundTask {
    UIApplication.shared.endBackgroundTask(bti)
} // error: variable used within its own initial value
```

Therefore, you need to declare the variable beforehand; but then Swift has another complaint:

```
var bti : UIBackgroundTaskIdentifier
bti = UIApplication.shared.beginBackgroundTask {
    UIApplication.shared.endBackgroundTask(bti)
} // error: variable captured by a closure before being initialized
```

One solution is to declare the variable beforehand with a placeholder value:

```
var bti : UIBackgroundTaskIdentifier = .invalid
bti = UIApplication.shared.beginBackgroundTask {
    UIApplication.shared.endBackgroundTask(bti)
}
```

The real trouble here is that `beginBackgroundTask` is rather archaic. A more modern method would probably pass the returned value directly into the function parameter. Cocoa's `UIAction` initializer `init(title:handler:)` is a case in point:

```
let myAction = UIAction(title: "Hello") { action in
    print(action)
}
```

In that code, *action* is `myAction`, so the body of the anonymous handler: function can refer to it without saying `myAction`, which would be illegal. (This approach also prevents a possible retain cycle, discussed in [Chapter 5](#).)

## Computed Variable Initialization

Sometimes, you'd like to run several lines of code in order to compute a variable's initial value. A simple and compact way to express this is with a define-and-call anonymous function (see [“Define-and-Call” on page 50](#)). I'll illustrate by rewriting an earlier example:

```
let timed : Bool = {
  if val == 1 {
    return true
  } else {
    return false
  }
}()
```

You can do the same thing when you're initializing an instance property. Here's a class with an image (a `UIImage`) that I'm going to need many times later on. It makes sense to create this image in advance as a constant instance property of the class. To create it means to draw it. That takes several lines of code. So I declare and initialize the property by defining and calling an anonymous function, like this (for my `imageOfSize` utility, see [Chapter 2](#)):

```
class RootViewController : UITableViewController {
  let cellBackgroundImage : UIImage = {
    return imageOfSize(CGSize(width:320, height:44)) {
      // ... drawing goes here ...
    }
  }()
  // ... rest of class goes here ...
}
```

You might ask: Instead of a define-and-call initializer, why don't I declare an instance method and initialize the instance property by calling that method? The reason is that that's illegal:

```
class RootViewController : UITableViewController {
  let cellBackgroundImage : UIImage = self.makeTheImage() // compile error
  func makeTheImage() -> UIImage {
    return imageOfSize(CGSize(width:320, height:44)) {
      // ... drawing goes here ...
    }
  }
}
```

The problem is that, at the time of initializing the instance property, there is no instance yet — the instance is what we are in the process of creating. Therefore you

can't refer to `self` (implicitly or explicitly) in a property declaration's initializer. A define-and-call anonymous function, however, is legal. But the define-and-call anonymous function *still* can't refer to `self`! I'll provide a workaround a little later in this chapter.

## Computed Variables

The variables I've been describing so far in this chapter have all been *stored* variables. The named shoebox analogy applies: a value can be put into the shoebox by assigning it to the variable, and it then sits there and can be retrieved later by referring to the variable, for as long the variable lives.

But a variable in Swift can work in a completely different way: it can be *computed*. This means that the variable, instead of having a value, has *functions*. One function, the *setter*, is called when the variable is assigned to. The other function, the *getter*, is called when the variable is referred to. Here's some code illustrating schematically the syntax for declaring a computed variable:

```
var now : String { ❶
    get { ❷
        return Date().description ❸
    }
    set { ❹
        print(newValue) ❺
    }
}
```

- ❶ The variable must be declared with `var` (not `let`). Its type must be declared explicitly. The type is followed immediately by curly braces.
- ❷ The getter function is called `get`. There is no formal function declaration; the word `get` is simply followed immediately by a function body in curly braces.
- ❸ The getter function must return a value of the same type as the variable. When the getter is a single statement, it is legal to omit the keyword `return`.
- ❹ The setter function is called `set`. There is no formal function declaration; the word `set` is simply followed immediately by a function body in curly braces.
- ❺ The setter behaves like a function taking one parameter. By default, this parameter arrives into the setter function body with the local name `newValue`.

Here's some code that illustrates the use of our computed variable. You don't treat it any differently than any other variable! To assign to the variable, assign to it; to use the variable, use it. Behind the scenes, though, the setter and getter functions are called:

```
now = "Howdy" // Howdy ❶  
print(now) // 2021-06-26 17:03:30 +0000 ❷
```

- ❶ Assigning to `now` calls its setter. The argument passed into this call is the assigned value; here, that's "Howdy". That value arrives in the `set` function as `newValue`. Our `set` function prints `newValue` to the console.
- ❷ Fetching `now` calls its getter. Our `get` function obtains the current date-time and translates it into a string, and returns the string. Our code then prints that string to the console.

There are a couple of variants on the basic syntax I've just illustrated:

- The name of the `set` function parameter doesn't have to be `newValue`. To specify a different name, put it in parentheses after the word `set`, like this:

```
set (val) { // now you can use "val" inside the setter function body
```

- There doesn't have to be a setter. If the setter is omitted, this becomes a *read-only* variable. This is the computed variable equivalent of a `let` variable: attempting to assign to it is a compile error.
- There must always be a getter! However, if there is no setter, the word `get` and the curly braces that follow it can be omitted. This is a legal declaration of a read-only variable (omitting the `return` keyword):

```
var now : String {  
    Date().description  
}
```

## Computed Properties

In real life, your main use of computed variables will nearly always be as instance properties. Here are some common ways in which computed properties are useful:

### *Façade for a longer expression*

When a value can be readily calculated or obtained each time it is needed, it often makes for simpler syntax to express it as a read-only computed variable, which effectively acts as a shorthand for a longer expression. Here's an example from my own code:

```
var mp : MPMusicPlayerController {  
    MPMusicPlayerController.systemMusicPlayer  
}  
var nowPlayingItem : MPMediaItem? {  
    self.mp.nowPlayingItem  
}
```

No work is saved by these computed variables; each time we ask for `self.nowPlayingItem`, we are fetching `MPMusicPlayerController.systemMusicPlayer.nowPlayingItem`. Still, the clarity and convenience of the resulting code justifies the use of computed variables here.

#### *Façade for an elaborate calculation*

A computed variable getter can encapsulate multiple lines of code, in effect turning a method into a property. Here's an example from my own code:

```
var authorOfItem : String? {
    guard let authorNodes =
        self.extensionElements(
            withXMLNamespace: "http://www.tidbits.com/dummy",
            elementName: "app_author_name")
        else {return nil}
    guard let authorNode = authorNodes.last as? FPEExtensionNode
        else {return nil}
    return authorNode.stringValue
}
```

In that example, I'm diving into some parsed XML and extracting a value. I could have declared this as a method `func authorOfItem() -> String?`, but a method expresses a *process*, whereas a computed property characterizes it more intuitively as a *thing*.

#### *Façade for storage*

A computed variable can sit in front of one or more stored variables, acting as a gatekeeper on how those stored variables are set and fetched. This is comparable to an accessor method in Objective-C. Commonly, a public computed variable is backed by a private stored variable. The simplest possible storage façade would do no more than get and set the private stored variable directly:

```
private var _p : String = ""
var p : String {
    get {
        self._p
    }
    set {
        self._p = newValue
    }
}
```

That's legal but pointless. A storage façade becomes useful when it does *other* things while getting or setting the stored variable. Here's a more realistic example: a "clamped" setter. This is an `Int` property to which only values between 0 and 5 can be assigned; larger values are replaced by 5, and smaller values are replaced by 0:



```

private var _pp : Int = 0
var pp : Int {
    get {
        self._pp
    }
    set {
        self._pp = max(min(newValue,5),0)
    }
}

```

As the preceding examples demonstrate, a computed instance property getter or setter can refer to other instance members. That’s important, because in general the initializer for a stored property can’t do that. The reason it’s legal for a computed property is that the getter and setter functions won’t be called until the instance actually exists.

## Property Wrappers

If we have several storage façade computed properties that effectively do the same thing, we’re going to end up with a lot of repeated code. Imagine implementing more than one `Int` property with a clamped setter, as in the preceding section. It would be nice to move the common functionality off into a single location. We can do that using a *property wrapper*.

A property wrapper is declared as a type marked with the `@propertyWrapper` attribute, and must have a `wrappedValue` computed property. Here’s a property wrapper implementing the “clamped” pattern:

```

@propertyWrapper struct Clamped {
    private var _i : Int = 0
    var wrappedValue : Int {
        get {
            self._i
        }
        set {
            self._i = Swift.max(Swift.min(newValue,5),0)
        }
    }
}

```

The result is that we can declare a computed property marked with a custom attribute whose name is the same as that struct (`@Clamped`), with *no* getter or setter:

```
@Clamped var p
```

Our property `p` doesn’t need to be initialized, because it’s a computed property. And it doesn’t need a getter or a setter — indeed, in this case it doesn’t even need a type declaration — because the `wrappedValue` computed property of the `Clamped` struct supplies them!

Behind the scenes, an actual `Clamped` instance has been created for us. When we set `self.p` to some value through assignment, the assignment passes through the `Clamped` instance's `wrappedValue` setter, and the resulting clamped value is stored in the `Clamped` instance's `_i` property. When we fetch the value of `self.p`, what we get is the value returned from the `Clamped` instance's `wrappedValue` getter, which is the value stored in the `Clamped` instance's `_i` property.

Thanks to our property wrapper, we have *encapsulated* this computed property pattern, which means we can now declare *another* `@Clamped` property which will behave in just the same way. It's also nice that this pattern now has a *name*: the declaration `@Clamped var` tells us what the behavior of this computed property will be.

(Believe it or not, I created the `Clamped` example *before* discovering that the Swift language proposal for property wrappers uses the same example!)

There's considerably more to know about property wrappers, but I'll postpone further discussion to [Chapter 5](#), after I've explained other language features that will help you appreciate their power and flexibility.

## Setter Observers

Computed variables are not needed as a stored variable façade as often as you might suppose. That's because Swift has another feature, which lets you inject functionality into the setter of a *stored* variable — *setter observers*. These are functions that are called just before and just after other code sets a stored variable.

The syntax for declaring a variable with a setter observer is very similar to the syntax for declaring a computed variable; you can write a `willSet` function, a `didSet` function, or both:

```
var s = "whatever" { ❶
    willSet { ❷
        print(newValue) ❸
    }
    didSet { ❹
        print(oldValue) ❺
        // self.s = "something else"
    }
}
```

- ❶ The variable must be declared with `var` (not `let`). It can be assigned an initial value. It is then followed immediately by curly braces.
- ❷ The `willSet` function, if there is one, is the word `willSet` followed immediately by a function body in curly braces. It is called when other code sets this variable, just *before* the variable actually receives its new value.

- ③ By default, the `willSet` function receives the incoming new value as `newValue`. You can change this name by writing a different name in parentheses after the word `willSet`. The old value is still sitting in the stored variable, and the `willSet` function can access it there.
- ④ The `didSet` function, if there is one, is the word `didSet` followed immediately by a function body in curly braces. It is called when other code sets this variable, just *after* the variable actually receives its new value.
- ⑤ By default, the `didSet` function receives the old value, which has already been replaced as the value of the variable, as `oldValue`. You can change this name by writing a different name in parentheses after the word `didSet`. The new value is already sitting in the stored variable, and the `didSet` function can access it there. Moreover, it is legal for the `didSet` function to set the stored variable to a different value.



Setter observer functions are *not* called when the stored variable is initialized or when the `didSet` function changes the stored variable's value. That would be circular!

In real-life iOS programming, you'll want the visible interface to reflect the state of your objects. A setter observer is a simple but powerful way to synchronize the interface with a property. In this example, we have an instance property of a view class, determining how much the view should be rotated; every time this property changes, we change the interface to reflect it, setting `self.transform` so that the view *is* rotated by that amount:

```
var angle : CGFloat = 0 {  
    didSet {  
        // modify interface to match  
        self.transform = CGAffineTransform(rotationAngle: self.angle)  
    }  
}
```

A computed variable can't have setter observers. But it doesn't need them! There's a setter function, so anything additional that needs to happen during setting can be programmed directly into that setter function. (But a property-wrapped computed variable *can* have setter observers.)

## Lazy Initialization

The term *lazy* is not a pejorative puritanical judgment; it's a formal description of a useful behavior. If a stored variable is assigned an initial value as part of its declaration, and if it uses lazy initialization, then the initial value is not actually evaluated and assigned until running code accesses the variable's value.

There are four types of variable that can be initialized lazily in Swift:

#### *Global variables*

Global variables are *automatically lazy*. This makes sense if you ask yourself when they should be initialized. As the app launches, files and their top-level code are encountered. It would make no sense to initialize globals now, because the app isn't even running yet. Thus global initialization must be postponed to some moment that *does* make sense. Therefore, a global variable's initialization doesn't happen until other code first refers to that global. Under the hood, this behavior is implemented in such a way as to make initialization both singular (it can happen only once) and thread-safe.

#### *Static properties*

Static properties are *automatically lazy*. They behave exactly like global variables, and for basically the same reason. (There are no stored class properties in Swift, so class properties can't be initialized and thus can't have lazy initialization.)

#### *Instance properties*

An instance property is not lazy by default, but it may be made lazy by marking its declaration with the keyword `lazy`. This property must be declared with `var`, not `let`.

#### *Local variables*

New in Swift 5.5, a local variable can be declared with `lazy var`.

If your code *never* refers to a lazily initialized variable, its initializer never runs; clearly, that's useful if the initial value might be expensive to generate, so you'd like to avoid generating it unless it is actually needed.

What if the first reference to a lazily initialized variable *sets* that variable? For a global variable or a static property, the initializer is evaluated and is immediately replaced by the new value. But the initializer for a lazy instance property or local variable will *never* be evaluated if the variable is set before it is fetched.

## Singleton

Lazy initialization is often used to implement *singleton*. Singleton is a pattern where all code is able to get access to a single shared instance of a certain class:

```
class MyClass {
    static let shared = MyClass()
}
```

Now other code can obtain a reference to `MyClass`'s singleton by saying `MyClass.shared`. The singleton instance is not created until the *first* time other code says `MyClass.shared`; subsequently, no matter how many times other code may say `MyClass.shared`, the instance returned is always *that same instance*. (That is *not* what

would happen if this were a computed read-only property whose getter calls `MyClass()` and returns that instance; do you see why?)

## Lazy Initialization of Instance Properties

Aside from the efficiency benefits of a laziness, a lazy initializer can do things that a normal initializer can't. In particular, a lazy initializer can *refer to the instance*. A normal initializer can't do that, because the instance doesn't yet exist at the time that a normal initializer would need to run (we're in the middle of creating the instance, so it isn't ready yet). A lazy initializer, by contrast, is guaranteed not to run until some time after the instance has fully come into existence, so referring to the instance is fine. This code would be illegal if the arrow property weren't declared lazy:

```
class MyView : UIView {
    lazy var arrow = self.arrowImage() // legal
    func arrowImage () -> UIImage {
        // ... big image-generating code goes here ...
    }
}
```

A very common idiom is to initialize a lazy instance property with a define-and-call anonymous function whose code can refer to `self`:

```
lazy var prog : UIProgressView = {
    let p = UIProgressView(progressViewStyle: .default)
    p.alpha = 0.7
    p.trackTintColor = UIColor.clear
    p.progressTintColor = UIColor.black
    p.frame =
        CGRect(x:0, y:0, width:self.view.bounds.size.width, height:20) // legal
    p.progress = 1.0
    return p
}()
```

## Built-In Simple Types

Every variable, and every value, must have a type. But what types are there? Up to this point, I've assumed the existence of some types, such as `Int` and `String`, without formally telling you about them. Here's a survey of the primary simple types provided by Swift, along with some instance methods, global functions, and operators that apply to them. (Collection types will be discussed at the end of [Chapter 4](#).)

### Bool

The `Bool` object type (a struct) has only two values, commonly regarded as true and false (or yes and no). You can represent these values using the literal keywords `true` and `false`, and it is natural to think of a `Bool` value as *being* either true or false:

## No Lazy Let for Instance Properties

There's no lazy `let` for instance properties, so you can't readily make a lazy instance property read-only. That's unfortunate, because there are some common situations that would benefit from such a feature.

Suppose we want to arm ourselves (`self`) with a helper property holding an instance of a `Helper` class that needs a reference back to `self`. We also want this one `Helper` instance to persist for the entire lifetime of `self`. We can enforce that rule by making `helper` a `let` property and initializing it in its declaration. But we can't pass `self` into the `Helper` initializer, because we can't refer to `self` in the property declaration. We can solve that problem by declaring the helper property `lazy`.

The trouble is that then this has to be a `var` property, meaning that, in theory, other code can come along and replace this `Helper` instance with another. That's not what we want. Of course, we'll try not to let it happen, but the point is that the expression `lazy var` fails to enforce the desired policy.

```
var selected : Bool = false
```

In that code, `selected` is a `Bool` variable initialized to `false`; it can subsequently be set to `false` or `true`, and to no other values. Because of its simple yes-or-no state, a `Bool` variable of this kind is often referred to as a *flag*.

Cocoa methods very often expect a `Bool` parameter or return a `Bool` value. For example, when your app launches, Cocoa calls a method in your code declared like this:

```
func application(_ application: UIApplication,
    didFinishLaunchingWithOptions
    launchOptions: [UIApplication.LaunchOptionsKey : Any]?)
    -> Bool {
```

You can do anything you like in that method; often, you will do nothing. But you must return a `Bool`! And in real life, that `Bool` will probably be `true`. A minimal implementation looks like this:

```
func application(_ application: UIApplication,
    didFinishLaunchingWithOptions
    launchOptions: [UIApplication.LaunchOptionsKey : Any]?)
    -> Bool {
    return true
}
```

A `Bool` is useful in conditions; as I'll explain in [Chapter 5](#), when you say if *something*, the *something* is the condition, and is a `Bool` or an expression that evaluates to a `Bool`. When you compare two values using the equality comparison operator `==`, the result is a `Bool` — `true` if they are equal to each other, `false` if they are not:

```
if meaningOfLife == 42 { // ...
```

(I'll talk more about equality comparison in a moment, when we come to discuss types that can be compared, such as `Int` and `String`.)

When preparing a condition, you will sometimes find that it enhances clarity to store the `Bool` value in a variable beforehand:

```
let comp = self.traitCollection.horizontalSizeClass == .compact
if comp { // ...
```

Observe that, when employing that idiom, we use the `Bool` variable `comp` *directly* as the condition. There is no need to test explicitly whether a `Bool` equals `true` or `false`; the conditional expression itself is already testing that. It is pointless to say `if comp == true`, because `if comp` already *means* “if `comp` is true.”

Since a `Bool` can be used as a condition, a call to a function that returns a `Bool` can be used as a condition. Here's an example from my own code. I've declared a function that returns a `Bool` to say whether the cards the user has selected constitute a correct answer to the puzzle:

```
func isCorrect(_ cells:[CardCell]) -> Bool { // ...
```

I can then use a call to `isCorrect` as a condition:

```
if self.isCorrect(cellsToTest) { // ...
```

Unlike many computer languages, nothing else in Swift is implicitly coerced to or treated as a `Bool`. In C, for example, a boolean is actually a number, and `0` is false. But in Swift, nothing is false but `false`, and nothing is true but `true`.

The type name, `Bool`, comes from the English mathematician George Boole; Boolean algebra provides operations on logical values. `Bool` values are subject to these same operations:

**!** (*not*)

The `!` unary operator reverses the truth value of the `Bool` to which it is applied as a prefix. If `ok` is `true`, `!ok` is `false` — and vice versa.

**&&** (*logical-and*)

Returns `true` only if both operands are `true`; otherwise, returns `false`. If the first operand is `false`, the second operand is not even evaluated (avoiding possible side effects).

**||** (*logical-or*)

Returns `true` if either operand is `true`; otherwise, returns `false`. If the first operand is `true`, the second operand is not even evaluated (avoiding possible side effects).

If a logical operation is complicated or elaborate, parentheses around subexpressions can help clarify both the logic and the order of operations.

A common situation is that we have a `Bool` stored in a `var` variable somewhere, and we want to reverse its value — that is, make it `true` if it is `false`, and `false` if it is `true`. The `!` operator solves the problem; we fetch the variable’s value, reverse it with `!`, and assign the result back into the variable:

```
v.isUserInteractionEnabled = !v.isUserInteractionEnabled
```

That, however, is cumbersome and error-prone, so there’s a simpler way — call the `toggle` method on the `Bool` variable:

```
v.isUserInteractionEnabled.toggle()
```

## Numbers

The main numeric types are `Int` and `Double` — meaning that, left to your own devices, those are the types you’ll generally use. Other numeric types exist mostly for compatibility with the C and Objective-C APIs that Swift needs to be able to talk to when you’re programming iOS.

### Int

The `Int` object type (a struct) represents an integer between `Int.min` and `Int.max` inclusive. The actual values of those limits might depend on the platform and architecture under which the app runs, so don’t count on them to be absolute; in my testing at this moment, they are  $-2^{63}$  and  $2^{63}-1$  respectively (64-bit words).

The easiest way to represent an `Int` value is as a numeric literal. A numeric literal without a decimal point is taken as an `Int` by default. Internal underscores are legal; this is useful for making long numbers readable. Leading zeroes are legal; this is useful for padding and aligning values in your code.

You can write an `Int` literal using binary, octal, or hexadecimal digits. To do so, start the literal with `0b`, `0o`, or `0x` respectively. For example, `0x10` is decimal 16.



Negative numbers are stored in the two’s complement format (consult Wikipedia if you’re curious). You can write a binary literal that looks like the underlying storage, but to use it you must pass it through the `Int(bitPattern:)` initializer.

### Double

The `Double` object type (a struct) represents a floating-point number to a precision of about 15 decimal places (64-bit storage).



The easiest way to represent a Double value is as a numeric literal. A numeric literal containing a decimal point is taken as a Double by default. Internal underscores and leading zeroes are legal.

A Double literal may *not* begin with a decimal point (unlike C and Objective-C). If the value to be represented is between 0 and 1, start the literal with a leading 0.

You can write a Double literal using scientific notation. Everything after the letter e is the exponent of 10. You can omit the decimal point if the fractional digits would be zero. For example, 3e2 is 3 times 10<sup>2</sup> (300).

You can write a Double literal using hexadecimal digits. To do so, start the literal with 0x. You can use exponentiation here too (and again, you can omit the decimal point); everything after the letter p is the exponent of 2. For example, 0x10p2 is decimal 64, because you are multiplying 16 by 2<sup>2</sup>.

There are static properties Double.infinity and Double.pi, and an instance property isZero, among others.

## Numeric coercion

*Coercion* is the conversion of a value from one type to another, and numeric coercion is the conversion of a value from one numeric type to another. Swift doesn't really have explicit coercion, but it has something that serves the same purpose — instantiation. Swift numeric types are supplied with initializers that take another numeric type as parameter. To convert an Int explicitly into a Double, instantiate Double with the Int in the parentheses. To convert a Double explicitly into an Int, instantiate Int with the Double in the parentheses; this will truncate the original value (everything after the decimal point will be thrown away):

```
let i = 10
let x = Double(i)
print(x) // 10.0, a Double
let y = 3.8
let j = Int(y)
print(j) // 3, an Int
```

When numeric values are assigned to variables or passed as arguments to a function, Swift can perform implicit coercion *of literals only*. This code is legal:

```
let d : Double = 10
```

But this code is not legal, because what you're assigning is a *variable* (not a literal) of a different type; the compiler will stop you:

```
let i = 10
let d : Double = i // compile error
```

The problem is that `i` is an `Int` and `d` is a `Double`, and never the twain shall meet. The solution is to *coerce explicitly* as you assign or pass the variable:

```
let i = 10
let d : Double = Double(i)
```

The same rule holds when numeric values are combined by an arithmetic operation. Swift will perform implicit coercion *of literals only*. The usual situation is an `Int` combined with a `Double`; the `Int` is treated as a `Double`:

```
let x = 10/3.0
print(x) // 3.333333333333333
```

But *variables* of different numeric types must be *coerced explicitly* so that they are the *same* type if you want to combine them in an arithmetic operation:

```
let i = 10
let n = 3.0
let x = i / n // compile error; you need to say Double(i)
```

These rules are evidently a consequence of Swift's strict typing; but (as far as I am aware) they constitute very unusual treatment of numeric values for a modern computer language, and will probably drive you mad in short order. The examples I've given so far were easily solved, but things can become more complicated if an arithmetic expression is longer, and the problem is compounded by the existence of other numeric types that are needed for compatibility with Cocoa, as I shall now proceed to explain.

## Other numeric types

If you were using Swift in some isolated, abstract world, you could probably do all necessary arithmetic with `Int` and `Double` alone. But when you're programming iOS, you encounter Cocoa, which is full of other numeric types; and Swift has types that match every one of them. In addition to `Int`, there are signed integer types of various sizes — `Int8`, `Int16`, `Int32`, `Int64` — plus the unsigned integer type `UInt` along with `UInt8`, `UInt16`, `UInt32`, and `UInt64`. In addition to `Double`, there is the lower-precision `Float` (32-bit storage, about 6 or 7 decimal places of precision), the even lower-precision `Float16`, the extended-precision `Float80`, and (from the Core Graphics framework) `CGFloat`.

You may also encounter a C numeric type when trying to interface with a C API. These types, as far as Swift is concerned, are just type aliases, meaning that they are alternate names for another type: a `CDouble` (corresponding to C's `double`) is just a `Double` by another name, a `CLong` (C's `long`) is an `Int`, and so on. Many other numeric type aliases will arise in various Cocoa frameworks; for example, `TimeInterval` (Objective-C `NSTimeInterval`) is merely a type alias for `Double`.



Figure 3-1. Quick Help displays a variable's type

Recall that you can't assign, pass, or combine values of different numeric types using variables; you have to coerce those values explicitly to the correct type. But now it turns out that you're being flooded by Cocoa with numeric values of many types! Cocoa will often hand you a numeric value that is neither an `Int` nor a `Double` — and you won't necessarily realize this, until the compiler stops you dead in your tracks for some sort of type mismatch. You must then figure out what you've done wrong and coerce everything to the same type.

Here's a typical example from one of my apps. A slider in the interface is a `UISlider`, whose `minimumValue` and `maximumValue` are `Floats`. In this code, `s` is a `UISlider`, `g` is a `UIGestureRecognizer`, and we're trying to use the gesture recognizer to move the slider's "thumb" to wherever the user tapped within the slider:

```
let pt = g.location(in:s) ❶
let percentage = pt.x / s.bounds.size.width ❷
let delta = percentage * (s.maximumValue - s.minimumValue) // compile error ❸
```

That won't compile. Here's why:

- ❶ `pt` is a `CGPoint`, and therefore `pt.x` is a `CGFloat`.
- ❷ Luckily, `s.bounds.size.width` is also a `CGFloat`, so the second line compiles; the type of `percentage` is now inferred as `CGFloat`.
- ❸ We now try to combine `percentage` with `s.maximumValue` and `s.minimumValue` — and they are `Floats`, not `CGFloats`. That's a compile error.

This sort of thing is not an issue in C or Objective-C, where there is implicit coercion; but in Swift a `CGFloat` can't be combined with `Floats`. We must coerce explicitly:

```
let delta = Float(percentage) * (s.maximumValue - s.minimumValue)
```

The good news here is that if you can get enough of your code to compile, Xcode's Quick Help feature (Chapter 9) will tell you what type Swift has inferred for a selected variable (Figure 3-1). This can assist you in tracking down your issues with numeric types.

`CGFloat` is a special case. It resolves to the size of `Float` or `Double`, depending on the bitness of the architecture (32-bit or 64-bit); but this distinction has lost much of its importance, because nowadays 32-bit architecture is rare and in any case it handles `Doubles` efficiently. New in Swift 5.5, therefore, a `Double` and a `CGFloat` are

interchangeable; you can supply one where the other is expected *without coercion*, relieving iOS programmers from considerable inconvenience:

```
var cfg : CGFloat = 1
var d : Double = 2
cfg = d // legal
d = cfg + d // legal
let x = cfg + d // x is inferred as Double
```

Another problem is that not every numeric value *can* be coerced to a numeric value of a different type. In particular, integers of various sizes can be out of range with respect to integer types of other sizes. For example, `Int8.max` is 127, so attempting to assign a literal 128 or larger to an `Int8` variable is illegal. Fortunately, the compiler will stop you in that case, because it knows what the literal is. But now consider *coercing* a variable value of a larger integer type to an `Int8`:

```
let i : Int16 = 128
let ii = Int8(i)
```

That code is legal — and will crash at runtime. One solution is to call the numeric `exactly:` initializer; this is a *failable* initializer — meaning, as I’ll explain in [Chapter 4](#), that you won’t crash, but you’ll have to add code to test whether the coercion succeeded (and you’ll understand what the test would be when you’ve read the discussion of Optionals later in this chapter):

```
let i : Int16 = 128
let ii = Int8(exactly:i)
if // ... test to learn whether ii holds a real Int8
```

Yet another solution is to call the `clamping:` initializer; it *always* succeeds, because an out of range value is forced to fall within range:

```
let i : Int16 = 128
let ii = Int8(clamping:i) // 127
```

(There is also a `truncatingIfNeeded:` initializer, but you probably won’t need to know about it unless you are deliberately manipulating integers as binary, so I won’t describe it here.)

When a floating-point type, such as a `Double`, is coerced to an integer type, the stuff after the decimal point is thrown away first and then the coercion is attempted. `Int8(127.9)` succeeds, because 127 is in bounds.

## Arithmetic operations

Swift’s arithmetic operators are as you would expect; they are familiar from other computer languages as well as from real arithmetic:

`+` (*addition operator*)

Add the second operand to the first and return the result.

- (*subtraction operator*)

Subtract the second operand from the first and return the result. A different operator (unary minus), used as a prefix, looks the same; it returns the additive inverse of its single operand. (There is, in fact, also a unary plus operator, which returns its operand unchanged.)

\* (*multiplication operator*)

Multiply the first operand by the second and return the result.

/ (*division operator*)

Divide the first operand by the second and return the result. As in C, division of one `Int` by another `Int` yields an `Int`; any remaining fraction is stripped away. `10/3` is 3, not 3-and-one-third.

% (*remainder operator*)

Divide the first operand by the second and return the remainder. The result can be negative, if the first operand is negative; if the second operand is negative, it is treated as positive. For floating-point operands, use a method such as `remainder(dividingBy:)`.

Integers also have a `quotientAndRemainder(dividingBy:)` method, which returns a tuple of two integers labeled `quotient` and `remainder`. (I'll discuss tuples later in this chapter.) If the question is whether one integer evenly divides another, calling `isMultiple(of:)` may be clearer than checking for a zero remainder.

Integer types can be treated as binary bitfields and subjected to binary bitwise operations:

& (*bitwise-and*)

A bit in the result is 1 if and only if that bit is 1 in both operands.

| (*bitwise-or*)

A bit in the result is 0 if and only if that bit is 0 in both operands.

^ (*bitwise-or, exclusive*)

A bit in the result is 1 if and only if that bit is not identical in both operands.

~ (*bitwise-not*)

Precedes its single operand; inverts the value of each bit and returns the result.

<< (*shift left*)

Shift the bits of the first operand leftward the number of times indicated by the second operand.

>> (*shift right*)

Shift the bits of the first operand rightward the number of times indicated by the second operand.



Technically, the shift operators perform a logical shift if the integer is unsigned, and an arithmetic shift if the integer is signed.

Integer overflow or underflow — for example, adding two `Int` values so as to exceed `Int.max` — is a runtime error (your app will crash). In simple cases the compiler will stop you, but you can get away with it easily enough:

```
let i = Int.max - 2
let j = i + 12/2 // crash
```

Under certain circumstances you might want to force such an operation to succeed, so special overflow/underflow methods are supplied. These methods return a tuple; I'll show you an example even though I haven't discussed tuples yet:

```
let i = Int.max - 2
let (j, over) = i.addingReportingOverflow(12/2)
```

Now `j` is `Int.min + 3` (because the value has wrapped around from `Int.max` to `Int.min`) and `over` is a `Bool` reporting that overflow occurred.

If you don't care to hear about whether or not there was an overflow/underflow, special arithmetic operators let you suppress the error: `&+`, `&-`, &\*.

You will frequently want to combine the value of an existing variable arithmetically with another value and store the result in the same variable. To do so, you will need to have declared the variable as a `var`:

```
var i = 1
i = i + 7
```

As a shorthand, operators are provided that perform the arithmetic operation and the assignment all in one move:

```
var i = 1
i += 7
```

The shorthand (*compound*) assignment arithmetic operators are `+=`, `-=`, `*=`, `/=`, `%=`, `&=`, `|=`, `^=`, `<=<=`, `>>=`.

Operation precedence is largely intuitive: for example, `*` has a higher precedence than `+`, so `x+y*z` multiplies `y` by `z` first, and then adds the result to `x`. Use parentheses to dictate precedence explicitly: `(x+y)*z` performs the addition first.

Global functions from the Swift standard library include `abs` (absolute value), `max`, and `min`:

```
let i = -7
let j = 6
print(abs(i)) // 7
print(max(i,j)) // 6
```

Doubles are also stocked with mathematical methods. If `d` is a `Double`, you can say `d.squareRoot()` or `d.rounded()`; if `dd` is also a `Double`, you can say `Double.maximum(d,dd)`. Other global mathematical functions, such as trigonometric `sin` and `cos`, come from the C standard libraries that are visible because you’ve imported `UIKit`. In addition, the Swift Numerics package unites the floating-point types under the `Real` protocol and supplies most of the mathematical functions you could ever want (`import Numerics`; see [Chapter 7](#)).

Numeric types have a `random(in:)` static method allowing generation of a random number. The parameter is a range representing the bounds within which the random number should fall. (Ranges are discussed later in this chapter.) This method is much easier to use correctly than the C library methods such as `arc4random_uniform`, which should be avoided:

```
// pick a number from 1 to 10
let i = Int.random(in: 1...10)
```

## Comparison

Numbers are compared using the comparison operators, which return a `Bool`. The expression `i==j` tests whether `i` and `j` are equal; when `i` and `j` are numbers, “equal” means numerically equal. So `i==j` is `true` only if `i` and `j` are “the same number,” in exactly the sense you would expect.

The comparison operators are:

`==` (*equality operator*)

Returns `true` if its operands are equal.

`!=` (*inequality operator*)

Returns `false` if its operands are equal.

`<` (*less-than operator*)

Returns `true` if the first operand is less than the second operand.

`<=` (*less-than-or-equal operator*)

Returns `true` if the first operand is less than or equal to the second operand.

`>` (*greater-than operator*)

Returns `true` if the first operand is greater than the second operand.

`>=` (*greater-than-or-equal operator*)

Returns `true` if the first operand is greater than or equal to the second operand.

Curiously, you can compare values of different integer types, even though you can't combine them in an arithmetic operation:

```
let i: Int = 1
let i2: UInt8 = 2
let ok = i < i2 // true
let ok2 = i == i2 // false
let sum = i + i2 // error
```

Because of the way computers store numbers, equality comparison of Double values may not succeed where you would expect. To give a classic example, adding 0.1 to 0 ten times does not give the same result as multiplying 0.1 by ten:

```
let f = 0.1
var sum = 0.0
for _ in 0..<10 { sum += f }
let product = f * 10
let ok = sum == product // false
```

Working around this sort of thing is not easy. The usual approach is to check whether two values are sufficiently close to one another, but this begs the question of what constitutes sufficient closeness. A useful formula is:

```
let ok = sum >= product.nextDown && sum <= product.nextUp // true
```

## String

The String object type (a struct) represents text. The simplest way to represent a String value is with a literal, delimited by double quotes:

```
let greeting = "hello"
```

A Swift string is thoroughly modern; under the hood, it's Unicode, and you can include any character (such as an emoji) directly in a string literal. If you don't want to bother typing a Unicode character whose codepoint you know, use the notation `\u{...}`, where what's between the curly braces is up to eight hex digits:

```
let leftTripleArrow = "\u{21DA}"
```

The backslash in that string representation is the *escape* character; it means, “I’m not really a backslash; I indicate that the next character gets special treatment.” Various nonprintable and ambiguous characters are entered as escaped characters; the most important are:

`\n`

A Unix newline character

`\t`

A tab character



`\`

A quotation mark (escaped to show that this is not the end of the string literal)

`\\`

A backslash (escaped because a lone backslash is the escape character)

Escaped quotation marks and backslashes can quickly make your string literals ugly and illegible. The issue arises particularly in contexts such as regular expression patterns. For example, the pattern `\b\d\d\b` (a word consisting of two digits) must be written `\\b\\d\\d\\b`. But you can omit the escape character before quotes and backslashes by surrounding your literal with one or more hash characters (`#`); these are all identical strings:

```
let pattold = "\\b\\d\\d\\b"
let pattnew = "#\\b\\d\\d\\b"# // same thing
let pattnew2 = "##\\b\\d\\d\\b"## // same thing
```

That's called a *raw* string literal. The downside is that if you *want* to use a backslash as an escape character in a raw string literal, you must follow it with the same number of `#` characters you are using to surround your literal. The string `#"hello\nthere"#` does not contain a newline character (`\n`), but `#"hello\#nthere"#` does.

A string literal containing newline characters can be entered as multiple lines (rather than a single-line expression containing `\n` characters). This is called a *multiline* string literal. The rules are:

- The multiline string literal must be delimited by a triple of double quotes (`"""`) at start and end.
- No material may follow the opening delimiter on the same line.
- No material other than whitespace may appear on the same line as the closing delimiter.
- The last implicit newline character before the closing delimiter is ignored.
- The indentation of the closing delimiter dictates the indentation of the lines of text, which must be indented at least as far as the closing delimiter (except for completely empty lines).

For example:

```
func f() {
  let s = """
    Line 1
      Line 2
    Line 3
    """
  // ...
}
```

In that code, the string `s` consists of three lines of text; lines 1 and 3 start with no whitespace; line 2 starts with four spaces; and there are two newline characters, namely after lines 1 and 2. To add a newline after line 3, you could enter a blank line, or write it as an escaped `\n`.

Quotation marks do *not* have to be escaped. A line ending with a backslash is joined with the following line. In this code, the string `s` consists of just two lines of text; the second line consists of four spaces followed by “Line 2 and this is still line 2”:

```
func f() {  
    let s = ""  
    Line "1"  
        Line 2 \  
    and this is still Line 2  
    ""  
    // ...  
}
```

(You can surround a multiline string literal with `#` characters, making a raw multiline string literal; but you are unlikely to do so.)

String interpolation permits you to embed any value that can be output with `print` inside a string literal *as a string*, even if it is not itself a string. The notation is escaped parentheses: `\(...)`:

```
let n = 5  
let s = "You have \(\n) widgets."
```

Now `s` is the string "You have 5 widgets." The example is not very compelling, because we know what `n` is and could have typed 5 directly into our string; but imagine that we *don't* know what `n` is! Moreover, the stuff in escaped parentheses doesn't have to be the name of a variable; it can be almost any expression that evaluates as legal Swift:

```
let m = 4  
let n = 5  
let s = "You have \(m + n) widgets."
```

Inside a string interpolation, the quotation marks delimiting a literal string do not need to be escaped:

```
let s = "You have \(\"numerous\".uppercased()) widgets"
```

String interpolation is legal inside a multiline string literal. It is also legal inside a raw string literal surrounded with `#` characters, but then the backslash must be followed by the same number of `#` characters, to indicate that it is the escape character.

String interpolation syntax can be customized to accept additional parameters, refining how the first parameter should be transformed. Expressions of this form can be legal:

```
let s = "You have \(n, roman:true) widgets"
```

(I'm imagining that if `n` is 5, this would yield "You have V widgets".) I'll say more in [Chapter 5](#) about how that is achieved.

To combine (concatenate) two strings, the simplest approach is to use the `+` operator:

```
let s = "hello"
let s2 = " world"
let greeting = s + s2
```

This convenient notation is possible because the `+` operator is *overloaded*: it does one thing when the operands are numbers (numeric addition) and another when the operands are strings (concatenation). As I'll explain in [Chapter 5](#), *all* operators can be overloaded, and you can overload them to operate in some appropriate way on your own types.

The `+` operator comes with a `+=` assignment shortcut; naturally, the variable on the left side must have been declared with `var`:

```
var s = "hello"
let s2 = " world"
s += s2
```

As an alternative to `+=`, you can call the `append(_ :)` instance method:

```
var s = "hello"
let s2 = " world"
s.append(s2)
```

Another way of concatenating strings is with the `joined(separator :)` method. You start with an array of strings to be concatenated, and hand it the string that is to be inserted between all of them:

```
let s = "hello"
let s2 = "world"
let space = " "
let greeting = [s,s2].joined(separator:space)
```

The comparison operators are also overloaded so that they work with `String` operands. Two `String` values are equal (`==`) if they are, in the natural sense, the same text. A `String` is less than another if it is alphabetically prior.

Some additional convenient instance methods and properties are provided. `isEmpty` returns a `Bool` reporting whether this string is the empty string (`""`). `hasPrefix(_ :)` and `hasSuffix(_ :)` report whether this string starts or ends with another string; `"hello".hasPrefix("he")` is `true`. The `uppercase` and `lowercase` methods provide uppercase and lowercase versions of the original string.

Coercion between a `String` and an `Int` is possible. To make a string that represents an `Int`, it is sufficient to use string interpolation; alternatively, use a `String` initializer taking the `Int`:

```
let i = 7
let s = String(i) // "7"
```

Your string can also represent an `Int` in some other base; in the initializer, supply a `radix`: argument expressing the base:

```
let i = 31
let s = String(i, radix:16) // "1f"
```

A `String` that might represent a number can be coerced to a numeric type; an integer type will accept a `radix`: argument expressing the base. The coercion might fail, because the `String` might *not* represent a number of the specified type; so the result is not a number but an `Optional` wrapping a number (I haven't talked about `Optionals` yet, so you'll have to trust me for now; failable initializers are discussed in [Chapter 4](#)):

```
let s = "31"
let i = Int(s) // Optional(31)
let s2 = "1f"
let i2 = Int(s2, radix:16) // Optional(31)
```

Similarly, you can coerce a `Bool` to a `String`, which will be `"true"` or `"false"`. Going the other way, you can coerce the string `"true"` to the `Bool true` and the string `"false"` to the `Bool false`; again, this is a failable initializer, and any other string will fail.

The length of a `String`, in characters, is given by its `count` property:

```
let s = "hello"
let length = s.count // 5
```

This property is called `count` rather than `length` because a `String` doesn't really have a simple length. The `String` comprises a sequence of Unicode codepoints, but multiple Unicode codepoints can combine to form a single character; so, in order to know how many characters are represented by such a sequence, we actually have to walk through the sequence and resolve it into the characters that it represents.

You, too, can walk through a `String`'s characters. The simplest way is with the `for...in` construct (see [Chapter 5](#)). What you get when you do this are `Character` objects; I'll talk more about `Character` objects later:

```
let s = "hello"
for c in s {
    print(c) // print each Character on its own line
}
```

At an even deeper level, you can decompose a `String` into its UTF-8 codepoints or its UTF-16 codepoints, using the `utf8` and `utf16` properties:

```

let s = "\u{BF}Qui\u{E9}n?"
for i in s.utf8 {
    print(i) // 194, 191, 81, 117, 105, 195, 169, 110, 63
}
for i in s.utf16 {
    print(i) // 191, 81, 117, 105, 233, 110, 63
}

```

There is also a `unicodeScalars` property representing a collection (a `String.UnicodeScalarView`) of the String’s UTF-32 codepoints expressed as `UnicodeScalar` structs. To illustrate, here’s a utility function that turns a two-letter country abbreviation into an emoji representation of its flag:

```

func flag(country:String) -> String {
    let base : UInt32 = 127397
    var s = ""
    for v in country.unicodeScalars {
        s.unicodeScalars.append(UnicodeScalar(base + v.value!))
    }
    return String(s)
}
// and here's how to use it:
let s = flag(country:"DE")

```

The curious thing is that there aren’t more methods for standard string manipulation. How do you capitalize a string, or find out whether a string contains a given substring? Most modern programming languages have a compact, convenient way of doing things like that; Swift doesn’t. The reason appears to be that missing features are provided by the Foundation framework, to which you’ll always be linked in real life (importing `UIKit` imports `Foundation`). A Swift String is bridged to a Foundation `NSString`. This means that, to a large extent, Foundation `NSString` properties and methods magically spring to life whenever you are using a Swift String:

```

let s = "hello world"
let s2 = s.capitalized // "Hello World"

```

The `capitalized` property comes from the Foundation framework; it’s provided by Cocoa, not by Swift. It’s an `NSString` property; it appears tacked onto String “for free.” Similarly, here’s how to locate a substring of a string:

```

let s = "hello"
let range = s.range(of:"ell") // Optional(Range(...)) [details omitted]

```

I haven’t explained yet what an `Optional` is or what a `Range` is (I’ll talk about them later in this chapter), but that innocent-looking code has made a remarkable round-trip from Swift to Cocoa and back again: the Swift String `s` becomes an `NSString`, an `NSString` method is called, a Foundation `NSRange` struct is returned, and the `NSRange` is converted to a Swift `Range` and wrapped up in an `Optional`.

## The String–NSString Element Mismatch

Swift and Cocoa have different ideas of what the elements of a string are. The Swift conception involves characters. The NSString conception involves UTF-16 codepoints. Each approach has its advantages. The NSString way makes for great speed and efficiency in comparison to Swift, which must walk the string to investigate how the characters are constructed; but the Swift way gives what you would intuitively think of as the right answer. To emphasize this difference, a nonliteral Swift string has no `length` property; its analog to an NSString’s `length` is its `utf16.count`.

Fortunately, the element mismatch doesn’t arise very often in practice; but it can arise. Here’s a good test case:

```
let s = "Ha\u{030A}kon"
print(s.count) // 5
let length = (s as NSString).length // or: s.utf16.count
print(length) // 6
```

We’ve created our string (the Norwegian name Håkon) using a Unicode codepoint that combines with the previous codepoint to form a character with a ring over it. Swift walks the whole string, so it normalizes the combination and reports five characters. Cocoa just sees at a glance that this string contains six 16-bit codepoints.

## Character and String Index

You are more likely to be interested in a string’s characters than its codepoints. Codepoints are numbers, but what we naturally think of as characters are effectively minimal strings: a character is a single “letter” or “symbol” — formally, a *grapheme*. The equivalence between numeric codepoints and symbolic graphemes is provided, in Unicode, by the notion of a grapheme cluster. To embody this equivalence, Swift provides the Character object type (a struct), representing a single grapheme cluster.

A String (in Swift 4 and later) simply *is* a character sequence — quite literally, a Sequence of the Character objects that constitute it. That is why, as I mentioned earlier, you can walk through a string with `for...in` to obtain the String’s Characters, one by one; when you do that, you’re walking through the string *qua* character sequence:

```
let s = "hello"
for c in s {
    print(c) // print each Character on its own line
}
```

It isn’t common to encounter Character objects outside of some character sequence of which they are a part. There isn’t even a way to write a literal Character. To make a Character from scratch, initialize it from a single-character String:

```
let c = Character("h")
```

Similarly, you can pass a one-character String literal where a Character is expected, and many examples in this section will do so.

By the same token, you can initialize a String from a Character:

```
let c = Character("h")
let s = (String(c)).uppercased()
```

Characters can be compared for equality; “less than” means what you would expect it to mean.

Formally, a String is both a Sequence of Characters and a Collection of Characters. Sequence and Collection are protocols; I’ll discuss protocols in [Chapter 4](#), but what’s important for now is that a String is endowed with methods and properties that it gets by virtue of being a Sequence and a Collection.

A String has a `first` and `last` property; the resulting Character is wrapped in an Optional because the string might be empty:

```
let s = "hello"
let c1 = s.first // Optional("h")
let c2 = s.last // Optional("o")
```

The `firstIndex(of:)` method locates the first occurrence of a given character within the sequence and returns its index. Again, this is an Optional, because the character might be absent:

```
let s = "hello"
let firstL = s.firstIndex(of:"l") // Optional(2)
```

All Swift indexes are numbered starting with 0, so 2 means the third character. The index value here, however, is not an Int; I’ll explain in a moment what it is and what it’s good for.

A related method, `firstIndex(where:)`, takes a function that takes a Character and returns a Bool. This code locates the first character smaller than “f”:

```
let s = "hello"
let firstSmall = s.firstIndex {$0 < "f"} // Optional(1)
```

Those methods are matched by `lastIndex(of:)` and `lastIndex(where:)`.

A String has a `contains(_:)` method that returns a Bool, reporting whether a certain character is present:

```
let s = "hello"
let ok = s.contains("o") // true
```

Alternatively, `contains(where:)` takes a function that takes a Character and returns a Bool. This code reports whether the target string contains a vowel:

```
let s = "hello"
let ok = s.contains {"aeiou".contains($0)} // true
```

The `filter(_:)` method, too, takes a function that takes a `Character` and returns a `Bool`, effectively eliminating those characters for which `false` is returned. Here, we delete all consonants from a string:

```
let s = "hello"
let s2 = s.filter {"aeiou".contains($0)} // "eo"
```

The `dropFirst` and `dropLast` methods return, in effect, a new string without the first or last character, respectively:

```
let s = "hello"
let s2 = s.dropFirst() // "ello"
```

I say “in effect” because a method that extracts a substring returns, in reality, a `Substring` instance. The `Substring` struct is an efficient way of pointing at part of some original `String`, rather than having to generate a new `String`. When we call `s.dropFirst()` on the string `"hello"`, the resulting `Substring` points at the `"ello"` part of `"hello"`, which continues to exist; there is still only one string, and no new string storage memory is required.

In general, the difference between a `String` and a `Substring` will make little practical difference to you, because what you can do with a `String`, you can usually do also with a `Substring`. Nevertheless, they are different classes; this code won’t compile:

```
var s = "hello"
let s2 = s.dropFirst()
s = s2 // compile error
```

To pass a `Substring` where a `String` is expected, coerce the `Substring` to a `String` explicitly:

```
var s = "hello"
let s2 = s.dropFirst()
s = String(s2)
```

You can coerce the other way, too, from a `String` to a `Substring`.

`prefix(_:)` and `suffix(_:)` extract a `Substring` of a given length from the start or end of the original string:

```
var s = "hello"
s = String(s.prefix(4)) // "hell"
```

`split` breaks a string up into an array, according to a function that takes a `Character` and returns a `Bool`. In this example, I obtain the words of a `String`, where a “word” is simply defined as a run of `Characters` other than a space:

```
let s = "hello world"
let arr = s.split {$0 == " "} // ["hello", "world"]
```



The result is actually an array of Substrings. If we needed to get String objects, we could apply the `map(_:)` function and coerce them all to Strings. I'll talk about `map(_:)` in [Chapter 4](#), so you'll have to trust me for now:

```
let s = "hello world"
let arr = s.split {$0 == " "} .map {String($0)} // ["hello", "world"]
```

A String, *qua* character sequence, can also be manipulated similarly to an array. For example, you can use subscripting to obtain the character at a certain position. Unfortunately, this isn't as easy as it might be. What's the second character of "hello"? This doesn't compile:

```
let s = "hello"
let c = s[1] // compile error
```

The reason is that the indexes on a String are not Int values, but rather a nested type, `String.Index` (actually a type alias for `String.CharacterView.Index`). To make an object of this type is rather tricky. Start with a String's `startIndex` or `endIndex`, or with the return value from `firstIndex` or `lastIndex`; you can then call the `index(_:offsetBy:)` method to derive the index you want:

```
let s = "hello"
let ix = s.startIndex
let ix2 = s.index(ix, offsetBy:1)
let c = s[ix2] // "e"
```

The reason for this clumsy circumlocution is that Swift doesn't know where the characters of a character sequence are until it actually walks the sequence; calling `index(_:offsetBy:)` is how you make Swift do that.

To offset an index by a single position, you can obtain the next or preceding index value with the `index(after:)` and `index(before:)` methods. I could have written the preceding example like this:

```
let s = "hello"
let ix = s.startIndex
let c = s[s.index(after:ix)] // "e"
```

Another reason why it's necessary to think of a string index as an offset from the `startIndex` or `endIndex` is that those values may not be what you think they are — in particular, when you're dealing with a Substring. Consider, once again, the following:

```
let s = "hello"
let s2 = s.dropFirst()
```

Now `s2` is "ello". What, then, is `s2.startIndex` (as an Int)? Not 0, but 1 — because `s2` is a Substring pointing into the original "hello", where the index of the "e" is 1. Similarly, `s2.firstIndex(of:"o")` is not 3, but 4, because the index value is reckoned with respect to the original "hello".

Once you’ve obtained a desired character index value, you can use it to modify the String. The `insert(contentsOf:at:)` method inserts a string into a string:

```
var s = "hello"
let ix = s.index(s.startIndex, offsetBy:1)
s.insert(contentsOf: "ey, h", at: ix) // s is now "hey, hello"
```

Similarly, `remove(at:)` deletes a single character, and also returns that character. (Manipulations involving longer character stretches require use of a `Range`, which is the subject of the next section.)

On the other hand, a character sequence can be coerced directly to an array of `Character` objects — `Array("hello")` creates an array of the characters "h", "e", and so on — and array indexes *are* `Int`s and are easy to work with. Once you’ve manipulated the array of `Character`s, you can coerce it directly to a `String`. I’ll give an example in the next section (and I’ll discuss arrays, and say more about collections and sequences, in [Chapter 4](#)).

## Range

The `Range` object type (a struct) represents a pair of endpoints. There are two operators for forming a `Range` literal; you supply a start value and an end value, with one of the `Range` operators between them:

... (*closed range operator*)

The notation `a...b` means “everything from `a` up to `b`, *including* `b`.”

..< (*half-open range operator*)

The notation `a..b` means “everything from `a` up to but *not* including `b`.”

Spaces around a `Range` operator are legal.

The types of a `Range`’s endpoints will typically be some kind of number — most often, `Int`s:

```
let r = 1...3
```

If the end value is a negative literal, it has to be enclosed in parentheses or preceded by whitespace:

```
let r = -1000 ... -1
```

A very common use of a `Range` is to loop through numbers with `for...in`:

```
for ix in 1...3 {
    print(ix) // 1, then 2, then 3
}
```

There are no reverse Ranges: the start value of a Range can't be greater than the end value (the compiler won't stop you, but you'll crash at runtime). In practice, you can use Range's `reversed()` method to iterate from a higher value to a lower one:

```
for ix in (1...3).reversed() {  
    print(ix) // 3, then 2, then 1  
}
```

In **Chapter 5** I'll show how to create a custom operator that effectively generates a reverse Range.

You can also use a Range's `contains(_)` instance method to test whether a value falls within given limits:

```
let ix = // ... an Int ...  
if (1...3).contains(ix) { // ...
```

For purposes of testing containment, a Range's endpoints can be Doubles:

```
let d = // ... a Double ...  
if (0.1...0.9).contains(d) { // ...
```

There are also methods for learning whether two ranges overlap, and for clamping one range to another.

Another common use of a Range is to index into a sequence. Here's one way to get the second, third, and fourth characters of a String. As I suggested at the end of the preceding section, if we coerce the String to an array of Character, we can then use an Int Range as an index into that array, and coerce back to a String:

```
let s = "hello"  
let arr = Array(s)  
let result = arr[1...3]  
let s2 = String(result) // "ell"
```

A String is itself a sequence — a character sequence — so you can use a Range to index directly into a String; but then it has to be a Range of String.Index, which, as I've already pointed out, is rather tricky to obtain. By manipulating String.Index values, you can form a Range of the proper type and use it to extract a substring by subscripting:

```
let s = "hello"  
let ix1 = s.index(s.startIndex, offsetBy:1)  
let ix2 = s.index(ix1, offsetBy:2)  
let s2 = s[ix1...ix2] // "ell"
```

The `replaceSubrange(_:with:)` method splices into a range, modifying the string:

```
var s = "hello"  
let ix = s.startIndex  
let r = s.index(ix, offsetBy:1)...s.index(ix, offsetBy:3)  
s.replaceSubrange(r, with: "ipp") // s is now "hippo"
```

Similarly, you can delete a stretch of characters with the `removeSubrange(_:)` method:

```
var s = "hello"
let ix = s.startIndex
let r = s.index(ix, offsetBy:1)...s.index(ix, offsetBy:3)
s.removeSubrange(r) // s is now "ho"
```

It is possible to omit one of the endpoints from a Range literal, specifying a *partial range*. There are three kinds of partial range expression, corresponding to three types of Range-like struct. To illustrate, the following expressions are identical ways of specifying the range of an entire String `s`:

```
let range1 = s.startIndex..
```

If you need to convert a partial range to a range, call `relative(to:)`. In the preceding code, `range1` and `range2.relative(to:s)` are identical. But in general you won't need to do that, because a partial range literal can be used wherever you would use a range literal. For instance, a partial range is a legal String subscript value:

```
let s = "hello"
let ix2 = s.index(before: s.endIndex)
let s2 = s[..<ix2] // "hell"
```

I'll show further practical examples later on.

## Tuple

A *tuple* is a lightweight custom ordered collection of multiple values. As a type, it is expressed by surrounding the types of the contained values with parentheses, separated by a comma. Here's a declaration for a variable whose type is a tuple of an `Int` and a `String`:

```
var pair : (Int, String)
```

The literal value of a tuple is expressed in the same way — the contained values, surrounded with parentheses and separated by a comma:

```
var pair : (Int, String) = (1, "Two")
```

Those types can be inferred, so there's no need for the explicit type in the declaration:

```
var pair = (1, "Two")
```

Tuples are a pure Swift language feature; they are not compatible with Cocoa and Objective-C, so you'll use them only for values that Cocoa never sees. Within Swift, however, they have many uses. For example, a tuple is an obvious solution to the problem that a function can return only one value; a tuple *is* one value, but it *contains*

multiple values, so using a tuple as the return type of a function permits that function to return multiple values.

Tuples come with numerous linguistic conveniences. You can assign to a tuple of variable names as a way of assigning to multiple variables simultaneously:

```
let ix: Int
let s: String
(ix, s) = (1, "Two")
```

That's such a convenient thing to do that Swift lets you do it in one line, declaring and initializing multiple variables simultaneously:

```
let (ix, s) = (1, "Two")
```

To ignore one of the assigned values, use an underscore to represent it in the receiving tuple:

```
let pair = (1, "Two")
let (_, s) = pair // now s is "Two"
```

Assigning variable values to one another through a tuple swaps them safely:

```
var s1 = "hello"
var s2 = "world"
(s1, s2) = (s2, s1) // now s1 is "world" and s2 is "hello"
```

The `enumerated` method lets you walk a sequence with `for ... in` and receive, on each iteration, each successive element's index number along with the element itself; this double result comes to you as — you guessed it — a tuple:

```
let s = "hello"
for (ix,c) in s.enumerated() {
    print("character \(ix) is \(c)")
}
```

I also pointed out earlier that numeric instance methods such as `addingReportingOverflow` return a tuple.

You can refer to the individual elements of a tuple directly, in two ways. The first way is by index number, using a *literal number* (not a variable value) as the name of a message sent to the tuple with dot-notation:

```
let pair = (1, "Two")
let ix = pair.0 // now ix is 1
```

If you have a `var` reference to a tuple, you can assign into it by the same means:

```
var pair = (1, "Two")
pair.0 = 2 // now pair is (2, "Two")
```

The second way to access tuple elements is to give them labels. The notation is like that of function parameters, and must appear as part of the explicit or implicit type declaration. Here's one way to establish tuple element labels:

```
let pair : (first:Int, second:String) = (1, "Two")
```

And here's another way:

```
let pair = (first:1, second:"Two")
```

The labels are now part of the type of this value, and travel with it through subsequent assignments. You can then use them as literal messages, just like (and together with) the numeric literals:

```
var pair = (first:1, second:"Two")
let x = pair.first // 1
pair.first = 2
let y = pair.0 // 2
```

The tuple generated by the `enumerated` method has labels `offset` and `element`, so we can rewrite an earlier example like this:

```
let s = "hello"
for t in s.enumerated() {
    print("character \${t.offset} is \${t.element}")
}
```

You can assign from a tuple without labels into a corresponding tuple with labels (and vice versa):

```
let pair = (1, "Two")
let pairWithNames : (first:Int, second:String) = pair
let ix = pairWithNames.first // 1
```

You can also pass, or return from a function, a tuple without labels where a corresponding tuple with labels is expected:

```
func tupleMaker() -> (first:Int, second:String) {
    return (1, "Two") // no labels here
}
let ix = tupleMaker().first // 1
```

If you're going to be using a certain type of tuple consistently throughout your program, it might be useful to give it a type name. To do so, define a type alias. In my `LinkSame` app, I have a `Board` class describing and manipulating the game layout. The board is a grid of `Piece` objects. I need a way to describe positions of the grid. That's a pair of integers, so I define my own type as a tuple:

```
class Board {
    typealias Point = (x:Int, y:Int)
    // ...
}
```

The advantage of that notation is that it now becomes easy to use `Points` throughout my code. Given a `Point`, I can fetch the corresponding `Piece`:

```
func piece(at p:Point) -> Piece? {
    let (i,j) = p
    // ... error-checking goes here ...
    return self.grid[i][j]
}
```

Still, one should not overuse tuples. In a very real sense, they are not a full-fledged type. Keep your tuples small, light, and temporary.



Void, the type of value returned by a function that doesn't return a value, is actually a type alias for an empty tuple. That's why it is also notated as ().

## Optional

The Optional object type (an enum) wraps another object of any type. What makes an Optional optional is this: it *might* wrap another object, but then again it might not. Think of an Optional as being itself a kind of shoebox — a shoebox which can quite legally be empty.

Let's start by creating an Optional that does wrap an object. Suppose we want an Optional wrapping the String "howdy". One way to create it is with the Optional initializer:

```
var stringMaybe = Optional("howdy")
```

If we log `stringMaybe` to the console with `print`, we'll see an expression identical to the corresponding initializer: `Optional("howdy")`.

After that declaration and initialization, `stringMaybe` is typed, not as a String, nor as an Optional plain and simple, but as an Optional wrapping a String. This means that any other Optional wrapping a String can be assigned to it — but not an Optional wrapping some other type. This code is legal:

```
var stringMaybe = Optional("howdy")
stringMaybe = Optional("farewell")
```

This code, however, is not legal:

```
var stringMaybe = Optional("howdy")
stringMaybe = Optional(123) // compile error
```

`Optional(123)` is an Optional wrapping an Int, and you can't assign an Optional wrapping an Int where an Optional wrapping a String is expected.

Optionals are so important to Swift that special syntax for working with them is baked into the language. The usual way to make an Optional is not to use the Optional initializer (though you can certainly do that), but to assign or pass a value of some type to a reference that is already typed as an Optional wrapping that type. This seems as if it should not be legal — but it is. Once `stringMaybe` is typed as an

Optional wrapping a `String`, it is legal to assign a `String` directly to it. The outcome is that the assigned `String` is wrapped in an `Optional` for us, automatically:

```
var stringMaybe = Optional("howdy")
stringMaybe = "farewell" // now stringMaybe is Optional("farewell")
```

We also need a way of typing something *explicitly* as an `Optional` wrapping a `String`. Otherwise, we cannot declare a variable or parameter with an `Optional` type. Formally, an `Optional` is a generic, so an `Optional` wrapping a `String` is an `Optional<String>`. (I'll explain that syntax in [Chapter 4](#).) However, you don't have to write that. The Swift language supports syntactic sugar for expressing an `Optional` type: use the name of the wrapped type followed by a question mark:

```
var stringMaybe : String?
```

Thus I don't need to use the `Optional` initializer at all. I can type the variable as an `Optional` wrapping a `String` and assign a `String` into it for wrapping, all in one move:

```
var stringMaybe : String? = "howdy"
```

That, in fact, is the normal way to make an `Optional` in Swift.

Once you've got an `Optional` wrapping a particular type, you can use it wherever an `Optional` wrapping that type is expected — just like any other value. If a function expects an `Optional` wrapping a `String` as its parameter, you can pass `stringMaybe` as the argument:

```
func optionalExpecter(_ s:String?) {}
let stringMaybe : String? = "howdy"
optionalExpecter(stringMaybe)
```

Moreover, where an `Optional` wrapping a certain type of value is expected, you can pass a value of that wrapped type instead. That's because parameter passing is just like assignment: an unwrapped value will be wrapped implicitly for you. If a function expects an `Optional` wrapping a `String`, you can pass a `String` argument, which will be wrapped into an `Optional` in the received parameter:

```
func optionalExpecter(_ s:String?) {
    // ... here, s will be an Optional wrapping a String ...
    print(s)
}
optionalExpecter("howdy") // console prints: Optional("howdy")
```

But you cannot do the opposite — you cannot use an `Optional` wrapping a type where the wrapped type is expected. This won't compile:

```
func realStringExpecter(_ s:String) {}
let stringMaybe : String? = "howdy"
realStringExpecter(stringMaybe) // compile error
```



The error message reads: “Value of Optional type String? must be unwrapped.” You’re going to be seeing that sort of message a lot in Swift, so get used to it! If you want to use an Optional where the type of thing it wraps is expected, you must *unwrap* the Optional — that is, you must reach inside it and *retrieve* the actual thing that it wraps. Now I’m going to talk about how to do that.

## Unwrapping an Optional

We have seen more than one way to wrap an object in an Optional. But what about the opposite procedure? How do we unwrap an Optional to get at the object wrapped inside it? One way is to use the *unwrap operator* (or *forced unwrap operator*), which is a postfix exclamation mark:

```
func realStringExpecter(_ s:String) {}  
let stringMaybe : String? = "howdy"  
realStringExpecter(stringMaybe!)
```

In that code, the `stringMaybe!` syntax expresses the operation of reaching inside the Optional `stringMaybe`, grabbing the wrapped value, and substituting it at that point. Since `stringMaybe` is an Optional wrapping a `String`, the thing inside it is a `String`. That is exactly what the `realStringExpecter` function wants as its parameter! `stringMaybe` is an Optional *wrapping* the `String` "howdy", but `stringMaybe!` *is* the `String` "howdy".

If an Optional wraps a certain type, you cannot send it a message expected by that type. You must unwrap it first. Let’s try to get an uppercase version of `stringMaybe`:

```
let stringMaybe : String? = "howdy"  
let upper = stringMaybe.uppercased() // compile error
```

The solution is to unwrap `stringMaybe` to get at the `String` inside it. We can do this directly, in place, using the `unwrap` operator:

```
let stringMaybe : String? = "howdy"  
let upper = stringMaybe!.uppercased()
```

If an Optional is to be used several times where the unwrapped type is expected, and if you’re going to be unwrapping it with the `unwrap` operator each time, your code can quickly start to look like the dialog from a 1960s Batman comic. For example, an app’s window is an Optional `UIWindow` property (`self.window`):

```
// self.window is an Optional wrapping a UIWindow  
self.window!.rootViewController = RootViewController()  
self.window!.backgroundColor = UIColor.white  
self.window!.makeKeyAndVisible()
```

That sort of thing soon gets old (or silly). One obvious alternative is to assign the unwrapped value *once* to a variable of the wrapped type and then use that variable:

```
// self.window is an Optional wrapping a UIWindow
let window = self.window!
// now window (not self.window) is a UIWindow, not an Optional
window.rootViewController = RootViewController()
window.backgroundColor = UIColor.white
window.makeKeyAndVisible()
```

## Implicitly unwrapped Optional

Swift provides another way of using an Optional where the wrapped type is expected: you can declare the Optional *type* as being *implicitly unwrapped*. An implicitly unwrapped Optional is an Optional, but the compiler permits some special magic associated with it: its value can be used *directly* where the wrapped type is expected. You *can* unwrap an implicitly unwrapped Optional explicitly, but you don't have to, because it will be unwrapped for you, automatically, if you try to use it where the wrapped type is expected. Moreover, Swift provides syntactic sugar for expressing an implicitly unwrapped Optional type: use the name of the wrapped type followed by an exclamation mark:

```
func realStringExpecter(_ s:String) {}
var stringMaybe : String! = "howdy"
realStringExpecter(stringMaybe) // no problem
```

Bear in mind that *an implicitly unwrapped Optional is still an Optional*. It's just a convenience. By declaring something as an implicitly unwrapped Optional, you are asking the compiler, if you happen to use this value where the wrapped type is expected, to forgive you and to unwrap the value for you.

In reality, an implicitly unwrapped Optional type is not really a distinct type; it is merely an Optional marked in a special way that allows it to be used where the unwrapped type is expected. For this reason, implicit unwrapping does not propagate by assignment. Here's a case in point. If `self` is a `UIViewController`, then `self.view` is typed as `UIView!`. As a result, this expression is legal (assume `v` is a `UIView`):

```
self.view.addSubview(v)
```

But this is not legal:

```
let mainview = self.view
mainview.addSubview(v) // compile error
```

The problem is that, although `self.view` is an implicitly unwrapped Optional wrapping a `UIView`, `mainview` is a *normal* Optional wrapping a `UIView`, and so it would have to be unwrapped explicitly before you could send it the `addSubview` message. Alternatively, you could unwrap the implicitly unwrapped Optional explicitly at the outset:

```
let mainview = self.view!
mainview.addSubview(v)
```

In real life, the primary situation in which you’re likely to declare an implicitly unwrapped Optional is when an instance property’s initial value can’t be provided until after the instance itself is created. I’ll give some examples at the end of this chapter.

## The keyword nil

I have talked so far about Optionals that contain a wrapped value. But what about an Optional that *doesn’t* contain any wrapped value? Such an Optional is, as I’ve already said, a perfectly legal entity; that, indeed, is the whole point of Optionals.

You are going to need a way to *ask* whether an Optional contains a wrapped value, and a way to *specify* an Optional *without* a wrapped value. Swift makes both of those things easy, through the use of a special keyword, `nil`:

*To learn whether an Optional contains a wrapped value*

Test the Optional for equality against `nil`. If the test succeeds, the Optional is empty. An empty Optional is also reported in the console as `nil`.

*To specify an Optional with no wrapped value*

Assign or pass `nil` where the Optional type is expected. The result is an Optional of the expected type, containing no wrapped value.

To illustrate:

```
var stringMaybe : String? = "Howdy"
print(stringMaybe) // Optional("Howdy")
if stringMaybe == nil {
    print("it is empty") // does not print
}
stringMaybe = nil
print(stringMaybe) // nil
if stringMaybe == nil {
    print("it is empty") // prints
}
```

The keyword `nil` lets you express the concept, “an Optional wrapping the appropriate type, but not actually containing any object of that type.” Clearly, that’s very convenient magic; you’ll want to take advantage of it. It is very important to understand, however, that it *is* magic: `nil` in Swift is *not* a thing and is *not* a value. *It is a shorthand.* It is natural to think and speak as if this shorthand were real. I will often say that something “is `nil`.” But in reality, nothing “is `nil`”; `nil` isn’t a thing. What I really mean is that this thing is equatable with `nil`, because it is an Optional not wrapping anything. (I’ll explain in [Chapter 4](#) how `nil`, and Optionals in general, really work.)

Because a variable typed as an Optional can be `nil`, Swift follows a special initialization rule: a variable (`var`) typed as an Optional *is* `nil`, automatically:

```
func optionalExpecter(_ s:String?) {}
var stringMaybe : String?
optionalExpecter(stringMaybe)
```

That code looks as if it should be illegal. We declared a variable `stringMaybe`, but we never assigned it a value. Nevertheless we are now passing it around as if it were an actual thing. That’s because it *is* an actual thing. This variable has been *implicitly initialized* — to `nil`. A variable (`var`) typed as an `Optional` is the *only* sort of variable that gets implicit initialization in Swift.

We come now to perhaps the most important rule in all of Swift: You *cannot unwrap an Optional containing nothing* (an `Optional` equatable with `nil`). Such an `Optional` contains nothing; there’s nothing to unwrap. Like Oakland, there’s no there there. In fact, explicitly unwrapping an `Optional` containing nothing will *crash your program* at runtime:

```
var stringMaybe : String?
let s = stringMaybe! // crash
```

The crash message reads: “Fatal error: unexpectedly found `nil` while unwrapping an `Optional` value.” Get used to it, because you’re going to be seeing it a lot. This is an easy mistake to make. Unwrapping an `Optional` that contains no value is, in fact, probably the most common way to crash a Swift program. You should look upon this kind of crash as a blessing. Very often, in fact, you will *want* to crash if your `Optional` contains no value, because it *should* contain a value, and the fact that it doesn’t indicates that you’ve made a mistake elsewhere.

In the long run, however, crashing is bad. To eliminate this kind of crash, you need to ensure that your `Optional` contains a value, and *don’t* unwrap it if it doesn’t! Ensuring that an `Optional` contains a value before attempting to unwrap it is clearly a very important thing to do. Accordingly, Swift provides several convenient ways of doing it. I’ll describe some of them now, and I’ll discuss others in [Chapter 5](#).

One obvious approach is to test your `Optional` against `nil` explicitly before you unwrap it:

```
var stringMaybe : String?
// ... stringMaybe might be assigned a real value here ...
if stringMaybe != nil {
    let s = stringMaybe!
    // ...
}
```

But there’s a more elegant way, as I shall now explain.

## Optional chains

A common situation is that you want to send a message to the value wrapped inside an `Optional`. You *cannot* send such a message to the `Optional` *itself*. If you try to do so, you will get an error message from the compiler:

```
let stringMaybe : String? = "howdy"
let upper = stringMaybe.uppercased() // compile error
```

You must unwrap the `Optional` first, so that you can send that message to the *actual* thing wrapped inside. Conveniently, you can unwrap the `Optional` *in place*. I gave an example earlier:

```
let stringMaybe : String? = "howdy"
let upper = stringMaybe!.uppercased()
```

That form of code is called an *Optional chain*. In the middle of a chain of dot-notation, you have unwrapped an `Optional`.

However, if you unwrap an `Optional` that contains no wrapped object, you'll crash. So what if you're *not sure* whether this `Optional` contains a wrapped object? How can you send a message to the value inside an `Optional` in that situation?

Swift provides a special shorthand for exactly this purpose. To send a message *safely* to the value wrapped inside an `Optional` that might be empty, you can *unwrap the Optional optionally*. To do so, unwrap the `Optional` with the question mark postfix operator instead of the exclamation mark:

```
var stringMaybe : String?
// ... stringMaybe might be assigned a real value here ...
let upper = stringMaybe?.uppercased()
```

That's an `Optional` chain in which you used a question mark to unwrap the `Optional`. By using that notation, you have unwrapped the `Optional` optionally — meaning conditionally. The condition in question is one of safety; a test for `nil` is performed for us. Our code means: "If `stringMaybe` contains a `String`, unwrap it and send that `String` the `uppercased` message. If it doesn't (that is, if it equates to `nil`), *do not* unwrap it and *do not* send it any messages!"

Such code is a double-edged sword. On the one hand, if `stringMaybe` is `nil`, you won't crash at runtime. On the other hand, if `stringMaybe` is `nil`, that line of code won't do anything useful — you won't get any `uppercase` string.

But now there's a new question. In that code, we initialized a variable `upper` to an expression that involves sending the `uppercased` message. Now it turns out that the `uppercased` message might not even be sent. So what, exactly, is `upper` initialized *to*?

To handle this situation, Swift has a special rule. If an `Optional` chain contains an optionally unwrapped `Optional`, and if this `Optional` chain produces a value, that value is itself *wrapped in an Optional*. Thus, `upper` is typed as an `Optional` wrapping a

String. This works brilliantly, because it covers both possible cases. Let's say, first, that `stringMaybe` contains a String:

```
var stringMaybe : String?
stringMaybe = "howdy"
let upper = stringMaybe?.uppercased()
```

After that code, `upper` is *not* a String; it is *not* "HOWDY". It is an Optional wrapping "HOWDY".

On the other hand, if the attempt to unwrap the Optional fails, the Optional chain can return `nil` instead:

```
var stringMaybe : String?
let upper = stringMaybe?.uppercased()
```

After that code, `upper` is typed as an Optional wrapping a String, but it wraps no string; its value is `nil`.

Unwrapping an Optional optionally in this way is elegant and safe; even if `stringMaybe` is `nil`, we won't crash at runtime. On the other hand, we've ended up with yet another Optional on our hands! `upper` is typed as an Optional wrapping a String, and in order to use that String, we're going to have to unwrap `upper`. And we don't know whether `upper` is `nil`, so we have exactly the same problem we had before — we need to make sure that we unwrap `upper` safely, and that we don't accidentally unwrap an empty Optional.

Longer Optional chains are legal. No matter how many Optionals are unwrapped in the course of the chain, if any of them is unwrapped optionally, the entire expression produces an Optional wrapping the type it would have produced if the Optionals were unwrapped normally, and is free to fail safely at any point along the way:

```
// self is a UIViewController
let f = self.view?.window?.rootViewController?.view?.frame
```

The frame property of a view is a `CGRect`. But after that code, `f` is *not* a `CGRect`. It's an Optional wrapping a `CGRect`. If *any* of the optional unwrapping along the chain fails (because the Optional we propose to unwrap is `nil`), `f` will be `nil` to indicate failure.

(Observe that the preceding code does *not* end up nesting Optionals; it doesn't produce a `CGRect` wrapped in an Optional wrapped in an Optional, and so on, merely because there are multiple Optionals being optionally unwrapped in the chain! However, it is possible, for other reasons, to end up with an Optional wrapped in an Optional, and I'll call out some examples as we proceed.)

If a function call returns an Optional, you can unwrap the result and use it. You don't necessarily have to capture the result in order to do that; you can unwrap it in place, by putting an exclamation mark or a question mark after the function call (that is,

after the closing parenthesis). That's really no different from what we've been doing all along, except that instead of an Optional property or variable, this is a function call that returns an Optional:

```
class Dog {
    var noise : String?
    func speak() -> String? {
        return self.noise
    }
}
let d = Dog()
let bigname = d.speak()?.uppercased()
```

After that, don't forget, `bigname` is not a `String` — it's an Optional wrapping a `String`.

You can also assign safely into an Optional chain. If any of the optionally unwrapped Optionals in the chain turns out to be `nil`, nothing happens:

```
// self is a UIViewController
self.navigationController?.hidesBarsOnTap = true
```

A view controller might or might not have a navigation controller, so its `navigationController` property is an Optional. In that code, we are setting our navigation controller's `hidesBarsOnTap` property safely; if we happen to have no navigation controller, no harm is done — because nothing happens.

When assigning into an Optional chain, if you also want to know whether the assignment succeeded, you can capture the result of the assignment as an Optional wrapping a `Void` and test it for `nil`:

```
let ok : Void? = self.navigationController?.hidesBarsOnTap = true
```

Now, if `ok` is not `nil`, `self.navigationController` was safely unwrapped and the assignment succeeded.

It is also possible to assign into an Optional chain where the chain ends with a question mark; if the chain is `nil`, no assignment takes place. For example, a `UILabel` has an Optional `String` text property:

```
let label = UILabel() // label.text is nil
label.text? = "testing" // label.text is _still_ nil!
```

But I can think of no practical use case, so perhaps this should be regarded as a curiosity.



The `!` and `?` postfix operators, which are used to unwrap an Optional, have basically *nothing* to do with the `!` and `?` used with type names as syntactic sugar for expressing Optional types (such as `String?` and `String!`). The outward similarity has confused many a beginner.

## Optional map and flatMap

When you want to do something to an `Optional`'s wrapped value more elaborate than sending it a simple message, such as calling `uppercased()`, while keeping the advantages of `Optional` chaining, Swift provides a method that elegantly and safely permits you to do so: `map(_:_:)`. This is a method of `Optional` itself, so it's fine to send it to an `Optional`. The parameter is a function that you supply (usually an anonymous function) that takes whatever type is wrapped in the `Optional`; the *unwrapped* value is passed to this function, and now you can manipulate it in any desired manner. The result of the function is then wrapped as an `Optional`. If the original `Optional` was `nil`, the whole thing produces `nil`, safely:

```
let s : String? = "howdy"
let s2 = s.map {($0 + ", world").uppercased()}
```

In that example, we start with an `Optional` wrapping a `String`; we append a string to the string, and uppercase the result. You can't apply the `+` operator to an `Optional` string, but inside the `map` function, the string is *not* `Optional`. Afterward, `s2` is an `Optional` wrapping a `String`. If `s` had turned out to be `nil`, there would be no crash, and `s2` would be set to `nil` as well.

The output `Optional` type doesn't have to be the same as the input `Optional` type. To illustrate, I'll use a closely related `Optional` method, `flatMap(_:_:)`. Here's an elegant way to coerce an `Optional String` to an (`Optional`) `Int`:

```
let s : String? = // whatever
let i = s.flatMap {Int($0)}
```

In that code, we attempt to unwrap an `Optional String` and coerce it to an `Int`. The result is an `Optional Int`, which will be `nil` if `s` is `nil`, or if `s` isn't `nil` but the coercion fails because the string wrapped by `s` doesn't represent an integer.

That example also illustrates the difference between `map` and `flatMap`. If the `map` function itself produces an `Optional` — as coercing a `String` to an `Int` does — `flatMap` unwraps it before wrapping the result in an `Optional`. `map` doesn't do that, so if we had used `map` here, we would have ended up with a double-wrapped `Optional` (an `Int??`).

## Comparison with Optional

In an equality comparison with something other than `nil`, an `Optional` gets special treatment: the wrapped value, not the `Optional` itself, is compared. This works:

```
let s : String? = "Howdy"
if s == "Howdy" { // ... they _are_ equal!
```

That shouldn't work — how can an `Optional` be the same as a `String?` — but it does. Instead of comparing the `Optional` itself with `"Howdy"`, Swift automatically (and



safely) compares its wrapped value (if there is one) with "Howdy". If the wrapped value is "Howdy", the comparison succeeds. If the wrapped value is not "Howdy", the comparison fails. If there is *no* wrapped value (*s* is *nil*), the comparison fails too — safely! You can compare *s* to *nil* or to a *String*, and the comparison works correctly in all cases.

(This feature depends upon the wrapped type itself being usable with *==*. This means that the wrapped type must adopt the *Equatable* protocol; otherwise, the compiler will stop you from using *==* with an *Optional* wrapping it. I'll talk about protocols and *Equatable* in Chapters 4 and 5.)

Direct comparison of *Optionals* does *not* work for an inequality comparison, using the greater-than and less-than operators:

```
let i : Int? = 2
if i < 3 { // compile error
```

To perform that sort of comparison, you can unwrap safely and perform the comparison directly on the unwrapped value:

```
if i != nil && i! < 3 { // ... it _is_ less
```



Do not compare an implicitly unwrapped *Optional* with anything; you can crash at runtime.

## Why Optionals?

Now that you know *how* to use an *Optional*, you are probably wondering *why* to use an *Optional*. Why does Swift have *Optionals* at all? What are they good for?

One important use of *Optionals* is to permit a value to be *marked as empty or erroneous*. Many built-in Swift functions use an *Optional* this way:

```
let arr = [1,2,3]
let ix = arr.firstIndex(of:4)
if ix == nil { // ...
```

Swift's *firstIndex(of:)* method returns an *Optional* because the object sought might not be present, in which case it has *no* index. The type returned cannot be an *Int*, because there is no *Int* value that can be taken to mean, "I didn't find this object at all." Returning an *Optional* solves the problem neatly: *nil* means "I didn't find the object," and otherwise the actual *Int* result is sitting there wrapped up in the *Optional*.

Another purpose of *Optionals* is to provide *interchange of object values with Objective-C*. In *Objective-C*, any object reference can be *nil*. You need a way to send *nil* to *Objective-C* and to receive *nil* from *Objective-C*. Swift *Optionals* provide your only way to do that.

Swift will typically assist you by a judicious use of appropriate types in the Cocoa APIs. Consider a `UIView`'s `backgroundColor` property. It's a `UIColor`, but it can be `nil`, and you are allowed to set it to `nil`. Thus, it is typed as `UIColor?`. You don't need to work directly with Optionals in order to *set* such a value! Remember, assigning the wrapped type to an Optional is legal, as the assigned value will be wrapped for you. You can set `myView.backgroundColor` to a `UIColor` — or to `nil`. If you *get* a `UIView`'s `backgroundColor`, you now have an Optional wrapping a `UIColor`, *and you must be conscious of that fact*, for all the reasons I've already discussed: if you're not, surprising things can happen:

```
let v = UIView()
let c = v.backgroundColor
let c2 = c.withAlphaComponent(0.5) // compile error
```

You're trying to send the `withAlphaComponent` message to `c`, as if it were a `UIColor`. It *isn't* a `UIColor`. It's an Optional wrapping a `UIColor`. Xcode will try to help you in this situation; if you use code completion ([Chapter 10](#)) to enter the name of the `withAlphaComponent` method, Xcode will insert a question mark after `c`, (optionally) unwrapping the Optional and giving you legal code:

```
let v = UIView()
let c = v.backgroundColor
let c2 = c?.withAlphaComponent(0.5)
```

In the vast majority of situations, however, a Cocoa object type will *not* be marked as an Optional. That's because, although in theory it *could* be `nil` (because any Objective-C object reference can be `nil`), in practice it won't be. Swift saves you a step by treating the value as the object type itself. This magic is performed by hand-tweaking the Cocoa APIs (also called *auditing*). In the very first public version of Swift (in June of 2014), *all* object values received from Cocoa were typed as Optionals (usually implicitly unwrapped Optionals); but then Apple embarked on the massive project of hand-tweaking the APIs to eliminate Optionals that didn't need to be Optionals, and that project is now essentially complete.

Finally, an important use of Optionals is to *defer initialization* of an instance property. If a variable (declared with `var`) is typed as an Optional, it has a value even if you don't initialize it — namely `nil`. That comes in very handy in situations where you know something *will* have a value, but not right away.

One way this can happen is that a property represents data that will take time to acquire. In my *Albumen* app, as we launch, I create an instance of my root view controller. I also want to gather a bunch of data about the user's music library and store that data in instance properties of the root view controller instance. But gathering that data will take time. Therefore I must instantiate the root view controller *first* and gather the data *later*, because if we pause to gather the data *before* instantiating the root view controller, the app will take too long to launch — the delay will be

perceptible, and we might even crash (because iOS forbids long launch times). Therefore the data properties are all typed as Optionals; they are `nil` until the data are gathered, at which time they are assigned their “real” values:

```
class RootViewController : UITableViewController {
    var albums : [MPMediaItemCollection]? // initialized to nil
    // ...
}
```

This approach has a second advantage: as with `firstIndex`, the initial `nil` value of `albums` is a signal to the rest of my code that we don’t yet have a real value. When my *Albumen* app launches, it displays a table listing all the user’s music albums. At launch time, however, that data has not yet been gathered. My table-display code tests `albums` to see whether it’s `nil` and, if it is, displays an empty table. After gathering the data, I tell my table to display its data *again*. This time, the table-display code finds that `albums` is *not* `nil`, but rather consists of actual data — and it now displays that data. The use of an Optional allows one and the same value, `albums`, to store the data or to state that there is no data.

Sometimes, a property’s value isn’t time-consuming to acquire, but it *still* won’t be ready at initialization time. A common case in real life is an outlet, which is a reference to something in your interface such as a button:

```
class ViewController: UIViewController {
    @IBOutlet var myButton: UIButton! // initialized to nil
    // ...
}
```

Ignore, for now, the `@IBOutlet` designation, which is an internal hint to Xcode (as I’ll explain in [Chapter 8](#)). The important thing is that this property, `myButton`, won’t have a value when our `ViewController` instance first comes into existence, but shortly thereafter the view controller’s view will be loaded and `myButton` will be set so that it points to an actual `UIButton` object in the interface. Therefore, the variable is typed as an implicitly unwrapped Optional:

- It’s an Optional because we need a placeholder value (namely `nil`) for `myButton` when the `ViewController` instance first comes into existence.
- It’s implicitly unwrapped so that in our code, once `self.myButton` has been assigned a `UIButton` value, we can treat it as a reference to an actual `UIButton`, passing through the Optional without noticing that it *is* an Optional.

In real life, nearly all of this view controller’s code will run after the view is loaded and the actual button is assigned to `myButton`. So the implicitly unwrapped Optional is generally safe: code can confidently refer to `myButton` without fear that it might be `nil`. So an implicitly unwrapped Optional is appropriate here.



---

# Object Types

In the preceding chapter, I discussed some built-in object types. But I have not yet explained object types themselves. As I mentioned in [Chapter 1](#), Swift object types come in three flavors: enum, struct, and class. What are the differences between them? And how would you create your own object type?

In this chapter, I'll describe first object types generally and then each of the three flavors. Then I'll explain three Swift ways of giving an object type greater flexibility: protocols, generics, and extensions. Finally, I'll complete the survey of Swift's main built-in types with three umbrella types and three collection types.

## Object Type Declarations and Features

Object types are declared with the flavor of the object type (enum, struct, or class), the name of the object type (which should start with a capital letter), and curly braces:

```
class Manny {  
}  
struct Moe {  
}  
enum Jack {  
}
```

The visibility of an object type to other code — its scope — depends upon where its declaration appears (compare [“Variable Scope and Lifetime” on page 71](#)):

### *Top level*

Object types declared at the top level of a file will, by default, be visible to all files in the same module. This is the usual place for object type declarations.

### *Inside another type declaration*

Sometimes it's useful to declare a type inside the declaration of another type, giving it a namespace. This is called a *nested type*.

### *Function body*

An object type declared within the body of a function will exist only inside the scope of the curly braces that surround it; such declarations are legal but rare.

Declarations for any object type may contain within their curly braces the following things:

### *Initializers*

An object type is merely the *type* of an object. The purpose of declaring an object type will usually (though not always) be so that you can make an actual object — an *instance* — that *has* this type. An *initializer* is a function, declared and called in a special way, allowing you to do that.

### *Properties*

A variable declared at the top level of an object type declaration is a *property*.

By default, a property is an *instance property*. An instance property is scoped to an instance: it is accessed through a particular instance of this type, and its value can be different for every instance of this type.

Alternatively, a property can be a *static/class property*. For an enum or struct, it is declared with the keyword `static`; for a class, it may instead be declared with the keyword `class`. It belongs to the object type itself: it is accessed through the type, and it has just one value, associated with the type.

### *Methods*

A function declared at the top level of an object type declaration is a *method*.

By default, a method is an *instance method*: it is called by sending a message to a particular instance of this type. Inside an instance method, `self` is the instance.

Alternatively, a method can be a *static/class method*. For an enum or struct, it is declared with the keyword `static`; for a class, it may be declared instead with the keyword `class`. It is called by sending a message to the type. Inside a static/class method, `self` is the type.

### *Subscripts*

A subscript is a special kind of method, called by appending square brackets to an instance reference or type name.

### *Object type declarations*

An object type declaration can contain an object type declaration — a nested type. From inside the containing object type, the nested type is in scope; from

outside the containing object type, the nested type must be referred to through the containing object type. The containing object type is a namespace for the nested type.

## Initializers

An *initializer* is a function for producing an instance of an object type. Strictly speaking, it is a static/class method, because it is called by talking to the object type. It is usually called by means of special syntax: the name of the type is followed directly by parentheses, as if the type itself were a function. When an initializer is called, a new instance is created and returned as a result. You will usually do something with the returned instance, such as assigning it to a variable, in order to preserve it and work with it in subsequent code.

Suppose we have a Dog class:

```
class Dog {  
}
```

Then we can make a Dog instance like this:

```
Dog()
```

That code, however, though legal, is silly — so silly that it warrants a warning from the compiler. We have created a Dog instance, but there is no reference to that instance. Without such a reference, the Dog instance comes into existence and then immediately vanishes in a puff of smoke. The usual sort of thing is more like this:

```
let fido = Dog()
```

Now our Dog instance will persist as long as the variable `fido` persists (see [Chapter 3](#)) and the variable `fido` gives us a reference to our Dog instance so that we can use it.

Observe that `Dog()` calls an initializer even though our Dog class doesn't declare any initializers! The reason is that object types may have *implicit initializers*. These are a convenience that save you the trouble of writing your own initializers. But you *can* write your own initializers, and you will often do so.

### How to write an initializer

An initializer is a kind of function, but its declaration syntax doesn't involve the keyword `func` or a return type. Instead, you use the keyword `init` with a parameter list, followed by curly braces containing the code. An object type can have multiple initializers, distinguished by their parameters. A frequent use of the parameters is to set the values of instance properties.

Here's a Dog class with two instance properties, `name` (a String) and `license` (an Int). We give these instance properties default values that are effectively placeholders — an empty string and the number zero. Then we declare three initializers, so that the

caller can create a Dog instance in three different ways: by supplying a name, by supplying a license number, or by supplying both. In each initializer, the parameters that are supplied are used to set the values of the corresponding properties:

```
class Dog {
    var name = ""
    var license = 0
    init(name:String) {
        self.name = name
    }
    init(license:Int) {
        self.license = license
    }
    init(name:String, license:Int) {
        self.name = name
        self.license = license
    }
}
```

In that code, in each initializer, I've given each parameter the same name as the property to which it corresponds. There's no reason to do that apart from stylistic clarity. In the initializer function body, I can distinguish the parameter from the property by using `self` explicitly to access the property.

The result of that declaration is that I can create a Dog in three different ways:

```
let fido = Dog(name:"Fido")
let rover = Dog(license:1234)
let spot = Dog(name:"Spot", license:1357)
```

But now I can't create a Dog with *no* initializer parameters. I wrote initializers, so my implicit initializer went away. This code is no longer legal:

```
let puff = Dog() // compile error
```

I could *make* that code legal by declaring an initializer with no parameters:

```
class Dog {
    var name = ""
    var license = 0
    init() {
    }
    init(name:String) {
        self.name = name
    }
    init(license:Int) {
        self.license = license
    }
    init(name:String, license:Int) {
        self.name = name
        self.license = license
    }
}
```



Now, the truth is that we don't need those four initializers, because an initializer is a function, and a function's parameters can have default values. I can condense all that code into a single initializer, like this:

```
class Dog {
    var name = ""
    var license = 0
    init(name:String = "", license:Int = 0) {
        self.name = name
        self.license = license
    }
}
```

I can still make an actual Dog instance in four different ways:

```
let fido = Dog(name:"Fido")
let rover = Dog(license:1234)
let spot = Dog(name:"Spot", license:1357)
let puff = Dog()
```

Now comes the really interesting part. In my property declarations, I can *eliminate* the assignment of default initial values (as long as I declare explicitly the *type* of each property):

```
class Dog {
    var name : String // no default value!
    var license : Int // no default value!
    init(name:String = "", license:Int = 0) {
        self.name = name
        self.license = license
    }
}
```

That code is legal (and common) — because an initializer initializes! In other words, I don't have to give my properties initial values in their declarations, *provided I give them initial values in all initializers*. That way, I am guaranteed that all my instance properties have values when the instance comes into existence, which is what matters. Conversely, an instance property without an initial value when the instance comes into existence *is illegal*. A property *must* be initialized either as part of its declaration or by every initializer, and the compiler will stop you otherwise.

The Swift compiler's insistence that all instance properties be properly initialized is a valuable feature of Swift. (Contrast Objective-C, where instance properties can go uninitialized — and often do, leading to mysterious errors later.) Don't fight the compiler; work with it. The compiler will help you by giving you an error message ("Return from initializer without initializing all stored properties") until *all* your initializers initialize *all* your instance properties:

```
class Dog {
    var name : String
    var license : Int
    init(name:String = "") {
        self.name = name // compile error (do you see why?)
    }
}
```

Because setting an instance property in an initializer counts as initialization, it is legal even if the instance property is a constant declared with `let`:

```
class Dog {
    let name : String
    let license : Int
    init(name:String = "", license:Int = 0) {
        self.name = name
        self.license = license
    }
}
```

In our artificial examples, we have been very generous with our initializers: we are letting the caller instantiate a `Dog` without supplying a `name:` argument or a `license:` argument. Usually, however, the purpose of an initializer is just the opposite: we want to *force* the caller to supply *all* needed information at instantiation time. In real life, it is much more likely that our `Dog` class would look like this:

```
class Dog {
    let name : String
    let license : Int
    init(name:String, license:Int) {
        self.name = name
        self.license = license
    }
}
```

In that code, our `Dog` has a `name` property and a `license` property, and values for these *must* be supplied at instantiation time (there are no default values), and those values can never be changed thereafter (the properties are constants). In this way, we enforce a rule that every `Dog` must have a meaningful name and license. There is now only *one* way to make a `Dog`:

```
let spot = Dog(name:"Spot", license:1357)
```

## Deferred initialization of properties

Sometimes there is no meaningful value that can be assigned to an instance property during initialization. Perhaps the initial value of this property will not be obtained until some time has elapsed *after* this instance has come into existence. This situation conflicts with the requirement that all instance properties be initialized either in their declaration or through an initializer. You could circumvent the problem by assigning

a default initial value anyway; but this fails to communicate to your own code the fact that this isn't a "real" value.

A common solution, as I explained in [Chapter 3](#), is to declare your instance property as a `var` having an `Optional` type. An `Optional` has a value, namely `nil`, signifying that no "real" value has been supplied; and an `Optional var` is initialized to `nil` automatically. Your code can test this instance property against `nil` and, if it is `nil`, it won't use the property. Later, the property will be given its "real" value. Of course, that value is now wrapped in an `Optional`; but if you declare this property as an implicitly unwrapped `Optional`, you can use the wrapped value directly, without explicitly unwrapping it — as if this weren't an `Optional` at all — once you're sure it is safe to do so:

```
// this property will be set automatically when the nib loads
@IBOutlet var myButton: UIButton!
// this property will be set after time-consuming gathering of data
var albums : [MPMediaItemCollection]?
```

## Referring to self

An initializer may refer to an already initialized instance property, and may refer to an uninitialized instance property in order to initialize it. Otherwise, an initializer *may not refer to self*, explicitly or implicitly, until *all* instance properties have been initialized. This rule guarantees that the instance is fully formed before it is used. This code is illegal:

```
struct Cat {
    var name : String
    var license : Int
    init(name:String, license:Int) {
        self.name = name
        meow() // too soon - compile error
        self.license = license
    }
    func meow() {
        print("meow")
    }
}
```

The call to the instance method `meow` is implicitly a reference to `self` — it means `self.meow()`. The initializer can say that, but not until it has fulfilled its primary contract of initializing all uninitialized properties. The call to the instance method `meow` simply needs to be moved down one line, so that it comes *after* both `name` and `license` have been initialized.

## Delegating initializers

Initializers within an object type can call one another by using the syntax `self.init(...)`. An initializer that calls another initializer is called a *delegating initializer*. When an initializer delegates, the other initializer — the one that it delegates to — must completely initialize the instance first, and then the delegating initializer can work with the fully initialized instance, possibly setting again a `var` property that was already set by the initializer that it delegated to.

A delegating initializer appears to be an exception to the rule against saying `self` too early. But it isn't, because it is saying `self` in order to delegate — and delegating will cause all instance properties to be initialized. In fact, the rules about a delegating initializer saying `self` are even more stringent: a delegating initializer *cannot refer to self at all*, not even to set a property, until *after* the call to the other initializer:

```
struct Digit {
  var number : Int
  var meaningOfLife : Bool
  init(number:Int) {
    self.number = number
    self.meaningOfLife = false
  }
  init() { // this is a delegating initializer
    self.init(number:42)
    self.meaningOfLife = true // legal
  }
}
```

A delegating initializer *cannot set a constant property* (a `let` variable). That is because it cannot refer to the property until after it has called the other initializer, and at that point the instance is fully formed — initialization proper is over, and the door for initialization of properties has closed. This property is a constant, it has been initialized, and that's that. The preceding code would be illegal if `meaningOfLife` were declared with `let`, because the second initializer is a delegating initializer and cannot set a constant property.

Be careful not to delegate recursively! If you tell an initializer to delegate to itself, or if you create a vicious circle of delegating initializers, the compiler won't stop you, but your running app will hang. Don't say this:

```
struct Digit {
  var number : Int = 100
  init(value:Int) {
    self.init(number:value) // do not do this!
  }
  init(number:Int) {
    self.init(value:number) // do not do this!
  }
}
```

## Failable initializers

An initializer can return an `Optional` wrapping the new instance. In this way, `nil` can be returned to signal failure. An initializer that behaves this way is a *failable initializer*. To mark an initializer as failable when declaring it, put a question mark after the keyword `init`. If your failable initializer needs to return `nil`, explicitly write `return nil`; that's legal even if you haven't fulfilled the initializer contract of initializing all stored properties.

Here's a `Dog` with an initializer that returns an `Optional`, returning `nil` if the `name:` argument is invalid:

```
class Dog {
  let name : String
  init?(name:String) {
    if name.isEmpty {
      return nil
    }
    self.name = name
  }
}
```

The resulting value is typed as an `Optional` wrapping a `Dog`, and the caller will need to unwrap that `Optional` (if isn't `nil`) before sending any messages to it.

To exit early from a failable initializer while signalling success, say simply `return`. Here's a rewrite of the previous example:

```
class Dog {
  let name : String
  init?(name:String) {
    if !name.isEmpty {
      self.name = name
      return
    }
    return nil
  }
}
```

Any Objective-C initializer can return `nil` to signal failure. For example, the `UIImage` initializer `init?(named:)` is failable because there might be no image with the given name. But most Objective-C initializers are not *bridged* as failable initializers; this is essentially the same hand-tweaking policy I described in “[Why Optionals?](#)” on page 121.)

## Properties

A *property* is a variable — one that happens to be declared at the top level of an object type declaration. This means that everything said about variables in [Chapter 3](#) applies. A property has a fixed type; it can be declared with `var` or `let`; it can be

stored or computed; it can have setter observers. An instance property can also be declared lazy.

A stored instance property must be given an initial value. As I explained a moment ago, this doesn't have to happen through assignment in the declaration; it can happen through initializer functions instead. Setter observers are not called during initialization of properties.

## How properties are accessed

If a property is an instance property (the default), it can be accessed only through an instance, and its value is separate for each instance. To illustrate, let's start once again with a Dog class:

```
class Dog {
  let name : String
  let license : Int
  init(name:String, license:Int) {
    self.name = name
    self.license = license
  }
}
```

Our Dog class has a `name` instance property. Then we can make two different Dog instances with two different name values, and we can access each Dog instance's name through the instance:

```
let fido = Dog(name:"Fido", license:1234)
let spot = Dog(name:"Spot", license:1357)
let aName = fido.name // "Fido"
let anotherName = spot.name // "Spot"
```

A static/class property, on the other hand, is accessed through the type, and is scoped to the type, which usually means that it is global and unique. I'll use a struct as an example:

```
struct Greeting {
  static let friendly = "hello there"
  static let hostile = "go away"
}
```

Now code elsewhere can fetch the values of `Greeting.friendly` and `Greeting.hostile`. That example is neither artificial nor trivial; immutable static properties are a convenient and effective way to supply your code with nicely name-spaced constants.

## Property initialization and self

A property declaration that assigns an initial value to the property *cannot fetch an instance property or call an instance method*. Such behavior would require a reference,

explicit or implicit, to `self`; and during initialization, there is no `self` yet — `self` is exactly what we are in the process of initializing. Making this mistake can result in some of Swift's most perplexing compile error messages. This is illegal (and removing the explicit references to `self` doesn't make it legal):

```
class Moi {
    let first = "Matt"
    let last = "Neuburg"
    let whole = self.first + " " + self.last // compile error
}
```

There are two common solutions in that situation:

#### *Make this a computed property*

A computed property can refer to `self` in a getter or setter function because the function won't run until the property is accessed, and that won't happen until after `self` has been fully initialized:

```
class Moi {
    let first = "Matt"
    let last = "Neuburg"
    var whole : String {
        self.first + " " + self.last
    }
}
```

#### *Declare this property lazy*

A lazy property can refer to `self` in its initializer because the initializer won't be evaluated until the property is accessed, and that won't happen until after `self` has been fully initialized:

```
class Moi {
    let first = "Matt"
    let last = "Neuburg"
    lazy var whole = self.first + " " + self.last
}
```

As I demonstrated in [Chapter 3](#), a variable can be initialized as part of its declaration using multiple lines of code by means of a define-and-call anonymous function. If this variable is an instance property, and if the function code refers to `self`, the variable must also be declared lazy:

```
class Moi {
    let first = "Matt"
    let last = "Neuburg"
    lazy var whole : String = {
        var s = self.first
        s.append(" ")
    }
}
```

```

        s.append(self.last)
        return s
    }()
}

```

Unlike instance properties, static properties *can* be initialized with reference to one another; the reason is that static property initializers *are* lazy:

```

struct Greeting {
    static let friendly = "hello there"
    static let hostile = "go away"
    static let ambivalent = friendly + " but " + hostile
}

```

Notice the lack of `self` in that code. In static/class code, `self` means the type itself. I like to use `self` explicitly wherever it would be implicit, but here I can't use it without arousing the ire of the compiler (I regard this as a bug). To clarify the status of the terms `friendly` and `hostile`, I can use the type name (or the term `Self`, as I'll explain later in this chapter):

```

struct Greeting {
    static let friendly = "hello there"
    static let hostile = "go away"
    static let ambivalent = Greeting.friendly + " but " + Greeting.hostile
}

```

On the other hand, if I write `ambivalent` as a computed property, I *can* use `self`:

```

struct Greeting {
    static let friendly = "hello there"
    static let hostile = "go away"
    static var ambivalent : String {
        self.friendly + " but " + self.hostile
    }
}

```

On the other other hand, I'm not allowed to use `self` when the initial value is set by a define-and-call anonymous function (again, I regard this as a bug):

```

struct Greeting {
    static let friendly = "hello there"
    static let hostile = "go away"
    static var ambivalent : String = {
        self.friendly + " but " + self.hostile // compile error
    }()
}

```

## Methods

A *method* is a function — one that happens to be declared at the top level of an object type declaration. This means that everything said about functions in [Chapter 2](#) applies.



By default, a method is an instance method. This means that it can be accessed only through an instance. Within the body of an instance method, `self` is the instance. To illustrate, let's continue to develop our Dog class:

```
class Dog {
  let name : String
  let license : Int
  let whatDogsSay = "woof"
  init(name:String, license:Int) {
    self.name = name
    self.license = license
  }
  func bark() {
    print(self.whatDogsSay)
  }
  func speak() {
    self.bark()
    print("I'm \(self.name)")
  }
}
```

Now I can make a Dog instance and tell it to speak:

```
let fido = Dog(name:"Fido", license:1234)
fido.speak() // woof I'm Fido
```

In my Dog class, the `speak` method calls the instance method `bark` by way of `self`, and obtains the value of the instance property `name` by way of `self`; and the `bark` instance method obtains the value of the instance property `whatDogsSay` by way of `self`. This is because instance code can use `self` to refer to this instance. Such code can omit `self` if the reference is unambiguous; I could have written this:

```
func speak() {
  bark()
  print("I'm \(name)")
}
```

A static/class method is accessed through the type. Within the body of a static/class method, `self` means the type:

```
struct Greeting {
  static let friendly = "hello there"
  static func beFriendly() {
    print(self.friendly)
  }
}
```

And here's how to call the static `beFriendly` method:

```
Greeting.beFriendly() // hello there
```

There is a kind of conceptual wall between static/class members, on the one hand, and instance members on the other; even though they may be declared within the

## The Secret Life of Instance Methods

Here's a secret: instance methods are actually static/class methods. This is legal (but strange):

```
class MyClass {
  var s = ""
  func store(_ s:String) {
    self.s = s
  }
}
let m = MyClass()
let f = MyClass.store(m) // what just happened!?
```

Even though `store` is an instance method, we are able to call it as a class method — with a parameter that is an instance of this class! The reason is that an instance method is actually a curried static/class method composed of two functions — one function that takes an instance, and another function that takes the parameters of the instance method. After that code, `f` is the *second* of those functions, and can be called as a way of passing a parameter to the `store` method of *the instance m*:

```
f("howdy")
print(m.s) // howdy
```

same object type declaration, they inhabit different worlds. A static/class method can't refer to "the instance" because there is no instance; thus, a static/class method cannot directly refer to any instance properties or call any instance methods. An instance method, on the other hand, can refer to the type, and can thus access static/class properties and can call static/class methods.

Let's return to our `Dog` class and grapple with the question of what dogs say. Presume that all dogs say the same thing. We'd prefer, therefore, to express `whatDogsSay` not at instance level but at class level. This would be a good use of a static property. Here's a simplified `Dog` class that illustrates:

```
class Dog {
  static var whatDogsSay = "woof"
  func bark() {
    print(Dog.whatDogsSay)
  }
}
```

(Instead of `Dog.whatDogsSay`, a `Dog` instance method can say `Self.whatDogsSay`, as I'll explain later in this chapter.) Now we can make a `Dog` instance and tell it to bark:

```
let fido = Dog()
fido.bark() // woof
```

## Subscripts

A *subscript* is a method that is called by appending square brackets containing arguments directly to a reference. You can use this feature for whatever you like, but it is suitable particularly for situations where this is an object type with *elements* that can be appropriately accessed by key or by index number. I have already described (in [Chapter 3](#)) the use of this syntax with strings, and it is familiar also from dictionaries and arrays; you can use square brackets with strings and dictionaries and arrays exactly because Swift's String and Dictionary and Array types declare subscript methods.

The syntax for declaring a subscript method is somewhat like a function declaration and somewhat like a computed property declaration. That's no coincidence. A subscript is like a function in that it can take parameters: arguments can appear in the square brackets when a subscript method is called. A subscript is like a computed property in that the call is used like a reference to a property: you can fetch its value or you can assign into it.

To illustrate the syntax, here's a struct that treats an integer as if it were a digit sequence, returning a digit that can be specified by an index number in square brackets; for simplicity, I'm deliberately omitting any error-checking:

```
struct Digit {
    var number : Int
    init(_ n:Int) {
        self.number = n
    }
    subscript(ix:Int) -> Int { ❶ ❷
        get { ❸
            let s = String(self.number)
            return Int(String(s[s.index(s.startIndex, offsetBy:ix)]))!
        }
    }
}
```

- ❶ After the keyword `subscript` we have a parameter list stating what parameters are to appear inside the square brackets. By default, *parameter names are not externalized*; if you want a parameter name to be externalized, your declaration must include an external name before the internal name, even if they are the same name — for example, `subscript(ix ix:Int)`. This is different from how external names work everywhere else in Swift (and therefore I regard it as a bug in the language).
- ❷ Then we have the type of value that is passed out (when the getter is called) or in (when the setter is called); this is parallel to the type declared for a computed property, except that (oddly) the type is preceded by the arrow operator instead of a colon.

- ❸ Finally, we have curly braces whose contents are exactly like those of a computed property. You can have `get` and curly braces for the getter, and `set` and curly braces for the setter. The setter can be omitted (as here); in that case, the word `get` and its curly braces can be omitted. If the getter consists of a single statement, the keyword `return` can be omitted. The setter receives the new value as `newValue`, but you can change that name by supplying a different name in parentheses after the word `set`.

Here's an example of calling the getter; the instance with appended square brackets containing the arguments is used just as if you were getting a property value:

```
let d = Digit(1234)
let aDigit = d[1] // 2
```

Now I'll expand my `Digit` struct so that its subscript method includes a setter (and again I'll omit error-checking):

```
struct Digit {
    var number : Int
    init(_ n:Int) {
        self.number = n
    }
    subscript(ix:Int) -> Int {
        get {
            let s = String(self.number)
            return Int(String(s[s.index(s.startIndex, offsetBy:ix)]))!
        }
        set {
            var s = String(self.number)
            let i = s.index(s.startIndex, offsetBy:ix)
            s.replaceSubrange(i...i, with: String(newValue))
            self.number = Int(s)!
        }
    }
}
```

And here's an example of calling the setter; the instance with appended square brackets containing the arguments is used just as if you were setting a property value:

```
var d = Digit(1234)
d[0] = 2 // now d.number is 2234
```

An object type can declare multiple subscript methods, distinguished by their parameters.

Starting in Swift 5.1, a subscript can be a static/class method. I'll demonstrate later, when we talk about enums.

Starting in Swift 5.2, a subscript can have default parameter values. I can declare my `Digit` subscript method like this (though I can't think why I'd want to):

```
subscript(ix:Int = 0) -> Int {
```

And then I can call it like this:

```
var d = Digit(1234)
let aDigit = d[] // 1
```

## Nested Object Types

An object type may be declared inside an object type declaration, forming a nested type:

```
class Dog {
    struct Noise {
        static var noise = "woof"
    }
    func bark() {
        print(Dog.Noise.noise)
    }
}
```

A nested object type is no different from any other object type, but the rules for referring to it from the outside are changed; the surrounding object type acts as a namespace, and must be referred to explicitly in order to access the nested object type:

```
Dog.Noise.noise = "arf"
```

Here, the Noise struct is namespaced inside the Dog class. This namespacing provides clarity: the name Noise does not float free, but is explicitly associated with the Dog class to which it belongs. Namespacing also allows more than one Noise type to exist, without any clash of names. Swift built-in object types often take advantage of namespacing; for example, the String struct is one of several structs that contain an Index struct, with no clash of names.

A nested type can't refer directly to the surrounding type's instance members, but it can refer directly to the surrounding type's static/class members:

```
class Dog {
    static let sound = "ruff"
    struct Noise {
        static var noise = "woof"
        func barkTheDog() { bark() } // compile error
        var othernoise = sound // fine!
    }
    func bark() {
        print(Dog.Noise.noise)
    }
}
```

In that example, code inside Noise cannot refer directly to Dog's bark method, because it's an instance method, which can be referred to only by way of some specific instance of Dog. But code inside Noise *can* refer directly to Dog's sound static

property. Moreover, it can do so *without explicit namespacing* — that is, it doesn't have to say `Dog.sound`. In effect, the term `sound` is global in scope to the nested type.

## Enums

An *enum* is an object type whose instances represent *distinct predefined alternative values*. Think of it as a list of known possibilities. An enum is the Swift way to express a set of constants that are alternatives to one another. An enum declaration includes case statements. Each case is the name of one of the alternatives. An instance of an enum will represent exactly one alternative — one case.

In my `Albumen` app, different instances of the same view controller can list any of four different sorts of music library contents: albums, playlists, podcasts, or audio-books. The view controller's behavior is slightly different in each case. So I need a sort of four-way switch that I can set once when the view controller is instantiated, saying which sort of contents this view controller is to display. That sounds like an enum!

Here's the basic declaration for that enum; I call it `Filter`, because each case represents a different way of filtering the contents of the music library:

```
enum Filter {
    case albums
    case playlists
    case podcasts
    case books
}
```

That enum doesn't have an initializer. You *can* write an initializer for an enum, as I'll demonstrate in a moment; but there is a default mode of initialization that you'll probably use most of the time — the name of the enum followed by dot-notation and one of the cases. Here's how to make an instance of `Filter` representing the `albums` case:

```
let type = Filter.albums
```

If the type is known in advance, you can omit the name of the enum; the bare case must still be preceded by a dot:

```
let type : Filter = .albums
```

You can't say `.albums` just anywhere out of the blue, because Swift doesn't know what enum it belongs to. But in that code, the variable is explicitly declared as a `Filter`, so Swift knows what `.albums` means. A similar thing happens when passing an enum instance as an argument in a function call:

```
func filterExpecter(_ type:Filter) {}
filterExpecter(.albums)
```

In the second line, I create an instance of `Filter` and pass it, all in one move, without having to include the name of the enum. That's because Swift knows from the function declaration that a `Filter` is expected here.

In real life, the space savings when omitting the enum name can be considerable — especially because, when talking to Cocoa, the enum type names are often long:

```
let v = UIView()
v.contentMode = .center
```

A `UIView`'s `contentMode` property is typed as a `UIView.ContentMode` enum. Our code is neater and simpler because we don't have to include the type name explicitly here; `.center` is nicer than `UIView.ContentMode.center`. But either is legal.

Instances of an enum with the same case are regarded as equal. You can compare an enum instance for equality against a case. Again, the type of enum is known from the first term in the comparison, so the second term can omit the enum name:

```
func filterExpecter(_ type:Filter) {
    if type == .albums {
        print("it is albums")
    }
}
filterExpecter(.albums) // "it is albums"
```

## Raw Values

Optionally, when you declare an enum, you can add a type declaration. Every case then carries with it a fixed (constant) value of that type. The types attached to an enum's cases in this way are limited to numbers and strings, and the values assigned must be literals.

If the type is an integer numeric type, the values can be implicitly assigned, and will start at zero by default:

```
enum PepBoy : Int {
    case manny
    case moe
    case jack
}
```

In that code, `.manny` carries a value of 0, `.moe` carries of a value of 1, and so on.

If the type is `String`, the implicitly assigned values are the string equivalents of the case names:

```
enum Filter : String {
    case albums
    case playlists
    case podcasts
    case books
}
```

In that code, `.albums` carries a value of "albums", and so on.

Regardless of the type, you can assign values explicitly as part of the case declarations, like this:

```
enum Normal : Double {
    case fahrenheit = 98.6
    case centigrade = 37
}
enum PepBoy : Int {
    case manny = 1
    case moe // 2 implicitly
    case jack = 4
}
enum Filter : String {
    case albums = "Albums"
    case playlists = "Playlists"
    case podcasts = "Podcasts"
    case books = "Audiobooks"
}
```

The values carried by the cases are called their *raw values*. An enum with a type declaration implicitly adopts the `RawRepresentable` protocol, meaning that it implicitly has an `init(rawValue:)` initializer and a `rawValue` property. (I'll explain later what a protocol is.) So you can retrieve a case's assigned value as its `rawValue`:

```
let type = Filter.albums
print(type.rawValue) // Albums
```

Having each case carry a fixed raw value can be quite useful. In my *Albumen* app, the `Filter` cases really do have those `String` values, and `type` is a `Filter` instance property of the view controller; when the view controller wants to know what title string to put at the top of the screen, it simply retrieves `self.type.rawValue`.

The raw value associated with each case must be unique within this enum; the compiler will enforce this rule. Therefore, the mapping works the other way: given a raw value, you can derive the case; in particular, you can instantiate an enum that has raw values by using its `init(rawValue:)` initializer:

```
let type = Filter(rawValue:"Albums")
```

However, the attempt to instantiate the enum in this way still might fail, because you might supply a raw value corresponding to *no* case; therefore, this is a failable initializer, and the value returned is an `Optional`. In that code, `type` is not a `Filter`; it's



an `Optional` wrapping a `Filter`. This might not be terribly important, however, because the thing you are most likely to want to do with an enum is to compare it for equality with a case of the enum; you can do that with an `Optional` without unwrapping it. This code is legal and works correctly:

```
let type = Filter(rawValue:"Albums")
if type == .albums { // ...
```

## Associated Values

The raw values discussed in the preceding section are fixed in the enum's declaration: a given case carries with it a certain raw value, and that's that. But there's also a way to construct a case whose constant value can be set *when the instance is created*. The attached value here is called an *associated value*.

To write an enum with one or more cases taking an associated value, do not declare any raw value type for the enum as a whole; instead, you append to the name of the case an expression that looks very much like a tuple declaration — that is, parentheses containing a list of possibly labeled types. Unlike a raw value, your choice of type is not limited. Most often, a single value will be attached to a case, so you'll write parentheses containing a single type name. Here's an example:

```
enum MyError {
    case number(Int)
    case message(String)
    case fatal
}
```

That code means that, at instantiation time, a `MyError` instance with the `.number` case must be assigned an `Int` value, a `MyError` instance with the `.message` case must be assigned a `String` value, and a `MyError` instance with the `.fatal` case can't be assigned any value. Instantiation with assignment of a value is really a way of calling an initialization function, so to supply the value, you pass it as an argument in parentheses:

```
let err : MyError = .number(4)
```

This is an ordinary function call, so the argument doesn't have to be a literal:

```
let num = 4
let err : MyError = .number(num)
```



At the risk of sounding like a magician explaining his best trick, I can now reveal how an `Optional` works. An `Optional` is simply an enum with two cases: `.none` and `.some`. If it is `.none`, it carries no associated value, and it equates to `nil`. If it is `.some`, it carries the wrapped value as its associated value.

## Inference of Type Name with Static/Class Members

Just as you can use a dot and the name of an enum case where an instance of that enum is expected, you can do the same thing when referring to a type's static/class member whose value is an instance of that type. For example, `UIColor` has many class properties that produce a `UIColor` instance, so you can omit `UIColor` where a `UIColor` is expected:

```
p.trackTintColor = .red // instead of UIColor.red
```

Starting in Swift 5.4, you can append a property or method call that also yields the expected type:

```
p.trackTintColor = .red.withAlphaComponent(0.5)
```

Similarly, suppose we have a struct `Thing` with static constants whose values are `Thing` instances:

```
struct Thing : RawRepresentable {  
    let rawValue : Int  
    static let one : Thing = Thing(rawValue:1)  
    static let two : Thing = Thing(rawValue:2)  
}
```

Then we can refer to `Thing.one` as `.one` where a `Thing` instance is expected:

```
let thing : Thing = .one
```

Many Objective-C enums are bridged to Swift as that kind of struct, as I'll explain later in the chapter.

By the same rule, when a certain type of instance is expected, that type's initializer can be used without saying the name of the type, by saying `.init` instead. Suppose `Dog` has an initializer that expects a `name:` parameter, and `dogExpecter` is a function that takes a `Dog` as its parameter:

```
struct Dog {  
    let name: String  
}  
func dogExpecter(_ dog: Dog) {  
    print(dog.name)  
}
```

Then we can create and pass a `Dog` to `dogExpecter` without using the term `Dog`, and this is regarded as good Swift style:

```
dogExpecter(.init(name:"Fido"))
```

If a case's associated value type has a label, that label must be used at initialization time:

```
enum MyError2 {
  case number(Int)
  case message(String)
  case fatal(n:Int, s:String)
}
let err : MyError2 = .fatal(n:-12, s:"Oh the horror")
```

By default, the `==` operator cannot be used to compare cases of an enum if any case of that enum has an associated value:

```
if err == MyError.fatal { // compile error
```

But if you declare this enum explicitly as adopting the `Equatable` protocol (discussed later in this chapter and in [Chapter 5](#)), the `==` operator starts working:

```
enum MyError : Equatable { // *
  case number(Int)
  case message(String)
  case fatal
}
```

That code won't compile, however, unless all the associated types are themselves `Equatable`. That makes sense; if we declare `case pet(Dog)` and there is no way to know whether any two `Dogs` are equal, there is obviously no way to know whether any two `pet` cases are equal.

I'll explain in [Chapter 5](#) how to *check the case* of an instance of an enum that has an associated value case, as well as how to *extract* the associated value from an enum instance that has one.

## Enum Case Iteration

It is often useful to have a list — that is, an array — of all the cases of an enum. You could define this list manually as a static property of the enum:

```
enum Filter : String {
  case albums = "Albums"
  case playlists = "Playlists"
  case podcasts = "Podcasts"
  case books = "Audiobooks"
  static let cases : [Filter] = [.albums, .playlists, .podcasts, .books]
}
```

That, however, is error-prone and hard to maintain; if, as you develop your program, you modify the enum's cases, you must remember to modify the `cases` property to match. Instead, the list of cases can be generated for you *automatically*. Simply have your enum adopt the `CaseIterable` protocol (adoption of protocols is explained later in this chapter); now the list of cases springs to life as a static property called `allCases`:

```
enum Filter : String, CaseIterable {
    case albums = "Albums"
    case playlists = "Playlists"
    case podcasts = "Podcasts"
    case books = "Audiobooks"
    // static allCases is now [.albums, .playlists, .podcasts, .books]
}
```

I'll put this feature to use in the next section.

Automatic generation of `allCases` is impossible if any of the enum's cases has an associated value, as it would then be unclear how that case should be defined in the list.

## Enum Initializers

An explicit enum initializer must do what default initialization does: it must return a particular case of this enum. To do so, set `self` to the case. In this example, I'll expand my `Filter` enum so that it can be initialized with a numeric argument:

```
enum Filter : String, CaseIterable {
    case albums = "Albums"
    case playlists = "Playlists"
    case podcasts = "Podcasts"
    case books = "Audiobooks"
    init(_ ix:Int) {
        self = Filter.allCases[ix]
    }
}
```

Now there are three ways to make a `Filter` instance:

```
let type1 = Filter.albums
let type2 = Filter(rawValue:"Playlists")!
let type3 = Filter(2) // .podcasts
```

In that example, we'll crash in the third line if the caller passes a number that's out of range (less than 0 or greater than 3). If we want to avoid that, we can make this a failable initializer and return `nil` if the number is out of range:

```
enum Filter : String, CaseIterable {
    case albums = "Albums"
    case playlists = "Playlists"
    case podcasts = "Podcasts"
    case books = "Audiobooks"
    init?(_ ix:Int) {
        if !Filter.allCases.indices.contains(ix) {
            return nil
        }
        self = Filter.allCases[ix]
    }
}
```

An enum can have multiple initializers. Enum initializers can delegate to one another by saying `self.init(...)`. The only requirement is that, at some point in the chain of calls, `self` must be set to a case; if that doesn't happen, your enum won't compile.

In this example, I improve my `Filter` enum so that it can be initialized with a `String` raw value without having to say `rawValue:` in the call. To do so, I declare a failable initializer with a string parameter that delegates to the built-in failable `rawValue:` initializer:

```
enum Filter : String, CaseIterable {
    case albums = "Albums"
    case playlists = "Playlists"
    case podcasts = "Podcasts"
    case books = "Audiobooks"
    init?(_ ix:Int) {
        if !Filter.allCases.indices.contains(ix) {
            return nil
        }
        self = Filter.allCases[ix]
    }
    init?(_ rawValue:String) {
        self.init(rawValue:rawValue)
    }
}
```

Now there are four ways to make a `Filter` instance:

```
let type1 = Filter.albums
let type2 = Filter(rawValue:"Playlists")!
let type3 = Filter(2)
let type4 = Filter("Audiobooks")!
```

## Enum Properties

An enum can have instance properties and static properties, but there's a limitation: an enum instance property can't be a stored property. Computed instance properties are fine, however, and the value of the property can depend on the case of `self`. In this example from my real code, I've associated an `MPMediaQuery` (obtained by calling an `MPMediaQuery` factory class method) with each case of my `Filter` enum, suitable for fetching the songs of that type from the music library:

```
enum Filter : String {
    case albums = "Albums"
    case playlists = "Playlists"
    case podcasts = "Podcasts"
    case books = "Audiobooks"
    var query : MPMediaQuery {
        switch self {
            case .albums:
                return .albums()
            case .playlists:
```

```

        return .playlists()
    case .podcasts:
        return .podcasts()
    case .books:
        return .audiobooks()
    }
}

```

If an enum instance property is a computed variable with a setter, other code can assign to this property. However, that code's reference to the enum instance itself must be a variable (`var`), not a constant (`let`). If you try to assign to an enum instance property through a `let` reference to the enum, you'll get a compile error.

For example, here's a silly enum:

```

enum Silly {
    case one
    var sillyProperty : String {
        get { "Howdy" }
        set {} // do nothing
    }
}

```

It is then legal to say this:

```

var silly = Silly.one
silly.sillyProperty = "silly"

```

But if `silly` were declared with `let` instead of `var`, trying to set `silly.sillyProperty` would cause a compile error.

An enum static property can have a property wrapper, but an enum instance property can't, because that would imply storage of an instance of the underlying `@propertyWrapper` type — and enums have no stored instance properties.

## Enum Methods

An enum can have instance methods (including subscripts) and static methods. Writing an enum method is straightforward. Here's an example from my own code. In a card game, the cards draw themselves as rectangles, ellipses, or diamonds. I've abstracted the drawing code into an enum that draws itself as a rectangle, an ellipse, or a diamond, depending on its case:

```

enum Shape {
    case rectangle
    case ellipse
    case diamond
    func addShape (to p: CGMutablePath, in r: CGRect) -> () {
        switch self {
            case .rectangle:

```

```

        p.addRect(r)
    case .ellipse:
        p.addEllipse(in:r)
    case .diamond:
        p.move(to: CGPoint(x:r.minX, y:r.midY))
        p.addLine(to: CGPoint(x: r.midX, y: r.minY))
        p.addLine(to: CGPoint(x: r.maxX, y: r.midY))
        p.addLine(to: CGPoint(x: r.midX, y: r.maxY))
        p.closeSubpath()
    }
}
}

```

Earlier, I mentioned that a subscript can be a static method. That gives me an idea for yet another way to make a `Filter` instance by number:

```

enum Filter : String, CaseIterable {
    case albums = "Albums"
    case playlists = "Playlists"
    case podcasts = "Podcasts"
    case books = "Audiobooks"
    static subscript(ix: Int) -> Filter {
        Filter.allCases[ix] // warning, no range checking
    }
}

```

And now we can say:

```
let type = Filter[2] // podcasts
```

An enum instance method that modifies the enum itself must be marked as `mutating`. For example, an enum instance method might assign to an instance property of `self`; even though this is a computed property, such assignment is illegal unless the method is marked as `mutating`. The caller of a mutating instance method must have a variable reference to the instance (`var`), not a constant reference (`let`).

A mutating enum instance method can replace this instance with another instance, by assigning another case to `self`. In this example, I add an `advance` method to my `Filter` enum. The idea is that the cases constitute a sequence, and the sequence can cycle. By calling `advance`, I transform a `Filter` instance into an instance of the next case in the sequence:

```

enum Filter : String, CaseIterable {
    case albums = "Albums"
    case playlists = "Playlists"
    case podcasts = "Podcasts"
    case books = "Audiobooks"
    mutating func advance() {
        let cases = Filter.allCases
        var ix = cases.firstIndex(of:self)!
    }
}

```

```

        ix = (ix + 1) % cases.count
        self = cases[ix]
    }
}

```

And here's how to call it:

```

var type = Filter.books
type.advance() // type is now Filter.albums

```

Observe that `type` is declared with `var`; if it were declared with `let`, we'd get a compile error.

A subscript or computed property setter is considered mutating by default and does not have to be specially marked. However, if a computed property getter sets another property as a side effect, it must be marked `mutating` `get`.

## Why Enums?

An enum is a switch whose states have names. There are many situations where that's a desirable thing. You could implement a multistate value yourself; if there are five possible states, you could use an `Int` whose values can be 0 through 4. But then you would have to provide a lot of additional overhead, interpreting those numeric values correctly and making sure that no other values are used. A list of five named cases is much better!

Even when there are only *two* states, an enum is often better than, say, a mere `Bool`, because the enum's states have names. With a `Bool`, you have to know what `true` and `false` signify in a particular usage; with an enum, the name of the enum and the names of its cases *tell* you its significance. Moreover, you can store extra information in an enum's associated value or raw value.

In my `LinkSame` app, the user can play a real game with a timer or a practice game without a timer. At various places in the code, I need to know which type of game this is. The game types are the cases of an enum:

```

enum InterfaceMode : Int {
    case timed = 0
    case practice = 1
}

```

The current game type is stored in an instance property `interfaceMode`, whose value is an `InterfaceMode`. It's easy to set the game type by case name:

```

// ... initialize new game ...
self.interfaceMode = .timed

```

And it's easy to examine the game type by case name:

```

// notify of high score only if user is not just practicing
if self.interfaceMode == .timed { // ...

```



And what are my `InterfaceMode` enum's raw value integers for? That's the really clever part. They correspond to the segment indexes of a `UISegmentedControl` in the interface! Whenever I change the `interfaceMode` property, a setter observer also selects the corresponding segment of the `UISegmentedControl` (`self.timedPractice`), simply by fetching the `rawValue` of the current enum case:

```
var interfaceMode : InterfaceMode = .timed {
    willSet (mode) {
        self.timedPractice?.selectedSegmentIndex = mode.rawValue
    }
}
```

## Structs

A *struct* is the Swift object type *par excellence*. An enum, with its fixed set of cases, is a reduced, specialized kind of object. A class, at the other extreme, will often turn out to be overkill; it has some features that a struct lacks (I'll talk later about what they are), but if you don't need those features, a struct may be preferable.

Of more than two hundred object types declared in the Swift header, maybe half a dozen are classes. A couple of dozen are enums. All the rest are structs. A `String` is a struct. An `Int` is a struct. A `Range` is a struct. An `Array` is a struct. And so on. That shows how powerful a struct can be.

## Struct Initializers

A struct that doesn't have an explicit initializer and that doesn't *need* an explicit initializer — because it has no stored properties, or because all its stored properties are assigned default values as part of their declaration — automatically gets an implicit initializer with no parameters, `init()`. For example:

```
struct Digit {
    var number = 42
}
```

That struct can be initialized by saying `Digit()`. But if you add any explicit initializers of your own, you lose that implicit initializer:

```
struct Digit {
    var number = 42
    init(number: Int) {
        self.number = number
    }
}
```

Now you can say `Digit(number:42)`, but you can't say `Digit()` any longer. Of course, you can add an explicit initializer that does the same thing:

```

struct Digit {
    var number = 42
    init() {}
    init(number: Int) {
        self.number = number
    }
}

```

Now you can say `Digit()` once again, as well as `Digit(number:42)`.

A struct that has stored properties and that doesn't have an explicit initializer automatically gets an implicit initializer derived from its instance properties. This is called the *memberwise initializer*. For example:

```

struct Test {
    var number = 42
    var name : String
    let age : Int
    let greeting = "Hello"
}

```

That struct is legal, even though it seems we have not fulfilled the contract requiring us to initialize all stored properties in their declaration or in an initializer. The reason is that this struct automatically has a memberwise initializer which *does* initialize all its properties. Given that declaration, there are two ways to make a `Test` instance:

```

let t1 = Test(number: 42, name: "matt", age: 67)
let t2 = Test(name: "matt", age: 67)

```

The memberwise initializer includes `number`, `name`, and `age`, but not `greeting`, because `greeting` is a `let` property that has already been initialized before the initializer is called. `number` has been initialized too, but it is a `var` property, so the memberwise initializer includes it — but you can also omit it from your call to the memberwise initializer, because it has been initialized already and therefore has a default value.

But if you add any explicit initializers of your own, or if any of the properties involved are declared `private`, you lose the implicit memberwise initializer (though of course you can write an explicit initializer that does the same thing).

All stored properties must be initialized either by direct initialization in the declaration or by all initializers. If a struct has multiple explicit initializers, they can delegate to one another by saying `self.init(...)`.

## Struct Properties

A struct can have instance properties and static properties, which can be stored or computed variables. If other code wants to set a property of a struct instance, its reference to that instance must be a variable (`var`), not a constant (`let`).

Here's a `Digit` struct with a `var number` instance property:

```
struct Digit {
    var number : Int
    init(_ n:Int) {
        self.number = n
    }
}
```

Then this is legal:

```
var d = Digit(123)
d.number = 42
```

But if `d` were declared with `let`, trying to set `d.number` would cause a compile error.

## Struct Methods

A struct can have instance methods and static methods, including subscripts. If an instance method sets a property, it must be marked as `mutating`, and the caller's reference to the struct instance must be a variable (`var`), not a constant (`let`).

Here's a new version of our `Digit` struct:

```
struct Digit {
    private var number : Int
    init(_ n:Int) {
        self.number = n
    }
    mutating func changeNumberTo(_ n:Int) {
        self.number = n
        // or: self = Digit(n)
    }
}
```

Here we have a private `number` property, along with a public method for setting it. We can then say this:

```
var d = Digit(123)
d.changeNumberTo(42)
```

The `changeNumberTo` method must be declared `mutating`, and if `d` were declared with `let`, trying to call `d.changeNumberTo` would cause a compile error.

Fetching the value of a lazy instance property may cause the property's initializer to run, setting the value of the property. That's a mutation! Therefore, an instance method must be declared `mutating` if it fetches the value of a lazy instance property:

## Constant Namespaces

I often use a degenerate struct or enum as a handy namespace for constants. I call such a type “degenerate” because it consists entirely of static members; I don’t intend to use this object type to make any instances. (A reason for preferring an enum over a struct is that a caseless enum *cannot* be instantiated.)

Let’s say I’m storing user preference information in Cocoa’s UserDefaults. UserDefaults is a kind of dictionary: each item is accessed through a key. The keys are typically strings. A common programmer mistake is to write out these string keys literally every time a key is used; if you misspell a key name, there’s no penalty at compile time, but your code will mysteriously fail to work correctly. A better approach is to embody those keys as constant strings with names; if you make a mistake typing a name, the compiler can catch you. An enum with static members is a great way to define constant strings and clump their names into a namespace. Here’s a real-life example:

```
enum Default {
    static let rows = "CardMatrixRows"
    static let columns = "CardMatrixColumns"
    static let hazyStripy = "HazyStripy"
}
```

I can now refer to a UserDefaults key with a name, such as `Default.hazyStripy`.

```
struct Person {
    private lazy var name = "matt"
    mutating func getName() -> String {
        return self.name
    }
}
```

A subscript, setter observer, or computed property setter is considered mutating by default and does not have to be specially marked. However, if a computed property getter sets another property as a side effect, it must be marked `mutating` `get`.

A mutating instance method can replace this instance with another instance, by setting `self` to a different instance of the same struct.

## Classes

A *class* is similar to a struct, with the following key differences:

### Reference type

Classes are reference types. This means, among other things, that a class instance has two remarkable features that are not true of struct or enum instances:

### *Mutability*

A class instance is mutable in place. Even if your reference to an instance of a class is a constant (`let`), you can change the value of an instance property through that reference. An instance method of a class never has to be marked `mutating` (and cannot be).

### *Multiple references*

When a given instance of a class is assigned to multiple variables or passed as argument to a function, you get multiple references to *one and the same object*.

### *Inheritance*

A class can have a superclass. A class that has a superclass is a *subclass* of that superclass, and inherits its superclass's members. Class types can form a hierarchical tree.

In Objective-C, classes are the only object type. Some built-in Swift struct types are magically bridged to Objective-C class types, but your custom struct types don't have that magic. Thus, when programming iOS with Swift, one reason for declaring a class, rather than a struct, is as a form of interchange with Objective-C and Cocoa.

## Value Types and Reference Types

A major difference between enums and structs, on the one hand, and classes, on the other, is that enums and structs are *value types*, whereas classes are *reference types*. I will now explain what that means.

### **Class instances are mutable**

A value type is *not mutable in place*, even though it seems to be. A struct is a value type. Here is a `Digit` struct:

```
struct Digit {
    var number : Int
    init(_ n:Int) {
        self.number = n
    }
}
```

Now, Swift's syntax of assignment would lead us to believe that changing a `Digit`'s `number` is possible:

```
var d = Digit(123)
d.number = 42
```

But in reality, when you apparently mutate an instance of a value type, you are actually *replacing* that instance with a *different* instance. To see that this is true, add a setter observer:

```
var d : Digit = Digit(123) { // Digit is a struct
    didSet {
        print("d was set")
    }
}
d.number = 42 // "d was set"
```

That explains why it is impossible to mutate a value type instance if the reference to that instance is declared with `let`:

```
let d = Digit(123) // Digit is a struct
d.number = 42 // compile error
```

Under the hood, this change would require us to *replace* the `Digit` instance pointed to by `d` with another `Digit` instance — and we can't do that, because it would mean assigning into `d`, which is exactly what the `let` declaration forbids.

That also explains why an instance method of a struct or enum that sets a property of the instance must be marked explicitly with the `mutating` keyword. Such a method can potentially replace this object with another, so the reference to the object must be `var`, not `let`.

But classes are *not* value types. They are reference types. A reference to a class instance does *not* have to be declared with `var` in order to set a `var` property through that reference:

```
class Dog {
    var name : String = "Fido"
}
let rover = Dog()
rover.name = "Rover" // fine
```

In the last line of that code, the class instance pointed to by `rover` is being *mutated in place*. No implicit assignment to `rover` is involved, and so the `let` declaration is powerless to prevent the mutation. A setter observer on a `Dog` variable is *not* called when a property is set:

```
var rover : Dog = Dog() { // Dog is a class
    didSet {
        print("did set rover")
    }
}
rover.name = "Rover" // nothing in console
```

The setter observer would be called if we were to set `rover` explicitly (to another `Dog` instance), but it is not called merely because we change a property of the `Dog` instance already pointed to by `rover`.

Exactly the same difference between a value type and a reference type may be seen with a parameter of a function call. When we receive an instance of a value type as a

## Mutating Captured Self

Here's a Digit struct with some mutating methods:

```
struct Digit {  
    var number : Int  
    init(_ n:Int) {  
        self.number = n  
    }  
    mutating func changeNumberTo(_ n:Int) {  
        self.number = n  
    }  
    func otherFunction(_ f: ()->()) {  
    }  
    mutating func callAnotherFunction() {  
        otherFunction {  
            self.changeNumberTo(345) // *  
        }  
    }  
}
```

Whether that's legal depends on whether `otherFunction` declares its function parameter `@escaping` (“[Escaping Closures](#)” on page 59). If it does, the compiler will stop us:

```
func otherFunction(_ f: @escaping ()->()) {  
}
```

That change causes a compile error at the starred line: “Escaping closure captures mutating self parameter.” Now that `otherFunction` is escaping, we are threatening to mutate a persisting captured self *at some later time*. `Digit` is a struct, so that would involve *replacing* the captured self with a different `Digit` — and that's incoherent. No such problem arises if `Digit` is a class, because the persistent captured self can be mutated in place.

parameter into a function body, the compiler will stop us in our tracks if we try to assign to its instance property. This doesn't compile:

```
func digitChanger(_ d:Digit) { // Digit is a struct  
    d.number = 42 // compile error  
}
```

But this does compile:

```
func dogChanger(_ d:Dog) { // Dog is a class  
    d.name = "Rover"  
}
```

## Class instance references are pointers

With a reference type, there is a concealed level of indirection between your reference to the instance and the instance itself; the reference actually holds a *pointer* to the instance. This means that when a class instance is assigned to a variable or passed as an argument to a function or as the result of a function, you can wind up with *multiple references to the same object*. That is not true of structs and enums:

### *Struct or enum instance (value type)*

When an enum instance or a struct instance is assigned or passed, what is assigned or passed is essentially a *new copy* of that instance.

### *Class instance (reference type)*

When a class instance is assigned or passed, what is assigned or passed is a reference to the *same* instance.

To prove it, I'll assign one reference to another, and then mutate the second reference — and then I'll examine what happened to the first reference. Let's start with the struct:

```
var d = Digit(123) // Digit is a struct
print(d.number) // 123
var d2 = d // assignment!
d2.number = 42
print(d.number) // 123
```

In that code, we changed the `number` property of `d2`, a struct instance; but nothing happened to the `number` property of `d`. Now let's try the class:

```
var fido = Dog() // Dog is a class
print(fido.name) // Fido
var rover = fido // assignment!
rover.name = "Rover"
print(fido.name) // Rover
```

In that code, we changed the `name` property of `rover`, a class instance — and the `name` property of `fido` was changed as well! That's because, after the assignment in the third line, `fido` and `rover` refer to *one and the same instance*.

The same thing is true of parameter passing. With a class instance, what is passed is a reference to the *same* instance:

```
func dogChanger(_ d:Dog) { // Dog is a class
    d.name = "Rover"
}
var fido = Dog()
print(fido.name) // "Fido"
dogChanger(fido)
print(fido.name) // "Rover"
```



The change made to `d` inside the function `dogChanger` affected *our* `Dog` instance `fido`! You can't do that with an enum or struct instance parameter — unless it's an inout parameter — because the instance is effectively *copied* as it is passed. But handing a class instance to a function does *not* copy that instance; it is more like *lending* that instance to the function.

### Advantages of value types vs. reference types

The ability to generate multiple references to the same instance is significant particularly in a world of object-based programming, where objects persist and can have properties that persist along with them. If object A and object B are both long-lived, and if they both have a `Dog` property where `Dog` is a class, and if they have each been handed a reference to one and the same `Dog` instance, then either object A or object B can mutate its `Dog`, and this mutation will affect the other's `Dog`. You can be holding on to an object, only to discover that it has been mutated by someone else behind your back. If that happens unexpectedly, it can put your program into an invalid state.

Class instances are also more complicated behind the scenes. Swift has to manage their memory (as I'll explain in detail in [Chapter 13](#)), precisely because there can be multiple references to the same object; this management can involve quite a bit of overhead.

On the whole, therefore, you should prefer a value type (such as a struct) to a reference type (a class) wherever possible. Struct instances are not shared between references, and so you are relieved from any worry about such an instance being mutated behind your back; moreover, under the hood, storage and memory management are far simpler as well. Apple likes to say that value types are *easier to reason about*. The Swift language itself will help you by imposing value types in front of many Cocoa Foundation reference types. Objective-C `NSDate` and `NSData` are classes, but Swift will steer you toward using struct types `Date` and `Data` instead ([Chapter 11](#)).

But don't get the wrong idea. Classes are not bad; they're good! For one thing, a class instance is very efficient to pass around, because all you're passing is a pointer. No matter how big and complicated a class instance may be, no matter how many properties it may have containing vast amounts of data, passing the instance is incredibly fast and efficient.

And although a class may be a reference type, a *particular* class can be implemented in such a way as to exhibit value *semantics*. Simply put, a class's API can refuse to mutate that class in place. Cocoa `NSString`, `NSArray`, `NSDictionary`, `NSDate`, `NSIndexSet`, `NSParagraphStyle`, and many more behave like this; they are *immutable* by design. Two objects may hold a reference to the same `NSArray` without fear that it will be mutated behind their backs, not because it's a value type (it isn't) but because

it's immutable. In effect, this architecture combines the ease of use of a value type with the pointer efficiency of a reference type.

Moreover, there are many situations where the independent identity of a class instance, no matter how many times it is referred to, is exactly what you want. The extended lifetime of a class instance, as it is passed around, can be crucial to its functionality and integrity. In particular, only a class instance can successfully represent an *independent reality*. `UIView` is a class so that an individual `UIView` instance keeps representing the same single real and persistent view in your running app's interface.

Still another reason for preferring a class over a struct or enum is when you need recursive references. A value type cannot be structurally recursive: a stored instance property of a value type cannot be an instance of the same type. This code won't compile:

```
struct Dog { // compile error
    var puppy : Dog?
}
```

(Oddly, you can work around this restriction by typing `puppy` as an *array* of `Dog`.) More complex circular chains, such as a `Dog` with a `Puppy` property and a `Puppy` with a `Dog` property, are similarly illegal. But if `Dog` is a class instead of a struct, there's no error. This is a consequence of the nature of memory management of value types as opposed to reference types.



An enum case's associated value *can* be an instance of that enum, provided the case (or the entire enum) is marked `indirect`:

```
enum Node {
    case none(Int)
    indirect case left(Int, Node)
    indirect case right(Int, Node)
    indirect case both(Int, Node, Node)
}
```

## Subclass and Superclass

Two classes can be *subclass* and *superclass* of one another. For example, we might have a class `Quadruped` and a class `Dog`, with `Quadruped` as the superclass of `Dog`. A class may have many subclasses, but a class can have only one immediate superclass. I say “immediate” because that superclass might itself have a superclass, and so on until we get to the ultimate superclass, called the *base class*, or *root class*. Thus there is a hierarchical tree of subclasses, each group of subclasses branching from its superclass, and so on, with a single class, the base class, at the top.

As far as the Swift language itself is concerned, there is no requirement that a class should have any superclass, or, if it does have a superclass, that it should ultimately be descended from any particular base class. A Swift program can have many classes




Figure 4-1. Part of the Cocoa class hierarchy as shown in Xcode

that have no superclass, and it can have many independent hierarchical subclass trees, each descended from a different base class.

Cocoa, however, doesn't work that way. In Cocoa, there is effectively just one base class, `NSObject`, which embodies all the functionality necessary for a class to *be* a class in the first place — and all other classes are subclasses, at some level, of that one base class. Cocoa thus consists of one huge tree of hierarchically arranged classes, even before you write a single line of code or create any classes of your own.

We can imagine diagramming this tree as an outline. And in fact Xcode will *show* you this outline (Figure 4-1): in an iOS project window, choose View → Navigators → Show Symbol Navigator and click Hierarchical, with the first and third icons in the filter bar selected (filled). Now locate `NSObject` in the list; the Cocoa classes are the part of the tree descending from it.

## Inheritance

The reason for having a superclass–subclass relationship in the first place is to allow related classes to *share functionality*. Suppose we have a `Dog` class and a `Cat` class, and we are considering declaring a `walk` method for both of them. We might reason that both a dog and a cat walk in pretty much the same way, by virtue of both being quadrupeds. So it might make sense to declare `walk` as a method of the `Quadruped` class, and make both `Dog` and `Cat` subclasses of `Quadruped`. When we do that, both `Dog` and `Cat` can be sent the `walk` message, even if neither of them has a `walk` method, because each of them has a superclass that *does* have a `walk` method. We say that a subclass *inherits* the methods of its superclass.

To declare that a certain class is a subclass of a certain superclass, add a colon and the superclass name after the class's name in its declaration:

```
class Quadruped {
    func walk () {
        print("walk walk walk")
    }
}
class Dog : Quadruped {}
class Cat : Quadruped {}
```

Now let's prove that Dog has indeed inherited walk from Quadruped:

```
let fido = Dog()
fido.walk() // walk walk walk
```

The walk message can be sent to a Dog instance just as if the walk instance method were declared in the Dog class, even though the walk instance method is in fact declared in a superclass of Dog. That's inheritance at work.



A class declaration can *prevent* the class from being subclassed by preceding the class declaration with the `final` keyword.

### Additional functionality

The purpose of subclassing is not *merely* so that a class can inherit another class's methods; it's so that it can also declare methods *of its own*. Typically, a subclass consists of the methods inherited from its superclass *and then some*. For example, dogs can bark, but quadrupeds in general can't. If we declare bark in the Dog class, and walk in the Quadruped class, and make Dog a subclass of Quadruped, then Dog inherits the ability to walk from the Quadruped class *and also* knows how to bark:

```
class Quadruped {
    func walk () {
        print("walk walk walk")
    }
}
class Dog : Quadruped {
    func bark () {
        print("woof")
    }
}
```

Again, let's prove that it works:

```
let fido = Dog()
fido.walk() // walk walk walk
fido.bark() // woof
```

Within a class, it is a matter of indifference whether that class has an instance method because that method is declared in that class or because the method is declared in a superclass and inherited. A message to `self` works equally well either way. In this code, we have declared a `barkAndWalk` instance method that sends two messages to `self`, without regard to where the corresponding methods are declared (one is native to the subclass, one is inherited from the superclass):

```
class Quadruped {
    func walk () {
        print("walk walk walk")
    }
}
class Dog : Quadruped {
    func bark () {
        print("woof")
    }
    func barkAndWalk() {
        self.bark()
        self.walk()
    }
}
```

And here's proof that it works:

```
let fido = Dog()
fido.barkAndWalk() // woof walk walk walk
```

## Overriding

It is also permitted for a subclass to *redefine* a method inherited from its superclass. For example, perhaps some dogs bark differently from other dogs. We might have a class `NoisyDog`, for instance, that is a subclass of `Dog`. `Dog` declares `bark`, but `NoisyDog` also declares `bark`, and defines it differently from how `Dog` defines it. This is called *overriding*. The very natural rule is that if a subclass overrides a method inherited from its superclass, then when the corresponding message is sent to an instance of that subclass, it is the subclass's version of that method that is called.

In Swift, when you override something inherited from a superclass, you must explicitly acknowledge this fact by preceding its declaration with the keyword `override`:

```
class Quadruped {
    func walk () {
        print("walk walk walk")
    }
}
class Dog : Quadruped {
    func bark () {
        print("woof")
    }
}
```

```
class NoisyDog : Dog {
    override func bark () {
        print("woof woof woof")
    }
}
```

And let's try it:

```
let fido = Dog()
fido.bark() // woof
let rover = NoisyDog()
rover.bark() // woof woof woof
```

Observe that a subclass method by the same *name* as a superclass's method is not necessarily, of itself, an override. Recall that Swift can distinguish two functions with the same name, provided they have different *signatures*. Those are different functions, and so an implementation of one in a subclass is not an override of the other in a superclass. An override situation exists only when the subclass redefines the *same* method that it inherits from a superclass — using the same name, including the external parameter names, and the same signature.

However, a method override need not have *exactly* the same signature as the overridden method. In particular, in a method override, the type of a parameter may be replaced with a superclass, or with an Optional wrapping the superclass. If we have a Cat class and its Kitten subclass, the following is legal:

```
class Dog {
    func barkAt(cat:Kitten) {}
}
class NoisyDog : Dog {
    override func barkAt(cat:Cat) {}
    // or: override func barkAt(cat:Cat?)
}
```

Moreover, a parameter may be overridden with an Optional wrapping its own type, and an Optional parameter may be overridden with an Optional wrapping its wrapped type's superclass:

```
class Dog {
    func barkAt(cat:Cat) {}
    // or: func barkAt(cat:Kitten)
    // or: func barkAt(cat:Kitten?)
}
class NoisyDog : Dog {
    override func barkAt(cat:Cat?) {}
}
```

There are further rules along the same lines, but I won't try to list them all here; you probably won't need to take advantage of them, and in any case the compiler will tell you if your override is illegal.

Along with methods, a subclass also inherits its superclass's properties. Naturally, the subclass may also declare additional properties of its own. It is possible to override an inherited property (with some restrictions that I'll talk about later).

I'll have more to say about the implications of overriding when I talk about polymorphism, later in this chapter.



A class declaration can *prevent* a class member from being overridden by a subclass by preceding the member's declaration with the `final` keyword.

## The keyword `super`

It often happens that we want to override something in a subclass and yet access the thing overridden in the superclass. This is done by sending a message to the keyword `super`. Our bark implementation in `NoisyDog` is a case in point. What `NoisyDog` really does when it barks is the same thing `Dog` does when *it* barks, but more times. We'd like to express that relationship in our implementation of `NoisyDog`'s bark. To do so, we have `NoisyDog`'s bark implementation send the bark message, not to `self` (which would be circular), but to `super`; this causes the search for a bark instance method implementation to start in the superclass rather than in our own class:

```
class Dog : Quadruped {
  func bark () {
    print("woof")
  }
}
class NoisyDog : Dog {
  override func bark () {
    for _ in 1...3 {
      super.bark()
    }
  }
}
```

And it works:

```
let fido = Dog()
fido.bark() // woof
let rover = NoisyDog()
rover.bark() // woof woof woof
```



A subscript function is a method. If a superclass declares a subscript, the subclass can declare a subscript with the same signature, provided it designates it with the `override` keyword. To call the superclass subscript implementation, the subclass can use square brackets after the keyword `super` (e.g. `super[3]`).

## Class Initializers

Initialization of a class instance is considerably more complicated than initialization of a struct or enum instance, because of class inheritance. The chief task of an initializer is to ensure that all properties have an initial value, making the instance well-formed as it comes into existence; and an initializer may have other tasks to perform that are essential to the initial state and integrity of this instance. A class, however, may have a superclass, which may have properties and initializers of its own. Thus we must somehow ensure that when a subclass is initialized, its *superclass*'s properties are initialized and the tasks of *its* initializers are performed in good order, in addition to those of the subclass itself.

Swift solves this problem coherently and reliably — and ingeniously — by enforcing some clear and well-defined rules about what a class initializer must do.

### Kinds of class initializer

The rules begin with a distinction between the kinds of initializer that a class can have:

#### *Designated initializer*

A class initializer, by default, is a *designated* initializer. A class can be instantiated only through a call to one of its designated initializers. A designated initializer must see to it that all stored properties are initialized. It may not delegate to another initializer in the same class; it is illegal for a designated initializer to use the phrase `self.init(...)`.

A class with any stored properties that are not initialized as part of their declaration must have at least one explicit designated initializer. A class with no stored properties, or with stored properties all of which are initialized as part of their declaration, and that has *no* explicit designated initializers, has an *implicit* designated initializer `init()`.

#### *Convenience initializer*

A *convenience* initializer is marked with the keyword `convenience`. A convenience initializer is not how a class is instantiated; it is merely a façade for a designated initializer. A convenience initializer is a delegating initializer; it *must* contain the phrase `self.init(...)`, which must call a *designated* initializer in the same class — or, if it calls another convenience initializer in the same class, the chain of convenience initializers must end by calling a designated initializer in the same class.

Here are some examples. This class has no stored properties, so it has an implicit `init()` designated initializer:



```
class Dog {
}
let d = Dog()
```

This class's stored properties have default values, so it has an implicit `init()` designated initializer too:

```
class Dog {
    var name = "Fido"
}
let d = Dog()
```

This class's stored properties have default values, but it has no implicit `init()` initializer because it has an explicit designated initializer:

```
class Dog {
    var name = "Fido"
    init(name:String) {self.name = name}
}
let d = Dog(name:"Rover") // ok
let d2 = Dog() // compile error
```

This class's stored properties have default values, and it has an explicit initializer, but it also has an implicit `init()` initializer because its explicit initializer is a convenience initializer. Moreover, the implicit `init()` initializer is a designated initializer, so the convenience initializer can delegate to it:

```
class Dog {
    var name = "Fido"
    convenience init(name:String) {
        self.init()
        self.name = name
    }
}
let d = Dog(name:"Rover")
let d2 = Dog()
```

This class has stored properties without default values; it has an explicit designated initializer, and all of those properties are initialized in that designated initializer:

```
class Dog {
    var name : String
    var license : Int
    init(name:String, license:Int) {
        self.name = name
        self.license = license
    }
}
let d = Dog(name:"Rover", license:42)
```

This class is similar to the previous example, but it also has convenience initializers forming a chain that ends with a designated initializer:

```

class Dog {
    var name : String
    var license : Int
    init(name:String, license:Int) {
        self.name = name
        self.license = license
    }
    convenience init(license:Int) {
        self.init(name:"Fido", license:license)
    }
    convenience init() {
        self.init(license:1)
    }
}
let d = Dog()

```

Note that the rules about what else an initializer can say and when it can say it, as I described them earlier in this chapter, are still in force:

- A designated initializer cannot, except in order to initialize a property (or to fetch the value of a property that is already initialized), say `self`, implicitly or explicitly, until *all* of this class's properties have been initialized.
- A convenience initializer is a delegating initializer, so it cannot say `self` for *any* purpose until after it has called, directly or indirectly, a designated initializer (and cannot set a constant property at all).

## Subclass initializers

Having defined and distinguished between designated initializers and convenience initializers, we are ready for the rules about a subclass's initializers:

### *No declared initializers*

If a subclass doesn't have to have any initializers of its own, and if it declares no initializers of its own, then its initializers consist of the initializers inherited from its superclass. (A subclass thus has no implicit `init()` initializer unless it inherits it from its superclass.)

### *Convenience initializers only*

If a subclass doesn't have to have any initializers of its own, it is eligible to declare convenience initializers, and these work exactly as convenience initializers always do, because inheritance supplies the designated initializers that the convenience initializers must call by saying `self.init(...)`.

### *Designated initializers*

If a subclass declares any designated initializers of its own, the entire game changes drastically. Now, *no initializers are inherited!* The existence of an explicit designated initializer *blocks initializer inheritance*. The only initializers the subclass now has are the initializers that you explicitly write (with one exception that

I'll mention later). This rule may seem surprising, but I'll justify it in an example later on.

Moreover, every designated initializer in the subclass now has an extra requirement: it must call one of the *superclass's designated initializers*, by saying `super.init(...)`. If it fails to do this, then `super.init()` is called implicitly if possible, but I disapprove of this feature (in my view, Swift should not indulge in secret behavior, even if that behavior might be considered “helpful”).

At the same time, the rules about saying `self` continue to apply.

Thus, a subclass designated initializer must do these things *in this order*:

1. It must ensure that all properties of *this* class (the subclass) are initialized.
2. It must call `super.init(...)`, and the initializer that it calls must be a designated initializer.
3. Only then may this initializer say `self` for such purposes as to call an instance method or to access an inherited property.

#### *Designated and convenience initializers*

If a subclass declares both designated and convenience initializers, the convenience initializers in the subclass are still subject to the rules I've already outlined. They must call `self.init(...)`, calling a designated initializer directly or through a chain of convenience initializers. There are no inherited initializers, so the designated initializer must be explicitly declared in the subclass.

#### *Override initializers*

A subclass may override initializers from its superclass:

- An initializer whose parameters match a *convenience* initializer of the superclass can be a designated initializer or a convenience initializer, and is *not* marked `override`.
- An initializer whose parameters match a *designated* initializer of the superclass can be a designated initializer or a convenience initializer, and *must* be marked `override`. An `override` designated initializer must still call some superclass designated initializer (possibly even the one that it overrides) with `super.init(...)`.

If a subclass overrides *all* of its superclass's *designated* initializers, then the subclass inherits the superclass's *convenience* initializers. (This is the exception to the rule that if a subclass has any designated initializers, no initializers are inherited.)

### *Failable initializers*

If an initializer called by a failable initializer is failable, the calling syntax does not change, and no additional test is needed — if a failable initializer fails, the whole initialization process will fail (and will be aborted) immediately.

There are some additional restrictions on failable initializers:

- `init` can override `init?`, but not vice versa.
- `init?` can call `init`.
- `init` can call `init?` by saying `init` and unwrapping the result with an exclamation mark (and if the `init?` fails, you'll crash).

At no time can a subclass initializer set a constant (`let`) property of a superclass. This is because, by the time the subclass is allowed to do anything other than initialize its own properties and call another initializer, the superclass has finished its own initialization and the door for initializing its constants has closed.

### **Subclass initializer examples**

Your eyes may glaze over reading the subclass initializer rules, but the most important rules are very easy to understand with the help of some basic examples. We start with a subclass that has no explicit initializers of its own:

```
class Dog {
  var name : String
  var license : Int
  init(name:String, license:Int) {
    self.name = name
    self.license = license
  }
  convenience init(license:Int) {
    self.init(name:"Fido", license:license)
  }
}
class NoisyDog : Dog {
}
```

Given that code, you can make a `NoisyDog` like this:

```
let nd1 = NoisyDog(name:"Fido", license:1)
let nd2 = NoisyDog(license:2)
```

That code is legal, because `NoisyDog` inherits its superclass's initializers. However, you can't make a `NoisyDog` like this:

```
let nd3 = NoisyDog() // compile error
```

That code is illegal. Even though a `NoisyDog` has no properties of its own, it has no implicit `init()` initializer; its initializers are its inherited initializers, and its superclass, `Dog`, has no implicit `init()` initializer to inherit.

Now here is a subclass whose only explicit initializer is a convenience initializer:

```
class Dog {
    var name : String
    var license : Int
    init(name:String, license:Int) {
        self.name = name
        self.license = license
    }
    convenience init(license:Int) {
        self.init(name:"Fido", license:license)
    }
}
class NoisyDog : Dog {
    convenience init(name:String) {
        self.init(name=name, license:1)
    }
}
```

Observe how NoisyDog's convenience initializer fulfills its contract by calling `self.init(...)` to call a designated initializer — which it happens to have inherited. Given that code, there are three ways to make a NoisyDog, just as you would expect:

```
let nd1 = NoisyDog(name:"Fido", license:1)
let nd2 = NoisyDog(license:2)
let nd3 = NoisyDog(name:"Rover")
```

Next, here is a subclass that declares a designated initializer:

```
class Dog {
    var name : String
    var license : Int
    init(name:String, license:Int) {
        self.name = name
        self.license = license
    }
    convenience init(license:Int) {
        self.init(name:"Fido", license:license)
    }
}
class NoisyDog : Dog {
    init(name:String) {
        super.init(name=name, license:1)
    }
}
```

NoisyDog's explicit initializer is now a designated initializer. It fulfills its contract by calling a designated initializer in `super`. NoisyDog has now *cut off inheritance* of all initializers; the *only* way to make a NoisyDog is like this:

```
let nd1 = NoisyDog(name:"Rover")
```

Earlier, I promised to justify the rule that adding a designated initializer to a subclass cuts off initializer inheritance. That example is a case in point. It would be terrible if the caller could bypass NoisyDog's designated initializer by using an inherited Dog initializer instead. NoisyDog's initializer enforces a rule that a NoisyDog can only have a license value of 1; if you could say NoisyDog(license:2), you'd bypass that rule.

Here's another example that makes the same point a little more realistically:

```
class Dog {
    let name : String
    init(name:String) {
        self.name = name
    }
}
class RoverDog : Dog {
    init() {
        super.init(name:"Rover")
    }
}
let fido = RoverDog(name:"Fido") // compile error
```

Clearly that last line *needs* to be an error; otherwise, a RoverDog could be named Fido, undermining the point of the subclass.

Finally, here is a subclass that overrides its designated initializers:

```
class Dog {
    var name : String
    var license : Int
    init(name:String, license:Int) {
        self.name = name
        self.license = license
    }
    convenience init(license:Int) {
        self.init(name:"Fido", license:license)
    }
}
class NoisyDog : Dog {
    override init(name:String, license:Int) {
        super.init(name=name, license:license)
    }
}
```

NoisyDog has overridden *all* of its superclass's designated initializers, so it inherits its superclass's convenience initializers. There are thus two ways to make a NoisyDog:

```
let nd1 = NoisyDog(name:"Rover", license:1)
let nd2 = NoisyDog(license:2)
```

Those examples illustrate the main rules that you should keep in your head. You probably don't need to memorize the remaining rules, because the compiler will enforce them, and will keep slapping you down until you get them right.

## Required initializers

A class initializer may be preceded by the keyword `required`. This means that a subclass may not lack this initializer. This, in turn, means that if a subclass implements designated initializers, thus blocking inheritance, it *must* override this initializer and mark the override `required`. Here's a (rather pointless) example:

```
class Dog {
    var name : String
    required init(name:String) {
        self.name = name
    }
}
class NoisyDog : Dog {
    var obedient = false
    init(obedient:Bool) {
        self.obedient = obedient
        super.init(name:"Fido")
    }
} // compile error
```

That code won't compile. `Dog's` `init(name:)` is marked `required`; our code won't compile unless we inherit or override `init(name:)` in `NoisyDog`. But we cannot inherit it, because, by implementing the `NoisyDog` designated initializer `init(obedient:)`, we have blocked inheritance. Therefore we must override it:

```
class Dog {
    var name : String
    required init(name:String) {
        self.name = name
    }
}
class NoisyDog : Dog {
    var obedient = false
    init(obedient:Bool) {
        self.obedient = obedient
        super.init(name:"Fido")
    }
    required init(name:String) {
        super.init(name=name)
    }
}
```

Observe that our overridden `required` initializer is not marked with `override`, but *is* marked with `required`, guaranteeing that the requirement continues drilling down to any further subclasses.

I have explained what declaring an initializer as `required` does, but I have not explained *why* you'd need to do it. That's another matter! I'll discuss it later in this chapter.

## Class Deinitializer

A class can have a deinitializer. This is a function declared with the keyword `deinit` followed by curly braces containing the function body. You never call this function yourself; it is called by the runtime when an instance of this class goes out of existence. If a class has a superclass, the subclass's deinitializer (if any) is called before the superclass's deinitializer (if any).

A deinitializer is a class feature only; a struct or enum has no deinitializer. That's because a class is a reference type (as I explained earlier in this chapter). The idea is that you might want to perform some internal cleanup. Another good use of a class's `deinit` is to log to the console to prove to yourself that your instance is going out of existence in good order; I'll take advantage of that when I discuss memory management issues in [Chapter 5](#).

Property observers are not called during `deinit`.

## Class Properties

A subclass can override its inherited properties. The override must have the same name and type as the inherited property, and must be marked with `override`. (A property cannot have the same name as an inherited property but a different type, as there is no way to distinguish them.)

The chief restriction here is that an `override` property *cannot be a stored property*. More specifically:

- If the superclass property is writable (a stored property or a computed property with a setter), the subclass's override may consist of adding setter observers to this property.
- Alternatively, the subclass's override may be a computed property. In that case:
  - If the superclass property is stored, it must be writable and the subclass's computed property override must have both a getter and a setter.
  - If the superclass property is computed, the subclass's computed property override must have at least a getter, and:
    - If the superclass property has a setter, the override must have a setter.
    - If the superclass property has no setter, the override can add one.

The overriding property's functions may refer to — and may read from and write to — the inherited property, through the `super` keyword.



## Static/Class Members

A class can have static members, marked `static`, just like a struct or an enum. It can also have class members, marked `class`. Both static and class members are inherited by subclasses.

### Static methods vs. class methods

The chief difference between static and class methods, from the programmer's point of view, is that a static method *cannot be overridden*; it is as if `static` were a synonym for `class final`.

Here, I'll use a static method to express what dogs say:

```
class Dog {
    static func whatDogsSay() -> String {
        return "woof"
    }
    func bark() {
        print(Dog.whatDogsSay())
    }
}
```

A subclass now inherits `whatDogsSay`, but can't override it. No subclass of `Dog` may contain any implementation of a class method or a static method `whatDogsSay` with this same signature.

Now I'll use a class method to express what dogs say:

```
class Dog {
    class func whatDogsSay() -> String {
        return "woof"
    }
    func bark() {
        print(Dog.whatDogsSay())
    }
}
```

A subclass inherits `whatDogsSay`, and *can* override it, either as a class method or as a static method:

```
class NoisyDog : Dog {
    override class func whatDogsSay() -> String {
        return "WOOF"
    }
}
```

## Static properties vs. class properties

The difference between static and class properties is similar to the difference between static and class methods, but with an additional, rather dramatic qualification: a static property can be stored, but a class property *must be a computed property*.

Here, I'll use a static class property to express what dogs say:

```
class Dog {
    static var whatDogsSay = "woof"
    func bark() {
        print(Dog.whatDogsSay)
    }
}
```

A subclass inherits `whatDogsSay`, but can't override it; no subclass of `Dog` can declare a class or static property `whatDogsSay`.

Now I'll use a class property to express what dogs say. It cannot be a stored property, so I'll have to use a computed property instead:

```
class Dog {
    class var whatDogsSay : String {
        return "woof"
    }
    func bark() {
        print(Dog.whatDogsSay)
    }
}
```

A subclass inherits `whatDogsSay` and can override it either as a class property or as a static property. But the rule about property overrides not being stored is still in force, even if the override is a static property:

```
class NoisyDog : Dog {
    override static var whatDogsSay : String {
        return "WOOF"
    }
}
```

## Polymorphism

When a computer language has a hierarchy of types and subtypes, it must resolve the question of what such a hierarchy means for the relationship between the type of an *object* and the declared type of a *reference* to that object. Swift obeys the principles of *polymorphism*. In my view, it is polymorphism that turns an object-based language into a full-fledged object-oriented language. We may summarize Swift's polymorphism principles:

### *Substitution*

Wherever a certain type of object is expected, the actual object may be a subtype of that type.

### *Internal identity*

An object's real type is a matter of its internal nature, regardless of how that object is referred to.

To see what these principles mean in practice, imagine we have a `Dog` class, along with its subclass, `NoisyDog`:

```
class Dog {  
}  
class NoisyDog : Dog {  
}  
let d : Dog = NoisyDog()
```

In that code:

- The substitution rule says that the last line is legal: we can assign a `NoisyDog` instance to a reference, `d`, that is typed as `Dog`.
- The internal identity rule says that, under the hood, even though `d` is typed as `Dog`, the instance that it refers to is a `NoisyDog`.

You may be asking: How is the internal identity rule manifested? If a reference to a `NoisyDog` is typed as `Dog`, in what sense is this “really” a `NoisyDog`? To illustrate, let's examine what happens when a subclass overrides an inherited method. I'll redefine `Dog` and `NoisyDog` to demonstrate:

```
class Dog {  
  func bark() {  
    print("woof")  
  }  
}  
class NoisyDog : Dog {  
  override func bark() {  
    for _ in 1...3 {  
      super.bark()  
    }  
  }  
}
```

Now consider the following code:

```
func tellToBark(_ d:Dog) {  
  d.bark()  
}  
var nd = NoisyDog()  
tellToBark(nd) // what will happen?????
```

That code is legal, because, by the substitution principle, we can pass `nd`, typed as `NoisyDog`, where a `Dog` is expected. Now, inside the `tellToBark` function, `d` is typed as `Dog`. How will it react to being told to bark? On the one hand, `d` is *typed* as `Dog`, and a `Dog` barks by saying "woof" once. On the other hand, in our code, when `tellToBark` is called, what is *really* passed is a `NoisyDog` instance, and a `NoisyDog` barks by saying "woof" three times. *What will happen?* Let's find out:

```
func tellToBark(_ d:Dog) {
    d.bark()
}
var nd = NoisyDog()
tellToBark(nd) // woof woof woof
```

The result is "woof woof woof". The internal identity rule says that what matters when a message is sent is not how the recipient of that message is *typed* through this or that *reference*, but what that recipient actually *is*. What arrives inside `tellToBark` is a `NoisyDog`, regardless of the type of variable that holds it; thus, the bark message causes this object to say "woof" three times.

Here's another important consequence of polymorphism — the meaning of the keyword `self`. Its meaning depends upon the type of the actual instance — even if the word `self` *appears* in a superclass's code. For example:

```
class Dog {
    func bark() {
        print("woof")
    }
    func speak() {
        self.bark()
    }
}
class NoisyDog : Dog {
    override func bark() {
        for _ in 1...3 {
            super.bark()
        }
    }
}
```

What happens when we tell a `NoisyDog` to `speak`? The `speak` method is declared in `Dog`, the superclass — not in `NoisyDog`. The `speak` method calls the `bark` method. It does this by way of the keyword `self`. (I could have omitted the explicit reference to `self` here, but `self` would still be involved implicitly, so I'm not cheating by making `self` explicit.) There's a `bark` method in `Dog`, and an override of the `bark` method in `NoisyDog`. *Which bark method will be called?* Let's find out:

```
let nd = NoisyDog()
nd.speak() // woof woof woof
```

The word `self` is encountered within the `Dog` class’s implementation of `speak`. But what matters is not where the word `self` *appears* but what it *means*. It means *this instance*. And the internal identity principle tells us that this instance is a `NoisyDog`! Thus, it is `NoisyDog`’s override of `bark` that is called when `Dog`’s `speak` says `self.bark()`.

Polymorphism applies to `Optional` types in the same way that it applies to the type of thing wrapped by the `Optional`. Suppose we have a reference typed as an `Optional` wrapping a `Dog`. You already know that you can assign a `Dog` to it. Well, you can also assign a `NoisyDog`, or an `Optional` wrapping a `NoisyDog`, and the underlying wrapped object will maintain its integrity:

```
var d : Dog?
d = Dog()
d = NoisyDog()
d = Optional(NoisyDog())
```

(The applicability of polymorphism to `Optionals` derives from a special dispensation of the Swift language: `Optionals` are *covariant*. I’ll talk more about that later in this chapter.)

Thanks to polymorphism, you can take advantage of subclasses to add power and customization to existing classes. This is important particularly in the world of iOS programming, where most of the classes are defined by Cocoa and don’t belong to you. The `UIViewController` class, for example, is defined by Cocoa; it has lots of built-in methods that Cocoa will call, and these methods perform various important tasks — but in a generic way. In real life, you’ll make a `UIViewController` *subclass*, and you’ll *override* those methods to do the tasks appropriate to your particular app. When you do that:

- It won’t bother Cocoa in the slightest, because (substitution principle) wherever Cocoa expects to receive or to be talking to a `UIViewController`, it will accept without question an instance of your `UIViewController` subclass.
- The substituted `UIViewController` subclass will also work as expected, because (internal identity principle) whenever Cocoa calls one of those `UIViewController` methods on your subclass, it is your subclass’s override that will be called, and wherever a `UIViewController` method refers to `self`, that will mean your subclass.

I’ll talk more about subclassing Cocoa classes in [Chapter 11](#).



Polymorphism is cool, but in the grand scheme of things it is also relatively slow. It requires *dynamic dispatch*, meaning that the compiler can't perform certain optimizations, and that the runtime has to think about what a message to a class instance means. You can reduce the need for dynamic dispatch by declaring a class or a class member `final` or `private`. Or use a struct, if appropriate; structs don't need dynamic dispatch.

## Casting

Here's a conundrum. The Swift compiler, with its strict typing, imposes severe restrictions on what messages can be sent to an object reference. The messages that the compiler will permit to be sent to an object reference depend upon the reference's *declared* type. But the internal identity principle of polymorphism says that, under the hood, an object may have a *real* type that is different from its reference's declared type. Such an object may be *capable* of receiving certain messages, but the compiler *won't permit us* to send them.

To illustrate the problem, let's give `NoisyDog` a method that `Dog` doesn't have:

```
class Dog {
    func bark() {
        print("woof")
    }
}
class NoisyDog : Dog {
    override func bark() {
        super.bark(); super.bark()
    }
    func beQuiet() {
        self.bark()
    }
}
```

In that code, we configure a `NoisyDog` so that we can tell it to `beQuiet`. Now look at what happens when we try to tell an object typed as `Dog` to be quiet:

```
func tellToHush(_ d:Dog) {
    d.beQuiet() // compile error
}
let nd = NoisyDog()
tellToHush(nd)
```

Our code doesn't compile. We can't send the `beQuiet` message to the reference `d` inside the function body, because it is typed as `Dog` — and a `Dog` has no `beQuiet` method. But there is a certain irony here: for once, we happen to know more than the compiler does — namely, that this object is *in fact* a `NoisyDog` and *does* have a `beQuiet` method! Our code would run correctly — because `d` really is a `NoisyDog` — if only we could get our code to compile in the first place. We need a way to say to the

compiler, “Look, compiler, just trust me: this thing is going to turn out to be a Noisy-Dog when the program actually runs, so let me send it this message.”

There is in fact a way to do this — *casting*. To cast, you use a form of the keyword `as` followed by the name of the type you claim something really is.

## Casting Down

Swift will not let you cast just any old type to any old other type — you can’t cast a `String` to an `Int` — but it will let you cast a superclass to a subclass. This is called *casting down*. When you cast down, the form of the keyword `as` that you use is `as!` with an exclamation mark. The exclamation mark reminds you that you are *forcing* the compiler to do something it would rather not do:

```
func tellToHush(_ d:Dog) {
    (d as! NoisyDog).beQuiet()
}
let nd = NoisyDog()
tellToHush(nd)
```

That code compiles, and works. A useful way to rewrite the example is like this:

```
func tellToHush(_ d:Dog) {
    let d = d as! NoisyDog
    d.beQuiet()
    // ... other NoisyDog messages to d can go here ...
}
let nd = NoisyDog()
tellToHush(nd)
```

The reason that way of rewriting the code is useful is in case we have other `NoisyDog` messages to send to this object. Instead of casting every time we want to send a message to it, we cast the object once to its internal identity type, and assign it to a variable. Now that variable’s type — inferred, in this case, from the cast — is the internal identity type, and we can send multiple `NoisyDog` messages to the variable.

## Type Testing and Casting Down Safely

A moment ago, I said that the `as!` operator’s exclamation mark reminds you that you are forcing the compiler’s hand. It also serves as a warning: your code can now crash! The reason is that you might be lying to the compiler. Casting down is a way of telling the compiler to relax its strict type checking and to let you call the shots. If you use casting to make a false claim, the compiler may permit it, but you will crash when the app runs:

```
func tellToHush(_ d:Dog) {
    let d = d as! NoisyDog // crash
    d.beQuiet()
}
let d = Dog()
tellToHush(d)
```

In that code, we told the compiler that this object would turn out to be a `NoisyDog`, and the compiler obediently took its hands off and allowed us to send the `beQuiet` message to it. But in fact, this object was a `Dog` when our code ran, and so we ultimately crashed when the cast failed because this object was *not* a `NoisyDog`.

To prevent yourself from lying accidentally, you can *test* the type of an instance at runtime. One way to do that is with the keyword `is`. You can use `is` in a condition; if the condition passes, *then* cast, in the knowledge that your cast is safe:

```
func tellToHush(_ d:Dog) {
    if d is NoisyDog {
        let d = d as! NoisyDog
        d.beQuiet()
    }
}
```

The result is that we won't cast `d` to a `NoisyDog` unless it really *is* a `NoisyDog`.

An alternative way to solve the same problem is to use Swift's `as?` operator. This casts down, but with the option of failure; therefore what it casts to is (you guessed it) an `Optional` — and now we are on familiar ground, because we know how to deal safely with an `Optional`:

```
func tellToHush(_ d:Dog) {
    let d = d as? NoisyDog // an Optional wrapping a NoisyDog
    if d != nil {
        d!.beQuiet()
    }
}
```

That doesn't look much cleaner or shorter than our previous approach. But remember that we can safely send a message to an `Optional` by optionally unwrapping the `Optional`:

```
func tellToHush(_ d:Dog) {
    let d = d as? NoisyDog // an Optional wrapping a NoisyDog
    d?.beQuiet()
}
```

Or, as a one-liner:

```
func tellToHush(_ d:Dog) {
    (d as? NoisyDog)?.beQuiet()
}
```



First we use the `as?` operator to obtain an `Optional` wrapping a `NoisyDog`. Then we optionally unwrap that `Optional` and send a message to it. If the original `d` wasn't a `NoisyDog`, the `Optional` will be `nil` and it won't be unwrapped and no message will be sent.

## Type Testing and Casting Optionals

The `is`, `as!`, and `as?` operators work with `Optionals` in the same way that the equality comparison operators do ([Chapter 3](#)): they are automatically applied to the object wrapped by the `Optional`.

Let's start with `is`. Consider an `Optional d` ostensibly wrapping a `Dog` (that is, `d` is a `Dog?` object). It might, in actual fact, be wrapping either a `Dog` or a `NoisyDog`. To find out which it is, you might be tempted to use `is`. But can you? After all, an `Optional` is neither a `Dog` nor a `NoisyDog` — it's an `Optional`! Nevertheless, Swift knows what you mean; when the thing on the left side of `is` is an `Optional`, Swift pretends that it's the value wrapped in the `Optional`. This works just as you would hope:

```
let d : Dog? = NoisyDog()
if d is NoisyDog { // it is!
```

When using `is` with an `Optional`, the test fails in good order if the `Optional` is `nil`. Our test really does *two* things: it checks whether the `Optional` is `nil`, and if it is not, it then checks whether the wrapped value is the type we specify.

What about casting? You can't really cast an `Optional` to anything. Nevertheless, Swift knows what you mean; you can use the `as!` operator with an `Optional`. When the thing on the left side of `as!` is an `Optional`, Swift treats it as the wrapped type. Moreover, the consequence of applying the `as!` operator is that two things happen: Swift unwraps first, and then casts. This code works, because `d` is unwrapped to give us `d2`, which is a `NoisyDog`:

```
let d : Dog? = NoisyDog()
let d2 = d as! NoisyDog
d2.beQuiet()
```

That code, however, is not safe. You shouldn't cast like that, without testing first, unless you are very sure of your ground. If `d` were `nil`, you'd crash in the second line because you're trying to unwrap a `nil` `Optional`. And if `d` were a `Dog`, not a `NoisyDog`, you'd *still* crash in the second line when the cast fails. That's why there's also an `as?` operator, which *is* safe — but yields an `Optional`:

```
let d : Dog? = NoisyDog()
let d2 = d as? NoisyDog
d2?.beQuiet()
```

In that code, we use `as?` to cast down from an `Optional` wrapping a `Dog` (`d`) to an `Optional` wrapping a `NoisyDog` (`d2`). The operation is safe, twice. If `d` is `nil`, `d2` will be `nil`, safely. If `d` is not `nil` but wraps a `Dog`, not a `NoisyDog`, the cast will fail, and `d2` will be `nil`, safely. If `d` wraps a `NoisyDog`, `d2` wraps a `NoisyDog`. In the last line, we unwrap `d2` and send it a `NoisyDog` message — safely.

## Bridging to Objective-C

Another way you'll use casting is during a value interchange between Swift and Objective-C when two types are *equivalent*. For example, you can cast a Swift `String` to a Cocoa `NSString`, and vice versa. That's not because one is a subclass of the other, but because they are *bridged* to one another; in a very real sense, they are the same type. When you cast from `String` to `NSString`, you're not casting down, and what you're doing is not dangerous, so you use the `as` operator, with no exclamation mark or question mark.

In general, to cross the bridge from a Swift type to a bridged Objective-C type, you will need to cast explicitly (except in the case of a string literal):

```
let s : NSString = "howdy"           // string literal to NSString
let s2 = "howdy"
let s3 : NSString = s2 as NSString // String to NSString
let i : NSNumber = 1 as NSNumber    // Int to NSNumber
```

That sort of code, however, is rather artificial. In real life, you won't be casting all that often, because the Cocoa API will present itself to you in terms of Swift types. This is legal with no cast:

```
let name = "MyNib" // Swift String
let vc = ViewController(nibName:name, bundle:nil)
```

The `UIViewController` class comes from Cocoa, and its `nibName` property is an Objective-C `NSString` — not a Swift `String`. But you don't have to help the Swift `String` name across the bridge by casting, because, in the Swift world, `nibName` is typed as a Swift `String` (actually, an `Optional` wrapping a `String`). The bridge, in effect, is crossed *later*.

Similarly, no cast is required here:

```
let ud = UserDefaults.standard
let s = "howdy"
ud.set(s, forKey:"greeting")
```

You don't have to help the Swift `String` `s` across the bridge by casting, because the first argument of `set(_:forKey:)` is typed as a Swift type, namely `Any` (actually, an `Optional` wrapping `Any`) — and any Swift type can be used, without casting, where an `Any` is expected. I'll talk more about `Any` later in this chapter.

Coming back the other way, it is possible that you'll receive from Objective-C a value about whose real underlying type Swift has no information. In that case, you'll probably want to cast explicitly to the underlying type — and now you *are* casting down, with all that that implies. Here's what happens when we go to retrieve the "howdy" that we put into UserDefaults in the previous example:

```
let ud = UserDefaults.standard
let test = ud.object(forKey:"greeting") as! String
```

When we call `ud.object(forKey:)`, Swift has no type information; the result is an Any (actually, an Optional wrapping Any). But we know that this particular call should yield a string — because that's what we put in to begin with. So we can force-cast this value down to a String — and it works. However, if `ud.object(forKey:"greeting")` were *not* a string (or if it were `nil`), we'd crash. If you're not sure of your ground, use `is` or `as?` to be safe.

## Type References

This section talks about the ways in which Swift can refer to the type of an object, other than saying the bare type literally.

### From Instance to Type

Sometimes, what you've got is an instance, and you want to know its type. This might be for no other reason than to log its type to the console, for the sake of information or debugging; or you might need to use the type as a value, as I'll explain later.

For this purpose, you can use the global `type(of:)` function:

```
let d : Dog = NoisyDog()
print(type(of:d)) // NoisyDog
```

As you would expect, the identity principle applies. We are not asking how `d`, the variable, is typed; we're asking what sort of object the instance referred to by `d` *really* is. It's typed as `Dog`, but it's a `NoisyDog` instance.

### From self to Type

It is particularly important for an instance to be able to refer to its *own* type. Quite commonly, this is in order to send a message to that type. For instance, suppose an instance wants to send a class message to its class. In an earlier example, a `Dog` instance method fetched a `Dog` class property by sending a message to the `Dog` type, literally using the word `Dog`:

```
class Dog {
  class var whatDogsSay : String {
    return "woof"
  }
  func bark() {
    print(Dog.whatDogsSay) // woof
  }
}
```

The expression `Dog.whatDogsSay` seems clumsy and inflexible. Why should we hard-code into `Dog` a knowledge of what type it is? It *has* a type; it should just *know* what it is. We can refer to the current type — the type of `self` — using the keyword `Self` (with a capital letter):

```
class Dog {
  class var whatDogsSay : String {
    return "woof"
  }
  func bark() {
    print(Self.whatDogsSay) // woof
  }
}
```

Similarly, we wrote a `Filter` enum earlier in this chapter that accessed its static `allCases` by saying `Filter.allCases`. We can say `Self.allCases` instead, and I prefer to do so; it's prettier.

Saying `Self` instead of a type name isn't *just* prettier; it's more powerful, because `Self`, like `self`, obeys polymorphism. Here are `Dog` and its subclass, `NoisyDog`:

```
class Dog {
  class var whatDogsSay : String {
    return "woof"
  }
  func bark() {
    print(Self.whatDogsSay)
  }
}
class NoisyDog : Dog {
  override class var whatDogsSay : String {
    return "woof woof woof"
  }
}
```

Now watch what happens:

```
let nd = NoisyDog()
nd.bark() // woof woof woof
```

If we tell a `NoisyDog` instance to bark, it says "woof woof woof". The reason is that `Self` means, "The type that this object actually is, right now." We send the bark message to a `NoisyDog` instance. The bark implementation refers to `Self`; even though

the bark implementation is inherited from Dog, Self means the type of this instance, which is a NoisyDog, and so Self is the NoisyDog class, and it is NoisyDog's version of whatDogsSay that is fetched.

Another important use of polymorphic Self is as a return type. To show why this is valuable, I'll introduce the notion of a *factory method*.

Suppose our Dog class has a name instance property, and its only initializer is init(name:). Let's give our Dog class a class method makeAndName. We want this class method to create and return a named Dog of whatever class we send the makeAndName message to. If we say Dog.makeAndName(), we should get a Dog. If we say NoisyDog.makeAndName(), we should get a NoisyDog. Well, we know how to do that; just initialize polymorphic Self. It works in a class method just as it works in an instance method:

```
class Dog {
  var name : String
  init(name:String) {
    self.name = name
  }
  class func makeAndName() -> Dog {
    let d = Self(name:"Fido") // compile error
    return d
  }
}
class NoisyDog : Dog {
}
```

However, there's a problem: that code doesn't compile. The reason is that the compiler is in doubt as to whether the init(name:) initializer is implemented by every possible subtype of Dog. To reassure the compiler, we must declare that initializer with the required keyword:

```
class Dog {
  var name : String
  required init(name:String) { // *
    self.name = name
  }
  class func makeAndName() -> Dog {
    let d = Self(name:"Fido")
    return d
  }
}
class NoisyDog : Dog {
}
```

I promised earlier that I'd tell you why you might need to declare an initializer as required; now I'm fulfilling that promise! The required designation means that every subclass of Dog *must inherit or reimplement* init(name:), so the compiler

permits us to call `init(name:)` on a type reference that might refer to `Dog` or some subclass of `Dog`.

So now our code compiles, and we can call our function:

```
let d = Dog.makeAndName() // d is a Dog named Fido
let d2 = NoisyDog.makeAndName() // d2 is a NoisyDog named Fido
```

That code works as expected. But now there's *another* problem. Although `d2` is in fact a `NoisyDog`, it is *typed* as a `Dog`. That's because our `makeAndName` class method is declared as returning a `Dog`. That isn't what we want to declare. We want to declare that this method returns an instance *of the same type* as the class to which the `makeAndName` message was originally sent. In other words, we need a polymorphic type declaration! That type is `Self` once again:

```
class Dog {
  var name : String
  required init(name:String) {
    self.name = name
  }
  class func makeAndName() -> Self { // *
    let d = Self(name:"Fido")
    return d
  }
}
class NoisyDog : Dog {
}
```

The `Self` type is used as a return type in a method declaration to mean “an instance of whatever type this is at runtime.” So when we call `NoisyDog.makeAndName()` we get a `NoisyDog` typed as `NoisyDog`.

`Self` also works for instance method declarations. Therefore, we can write an instance method version of our factory method. Here, we start with a `Dog` or a `NoisyDog` and tell it to have a puppy of the same type as itself:

```
class Dog {
  var name : String
  required init(name:String) {
    self.name = name
  }
  func havePuppy(name:String) -> Self {
    return Self(name:name)
  }
}
class NoisyDog : Dog {
}
```

And here's some code to test it:

```
let d = Dog(name:"Fido")
let d2 = d.havePuppy(name:"Fido Junior")
let nd = NoisyDog(name:"Rover")
let nd2 = nd.havePuppy(name:"Rover Junior")
```

As expected, `d2` is a `Dog`, but `nd2` is a `NoisyDog` typed as `NoisyDog`.

## Type as Value

In some situations, you may want to treat an object type *as a value*. That is legal. An object type is itself an object, of a sort; it's what Swift calls a *metatype*. So an object type can be assigned to a variable or passed as a parameter:

- To *declare* that an object type is acceptable — as when declaring the type of a variable or parameter — use dot-notation with the name of the type and the keyword `Type`.
- To *use* an object type as a value — as when assigning a type to a variable or passing it as a parameter — hand the object to `type(of:)`, or use dot-notation with the name of the type and the keyword `self`. (In the latter case, the name of the type might be `Self`, in which case you'll be saying `Self.self`!)

Here's a function `dogTypeExpecter` that accepts a `Dog` type as its parameter:

```
func dogTypeExpecter(_ whattype:Dog.Type) {
}
```

And here's an example of calling that function:

```
dogTypeExpecter(Dog.self)
```

Or you could call it like this:

```
let d = Dog()
dogTypeExpecter(type(of:d))
```

The substitution principle applies, so you could call `dogTypeExpecter` like this:

```
dogTypeExpecter(NoisyDog.self)
```

Or like this:

```
let nd = NoisyDog()
dogTypeExpecter(type(of:nd))
```

To illustrate more practically, I'll rewrite our `Dog` factory method as a global factory function that will accept a `Dog` *type* as a parameter and will create an instance from that type. You can use a variable reference to a type (a metatype) to instantiate that type, but you can't just append parentheses to a variable reference:

```
func dogMakerAndNamer(_ whattype:Dog.Type) -> Dog {
    let d = whattype(name:"Fido") // compile error
    return d
}
```

Instead, you must explicitly send the reference an `init(...)` message:

```
func dogMakerAndNamer(_ whattype:Dog.Type) -> Dog {
    let d = whattype.init(name:"Fido")
    return d
}
```

And here's how to call our function:

```
let d = dogMakerAndNamer(Dog.self) // d is a Dog named Fido
let d2 = dogMakerAndNamer(NoisyDog.self) // d2 is a NoisyDog named Fido
```

Unfortunately, the global factory function `dogMakerAndNamer`, displays the same problem we had before — it returns an object typed as `Dog`, even if the underlying instance is in fact a `NoisyDog`. We can't return `Self` to solve the problem here, because there's no type for it to refer to. Swift does have a solution, however — generics. I'll discuss generic functions later in this chapter.

## Summary of Type Terminology

All this terminology can get a bit confusing, so here's a quick summary:

`type(of:)`

Applied to an object: the polymorphic (internal) type of the object, regardless of how a reference is typed.

`Self`

In a method body, or in a method declaration when specifying the return type, this type or this instance's type, polymorphically.

`.Type`

Appended to a type in a type declaration to specify that the type itself (or a subtype) is expected.

`.self`

Sent to a type to generate a metatype, suitable for passing where a type (`.Type`) is expected.

## Comparing Types

Type references can be compared to one another. On the right side of an `==` comparison, you can use the name of a type with `.self`; on the right side of an `is` comparison, you can use the name of a type with `.Type`. The difference, as you might expect, is that `==` tests for absolutely identical types, whereas `is` permits subtypes.

In this artificial example, if the parameter `whattype` is `Dog.self`, both equality and typology are true; if `whattype` is `NoisyDog.self`, equality is false but typology is still true:



```
func dogTypeExpecter(_ whattype:Dog.Type) {
    let equality = whattype == Dog.self
    let typology = whattype is Dog.Type
}
```

In that example, `whattype` might be replaced on the left side of the comparisons by the result of a call to `type(of:)` (or by a type name qualified by `.self`, though that would be pointless); and `Dog.self` might be replaced on the right side of the `==` comparison by `whattype` or the result of a call to `type(of:)`. But neither `whattype` nor `type(of:)` can appear on the right side of an `is` comparison; `is` requires a literal type as its second operand.

In real life, however, comparing type references is a *very* rare thing to do. Passing metatypes around is not Swiftly, and comparing metatypes is *really* not Swiftly. In general, if you find yourself talking like that, you should probably think of another way of doing whatever it is you’re trying to do.

## Protocols

A *protocol* is a way of expressing commonalities between otherwise unrelated types. For example, a Bee object and a Bird object might have features in common by virtue of the fact that both a bee and a bird can fly. Thus, it might be useful to define a Flier type. The question is: In what sense can both Bee and Bird be Fliers?

One possibility might be class inheritance. If Bee and Bird are both classes, Flier could be the superclass of both Bee and Bird. However, there may be other reasons why Flier *can’t* be the superclass of both Bee and Bird. A Bee is an Insect; a Bird isn’t. Yet they both have the power of flight — independently. We need a type that cuts across the class hierarchy somehow, tying remote classes together.

Moreover, what if Bee and Bird are *not* both classes? In Swift, that’s a real possibility. Important and powerful objects can be structs instead of classes. But there is no hierarchy of superstructs and substructs! How can a Bee struct and a Bird struct both be Fliers?

Swift solves this problem through the use of protocols. Protocols are tremendously important in Swift; the Swift header defines over 60 protocols! Moreover, Objective-C has protocols as well, and Cocoa makes heavy use of protocols; Swift protocols correspond roughly to Objective-C protocols, and can interchange with them.

A protocol is an object *type*, but there are no protocol *objects* — you can’t instantiate a protocol. A protocol declaration is just a lightweight list of properties and methods. The properties have no values, and the methods have no code! The idea is that a “real” object type can formally declare that it belongs to a protocol type; this is called *adopting* the protocol. An object type that adopts a protocol is promising to

implement the properties and methods listed by the protocol. And it must keep that promise! This is called *conforming to* the protocol.

Let's say that being a Flier consists of no more than implementing a fly method. Then a Flier protocol could specify that there must be a fly method; to do so, it lists the fly method *with no function body*, like this:

```
protocol Flier {  
    func fly()  
}
```

Any type — an enum, a struct, a class, or even another protocol — can then adopt this protocol. To do so, it lists the protocol after a colon after its name in its declaration. (If the adopter is a class with a superclass, the protocol comes after a comma after the superclass specification.)

Let's say Bird is a struct. Then it can adopt Flier like this:

```
struct Bird : Flier {  
} // compile error
```

So far, so good. But that code won't compile. The Bird struct has promised to implement the features listed in the Flier protocol. Now it must keep that promise! The fly method is the only requirement of the Flier protocol. To satisfy that requirement, I'll just give Bird an empty fly method:

```
protocol Flier {  
    func fly()  
}  
struct Bird : Flier {  
    func fly() {  
    }  
}
```

That's all there is to it. We've defined a protocol, and we've made a struct adopt and conform to that protocol. Of course, in real life you'll probably want to make the adopter's implementation of the protocol's methods *do* something; but the protocol says nothing about that.



A protocol can also declare a method *and provide its implementation*, thanks to protocol extensions, which I'll discuss later in this chapter.

## Why Protocols?

Perhaps at this point you're wondering: So what? If we wanted a Bird to know how to fly, why didn't we just give Bird a fly method *without* adopting any protocol? What difference does the protocol make?

The answer has to do with types. A protocol, such as our `Flier`, is a kind of type. Therefore, I can *use* `Flier` as a type when declaring the type of a variable or a function parameter:

```
func tellToFly(_ f:Flier) {
    f.fly()
}
```

Protocols thus give us another way of expressing the notion of type and subtype — and *polymorphism applies*. By the substitution principle, a `Flier` here could be an instance of *any* object type, *as long as it adopts the Flier protocol*. It might be a `Bird`, it might be something else; we don't care. If it adopts the `Flier` protocol, it can be passed where a `Flier` is expected; moreover, it must have a `fly` method, because that's exactly what it *means* to adopt the `Flier` protocol! Therefore we can confidently send the `fly` message to this object, and the compiler lets us do that.

The converse, however, is not true: an object with a `fly` method is *not* automatically a `Flier`. It isn't enough to *obey* the requirements of a protocol; the object type must formally *adopt* the protocol. This code won't compile:

```
func tellToFly(_ f:Flier) {
    f.fly()
}
struct Bee {
    func fly() {
    }
}
let b = Bee()
tellToFly(b) // compile error
```

A `Bee` *can* be sent the `fly` message, *qua* `Bee`. But `tellToFly` doesn't take a `Bee` parameter; it takes a `Flier` parameter. Formally, a `Bee` is *not* a `Flier`. To make a `Bee` a `Flier`, just declare formally that `Bee` adopts the `Flier` protocol! This code does compile:

```
func tellToFly(_ f:Flier) {
    f.fly()
}
struct Bee : Flier {
    func fly() {
    }
}
let b = Bee()
tellToFly(b)
```

## Adopting a Library Protocol

Enough of birds and bees; we're ready for a real-life example! The Swift standard library is chock full of protocols already; let's make one of our own object types adopt one and watch the powers of that protocol spring to life for us.

The CustomStringConvertible protocol requires that we implement a description String property. If we do that, a wonderful thing happens: when an instance of this type is used in string interpolation or with print (or the po command in the console, or in the String initializer init(describing:)), its description property value is used automatically to represent it.

Recall the Filter enum, from earlier in this chapter. I'll add a description property to it:

```
enum Filter : String {
    case albums = "Albums"
    case playlists = "Playlists"
    case podcasts = "Podcasts"
    case books = "Audiobooks"
    var description : String { return self.rawValue }
}
```

But that isn't enough, in and of itself, to give Filter the power of the CustomStringConvertible protocol; to do that, we also need to *adopt* the CustomStringConvertible protocol formally. There is already a colon and a type in the Filter declaration, so an adopted protocol comes after a comma:

```
enum Filter : String, CustomStringConvertible {
    case albums = "Albums"
    case playlists = "Playlists"
    case podcasts = "Podcasts"
    case books = "Audiobooks"
    var description : String { return self.rawValue }
}
```

We have now made Filter formally adopt the CustomStringConvertible protocol. The CustomStringConvertible protocol requires that we implement a description String property; we *do* implement a description String property, so our code compiles. Now we can interpolate a Filter into a string, or hand it over to print, or coerce it to a String, and its description will be used automatically:

```
let type = Filter.albums
print("It is \(type)") // It is Albums
print(type) // Albums
let s = String(describing:type) // Albums
```

Behold the power of protocols. You can give *any* object type the power of string conversion in exactly the same way.

Note that a type can adopt more than one protocol! The built-in Double type adopts CustomStringConvertible, Hashable, Strideable, and several other built-in protocols. To declare adoption of multiple protocols, list them separated by a comma after the protocol name and colon in the declaration (after the raw value type or superclass type if there is one):

```
struct MyType : CustomStringConvertible, TextOutputStreamable, Strideable {
    // ...
}
```

(Of course, that code won't compile unless I also declare, in `MyType`, any required properties and methods, so that `MyType` actually conforms to those protocols.)

## Protocol Type Testing and Casting

The operators for mediating between an object's declared type and its real type work when the declared type is a protocol type. Given a protocol `Flier` that is adopted by both `Bird` and `Bee`, we can use the `is` operator to test whether a particular `Flier` is in fact a `Bird`:

```
func isBird(_ f:Flier) -> Bool {
    return f is Bird
}
```

Similarly, `as!` and `as?` can be used to cast an object declared as a protocol type down to its actual type. This is important to be able to do, because the adopting object will typically be able to receive messages that the protocol can't receive. Let's say that a `Bird` can get a worm:

```
struct Bird : Flier {
    func fly() {
    }
    func getWorm() {
    }
}
```

A `Bird` can fly *qua* `Flier`, but it can `getWorm` only *qua* `Bird`. You can't tell just any old `Flier` to get a worm:

```
func tellGetWorm(_ f:Flier) {
    f.getWorm() // compile error
}
```

But if this `Flier` is a `Bird`, clearly it *can* get a worm. That is exactly what casting is all about:

```
func tellGetWorm(f:Flier) {
    (f as? Bird)?.getWorm()
}
```

## Declaring a Protocol

Protocol declaration can take place only at the top level of a file. To declare a protocol, use the keyword `protocol` followed by the name of the protocol (which should start with a capital letter, as this is a type). Then come curly braces which may contain declarations for any of the following:

## Properties

A property declaration in a protocol consists of `var` (not `let`), the property name, a colon, its type, and curly braces containing the word `get` or the words `get set`. In the former case, the adopter's implementation of this property *can* be writable, while in the latter case, it *must* be: the adopter may not implement a `get set` property as a read-only computed property or as a constant (`let`) stored property.

To declare a static/class property, precede it with the keyword `static`. A class adopter is free to implement this as a class property.

## Methods

A method declaration in a protocol is a function declaration without a function body; it has no curly braces and no code. Any object function type is legal, including `init` and `subscript`. (The syntax for declaring a subscript in a protocol is the same as the syntax for declaring a subscript in an object type, except that the curly braces will contain `get` or `get set`.)

To declare a static/class method, precede it with the keyword `static`. A class adopter is free to implement this as a class method.

To permit an enum or struct adopter to declare a method `mutating`, declare it `mutating` in the protocol. An adopter cannot add `mutating` if the protocol lacks it, but the adopter may omit `mutating` if the protocol has it.

A protocol can itself adopt one or more protocols; the syntax is just as you would expect — a colon after the protocol's name in the declaration, followed by a comma-separated list of the protocols it adopts. In effect, this gives you a way to create an entire secondary hierarchy of types! The Swift headers make heavy use of this.

A protocol that adopts another protocol may repeat the contents of the adopted protocol's curly braces, for clarity; but it doesn't have to, as this repetition is implicit. An object type that adopts a protocol must satisfy the requirements of this protocol and all protocols that the protocol adopts.

## Protocol Composition

If the only purpose of a protocol is to combine other protocols by adopting all of them, without adding any new requirements, you can avoid formally declaring the protocol in the first place by specifying the protocol combination on the fly. To do so, join the protocol names with `&`. This is called *protocol composition*:

```
func f(_ x: CustomStringConvertible & CustomDebugStringConvertible) {  
}
```

That is a function declaration with a parameter whose type is specified as being some object type that adopts both the CustomStringConvertible protocol and the CustomDebugStringConvertible protocol.

A type can also be specified as a composite of a class type and one or more protocols. A case in point might look something like this:

```
protocol MyViewProtocol {
    func doSomethingReallyCool()
}
class ViewController: UIViewController {
    var v: (UIView & MyViewProtocol)?
    func test() {
        self.v?.doSomethingReallyCool() // a MyViewProtocol requirement
        self.v?.backgroundColor = .red // a UIView property
    }
}
```

To be assigned to ViewController's `v` property, an object would need to be an instance of a UIView subclass that is also an adopter of MyViewProtocol. In this way, we guarantee to the compiler that both UIView messages and MyViewProtocol messages can be sent to a ViewController's `v`; otherwise, we'd have to type `v` as a MyViewProtocol and then cast down to UIView in order to send it UIView messages, even if we knew that `v` would in fact always be a UIView.

There's another way to accomplish the same thing; we can declare MyViewProtocol itself in such a way that it can be adopted *only* by UIView, as I shall now explain.

## Class Protocols

A protocol declaration may include the name of a class after the colon. This limits the types capable of adopting this protocol to that class or its subclasses:

```
protocol MyViewProtocol : UIView {
    func doSomethingReallyCool()
}
class ViewController: UIViewController {
    var v: MyViewProtocol? // and therefore a UIView
    func test() {
        self.v?.doSomethingReallyCool() // a MyViewProtocol requirement
        self.v?.backgroundColor = .red // a UIView property
    }
}
```

Here, MyViewProtocol can be adopted only by UIView or a UIView subclass. This means that an object typed as MyViewProtocol can be sent both MyViewProtocol messages and UIView messages, because *ex hypothesi* a MyViewProtocol adopter must *be* a UIView.

To specify that a protocol can be adopted only by *some* class (and not a struct or enum) without specifying *what* class it must be, use the protocol type `AnyObject`, which every class type adopts (as I'll explain later):

```
protocol MyClassProtocol : AnyObject {  
    // ...  
}
```

An alternative notation is a `where` clause before the curly braces. I have not yet talked about `where` clauses or the use of `Self` to signify the protocol's adopter, but I'll show you the notation now anyway:

```
protocol MyViewProtocol where Self:UIView {  
    func doSomethingReallyCool()  
}  
protocol MyClassProtocol where Self:AnyObject {  
    // ...  
}
```

A valuable byproduct of declaring a class protocol is that the resulting type can take advantage of special memory management features that apply only to classes. I haven't discussed memory management yet, but I'll give an example anyway (and I'll repeat it when I talk about memory management in [Chapter 5](#)):

```
protocol SecondViewControllerDelegate : AnyObject {  
    func accept(data:Any)  
}  
class SecondViewController : UIViewController {  
    weak var delegate : SecondViewControllerDelegate?  
    // ...  
}
```

The keyword `weak` marks the `delegate` property as having special memory management that applies only to class instances. The `delegate` property is typed as a protocol, and a protocol might be adopted by a struct or an enum type. So to satisfy the compiler that this object *will* in fact be a class instance, and *not* a struct or enum instance, the protocol is declared as a class protocol.



An `@objc` protocol is a class protocol, as class protocols are the only kind of protocol Objective-C understands.

## Optional Protocol Members

In Objective-C, a protocol member can be declared optional, meaning that this member doesn't have to be implemented by the adopter, but it may be. Swift allows optional protocol members, but this feature is solely for compatibility with Objective-C, and in fact is implemented *by* Objective-C; it isn't really a Swift feature at all. Therefore, everything about an optional protocol member must be explicitly exposed



to Objective-C. The protocol declaration must be marked with the `@objc` attribute, and an optional member's declaration must be marked with the keywords `@objc optional`:

```
@objc protocol Flier {
    @objc optional var song : String {get}
    @objc optional func sing()
}
```

(I'll explain in [Chapter 11](#) *how* Objective-C implements optional protocol members.)

Many Cocoa protocols have optional members. For example, your iOS app will have an app delegate class that adopts the `UIApplicationDelegate` protocol; this protocol has many methods, all of them optional. That fact, however, will have no effect on how you implement those methods; either you implement a method or you don't. (I'll talk more about Cocoa protocols in [Chapter 11](#), and about delegate protocols in [Chapter 12](#).)

An optional member is not guaranteed to be implemented by the adopter, so Swift doesn't know whether it's safe to send a `Flier` either the `song` message or the `sing` message. How Swift solves that problem depends on whether this is an optional property or an optional method.

## Optional properties

In the case of an optional property (like `song`), Swift solves the problem by wrapping its fetched value in an `Optional`. If the `Flier` adopter doesn't implement the property, the result is `nil` and no harm done:

```
@objc protocol Flier {
    @objc optional var song : String {get}
}
let f : Flier = Bird()
let s = f.song // s is an Optional wrapping a String
```

This is one of those rare situations where you can wind up with a double-wrapped `Optional`. If the value of the optional property `song` were itself a `String?`, then fetching its value from a `Flier` would yield a `String??`.

A curious limitation is that if a protocol declares an optional property `{get set}`, you can't set that property. If `f` is a `Flier` and `song` is declared `{get set}`, you can't set `f.song`:

```
@objc protocol Flier {
    @objc optional var song : String? {get set}
}
let f : Flier = Bird()
f.song = "tweet tweet" // compile error
```

The error message claims that `f` is immutable, which is blatantly false. This is evidently a bug in the language. A workaround (pointed out to me by Jordan Rose) is to use key path notation (which I'll explain in [Chapter 5](#)):

```
let f : Flier = Bird()
f[keyPath: \.song] = "tweet tweet"
```

## Optional methods

In the case of an optional method (like `sing`), things are more elaborate. If the method is not implemented, we must not be permitted to call it in the first place. To handle this situation, the method is typed as an `Optional` version of its declared type. To send the `sing` message to a `Flier`, therefore, you must unwrap it. What you are unwrapping is not the result of the method call; it's the method *itself*. In the method call, the `unwrap` operator must appear *before* the parentheses!

The safe approach is to unwrap an optional method optionally, with a question mark:

```
@objc protocol Flier {
    @objc optional func sing()
}
let f : Flier = Bird()
f.sing?()
```

The effect is to send the `sing` message to `f` only if this `Flier` adopter implements `sing`. If this `Flier` adopter *doesn't* implement `sing`, nothing happens. You could have force-unwrapped the call — `f.sing!()` — but then your app would crash if the adopter doesn't implement `sing`.

If an optional method returns a value, that value is wrapped in an `Optional` as well:

```
@objc protocol Flier {
    @objc optional func sing() -> String
}
```

If we now call `sing?()` on a `Flier`, the result is an `Optional` wrapping a `String`:

```
let f : Flier = Bird()
let s = f.sing?() // s is an Optional wrapping a String
```

If we force-unwrap the call — `f.sing!()` — the result is either a `String` (if the adopter implements `sing`) or a crash (if it doesn't).

## Implicitly Required Initializers

Suppose that a protocol declares an initializer. And suppose that a class adopts this protocol. By the terms of this protocol, this class and any subclass it may ever have must implement this initializer. Therefore, the class not only must implement the initializer, but also must mark it as `required`. An initializer declared in a protocol is

*implicitly required*, and a class that adopts this protocol is forced to make that requirement explicit.

Consider this simple example, which won't compile:

```
protocol Flier {
    init()
}
class Bird : Flier {
    init() {} // compile error
}
```

That code generates an elaborate but perfectly informative compile error message: “Initializer requirement `init()` can only be satisfied by a required initializer in non-final class `Bird`.” To compile our code, we must designate our initializer as required:

```
protocol Flier {
    init()
}
class Bird : Flier {
    required init() {}
}
```

Alternatively, if `Bird` were marked `final`, there would be no need to mark its `init` as required, because this would mean that `Bird` cannot have any subclasses — guaranteeing that the problem will never arise in the first place.

In the above code, `Bird` is *not* marked as `final`, and its `init` is marked as required. This, as I've already explained, means that any subclass of `Bird` that implements any designated initializers — and thus loses initializer inheritance — must implement the required initializer and mark it required as well.

That fact is responsible for a strange and annoying feature of real-life iOS programming with Swift. Let's say you subclass the built-in Cocoa class `UIViewController` — something that you are extremely likely to do. And let's say you give your subclass an initializer — something that you are also extremely likely to do:

```
class ViewController: UIViewController {
    init() {
        super.init(nibName:"ViewController", bundle:nil) // compile error
    }
}
```

That code won't compile. The compile error says: “required initializer `init(coder:)` must be provided by subclass of `UIViewController`.” What's going on here?

It turns out that `UIViewController` adopts a protocol called `NSCoding`. And this protocol requires an initializer `init(coder:)`, which `UIViewController` duly implements. None of that is your doing; `UIViewController` and `NSCoding` are declared by Cocoa, not by you. But that doesn't matter! This is the same situation I was just

describing. Your UIViewController subclass must either inherit `init(coder:)` or must explicitly implement it and mark it `required`. Well, your subclass has implemented a designated initializer of its own — thus *cutting off initializer inheritance*. Therefore it *must* implement `init(coder:)` and mark it `required`.

But that makes no sense if you are not expecting `init(coder:)` ever to be *called* on your UIViewController subclass. You are being forced to write an initializer for which you can provide no meaningful functionality! Fortunately, Xcode’s Fix-it feature ([Chapter 10](#)) will offer to write the initializer for you, like this:

```
required init?(coder: NSCoder) {  
    fatalError("init(coder:) has not been implemented")  
}
```

That code satisfies the compiler. The initializer is aborted, so it is legal even though it doesn’t fulfill an initializer’s contract. It also crashes if it is ever called — which is fine, because *ex hypothesi* you don’t expect it ever to be called. (I’ll talk more about `fatalError` in [Chapter 5](#)).

If, on the other hand, you *do* have functionality for this initializer, you will delete the `fatalError` line and insert that functionality in its place. A minimum meaningful implementation would be to call `super.init(coder:coder)`, but of course if your class has properties that need initialization, you will need to initialize them first.

Not only UIViewController but *lots* of built-in Cocoa classes adopt NSCoding. You will encounter this problem if you subclass *any* of those classes and implement your own initializer. It’s just something you’ll have to get used to.

## Expressible by Literal

One of the delightful things about Swift is that so many of its features, rather than being built-in and accomplished by magic, are exposed in the Swift header. Literals are a case in point. The reason you can say 5 to express an `Int` whose value is 5, instead of formally initializing `Int` by saying `Int(5)`, is not because of magic (or at least, not entirely because of magic). It’s because `Int` adopts a protocol, `ExpressibleByIntegerLiteral`. Not only `Int` literals, but *all* literals work this way. The following protocols are declared in the Swift header:

- `ExpressibleByNilLiteral`
- `ExpressibleByBooleanLiteral`
- `ExpressibleByIntegerLiteral`
- `ExpressibleByFloatLiteral`
- `ExpressibleByStringLiteral`
- `ExpressibleByExtendedGraphemeClusterLiteral`

- ExpressibleByUnicodeScalarLiteral
- ExpressibleByArrayLiteral
- ExpressibleByDictionaryLiteral

Your own object type can adopt an expressible-by-literal protocol as well. This means that a literal can appear where an instance of your object type is expected! Here we declare a `Nest` type that contains some number of eggs (its `eggCount`):

```
struct Nest : ExpressibleByIntegerLiteral {
    var eggCount : Int = 0
    init() {}
    init(integerLiteral val: Int) {
        self.eggCount = val
    }
}
```

Because `Nest` adopts `ExpressibleByIntegerLiteral`, we can pass an `Int` where a `Nest` is expected, and our `init(integerLiteral:)` will be called automatically, causing a new `Nest` object with the specified `eggCount` to come into existence at that moment:

```
func reportEggs(_ nest:Nest) {
    print("this nest contains \(nest.eggCount) eggs")
}
reportEggs(4) // this nest contains 4 eggs
```

## Generics

A *generic* is a sort of placeholder for a type, into which an actual type will be slotted later. In particular, there are situations where you want to say that a certain *same* type is to be used in several places, without specifying precisely *what* type this is to be. Swift generics allow you to say that, without sacrificing or evading Swift’s fundamental strict typing.

We’re already familiar with one very important case in point: an `Optional`. Any type of value can be wrapped up in an `Optional`. Yet there is no doubt as to what type is wrapped up in a *particular* `Optional`. How can this be? Here’s how an `Optional` works.

I have already said that an `Optional` is an enum, with two cases: `.none` and `.some`. If an `Optional`’s case is `.some`, it has an associated value — the value that is wrapped by this `Optional`. But what is the type of that associated value? On the one hand, one wants to say that it can be any type; that, after all, is why anything can be wrapped up in an `Optional`. On the other hand, any *particular* `Optional` can wrap a value only of some one *specific* known type.

That is the very essence of a generic! The declaration for the `Optional` enum in the Swift header starts like this:

```
enum Optional<Wrapped> : ExpressibleByNilLiteral {
    // ...
}
```

That syntax means: “In the course of this enum declaration, I’m going to be using a made-up type — a type *placeholder* — that I call *Wrapped*. It’s a real and individual type, but I’m not going to say more about it right now. All you need to know is that whenever I say *Wrapped*, I mean this one particular type. When an actual *Optional* is created, it will be perfectly clear what type *Wrapped* stands for, and then, wherever I say *Wrapped*, you should substitute the type that it stands for.”

Let’s look at more of the *Optional* declaration:

```
enum Optional<Wrapped> : ExpressibleByNilLiteral { ❶
    case none
    case some(Wrapped) ❷
    init(_ some: Wrapped) ❸
    // ...
}
```

Here’s how that code works. The placeholder type name *Wrapped* appears in three different places:

- ❶ The angle-bracket syntax *<Wrapped>* *declares* that *Wrapped* is a placeholder.
- ❷ Besides the case *.none*, there’s also a case *.some*, which has an associated value — of type *Wrapped*.
- ❸ There’s also an initializer, which takes a parameter — of type *Wrapped*.

All of that constitutes a sort of template for how *Optional* works. In real life, Swift has strict typing, so any *particular* *Optional* instance must have a real type substituted for the *Wrapped* placeholder. The process of substitution is called *resolving* (or *specializing*) the generic. The type in question must be made unambiguously clear for each actual usage of this enum, so that the compiler is satisfied.

And how will the placeholder be resolved? Here’s one way. When an *Optional* is created, it will be initialized with an actual value of some definite type:

```
let s = Optional("howdy")
```

We’re calling *init(\_ some: Wrapped)*, so “howdy” is being supplied here as a *Wrapped* instance — resolving the generic as *String*. So the compiler now knows that *Wrapped* must be *String* *throughout* this particular *Optional<Wrapped>*. The type with which we are initialized — whatever type that may be — *is* type *Wrapped*, and therefore is the type associated with the *.some* case. The declaration for this *particular* *Optional* looks, in the compiler’s mind, like this (pseudocode):

```
enum Optional<String> {
  case none
  case some(String)
  init(_ some: String)
  // ...
}
```

That is the pseudocode declaration of an `Optional` whose `Wrapped` placeholder has been replaced everywhere with the `String` type. We can summarize this by saying that `s` is an `Optional<String>`. In fact, that is legal syntax! We can create the same `Optional` like this:

```
let s : Optional<String> = "howdy"
```

Not only can types (such as enums) be generic; so can functions. A generic function solves a problem that was posed earlier. We wrote a global factory function for dogs:

```
func dogMakerAndNamer(_ whattype:Dog.Type) -> Dog {
  let d = whattype.init(name:"Fido")
  return d
}
```

That works, but it isn't quite what we'd like to say. This function's declared return type is `Dog`. So if we are passed a `Dog` subclass such as `NoisyDog` as the parameter, we will instantiate that type (which is good) but then return that instance typed as `Dog` (which is bad). Instead, we'd like the type declared as the return type after the arrow operator to be the *same* type that we were passed as a parameter in the first line and that we instantiated in the second line — whatever that type may be. Generics permit us to say that:

```
func dogMakerAndNamer<WhatType:Dog>(_:WhatType.Type) -> WhatType {
  let d = WhatType.init(name:"Fido")
  return d
}
```

The generic is resolved when we actually call that function. For example:

```
let dog = dogMakerAndNamer(NoisyDog.self)
```

In that call, we pass `NoisyDog.self` as the parameter. That tells the compiler what `WhatType` is! It is `NoisyDog`. In effect, the compiler now substitutes `NoisyDog` for `WhatType` throughout the generic, like this (pseudocode):

```
func dogMakerAndNamer(_:NoisyDog.Type) -> NoisyDog {
  let d = NoisyDog.init(name:"Fido")
  return d
}
```

And this resolution extends beyond the generic itself. Now that the compiler knows that this call to our function will return a `NoisyDog` instance, it can type the variable initialized to the result of the call as a `NoisyDog` by inference:

```
let dog = dogMakerAndNamer(NoisyDog.self) // dog is typed as NoisyDog
```

## Generic Declarations

Here's a list of places where generics, in one form or another, can be declared in Swift:

### *Generic protocol with Self*

In a protocol body, use of the keyword `Self` turns the protocol into a generic. `Self` here is a placeholder meaning *the type of the adopter*. Here's a `Flier` protocol that declares a method that takes a `Self` parameter:

```
protocol Flier {
    func flockTogetherWith(_ f:Self)
}
```

That means that if a `Bird` object type adopts the `Flier` protocol, its implementation of `flockTogetherWith` must declare its parameter as a `Bird`:

```
struct Bird : Flier {
    func flockTogetherWith(_ f:Bird) {}
}
```

### *Generic protocol with associated type*

A protocol can declare an *associated type* using an `associatedtype` statement. This turns the protocol into a generic; the associated type name is a placeholder:

```
protocol Flier {
    associatedtype T
    func flockTogetherWith(_ f:T)
    func mateWith(_ f:T)
}
```

An adopter will declare a particular type at some point where the generic uses the associated type name, resolving the placeholder:

```
struct Bee {}
struct Bird : Flier {
    func flockTogetherWith(_ f:Bee) {}
    func mateWith(_ f:Bee) {}
}
```

`T` here does *not* have to be this adopter of `Flier`, or *any* adopter of `Flier`. It could be `String`, or `Int`, or anything at all. Rather, the protocol dictates that whatever a `Flier` adopter is declared as flocking together with, it must be declared as mating with as well. The `Bird` struct adopts the `Flier` protocol and declares the parameter of `flockTogetherWith` as a `Bee`. That declaration resolves `T` to `Bee` for this particular adopter — and therefore `Bird` must declare the parameter for `mateWith` as a `Bee` as well.



### *Generic functions*

A function declaration can use a generic placeholder type for any of its parameters, for its return type, and within its body. The placeholder name is declared in angle brackets after the function name:

```
func takeAndReturnSameThing<T> (_ t:T) -> T {
    print(T.self)
    return t
}
```

The caller will use a particular type at some point where the placeholder appears in the function declaration, resolving the placeholder:

```
let thing = takeAndReturnSameThing("howdy")
```

Here, the type of the argument "howdy" used in the call resolves `T` to `String`; therefore this call to `takeAndReturnSameThing` must also return a `String`, and the type of the variable capturing the result, `thing`, is inferred as `String`.

### *Generic object types*

An object type declaration can use a generic placeholder type anywhere within its curly braces. The placeholder name is declared in angle brackets after the object type name:

```
struct HolderOfTwoSameThings<T> {
    var firstThing : T
    var secondThing : T
    init(thingOne:T, thingTwo:T) {
        self.firstThing = thingOne
        self.secondThing = thingTwo
    }
}
```

A user of this object type will use a particular type at some point where the placeholder appears in the object type declaration, resolving the placeholder:

```
let holder = HolderOfTwoSameThings(thingOne:"howdy", thingTwo:"bye")
```

Here, the type of the `thingOne`: argument, "howdy", used in the initializer call, resolves `T` to `String`; therefore `thingTwo`: must also be a `String`, and the properties `firstThing` and `secondThing` must be `Strings` as well.

The angle brackets that declare a placeholder may declare multiple placeholders, separated by a comma:

```
func flockTwoTogether<T, U>(_ f1:T, _ f2:U) {}
```

The two parameters of `flockTwoTogether` can now be resolved to two different types (though they do not *have* to be different).

Inside a generic's code, the generic placeholder is a type reference standing for the resolved type, which can be interrogated using type reference comparison, as described earlier in this chapter:

```
func takeAndReturnSameThing<T> (_ t:T) -> T {
    if T.self is String.Type {
        // ...
    }
    return t
}
```

If we call `takeAndReturnSameThing("howdy")`, the condition will be true. That sort of thing, however, is unusual; a generic whose behavior depends on interrogation of the placeholder type may need to be rewritten in some other way.

## Type Constraints

A generic declaration can *limit* the types that are eligible to be used for resolving a particular placeholder. This is called a *type constraint*.

The simplest form of type constraint is to put a colon and a type name after the placeholder's name when it is declared. The type name after the colon can be a class name or a protocol name:

### *Class name*

A class name means that the type must be this class *or a subclass* of this class.

### *Protocol name*

A protocol name means that the type must be *an adopter* of this protocol.

For a protocol associated type, the type constraint can appear as part of the `associatedtype` declaration:

```
protocol Flier {
    func fly()
}
protocol Flocker {
    associatedtype T : Flier // *
    func flockTogetherWith(f:T)
}
struct Bee : Flier {
    func fly() {}
}
struct Bird : Flocker {
    func flockTogetherWith(f:Bee) {}
}
```

In that example, `Flocker`'s associated type `T` is constrained to be an adopter of `Flier`. `Bee` is an adopter of `Flier`; therefore `Bird` can adopt `Flocker` by specifying that the parameter type in its `flockTogetherWith` implementation is `Bee`.

Observe that we could not have achieved the same effect without the associated type, by declaring `Flocker` like this:

```
protocol Flocker {
    func flockTogetherWith(f:Flier)
}
```

That's not the same thing! That requires that a `Flocker` adopter specify the parameter for `flockTogetherWith` as *Flier*; we would have had to write `Bird` like this:

```
struct Bird : Flocker {
    func flockTogetherWith(f:Flier) {}
}
```

For a generic function or a generic object type, the type constraint can appear in the angle brackets. For example, earlier I described a global function `func dogMakerAndNamer<WhatType:Dog>`; `Dog` is a class, so the constraint says that `WhatType` must be `Dog` or a `Dog` subclass.

A type constraint on a placeholder is often used to reassure the compiler that some message can be sent to an instance of the placeholder type. Let's say we want to implement a function `myMin` that returns the smallest member of a list. Here's a promising implementation as a generic function, but there's one problem — it doesn't compile:

```
func myMin<T>(_ things:T...) -> T {
    var minimum = things.first!
    for item in things.dropFirst() {
        if item < minimum { // compile error
            minimum = item
        }
    }
    return minimum
}
```

The problem is the comparison `item < minimum`. How does the compiler know that the type `T`, the type of `item` and `minimum`, will be resolved to a type that can in fact be compared using the less-than operator in this way? It doesn't, and that's exactly why it rejects that code. The solution is to promise the compiler that the resolved type of `T` *will* in fact work with the less-than operator. The way to do that, it turns out, is to constrain `T` to Swift's built-in `Comparable` protocol:

```
func myMin<T:Comparable>(_ things:T...) -> T {
```

Now `myMin` compiles, because it cannot be called except by resolving `T` to an object type that adopts `Comparable` and hence *can* be compared with the less-than operator. Naturally, built-in object types that you think should be comparable, such as `Int`, `Double`, `String`, and `Character`, do in fact adopt the `Comparable` protocol! If you look in the Swift headers, you'll find that the built-in `min` global function is declared in just this way, and for just this reason.



A generic protocol type can be used *only* as a type constraint. If you try to use it in any other way, you'll get a compile error. This restriction can be quite frustrating. One way of circumventing it is *type erasure*; for an excellent discussion, see <http://robnapier.net/erasure>.

## Explicit Specialization

In the generic examples so far, the placeholder's type has been resolved mostly through *inference*. But there's another way to perform resolution: we can resolve the type *manually*. This is called *explicit specialization*.

There are two forms of explicit specialization:

### *Generic protocol with associated type*

The adopter of a protocol can resolve an associated type manually through a type alias equating the associated type with some explicit type:

```
protocol Flier {
    associatedtype T
}
struct Bird : Flier {
    typealias T = String
}
```

### *Generic object type*

The user of a generic object type can resolve a placeholder type manually using the same angle bracket syntax used to declare the generic in the first place, with the actual type name in the angle brackets:

```
class Dog<T> {
    var name : T?
}
let d = Dog<String>()
```

You cannot explicitly specialize a generic function. One solution is to make your generic function take a type parameter resolving the generic. That's what I did in my earlier `dogMakerAndNamer` example:

```
func dogMakerAndNamer<WhatType:Dog>(_:WhatType.Type) -> WhatType {
    let d = WhatType.init(name:"Fido")
    return d
}
```

The parameter to `dogMakerAndNamer` is never used within the function body, which is why it has no name (just an underscore). It does, however, serve to resolve the generic!

Another approach is not to use a generic function in the first place. Instead, declare a generic object type wrapping a nongeneric function that uses the generic type's

placeholder. The generic type *can* be explicitly specialized, resolving the placeholder in the function:

```
protocol Flier {
    init()
}
struct Bird : Flier {
    init() {}
}
struct FlierMaker<T:Flier> {
    static func makeFlier() -> T {
        return T()
    }
}
let f = FlierMaker<Bird>.makeFlier() // returns a Bird
```

When a class is generic, you can subclass it, provided you resolve the generic. You can do this either through a matching generic subclass or by resolving the superclass generic explicitly. Here's a generic Dog:

```
class Dog<T> {
    func speak(_ what:T) {}
}
```

You can subclass it as a generic whose placeholder matches that of the superclass:

```
class NoisyDog<T> : Dog<T> {}
```

That's legal because the resolution of the NoisyDog placeholder T will resolve the Dog placeholder T. The alternative is a nongeneric subclass of an explicitly specialized Dog:

```
class NoisyDog : Dog<String> {}
```

In that case, a method override in the subclass can use the specialized type where the superclass uses the generic:

```
class NoisyDog : Dog<String> {
    override func speak(_ what:String) {}
}
```

## Generic Types and Covariance

A generic object type can't be used as the declared type of anything. Given a class Dog<T>, you can't declare a variable as a Dog plain and simple:

```
class Dog<T> {
    func speak(_ what:T) {}
}
var d: Dog? // compile error
```

Only a *resolved* generic object type can be a declared type — and there can be as many of those as there are possible resolutions, each different resolution constituting a distinct type:

```
class Dog<T> {  
    func speak(_ what:T) {}  
}  
var d: Dog<Int>? // that's a type  
var d2: Dog<String>? // that's a different type  
// ... and so on ...
```

The exception, which is only apparent, is when the resolution can be inferred from the context. Here's a classic example:

```
class Node<T> {  
    let value:T  
    let parent:Node?  
    init(_ value:T, parent:Node?) {  
        self.value = value  
        self.parent = parent  
    }  
}
```

It looks as if the parent property is typed as an unresolved Node (wrapped in an Optional); but it isn't. In the absence of an explicit specialization, the compiler assumes we mean Node<T>, resolving parent to the same type as the surrounding instance.

Not only are different specializations of a generic *distinct* types; they are *unrelated* types. In particular, a generic type specialized to a subtype is *not polymorphic* with respect to the same generic type specialized to a supertype.

Suppose we have a simple generic Wrapper struct along with a Cat class and its CalicoCat subclass:

```
struct Wrapper<T> {  
}  
class Cat {  
}  
class CalicoCat : Cat {  
}
```

Then you can't assign a Wrapper specialized to CalicoCat where a Wrapper specialized to Cat is expected:

```
let w : Wrapper<Cat> = Wrapper<CalicoCat>() // compile error
```

It appears that polymorphism is failing here — but it isn't. The two generic types, Wrapper<Cat> and Wrapper<CalicoCat>, are not superclass and subclass. Rather, if this assignment were possible, we would say that the types are *covariant*, meaning that the polymorphic relationship between the specializations of the placeholders is

applied to the generic types themselves. Certain Swift built-in generic types *are* covariant; `Optional` is a clear example! But, frustratingly, covariance is not a *general* language feature; there's no way for you to specify that *your* generic types should be covariant.

One workaround is to have your generic placeholder constrained to a protocol, and have your types adopt that protocol:

```
protocol Meower {
    func meow()
}
struct Wrapper<T:Meower> {
    let meower : T
}
class Cat : Meower {
    func meow() { print("meow") }
}
class CalicoCat : Cat {
}
```

Now it is legal to say:

```
let w : Wrapper<Cat> = Wrapper(meower:CalicoCat())
```

## Associated Type Chains

When a generic placeholder is constrained to a generic protocol with an associated type, you can refer to the associated type using dot-notation: the placeholder name, a dot, and the associated type name.

Here's an example. Imagine that in a game program, soldiers and archers are enemies of one another. I'll express this by subsuming a `Soldier` struct and an `Archer` struct under a `Fighter` protocol that has an `Enemy` associated type, which is itself constrained to be a `Fighter`:

```
protocol Fighter {
    associatedtype Enemy : Fighter
}
```

I'll resolve that associated type manually for both the `Soldier` and the `Archer` structs:

```
struct Soldier : Fighter {
    typealias Enemy = Archer
}
struct Archer : Fighter {
    typealias Enemy = Soldier
}
```

Now I'll create a generic struct to express the opposing camps of these fighters:

```
struct Camp<T:Fighter> {
}
```

Now suppose that a camp may contain a spy from the opposing camp. What is the type of that spy? Well, if this is a Soldier camp, it's an Archer; and if it's an Archer camp, it's a Soldier. More generally, since `T` is a `Fighter`, it's the type of the `Enemy` of this adopter of `Fighter`. I can express that as `T.Enemy`:

```
struct Camp<T:Fighter> {  
    var spy : T.Enemy?  
}
```

The result is that if, for a particular `Camp`, `T` is resolved to `Soldier`, `T.Enemy` means `Archer` (and vice versa). The compiler will enforce that rule:

```
var c = Camp<Soldier>()  
c.spy = Archer() // compiles  
c.spy = Soldier() // compile error
```

Longer chains of associated type names are possible — because a generic protocol might have an associated type which is constrained to a generic protocol that *also* has an associated type. Let's give each type of `Fighter` a characteristic weapon: a soldier has a sword, while an archer has a bow. I'll make a `Sword` struct and a `Bow` struct, and I'll unite them under an `Armament` protocol:

```
protocol Armament {}  
struct Sword : Armament {}  
struct Bow : Armament {}
```

I'll add a `Weapon` associated type to `Fighter`, which is constrained to be an `Armament`, and I'll resolve it manually for each type of `Fighter`:

```
protocol Fighter {  
    associatedtype Enemy : Fighter  
    associatedtype Weapon : Armament  
}  
struct Soldier : Fighter {  
    typealias Weapon = Sword  
    typealias Enemy = Archer  
}  
struct Archer : Fighter {  
    typealias Weapon = Bow  
    typealias Enemy = Soldier  
}
```

Now let's say that every `Fighter` has the ability to steal his enemy's weapon. I'll give the `Fighter` generic protocol a `steal(weapon:from:)` method. How can the `Fighter` generic protocol express the parameter types in a way that forces its adopter to declare this method with the proper types?

The `from:` parameter type is this `Fighter`'s `Enemy`. We already know how to express that: it's the placeholder plus dot-notation with the associated type name. Here, the placeholder is the adopter of this protocol — namely, `Self`. So the `from:` parameter



type is `Self.Enemy`. And what about the `weapon: parameter` type? That's the `Weapon` of that `Enemy`! So the `weapon: parameter` type is `Self.Enemy.Weapon`:

```
protocol Fighter {  
    associatedtype Enemy : Fighter  
    associatedtype Weapon : Armament  
    func steal(weapon:Self.Enemy.Weapon, from:Self.Enemy)  
}
```

(We could omit `Self` from that code, and it would compile and would mean the same thing. But `Self` would still be the implicit start of the chain, and I think explicit `Self` makes the meaning of the code clearer.)

The following declarations for `Soldier` and `Archer` correctly adopt the `Fighter` protocol, and the compiler approves:

```
struct Soldier : Fighter {  
    typealias Weapon = Sword  
    typealias Enemy = Archer  
    func steal(weapon:Bow, from:Archer) { }  
}  
struct Archer : Fighter {  
    typealias Weapon = Bow  
    typealias Enemy = Soldier  
    func steal(weapon:Sword, from:Soldier) { }  
}
```

(There's a trick for shortening potentially long associated type chains, which I'll demonstrate in the next section.)

## Where Clauses

The most flexible way to express a type constraint is to add a `where` clause. Before I tell you what a `where` clause looks like, I'll tell you where it goes:

- For a generic function, a `where` clause may appear after the signature declaration (after the parameter list, following the arrow operator and return type if included).
- For a generic type, a `where` clause may appear after the type declaration, before the curly braces.
- For a generic protocol, a `where` clause may appear after the protocol declaration, before the curly braces.
- For an associated type in a generic protocol, a `where` clause may appear at the end of the associated type declaration.

Now let's talk about the syntax of a `where` clause. It starts with the keyword `where`. Then what? One possibility is a comma-separated list of additional constraints on an already declared placeholder.

I'll start with some trivial examples. You already know that we can constrain a placeholder at the point of declaration, using a colon and a type (which might be a protocol composition):

```
func flyAndWalk<T: Flier> (_ f:T) {}  
func flyAndWalk2<T: Flier & Walker> (_ f:T) {}
```

Using a where clause, we can move those constraints out of the angle brackets. No new functionality is gained, but the resulting notation is arguably neater (and we can even use multiple type constraints to replace the protocol composition):

```
func flyAndWalk<T> (_ f:T) where T: Flier {}  
func flyAndWalk2<T> (_ f:T) where T: Flier & Walker {}  
func flyAndWalk2a<T> (_ f:T) where T: Flier, T: Walker {}
```

Similarly, an associated type declaration can express a type constraint as a where clause. Instead of this:

```
protocol Flocker {  
    associatedtype T : Flier  
}
```

We can write this, which is arguably clearer:

```
protocol Flocker {  
    associatedtype T where T : Flier  
}
```

Now let's do something a bit more powerful. When a constraint on a placeholder is a generic protocol with an associated type, you can use an associated type chain to impose additional constraints *on the associated type*. This pseudocode shows what I mean (I've omitted the content of the where clause, to focus on what the where clause will be constraining):

```
protocol Flier {  
    associatedtype T  
}  
func flockTogether<U> (_ f:U) where U:Flier, U.T /* ... */ {}
```

In that pseudocode, the placeholder U is constrained to be a Flier adopter — and Flier is itself a generic protocol, with an associated type T. We can constrain the types eligible to resolve this Flier adopter's T — and this, in turn, will further constrain the types eligible to resolve U.

Let's fill in the blank in our pseudocode. What sort of restriction are we allowed to impose here? One possibility is a colon expression, as for any type constraint:

```
protocol Flier {  
    associatedtype T  
}  
struct Bird : Flier {  
    typealias T = String  
}
```

```

struct Insect : Flier {
    typealias T = Bird
}
func flockTogether<U> (<_ f:U) where U:Flier, U.T:Equatable {}

```

Both Bird and Insect adopt Flier. The flockTogether function can be called with a Bird argument, because a Bird’s T associated type is resolved to String, which adopts the built-in Equatable protocol. But flockTogether can’t be called with an Insect argument, because an Insect’s T associated type is resolved to Bird, which *doesn’t* adopt the Equatable protocol:

```

flockTogether(Bird()) // okay
flockTogether(Insect()) // compile error

```

The other possibility is the equality operator == followed by a type or an associated type chain, and the constrained type must then match it *exactly*:

```

protocol Flier {
    associatedtype T
}
struct Bird : Flier {
    typealias T = String
}
struct Airplane : Flier {
    typealias T = String
}
struct Insect : Flier {
    typealias T = Int
}
func flockTwoTogether<U1,U2> (<_ f1:U1, _ f2:U2)
    where U1:Flier, U2:Flier, U1.T == U2.T {}

```

Bird, Airplane, and Insect are all Flier adopters. The flockTwoTogether function can be called with a Bird and a Bird, or an Insect and an Insect, or an Airplane and an Airplane, or even a Bird and an Airplane. But it can’t be called with an Insect and a Bird, because they don’t resolve their associated type T to the same type as one another.

The Swift header makes extensive use of where clauses with an == operator, especially as a way of restricting a sequence type. Take the String append(contentsOf:) method, declared like this:

```

mutating func append<S>(contentsOf newElements: S)
    where S:Sequence, S.Element == Character

```

The Sequence protocol has an Element associated type, representing the type of the sequence’s elements. This where clause means that a sequence of Character — but *not* a sequence of something else, such as Int — can be concatenated to a String:

```
var s = "hello"
s.append(contentsOf: " there")
s.append(contentsOf: Array(" world"))
s.append(contentsOf: ["!" as Character])
```

The `Array.append(contentsOf:)` method is declared a little differently:

```
mutating func append<S>(contentsOf newElements: S)
    where S: Sequence, S.Element == Self.Element
```

An array is a sequence; its element type is its `Element` associated type. The `where` clause means that you can append to an `Array` the elements of any sort of `Sequence`, but only if they are the same kind of element as the elements of this array. If the array consists of `String` elements, you can add more `String` elements to it, but you can't add `Int` elements.

Actually, a sequence's `Element` associated type is just a kind of shorthand. In reality, a sequence has an `Iterator` associated type, which is constrained to be an adopter of the generic `IteratorProtocol`, which in turn has an associated type `Element`. So a sequence's element type is its `Iterator.Element`. But a generic protocol or its associated type can have a `where` clause, and this can be used to reduce the length of associated type chains:

```
protocol Sequence {
    associatedtype Iterator : IteratorProtocol
    associatedtype Element where Self.Element == Self.Iterator.Element
    // ...
}
```

As a result, wherever the Swift header would have to say `Iterator.Element`, it can say simply `Element` instead.

## Extensions

An *extension* is a way of injecting your own code into an object type that has already been declared elsewhere; you are *extending* an existing object type. You can extend your own object types; you can also extend one of Swift's object types or one of Cocoa's object types, in which case you are *adding functionality* to a type that doesn't belong to you!

Extension declaration can take place only at the top level of a file. To declare an extension, put the keyword `extension` followed by the name of an existing object type, then optionally a colon plus the names of any protocols you want to add to the list of those adopted by this type, and finally curly braces containing the usual things that go inside an object type declaration — with some restrictions:

- An extension can't declare a stored property (but it can declare a computed property).

- An extension of a class can't declare a designated initializer or a deinitializer (but it can declare a convenience initializer).
- An extension can't override an existing member (but it can overload an existing method), and a method declared in an extension can't be overridden.

In my real programming life, I sometimes extend a built-in Swift or Cocoa type just to inject some missing functionality by expressing it as a property or method.

For example, Cocoa's Core Graphics framework has many useful functions associated with the `CGRect` struct, and Swift already extends `CGRect` to add some helpful properties and methods; but there's no shortcut for getting the center point (a `CGPoint`) of a `CGRect`, something that in practice is often needed. I extend `CGRect` to give it a center property:

```
extension CGRect {
    var center : CGPoint {
        return CGPoint(x:self.midX, y:self.midY)
    }
}
```

An extension can declare a static or class member; this can be a good way to slot a global function into an appropriate namespace. In one of my apps, I find myself frequently using a certain color (a `UIColor`). Instead of creating that color repeatedly, it makes sense to encapsulate the instructions for generating it in a global function. But instead of making that function *completely* global, I make it — appropriately enough — a read-only static property of `UIColor`:

```
extension UIColor {
    static var myGolden : UIColor {
        return self.init(
            red:1.000, green:0.894, blue:0.541, alpha:0.900
        )
    }
}
```

Now I can use that color throughout my code as `UIColor.myGolden`, parallel to built-in class properties such as `UIColor.red`.

Extensions on one's own object types can help to organize code. A common convention is to add an extension for each protocol the object type needs to adopt:

```
class ViewController: UIViewController {
    // ... UIViewController method overrides go here ...
}
extension ViewController : UIPopoverPresentationControllerDelegate {
    // ... UIPopoverPresentationControllerDelegate methods go here ...
}
extension ViewController : UIToolbarDelegate {
    // ... UIToolbarDelegate methods go here ...
}
```

## Extensions and Overrides

The rules about class extensions and overrides are more complicated than I've stated. A native Swift method in an extension can neither override nor be overridden, but then Objective-C comes along with its own rules and messes everything up. Let's say we have a class `Dog` and its subclass `NoisyDog`:

- If we have an extension on `Dog` that declares a method, `NoisyDog` *can* override the `Dog` extension method *if* the method is exposed to Objective-C.
- If we have a method in `Dog`, an extension on `NoisyDog` *can* override it *if* `Dog`'s method is exposed to Objective-C and is marked `dynamic`.

Things are made even messier by the existence of modules; if there's a type with a method in a module, an extension on that type in another module can declare *the same method*, not overriding but effectively replacing it. My advice: Don't do that.

An extension on your own object type can also be a way to spread your definition of that object type over multiple files, if you feel that several shorter files are better than one long file.

When you extend a Swift struct, a curious thing happens with initializers: it becomes possible to declare an initializer and keep the implicit initializers:

```
struct Digit {  
    var number : Int  
}  
extension Digit {  
    init() {  
        self.init(number:42)  
    }  
}
```

In that code, the explicit declaration of an initializer through an extension did not cause us to lose the implicit memberwise initializer, as would have happened if we had declared the same initializer inside the original struct declaration. Now we can instantiate a `Digit` by calling the explicitly declared initializer — `Digit()` — or by calling the implicit memberwise initializer — `Digit(number:7)`.

## Extending Protocols

When you extend a protocol, you can add methods and properties to the protocol, just as for any object type. Unlike a protocol declaration, these methods and properties are not mere requirements, to be fulfilled by the adopter of the protocol; they are actual methods and properties, to be *inherited* by the adopter of the protocol (or perhaps I should say they are *injected* into the adopter):

```

protocol Flier {
}
extension Flier {
    func fly() {
        print("flap flap flap")
    }
}
struct Bird : Flier {
}

```

As that code demonstrates, Bird can now adopt Flier *without* implementing the fly method! That's because the Flier protocol extension supplies the fly method implementation and injects it into Bird:

```

let b = Bird()
b.fly() // flap flap flap

```

An adopter can still provide its own implementation of a method inherited from a protocol extension:

```

protocol Flier {
}
extension Flier {
    func fly() {
        print("flap flap flap")
    }
}
struct Insect : Flier {
    func fly() {
        print("whirr")
    }
}
let i = Insect()
i.fly() // whirr

```

But this kind of inheritance is *not polymorphic*! The adopter's implementation is not an override; it is merely another implementation. The internal identity rule does *not* apply; it matters how a reference is typed:

```

let f : Flier = Insect()
f.fly() // flap flap flap (!!)

```

Even though `f` is internally an `Insect` (as we can discover with the `is` operator), the fly message is being sent to an object reference typed as `Flier`, so it is `Flier`'s implementation of the fly method that is called, not `Insect`'s implementation.

To get something that looks like polymorphic inheritance, we must also declare fly as a requirement *in the original protocol*:

```

protocol Flier {
    func fly() // *
}
extension Flier {

```

```

    func fly() {
        print("flap flap flap")
    }
}
struct Insect : Flier {
    func fly() {
        print("whirr")
    }
}

```

Now an Insect maintains its internal integrity:

```

let f : Flier = Insect()
f.fly() // whirr

```

Protocol extensions sometimes allow you to say things that a type adopting the protocol would not be able to say directly. Here’s an example. We have a Dog class and its NoisyDog subclass, and we have a DogWrapper struct that wraps a Dog:

```

class Dog {
    func wrapped() -> DogWrapper { DogWrapper(self) }
}
class NoisyDog : Dog {}
struct DogWrapper {
    private let dog : Dog
    init(_ dog: Dog) { self.dog = dog }
    func unwrap() -> Dog { self.dog }
}

```

However, we’re not getting quite the result I was hoping for. The return type of `unwrap` is `Dog`, whereas I want it to be the *real* type that is wrapped inside the `DogWrapper` (`Dog` or `NoisyDog`). That sounds like a generic:

```

struct DogWrapper<T:Dog> {
    private let dog : T
    init(_ dog: T) { self.dog = dog }
    func unwrap() -> T { self.dog }
}

```

So far, so good; but now `Dog` doesn’t compile:

```

class Dog {
    func wrapped() -> DogWrapper { DogWrapper(self) } // compile error
}

```

The trouble is that the return type of `wrapped`, `DogWrapper`, is no longer a legal type; it is now generic, and a generic type can’t be used as the declared type of anything. We have to resolve the generic with angle brackets. But we can’t do that either, because there is no way to say “the type that I really am” (`Dog` or `NoisyDog`); the phrase `DogWrapper<Self>` is illegal.

The solution is to remove the `wrapped` method from `Dog` itself, and inject it back into `Dog` by way of a protocol extension:



```
protocol WrappableDog : Dog { }
extension WrappableDog {
    func wrapped() -> DogWrapper<Self> { DogWrapper(self) }
}
class Dog : WrappableDog {
}
```

That's legal because the phrase `DogWrapper<Self>` is legal in a protocol. (Thanks go to Tyler Prevost; see <https://stackoverflow.com/a/66414305/341994>.)

## Extending Generics

When you extend a generic type, the generic's placeholder type names are visible to your extension. That's good, because you might need to use them; but it can make your code a little mystifying, because you seem to be using an undefined type name out of the blue. It might be a good idea to add a comment, to remind yourself what you're up to:

```
class Dog<T> {
    var name : T?
}
extension Dog {
    func sayYourName() -> T? { // T? is the type of self.name
        return self.name
    }
}
```

A generic type extension declaration can include a *where* clause. This limits *which* resolutions of the generic placeholder can call the code injected by this extension.

That, in turn, can be used to assure the compiler that your code is legal. For instance, recall this example from earlier in this chapter:

```
func myMin<T:Comparable>(_ things:T...) -> T {
    var minimum = things.first!
    for item in things.dropFirst() {
        if item < minimum {
            minimum = item
        }
    }
    return minimum
}
```

That's a global function. I'd prefer to inject it into `Array` as a method. I can do that with an extension. `Array` is a generic struct whose placeholder type is called `Element`. To make this work, I need somehow to bring along the `Comparable` type constraint that makes this code legal; without it, as you remember, my use of the `<` operator won't compile. I can do that with a *where* clause on the extension:

```

extension Array where Element:Comparable {
    func myMin() -> Element? {
        var minimum = self.first
        for item in self.dropFirst() {
            if item < minimum! {
                minimum = item
            }
        }
        return minimum
    }
}

```

The `where` clause is a constraint guaranteeing that this array’s elements adopt `Comparable`, so the compiler permits the use of the `<` operator — and it doesn’t permit the `myMin` method to be called on an array whose elements *don’t* adopt `Comparable`. The Swift standard library makes heavy use of that sort of thing, and in fact `Sequence` has a `min` method declared like `myMin`.

Starting in Swift 5.3, a `where` clause constraining a generic’s placeholder can be applied to a *method* of the generic:

```

extension Array {
    func myMin() -> Element? where Element:Comparable {
        // ...
    }
}

```

The advantages are primarily organizational. In Swift 5.2 and before, the only way for a generic type to restrict a method to one or more constraints on the placeholder type was to put the method into an extension with all of the constraints in the extension declaration:

```

struct MyStruct<T> {
    // ...
}
extension MyStruct where T:Protocol1, T:Protocol2 {
    func f() {
        // ...
    }
}

```

Now, however, we can distribute the statement of the constraints in whatever way seems clearest. Perhaps we prefer this:

```

extension MyStruct where T:Protocol1 {
    func f() where T:Protocol2 {
        // ...
    }
}

```

If the type belongs to us, we could forego the extension altogether:

```

struct MyStruct<T> {
    // ...
    func f() where T:Protocol1, T:Protocol2 {
        // ...
    }
}

```

An extension with a where clause can also be used to express *conditional conformance* to a protocol. The syntax is:

```

extension GenericType : SomeProtocol where constraint {

```

The idea is that a generic type should adopt a certain protocol only if something is true of its placeholder type — and the extension then contains whatever is needed to satisfy the protocol requirements.

In the standard library, conditional conformance fills what used to be a serious hole in the Swift language. For example, an `Array` can consist of `Equatable` elements, and in that case it is possible to compare two arrays for equality:

```

let arr1 = [1,2,3]
let arr2 = [1,2,3]
if arr1 == arr2 { // ...

```

It’s clear what array equality should consist of: the two arrays should consist of the same elements in the same order. The elements must be `Equatable` so as to guarantee the meaningfulness of the notion “same elements.”

Now consider what it takes to compare two arrays of arrays:

```

let arr1 = [[1], [2], [3]]
let arr2 = [[1], [2], [3]]
if arr1 == arr2 { // ...

```

That’s possible only if we can make `Array` *itself* `Equatable`. In particular, we want to assert that an `Array` should be `Equatable` only just in case its elements are `Equatable`. That’s conditional conformance! Here’s what the standard library says:

```

extension Array : Equatable where Element : Equatable {
    // ...
}

```

## Umbrella Types

Swift provides a few built-in types as general umbrella types, capable of embracing multiple real types under a single heading.

### Any

The `Any` type is the universal Swift umbrella type. Where an `Any` object is expected, absolutely any object or function can be passed, without casting:

```

func anyExpecter(_ a:Any) {}
anyExpecter("howdy")      // a struct instance
anyExpecter(String.self)  // a struct type
anyExpecter(Dog())        // a class instance
anyExpecter(Dog.self)     // a class type
anyExpecter(anyExpecter)  // a function

```

Going the other way, if you want to type an Any object as a more specific type, you will generally have to cast down. Such a cast is legal for any specific object type or function type. A forced cast isn't safe, but you can easily make it safe, because you can also test an Any object against any specific object type or function type. Here, anything is typed as Any:

```

if anything is String {
    let s = anything as! String
    // ...
}

```

(In [Chapter 5](#) I'll introduce a more elegant syntax for casting down safely.)

The Any umbrella type is the general medium of interchange between Swift and the Cocoa Objective-C APIs. When an Objective-C object type is nonspecific (`id`), it will appear to Swift as Any. Commonly encountered examples are UserDefaults and key-value coding ([Chapter 11](#)); these allow you to *pass* an object of indeterminate class along with a string key name, and they allow you to *retrieve* an object of indeterminate class by a string key name.

For example, the first parameter of UserDefaults `set(_:forKey:)` is typed as Any (actually, an Optional wrapping Any, so that it can be `nil`). So I can pass anything as the argument. Here, I'll pass a Date:

```

let ud = UserDefaults.standard
ud.set(Date(), forKey:"now")

```

When a Swift object is assigned or passed to an Any that acts as a conduit to Objective-C, it crosses the bridge to Objective-C. If the object's type is not an Objective-C type (a class derived from NSObject), it will be transformed in order to cross the bridge. If this type is automatically bridged to an Objective-C class type, it becomes that type; other types are boxed up in a way that allows them to survive the journey into Objective-C's world, even though Objective-C can't deal with them directly. (For full details, see the [Appendix](#).)

To illustrate, suppose we have an Objective-C class Thing with a method `take1id:`, declared like this:

```

- (void) take1id: (id) anid;

```

That appears to Swift as:

```

func take1id(_ anid: Any)

```

When we pass an object to `take1Id(_)` as its parameter, it crosses the bridge:

```
let t = Thing()
t.take1id("howdy") // String to NSString
t.take1id(1)       // Int to NSNumber
t.take1id(CGRect()) // CGRect to NSValue
t.take1id(Date())  // Date to NSDate
t.take1id(Bird())  // Bird (struct) to boxed type
```

Coming back the other way, if Objective-C hands you an `Any` object, you will need to cast it down to its underlying type in order to do anything useful with it:

```
let ud = UserDefaults.standard
let d = ud.object(forKey:"now")
if d is Date {
    let d = d as! Date
    // ...
}
```

The result returned from `UserDefaults object(forKey:)` is typed as `Any` — actually, as an `Optional` wrapping an `Any`, because `UserDefaults` might need to return `nil` to indicate that no object exists for that key. But you know that it's supposed to be a date, so you cast it down to `Date`.

## AnyObject

`AnyObject` is an empty protocol with the special feature that *all class types* conform to it automatically. Although Objective-C APIs present Objective-C `id` as `Any` in Swift, Swift `AnyObject` is Objective-C `id`. `AnyObject` is useful primarily when you want to take advantage of the *behavior* of Objective-C `id`, as I'll demonstrate in a moment.

A class instance can be assigned directly where an `AnyObject` is expected; to retrieve it as its original type, you'll need to cast down:

```
class Dog {
}
let d = Dog()
let anyo : AnyObject = d
let d2 = anyo as! Dog
```

Assigning a nonclass type to an `AnyObject` requires casting (with `as`). The bridge to Objective-C is then crossed immediately, as I described for `Any` in the preceding section:

```
let s = "howdy" as AnyObject // String to NSString to AnyObject
let i = 1 as AnyObject       // Int to NSNumber to AnyObject
let r = CGRect() as AnyObject // CGRect to NSValue to AnyObject
let d = Date() as AnyObject   // Date to NSDate to AnyObject
let b = Bird() as AnyObject   // Bird (struct) to boxed type to AnyObject
```

## Suppressing type checking

Because `AnyObject` is Objective-C `id`, it can be used, like Objective-C `id`, to suspend the compiler's judgment as to whether a certain message can be sent to an object. Thus, you can send a message to an `AnyObject` without bothering to cast down to its real type.

You can't send just any old message to an `AnyObject`; this is an Objective-C feature, so the message must correspond to a class member that meets one of the following criteria:

- It is a member of an Objective-C class.
- It is a member of your own Swift subclass of an Objective-C class.
- It is a member of your own Swift extension of an Objective-C class.
- It is a member of a Swift class or protocol marked `@objc`.

This feature is fundamentally parallel to optional protocol members, which I discussed earlier in this chapter. Let's start with two classes:

```
class Dog {
    @objc var noise : String = "woof"
    @objc func bark() -> String {
        return "woof"
    }
}
class Cat {}
```

The `Dog` property `noise` and the `Dog` method `bark` are marked `@objc`, so they are visible as potential messages to be sent to an `AnyObject`. To prove it, I'll type a `Cat` as an `AnyObject` and send it one of those messages. Let's start with the `noise` property:

```
let c : AnyObject = Cat()
let s = c.noise
```

That code, amazingly, compiles. Moreover, it doesn't crash when the code runs! The `noise` property has been typed as an `Optional` wrapping its original type. Here, that's an `Optional` wrapping a `String`. If the object typed as `AnyObject` doesn't implement `noise`, the result is `nil` and no harm done.

Now let's try it with a method call:

```
let c : AnyObject = Cat()
let s = c.bark?()
```

Again, that code compiles and is safe. If the Object typed as `AnyObject` doesn't implement `bark`, no `bark()` call is performed; the method result type has been wrapped in an `Optional`, so `s` is typed as `String?` and has been set to `nil`. If the `AnyObject` turns out to have a `bark` method (because it's a `Dog`), the result is an `Optional` wrapping the returned `String`. If you call `bark!()` on the `AnyObject` instead, the result will

be a `String`, but you'll crash if the `AnyObject` doesn't implement `bark`. Unlike an optional protocol member, you can even send the message *with no unwrapping*. This is legal:

```
let c : AnyObject = Cat()
let s = c.bark()
```

That's just like force-unwrapping the call: the result is a `String`, but it's possible to crash.



Don't make a habit of sending messages to an `AnyObject`; because it involves dynamic lookup, it's expensive at build time and expensive at runtime.

## Object identity

Sometimes, what you want to know is not what *type* an object is, but whether an object itself is the *particular object* you think it is. This problem can't arise with a value type, but it can arise with a reference type — in particular, with class instances.

Swift's solution is the identity operator (`===`). Its operands are typed as `AnyObject?`, meaning an object whose type is a class or an `Optional` whose wrapped type is a class; it compares one object reference with another. This is not a comparison of *values*, like the equality operator (`==`); you're asking whether two object *references* refer to *one and the same* object. There is also a negative version (`!==`) of the identity operator.

A typical use case is that a class instance arrives from Cocoa, and you need to know whether it is in fact a particular object to which you already have a reference. For example, a `Notification` has an `object` property that helps identify the notification (usually, it is the original sender of the notification). We can use `===` to test whether this object is a certain object to which we already have a reference. However, `object` is typed as `Any` (actually, as an `Optional` wrapping `Any`), so we must cast to `AnyObject` in order to take advantage of the identity operator:

```
@objc func changed(_ n:Notification) {
    let player = MPMusicPlayerController.applicationMusicPlayer
    if n.object as AnyObject === player {
        // ...
    }
}
```

## AnyClass

`AnyClass` is the type of `AnyObject`. It corresponds to the Objective-C `Class` type. It arises typically in declarations where a Cocoa API wants to say that a class is

expected. The `UIView` `layerClass` class property is declared, in its Swift translation, like this:

```
class var layerClass : AnyClass {get}
```

That means that if you override this class property, you'll implement your getter to return a class (which will presumably be a `CALayer` subclass):

```
override class var layerClass : AnyClass { CATiledLayer.self }
```

A reference to an `AnyClass` object behaves much like a reference to an `AnyObject` object. You can send it any Objective-C message that Swift knows about — any Objective-C *class* message. To demonstrate, once again I'll start with two classes:

```
class Dog {  
    @objc static var whatADogSays : String = "woof"  
}  
class Cat {}
```

Objective-C can see `whatADogSays`, and it sees it as a class property. Therefore you can send `whatADogSays` to an `AnyClass` reference:

```
let c : AnyClass = Cat.self  
let s = c.whatADogSays
```

## Collection Types

Swift, in common with most modern computer languages, has built-in collection types `Array` and `Dictionary`, along with a third type, `Set`. `Array` and `Dictionary` are sufficiently important that the language accommodates them with some special syntax.

### Array

An array (`Array`, a struct) is an ordered collection of object instances (the *elements* of the array) accessible by index number, where an index number is an `Int` numbered from 0. If an array contains four elements, the first has index 0 and the last has index 3. A Swift array cannot be sparse: if there is an element with index 3, there is also an element with index 2 and so on.

The salient feature of Swift arrays is their strict typing. Unlike some other computer languages, a Swift array's elements must be *uniform* — that is, the array must consist solely of elements of the same definite type. Even an empty array must have a definite element type, despite lacking elements at this moment. An array is itself typed in accordance with its element type. Two arrays whose elements are of different types are considered, themselves, to be of two different types: an array of `Int` elements has a different type from an array of `String` elements.



If all this reminds you of Optionals, it should. Like Optional, Array is a generic. It is declared as `Array<Element>`, where the placeholder `Element` is the type of a particular array's elements. And, like Optional types, Array types are covariant, meaning that they behave polymorphically in accordance with their element types: if `NoisyDog` is a subclass of `Dog`, then an array of `NoisyDog` can be used where an array of `Dog` is expected.

To state an Array type, then, you need to state its element type. You could explicitly resolve the generic placeholder; an array of `Int` elements would be an `Array<Int>`. However, Swift offers syntactic sugar using square brackets around the name of the element type, like this: `[Int]`. That's the syntax you'll use most of the time.

A literal array is represented as square brackets containing a list of its elements separated by a comma (and optional spaces): `[1,2,3]`. The literal for an empty array is empty square brackets: `[]`.

Array's default initializer `init()`, called by appending empty parentheses to the array's type, yields an empty array of that type. You can create an empty array of `Int` like this:

```
var arr = [Int]()
```

Alternatively, if a reference's type is known in advance, the empty array `[]` can be inferred as that type. So you can also create an empty array of `Int` like this:

```
var arr : [Int] = []
```

If you're starting with a literal array containing elements, you won't usually need to declare the array's type, because Swift can infer it by looking at the elements. Swift will infer that `[1,2,3]` is an array of `Int`. If the array element types consist of a class and its subclasses, like `Dog` and `NoisyDog`, Swift will infer the common superclass as the array's type. However, in some cases you will need to declare an array reference's type explicitly even while assigning a literal to that array:

```
let arr : [Any] = [1, "howdy"]           // mixed bag
let arr2 : [Flier] = [Insect(), Bird()] // protocol adopters
```

Moreover, if an array variable is declared and initialized to a literal with many elements, even though Swift might be able to infer the type, it's often a good idea to declare the variable's type explicitly anyway. This saves the compiler from having to examine the entire array to decide its type, and makes compilation faster.

Array also has an initializer whose parameter is a sequence. This means that if a type is a sequence, you can split an instance of it into the elements of an array. For example:

- `Array(1...3)` generates the array of `Int` `[1,2,3]`.
- `Array("hey")` generates the array of `Character` `["h","e","y"]`.

- `Array(d)`, where `d` is a Dictionary, generates an array of tuples of the key–value pairs of `d`.

Another Array initializer, `init(repeating:count:)`, lets you populate an array with the same value. In this example, I create an array of 100 Optional strings initialized to `nil`:

```
let strings : [String?] = Array(repeating:nil, count:100)
```

That’s the closest you can get in Swift to a sparse array; we have 100 slots, each of which might or might not contain a string (and to start with, none of them do).



Beware of using `init(repeating:count:)` with a reference type! If `Dog` is a class, and you say `let dogs = Array(repeating:Dog(), count:3)`, you don’t have an array of three Dogs; you have an array consisting of three *references* to *one* Dog. I’ll give a workaround later.

## Array casting and type testing

When you assign, pass, or cast an array of a certain type to another array type, you are really operating on the individual elements of the array:

```
let arr : [Int?] = [1,2,3]
```

That code is actually syntactic sugar: assigning an array of `Int` where an array of Optionals wrapping `Int` is expected constitutes a request that each individual `Int` in the original array should be wrapped in an `Optional`. And that is exactly what happens:

```
let arr : [Int?] = [1,2,3]
print(arr) // [Optional(1), Optional(2), Optional(3)]
```

Similarly, suppose we have a `Dog` class and its `NoisyDog` subclass; then this code is legal:

```
let dog1 : Dog = NoisyDog()
let dog2 : Dog = NoisyDog()
let arr = [dog1, dog2]
let arr2 = arr as! [NoisyDog]
```

In the third line, we have an array of `Dog`. In the fourth line, we apparently cast this array down to an array of `NoisyDog` — which really means that we cast each individual `Dog` in the first array to a `NoisyDog`. We can crash when we do that, but we won’t if each element of the first array really *is* a `NoisyDog`.

The `as?` operator will cast an array to an `Optional` wrapping an array, which will be `nil` if the requested cast cannot be performed for each element individually:

```

let dog1 : Dog = NoisyDog()
let dog2 : Dog = NoisyDog()
let dog3 : Dog = Dog()
let arr = [dog1, dog2]
let arr2 = arr as? [NoisyDog] // Optional wrapping an array of NoisyDog
let arr3 = [dog2, dog3]
let arr4 = arr3 as? [NoisyDog] // nil

```

You can test each element of an array with the `is` operator by testing the array itself. Given the array of `Dog` from the previous code, you can say:

```
if arr is [NoisyDog] { // ...
```

That will be true if each element of the array is in fact a `NoisyDog`.

## Array comparison

Array equality works just as you would expect: two arrays are equal if they contain the same number of elements and all the elements are pairwise equal in order. Of course, this presupposes that the notion “equal” is meaningful for these elements:

```

let i1 = 1
let i2 = 2
let i3 = 3
let arr : [Int] = [1,2,3]
if arr == [i1,i2,i3] { // they are equal!

```

Two arrays don’t have to be of the same type to be compared against one another for equality, but the test won’t succeed unless they do in fact contain objects that are equal to one another. Here, I compare a `Dog` array against a `NoisyDog` array; this is legal if equatability is defined for two `Dogs`. (`Dog` might be an `NSObject` subclass; or you might make `Dog` adopt `Equatable`, as I’ll explain in [Chapter 5](#).) The two arrays are in fact equal, because the dogs they contain are the same dogs in the same order:

```

let nd1 = NoisyDog()
let d1 = nd1 as Dog
let nd2 = NoisyDog()
let d2 = nd2 as Dog
let arr1 = [d1,d2] // [Dog]
let arr2 = [nd1,nd2] // [NoisyDog]
if arr1 == arr2 { // they are equal!

```

## Arrays are value types

Because an array is a struct, it is a value type, not a reference type. This means that every time an array is assigned to a variable or passed as argument to a function, it is effectively copied.

I do not mean to imply, however, that merely assigning or passing an array is expensive, or that a lot of actual copying takes place every time. If the reference to an array is a constant, clearly no copying is necessary; and even operations that yield a new

array derived from another array, or that mutate an array, may be quite efficient. You just have to trust that the designers of Swift have thought about these problems and have implemented arrays efficiently behind the scenes.

Although an array is *itself* a value type, its *elements* might not be. If an array of class instances is assigned to multiple variables, the result is multiple references to the same instances.

## Array subscripting

The `Array` struct implements subscript methods to allow access to elements using square brackets after a reference to an array.

You can use an `Int` inside the square brackets. If an array is referred to by a variable `arr`, then `arr[1]` accesses the second element.

You can also use a Range of `Int` inside the square brackets. If `arr` is an array, then `arr[1...2]` signifies the second and third elements. Technically, an expression like `arr[1...2]` yields something called an `ArraySlice`, which stands in relation to `Array` much as `Substring` stands in relation to `String` ([Chapter 3](#)). It's very similar to an array, and in general you will probably pretend that an `ArraySlice` *is* an array. You can subscript an `ArraySlice` in just the same ways you would subscript an array. Nevertheless, they are not the same thing. An `ArraySlice` is not a new array; it's just a way of pointing into a section of the original array. For this reason, its index numbers are those of the original array:

```
let arr = ["manny", "moe", "jack"]
let slice = arr[1...2] // ["moe", "jack"]
print(slice[1]) // moe
```

The `ArraySlice` `slice` consists of two elements, "moe" and "jack", of which "moe" is the first element. But these are not merely "moe" and "jack" taken *from* the original array, but the "moe" and "jack" *in* the original array. For this reason, their index numbers are not 0 and 1, but rather 1 and 2, just as in the original array. If you need to extract a new array based on this slice, coerce the slice to an `Array`:

```
let arr2 = Array(slice) // ["moe", "jack"]
print(arr2[1]) // jack
```

If the reference to an array is mutable (`var`, not `let`), then it's possible to assign to a subscript expression. This alters what's in that slot. Of course, what is assigned must accord with the type of the array's elements:

```
var arr = [1,2,3]
arr[1] = 4 // arr is now [1,4,3]
```

If the subscript is a range, what is assigned must be a slice. You can assign a literal array, because it will be coerced for you to an `ArraySlice`; but if what you're starting

with is an array reference, you'll have to coerce it to a slice yourself. Such assignment can change the length of the array being assigned to:

```
var arr = [1,2,3]
arr[1..<2] = [7,8] // arr is now [1,7,8,3]
arr[1..<2] = []    // arr is now [1,8,3]
arr[1..<1] = [10]  // arr is now [1,10,8,3] (no element was removed!)
let arr2 = [20,21]
// arr[1..<1] = arr2 // compile error! You have to say this:
arr[1..<1] = ArraySlice(arr2) // arr is now [1,20,21,10,8,3]
```

Subscripting an array with a Range is an opportunity to use partial range notation. The missing value is taken to be the array's first or last index. If `arr` is `[1,2,3]`, then `arr[1...]` is `[2,3]`, and `arr[...1]` is `[1,2]`. Similarly, you can assign into a range specified as a partial range:

```
var arr = [1,2,3]
arr[1...] = [4,5] // arr is now [1,4,5]
```



It is a runtime error to access an element by an index number larger than the largest element number or smaller than the smallest element number. If `arr` has three elements, speaking of `arr[-1]` or `arr[3]` is not illegal linguistically, but your program will crash.

## Nested arrays

It is legal for the elements of an array to be arrays:

```
let arr = [[1,2,3], [4,5,6], [7,8,9]]
```

That's an array of arrays of `Int`. Its type declaration, therefore, is `[[Int]]`. (No law says that the contained arrays have to be the same length; that's just something I did for clarity.)

To access an individual `Int` inside those nested arrays, you can chain subscripts:

```
let arr = [[1,2,3], [4,5,6], [7,8,9]]
let i = arr[1][1] // 5
```

If the outer array reference is mutable, you can also write into a nested array:

```
var arr = [[1,2,3], [4,5,6], [7,8,9]]
arr[1][1] = 100
```

You can modify the inner arrays in other ways as well; for example, you can insert additional elements into them.

Thanks to conditional conformance (discussed earlier in this chapter), nested arrays can be compared with `==` as long as the inner array's elements are `Equatable`. If `arr` and `arr2` are both `[[Int]]`, you can compare them by saying `arr == arr2`.

## Basic array properties and methods

An array is a Collection, which is itself a Sequence. If those terms have a familiar ring, they should: the same is true of a String's underlying character sequence, which I discussed in [Chapter 3](#). For this reason, an array and a character sequence have some properties and methods that bear striking similarities to one another.

Many additional methods on sequences and collections are provided in the Swift Algorithms package (`import Algorithms`; see [Chapter 7](#)). These, too, are applicable to arrays, so I'll mention some of them here as well.

As a collection, an array's `count` read-only property reports the number of elements it contains. If an array's count is 0, its `isEmpty` property is true.

An array's `first` and `last` read-only properties return its first and last elements, but they are wrapped in an `Optional` because the array might be empty and so these properties would need to be `nil`. This is one of those rare situations in Swift where you can wind up with an `Optional` wrapping an `Optional`; consider an array of `Optionals` wrapping `Ints`, and what happens when you get its `last` property.

An array's largest accessible index is one less than its count. You may find yourself calculating index values with reference to the count; to refer to the last two elements of `arr`, you might say:

```
let arr = [1,2,3]
let slice = arr[arr.count-2...arr.count-1] // [2,3]
```

Can we do better? Unfortunately, Swift doesn't adopt the modern convention of letting you use negative indexes as a shorthand. On the other hand, if you want the last `n` elements of an array, you can use the `suffix(_)` method:

```
let arr = [1,2,3]
let slice = arr.suffix(2) // [2,3]
```

Therefore, a neat way to obtain, say, the next-to-last element of an array is to combine `suffix` with `first`:

```
let arr = [1,2,3]
let nextToLast = arr.suffix(2).first // Optional(2)
```

Both `suffix(_)` and its companion `prefix(_)` yield `ArraySlices`, and have the remarkable feature that there is no penalty for going out of range:

```
let arr = [1,2,3]
let slice = arr.suffix(10) // [1,2,3] (and no crash)
```

Instead of describing the size of the suffix or prefix by its count, you can express the limit of the suffix or prefix by its index. And partial range notation may provide yet another useful alternative:

```

let arr = [1,2,3]
let slice = arr.suffix(from:1)    // [2,3]
let slice2 = arr[1...]           // [2,3]
let slice3 = arr.prefix(upTo:1)   // [1]
let slice4 = arr.prefix(through:1) // [1,2]

```

An array's `startIndex` property is 0, and its `endIndex` property is its count. An array's `indices` property is a half-open range whose endpoints are the array's `startIndex` and `endIndex` — that is, a range accessing the entire array. Moreover, these values are `Ints`, so you can use ordinary arithmetic operations on them:

```

let arr = [1,2,3]
let slice = arr[arr.endIndex-2..

```

But the `startIndex`, `endIndex`, and `indices` of an `ArraySlice` are measured against the original array; after the previous code, `slice.indices` is `1..3`, and `slice.startIndex` is 1.

The `firstIndex(of:)` method reports the index of the first occurrence of an element in an array, but it is wrapped in an `Optional` so that `nil` can be returned if the element doesn't appear in the array. In general, the comparison uses `==` behind the scenes to identify the element being sought, and therefore the array elements must adopt `Equatable` (otherwise the compiler will stop you):

```

let arr = [1,2,3]
let ix = arr.firstIndex(of:2) // Optional wrapping 1

```

Alternatively, you can call `firstIndex(where:)`, supplying your own function that takes an element type and returns a `Bool`, and you'll get back the index of the first element for which that `Bool` is true. In this example, my `Bird` struct has a `name` `String` property:

```

let aviary = [Bird(name:"Tweety"), Bird(name:"Flappy"), Bird(name:"Lady")]
let ix = aviary.firstIndex {$0.name.count < 5} // Optional(2)

```

If what you want is not the index but the object itself, the `first(where:)` method returns it — wrapped, naturally, in an `Optional`. These methods are matched by `lastIndex(of:)`, `lastIndex(where:)`, and `last(where:)`.

As a sequence, an array's `contains(_:)` method reports whether it contains an element. Again, you can rely on the `==` operator if the elements are `Equatable`, or you can supply your own function that takes an element type and returns a `Bool`:

```

let arr = [1,2,3]
let ok = arr.contains(2) // true
let ok2 = arr.contains {$0 > 3} // false

```

The `starts(with:)` method reports whether an array's starting elements match the elements of a given sequence of the same type. Once more, you can rely on the `==`

operator for Equatable elements, or you can supply a function that takes two values of the element type and returns a Bool stating whether they match:

```
let arr = [1,2,3]
let ok = arr.starts(with:[1,2]) // true
let ok2 = arr.starts(with:[1,-2]) {abs($0) == abs($1)} // true
```

The `min` and `max` methods return the smallest or largest element in an array, wrapped in an `Optional` in case the array is empty. If the array consists of `Comparable` elements, you can let the `<` operator do its work; alternatively, you can call `min(by:)` or `max(by:)`, supplying a function that returns a Bool stating whether the smaller of two given elements is the first:

```
let arr = [3,1,-2]
let min = arr.min() // Optional(-2)
let min2 = arr.min {abs($0) < abs($1)} // Optional(1)
```

The Swift Algorithms package adds variants with a `count:` parameter, letting you specify how many smallest or largest elements you want returned, as an array:

```
let arr = [3,1,-2]
let min = arr.min(count: 2) // [-2, 1]
let min2 = arr.min(count: 2) {abs($0) < abs($1)} // [1, -2]
```

If the reference to an array is mutable, the `append(_:)` and `append(contentsOf:)` instance methods add elements to the end of it. The difference between them is that `append(_:)` takes a single value of the element type, while `append(contentsOf:)` takes a sequence of the element type:

```
var arr = [1,2,3]
arr.append(4)
arr.append(contentsOf:[5,6])
arr.append(contentsOf:7...8) // arr is now [1,2,3,4,5,6,7,8]
```

The `+` operator is overloaded to behave like `append(contentsOf:)` when the left-hand operand is an array, except that it generates a new array, so it works even if the reference to the array is a constant (`let`). If the reference to the array is mutable (`var`), you can append to it in place with the overloaded `+=` operator:

```
let arr = [1,2,3]
let arr2 = arr + [4] // arr2 is now [1,2,3,4]
var arr3 = [1,2,3]
arr3 += [4] // arr3 is now [1,2,3,4]
```

If the reference to an array is mutable, the instance method `insert(at:)` inserts a single element at the given index. To insert multiple elements at once, call the `insert(contentsOf:at:)` method. Assignment into a range-subscripted array, which I described earlier, is even more flexible.

If the reference to an array is mutable, the instance method `remove(at:)` removes the element at that index; the instance method `removeLast` removes the last element.



These methods also *return* the value that was removed from the array; you can ignore the returned value if you don't need it. These methods do not wrap the returned value in an `Optional`, and accessing an out-of-range index will crash your program. On the other hand, `popLast` does wrap the returned value in an `Optional`, and is safe even if the array is empty.

Similar to `removeLast` and `popLast` are `removeFirst` and `popFirst`. Alternate forms `removeFirst(_:)` and `removeLast(_:)` allow you to specify how many elements to remove, but return no value; they, too, can crash if there aren't as many elements as you specify. `popFirst`, remarkably, operates on a slice, not an array, presumably for the sake of efficiency: all it has to do is increase the slice's `startIndex`, whereas with an array, the whole array must be renumbered.

Even if the reference is not mutable, you can use the `dropFirst` and `dropLast` methods to return a slice with the end element removed. Again, you can supply a parameter stating how many elements to drop. And again, there is no penalty for dropping too many elements; you simply end up with an empty slice.



If your intention is primarily to insert or remove elements at the start and end of an array — as in a FIFO queue (first in, first out) — consider instead using a `Deque`, which is optimized for that sort of usage. It's available from the Swift Collections package (`import Collections`; see [Chapter 7](#)).

The `joined(separator:)` instance method starts with an array of arrays. It extracts their individual elements, and interposes between each sequence of extracted elements the elements of the `separator:` array. The result is an intermediate sequence called a `JoinSequence`, which might have to be coerced further to an `Array` if that's what you were after:

```
let arr = [[1,2], [3,4], [5,6]]
let joined = Array(arr.joined(separator:[10,11]))
// [1, 2, 10, 11, 3, 4, 10, 11, 5, 6]
```

The `joined()` method is extended in the Swift Algorithms package so that the separator can be generated through a function that you supply. The function receives as its parameters two adjacent inner arrays, and returns the separator array whose elements will go between theirs:

```
let arr = [[1,2], [3,4], [5,6]]
let joined = arr.joined { [$0.last!*10, $1.first!*10] }
let result = Array(joined)
// [1, 2, 20, 30, 3, 4, 40, 50, 5, 6]
```

Calling `joined()` with no separator is a way to flatten an array of arrays. Again, it returns an intermediate sequence (or collection), so you might want to coerce to an `Array`:

```
let arr = [[1,2], [3,4], [5,6]]
let arr2 = Array(arr.joined())
// [1, 2, 3, 4, 5, 6]
```

The `split` instance method breaks an array into an array of slices. If you call `split(separator:)`, the parameter is an element value, and the array is broken at elements equatable to that parameter. If you call `split(isSeparator:)`, the parameter is a function that takes a value of the element type and returns a `Bool`, and the array is broken at elements for which the function returns `true`. The separator elements themselves are eliminated:

```
let arr = [1,2,3,4,5,6]
let arr2 = arr.split {$0.isMultiple(of:2)}
// split at evens, removing the evens: [[1], [3], [5]]
```

The Swift Algorithms package has a `chunked(by:)` method that lets you break up an array *without* eliminating any elements. You supply a function that inspects each successive pair of elements and returns a `Bool`; returning `true` means that the given next element should be chunked together with the given preceding element:

```
let arr = [1,2,3,4,5,6]
let chunks = arr.chunked {before, after in !after.isMultiple(of: 2)}
// split before evens, keeping the evens: [[1], [2, 3], [4, 5], [6]]
```

The `reverse` instance method reverses an array (if the reference to it is mutable). The `reversed` instance method yields a new array reversed from the original.

The `sort` and `sorted` instance methods respectively sort the original array (if the reference to it is mutable) and yield a new sorted array based on the original. Once again, you get two choices. If this is an array of `Comparable` elements, you can let the `<` operator dictate the new order. Alternatively, you can call `sort(by:)` or `sorted(by:)`; you supply a function that takes two parameters of the element type and returns a `Bool` stating whether the first parameter should be ordered before the second (just like `min` and `max`):

```
var arr = [4,3,5,2,6,1]
arr.sort() // [1, 2, 3, 4, 5, 6]
arr.sort {$0 > $1} // [6, 5, 4, 3, 2, 1]
```

In that last line, I provided an anonymous function. Alternatively, of course, you can pass as argument the name of a declared function. In Swift, comparison operators *are* the names of functions! Therefore, I can do the same thing like this:

```
var arr = [4,3,5,2,6,1]
arr.sort(by: >) // [6, 5, 4, 3, 2, 1]
```

An interesting problem is *subsorting* an array. Suppose we have a `Person` struct with a `firstName` and a `lastName`, and we have an array of `Persons`:

```
var arr = [
    Person(firstName: "Manny", lastName: "Pep"),
    Person(firstName: "Harpo", lastName: "Marx"),
    Person(firstName: "Jack", lastName: "Pep"),
    Person(firstName: "Groucho", lastName: "Marx")
]
```

We wish to sort this array by last name, but if two Persons have the *same* last name, they should be sorted by first name. In other words, all Marx brothers should precede all Pep boys, and within those groups, Groucho should precede Harpo, and Jack should precede Manny.

Cocoa provides an elegant solution, `NSSortDescriptor`. New in Swift 5.5, there's a Swift Foundation overlay type `SortDescriptor` ([Chapter 11](#)), but it's still just an overlay on Cocoa, effectively requiring that the array elements be Objective-C class instances. Instead, we could write our own comparison function; but that's an invitation to make a mistake, and won't scale if we're subsorting on many properties.

In a simple case like this one, where the comparison operator is the same for all properties, there's a trick: use *tuples*. It turns out that tuples, by default, are comparable if their element types are comparable, by a rule that a given element is compared only if all preceding elements are equal. That's exactly how we want to sort this array! So we can sort the array in accordance with the corresponding tuple:

```
arr.sort { ($0.lastName, $0.firstName) < ($1.lastName, $1.firstName) }
```

The `swapAt` method accepts two `Int` index numbers and interchanges those elements of a mutable array:

```
var arr = [1,2,3]
arr.swapAt(0,2) // [3,2,1]
```

The `shuffle` and `shuffled` methods sort an array in random order. The `randomElement` method generates a valid index at random and hands you the element at that index (wrapped in an `Optional`, in case the array is empty). To generate an array of elements chosen randomly from an array, the Swift Algorithms package provides `randomSample` and `randomStableSample` methods.

There are even more utility methods in the Swift Algorithms package. There are methods for chaining arrays or repeating an array without allocating new storage. You can obtain an array's combinations and permutations. You can rotate an array. You can partition an array into two subarrays of which a given predicate is false and true, respectively, maintaining the element order:

```
var arr = [1,2,3,4,5,6,7]
let ix = arr.stablePartition {$0.isMultiple(of: 2)} // odds followed by evens
let odds = arr[..<ix] // [1, 3, 5, 7]
let evens = arr[ix...] // [2, 4, 6]
```

You can also generate tuples of adjacent pairs (`adjacentPairs`) or successive groups of a given length (`windows(ofCount:)`); alternatively, you can chunk an array into smaller arrays by length. An example will demonstrate the difference between `windows` and `chunks`:

```
let arr = [1,2,3,4,5]
let windows = arr.windows(ofCount: 3)
// [[1, 2, 3], [2, 3, 4], [3, 4, 5]]
let chunks = arr.chunks(ofCount: 3)
// [[1, 2, 3], [4, 5]]
```

## Array enumeration and transformation

An array is a sequence, and so you can enumerate it, inspecting or operating with each element in turn. The simplest way is by means of a `for...in` loop; I'll have more to say about this construct in [Chapter 5](#):

```
let pepboys = ["Manny", "Moe", "Jack"]
for pepboy in pepboys {
    print(pepboy) // prints Manny, then Moe, then Jack
}
```

Alternatively, you can use the `forEach(_:)` instance method. Its parameter is a function that takes an element and returns no value. Think of it as the functional equivalent of the imperative `for...in` loop:

```
let pepboys = ["Manny", "Moe", "Jack"]
pepboys.forEach {print($0)} // prints Manny, then Moe, then Jack
```

If you need index numbers as well as elements, call the `enumerated` instance method and loop on the result; what you get on each iteration is a tuple with labels `offset` and `element`:

```
let pepboys = ["Manny", "Moe", "Jack"]
for (ix,pepboy) in pepboys.enumerated() {
    print("Pep boy \(ix) is \(pepboy)") // Pep boy 0 is Manny, etc.
}
// or:
pepboys.enumerated().forEach {
    print("Pep boy \( $0.offset) is \( $0.element)")
}
```

The `offset` member of the tuple is actually just a counter that starts at zero. In some situations, the start index might not be zero. If you need the *real* index number, use the `indexed` method, available from the `Swift Algorithms` package.

The `allSatisfy(_:)` method tells you whether all elements pass some test; you supply a function that takes an element and returns a `Bool`:

```
let pepboys = ["Manny", "Moe", "Jack"]
let ok = pepboys.allSatisfy {$0.hasPrefix("M")} // false
let ok2 = pepboys.allSatisfy {$0.hasPrefix("M") || $0.hasPrefix("J")} // true
```

Swift also provides some powerful array transformation instance methods. Like `forEach(_:)` and `allSatisfy(_:)`, these methods enumerate the array for you, so that the loop is buried implicitly inside the method call, making your code tighter and cleaner.

The `filter(_:)` instance method yields a new array, each element of which is an element of the old array, in the same order; but some of the elements of the old array may be omitted — they were filtered out. What filters them out is a function that you supply; it accepts a parameter of the element type and returns a `Bool` stating whether this element should go into the new array:

```
let pepboys = ["Manny", "Moe", "Jack"]
let pepboys2 = pepboys.filter {$0.hasPrefix("M")} // ["Manny", "Moe"]
```

If the function is effectively negative, and if the reference to the collection is mutable, you should call `removeAll(where:)` rather than `filter(_:)`:

```
var pepboys = ["Manny", "Jack", "Moe"]
pepboys.removeAll {$0.hasPrefix("M")} // pepboys is now ["Jack"]
```

That's better in general than saying `pepboys.filter {!$0.hasPrefix("M")}` because of efficiencies achieved under the hood.

Similar to `filter(_:)` is `prefix(while:)`. The difference is that `prefix(while:)` stops looping as soon as it encounters an element for which the supplied function returns `false`; it returns the start of the original array as a slice. The complement of `prefix(while:)` is `drop(while:)`; it stops where `prefix(while:)` stops, but it returns the *rest* of the original array as a slice:

```
let pepboys = ["Manny", "Jack", "Moe"]
let arr1 = pepboys.filter {$0.hasPrefix("M")} // ["Manny", "Moe"]
let arr2 = pepboys.prefix {$0.hasPrefix("M")} // ["Manny"]
let arr3 = pepboys.drop {$0.hasPrefix("M")} // ["Jack", "Moe"]
```

The Swift Algorithms package adds `suffix(while:)`, `trimmingPrefix(while:)`, `trimmingSuffix(while:)`, and `trimming(while:)`. These methods are also applicable to strings.

The `map(_:)` instance method yields a new array, each element of which is the result of passing the corresponding element of the old array through a function that you supply. This function accepts a parameter of the element type and returns a result which may be of some other type; Swift can usually infer the type of the resulting array elements by looking at the type returned by the function.

Here's how to multiply every element of an array by 2:

```
let arr = [1,2,3]
let arr2 = arr.map {$0 * 2} // [2,4,6]
```

Here's another example, to illustrate the fact that `map(_:)` can yield an array with a different element type:

```
let arr = [1,2,3]
let arr2 = arr.map {Double($0)} // [1.0, 2.0, 3.0]
```

Here's a real-life example showing how neat and compact your code can be when you use `map(_:)`. In order to remove all the table cells in a section of a `UITableView`, I have to specify the cells as an array of `IndexPath` objects. If `sec` is the section number, I can form those `IndexPath` objects individually like this:

```
let path0 = IndexPath(row:0, section:sec)
let path1 = IndexPath(row:1, section:sec)
// ...
```

Hmmm, I think I see a pattern here! I could generate my array of `IndexPath` objects by looping through the row values using `for...in`. But with `map(_:)`, there's a much tighter way to express the same loop — namely, to loop through the range `0..ct` (where `ct` is the number of rows in the section). Since `map(_:)` is a `Collection` instance method, and a `Range` is itself a `Collection`, I can call `map(_:)` directly on the range:

```
let paths = (0..ct).map {IndexPath(row:$0, section:sec)}
```

The `map(_:)` method provides a neat alternative to `init(repeating:count:)` with a reference type:

```
let dogs = Array(repeating:Dog(), count:3) // probably a mistake
```

You probably wanted an array of three Dogs. But if `Dog` is a class, the array consists of three references to *one and the same* `Dog` instance! Instead, generate the array using `map(_:)`, like this:

```
let dogs = (0..3).map {_ in Dog()}
```

The `map(_:)` method has a specialized companion, `flatMap(_:)`. Applied to an array, `flatMap(_:)` first calls `map(_:)`, and then, if the `map` function produces an array of arrays, flattens it. In the simplest case, the `map` function does nothing and `flatMap` just flattens the array:

```
let arr = [[1],[2]]
let flattened = arr.flatMap {$0} // [1,2]
```

Here's a more interesting example:

```
let arr = [[1, 2], [3, 4]]
let arr2 = arr.flatMap {$0.map {String($0)}} // ["1", "2", "3", "4"]
```

First our `map` function calls `map(_:)` to coerce the individual elements of each inner array to a string, yielding an array of arrays of `String`: `[["1", "2"], ["3", "4"]]`. Then `flatMap(_:)` flattens the array of arrays, and we end up with a single array of `String`.

Another specialized `map(_:)` companion is `compactMap(_:)`. Given a map function that produces an array of `Optionals`, `compactMap(_:)` safely unwraps them by first eliminating any `nil` elements. In the simple case where you already have an array of `Optionals` and you just want to unwrap them all while eliminating `nil` elements, you can write that as `compactMap{$0}`. The Swift Algorithms package provides a nice synonym for it, `compacted`.

`compactMap(_:)` neatly solves a type of problem that arises quite often, where we want to coerce or cast an array safely while eliminating those elements that *can't* be coerced or cast. Suppose I have a mixed bag of strings, some of which represent integers. I'd like to coerce to `Int` those that *can* be coerced to `Int`, and eliminate the others. `Int` coercion of a `String` yields an `Optional`, so the `compactMap(_:)` lightbulb should go on in our heads:

```
let arr = ["1", "hey", "2", "ho"]
let arr2 = arr.compactMap {Int($0)} // [1, 2]
```

First we map the original array to an array of `Optionals` wrapping `Int`, by coercing; that yields `[Optional(1), nil, Optional(2), nil]`. Then `compactMap(_:)` removes the `nil` elements and unwraps the remaining elements, resulting in an array of `Int`.

The Swift Algorithms package has a `firstNonNil` method that applies a map function yielding an `Optional` and returns the first mapped value that isn't `nil`:

```
if let result = ["hey", "1", "ho", "2"].firstNonNil {Int($0)} {
    // result is 1
}
```

The `reduce` instance method is a way of *combining* all the elements of an array (actually, a sequence) into a single value. This value's type — the result type — doesn't have to be the same as the array's element type. `reduce` takes two parameters:

- You supply, as the *second* parameter, a function that takes two parameters; the first is of the result type, the second is of the element type, and the function's result is your combination of those two parameters, as the result type. That result, on each iteration, becomes the function's *first* parameter in the *next* iteration, along with the next element of the array as the *second* parameter. In this way, the output of combining pairs accumulates, and the final accumulated value is the final output of the function.

- However, that doesn't explain where the first parameter for the *first* iteration comes from. The answer is that you have to supply it as the *first* parameter of the `reduce` call.

That will all be easier to understand with a simple example. Suppose we've got an array of `Int`. Then we can use `reduce` to sum the elements of the array. Here's some pseudocode where I've left out the first argument of the call, so that you can think about what it needs to be:

```
let sum = arr.reduce(/* ... */) {$0 + $1}
```

Each pair of parameters will be added together to get the first parameter (`$0`) on the next iteration. The second parameter on every iteration (`$1`) is a successive element of the array. Clearly we are just summing the elements, adding each element one by one to an accumulated total. So the remaining question is: What should the *first* element of the array be added to? We want the actual sum of all the elements, no more and no less; so the first element of the array should be added to `0`:

```
let arr = [1, 4, 9, 13, 112]
let sum = arr.reduce(0) {$0 + $1} // 139
```

The `+` operator is the name of a function of the required type, so here's another way to write the same thing:

```
let sum = arr.reduce(0, +)
```

There is also `reduce(into:)`, which greatly improves efficiency when the goal is to build a collection such as an array or a dictionary. The `into:` argument is passed into your function as an `inout` parameter, and persists through each iteration; instead of returning a value, your function modifies it, and the final result is its final value.

Suppose we have an array of integers, and our goal is to “deal” them into two piles consisting of the even elements and the odd elements respectively. You can't do that with a single call to `map`; you'd have to cycle through the original array *twice*. With `reduce(into:)`, both target arrays are constructed while cycling through the original array once:

```
let nums = [1,3,2,4,5]
let result = nums.reduce(into: [],[]) { temp, i in
    temp[i%2].append(i)
}
// result is now [[2, 4], [1, 3, 5]]
```

The Swift Algorithms package supplies reductions methods corresponding to those `reduce` methods. The result is an array of the initial, intermediate, and final values that are accumulated as the `reduce` method loops through the array:

```
let reduct = [1,2,3,4].reductions(0,+) // [0, 1, 3, 6, 10]
```



Swift's array transformation methods are very powerful and very useful. In real life, your code is likely to depend heavily on methods like `filter`, `map`, and `reduce`, alone or in combination, nested or chained together.

## Swift Array and Objective-C NSArray

When you're programming iOS, you import the Foundation framework (or UIKit, which imports Foundation) and the Objective-C `NSArray` type. Swift Array is bridged to Objective-C `NSArray`.

The most general medium of array interchange between Objective-C and Swift is `[Any]`; if an Objective-C API specifies an `NSArray`, with no further type information, Swift will see this as an array of `Any`. This reflects the fact that Objective-C's rules for what can be an element of an `NSArray` are looser than Swift's: the elements of an `NSArray` do not all have to be of the same type. On the other hand, the elements of an Objective-C `NSArray` must be Objective-C *objects* — that is, they must be class types.

Passing a Swift array to Objective-C is usually easy. Typically, you'll just pass the array, either by assignment or as an argument in a function call:

```
let arr = [UIBarButtonItem(), UIBarButtonItem()]
self.navigationItem.leftBarButtonItems = arr
```

The objects that you pass as elements of the array will cross the bridge to Objective-C in the usual way:

```
let lay = CAGradientLayer()
lay.locations = [0.25, 0.5, 0.75] // bridged to NSArray of NSNumber
```

`CAGradientLayer`'s `locations` property needs to be an array of `NSNumber`; but we can pass an array of `Double`, because `Double` is bridged to `NSNumber`, and so Objective-C receives an `NSArray` of `NSNumber`.

To call an `NSArray` method on a Swift array, you may have to cast to `NSArray`:

```
let arr = ["Manny", "Moe", "Jack"]
let s = (arr as NSArray).componentsJoined(by:", ")
// s is "Manny, Moe, Jack"
```

A Swift Array seen through a `var` reference is mutable, but an `NSArray` isn't mutable ever. For mutability in Objective-C, you need an `NSMutableArray`, a subclass of `NSArray`. You can't cast, assign, or pass a Swift array as an `NSMutableArray`; you have to coerce. The best way is to call the `NSMutableArray` initializer `init(array:)`, to which you can pass a Swift array directly. To convert back from an `NSMutableArray` to a Swift array, you can cast:

```
var arr = ["Manny", "Moe", "Jack"]
let arr2 = NSMutableArray(array:arr)
arr2.remove("Moe")
arr = arr2 as! [String]
```

Now let's talk about what happens when an NSArray arrives from Objective-C into Swift. There won't be any problem crossing the bridge: the NSArray will arrive safely as a Swift Array. But a Swift Array *of what*?

Of itself, an NSArray carries no information about what type of element it contains. Starting in Xcode 7, however, the Objective-C language was modified so that the declaration of an NSArray, NSDictionary, or NSSet — the three collection types that are bridged to Swift — can include element type information. (Objective-C calls this a *lightweight generic*.) Thus, for the most part, the arrays you receive from Cocoa will be correctly typed.

For example, this elegant code was impossible in the bad old days before Xcode 7:

```
let arr = UIFont.familyNames.map {
    UIFont.fontNamesForFamilyName($0)
}
```

The result is an array of arrays of String, listing all available fonts grouped by family. That code is possible because both of those UIFont class methods are seen by Swift as returning an array of String. Before Xcode 7, however, those arrays were untyped, and casting down to an array of String was up to you.

Nevertheless, lightweight generics are not omnipresent. You might read an array from a *.plist* file stored on disk with NSArray's initializer `init(contentsOf:)`; you might retrieve an array from UserDefaults; you might even be dealing with an Objective-C API that hasn't been updated to use lightweight generics. In such a situation, you're going to end up with a plain vanilla NSArray or a Swift array of Any. If that happens, you will usually want to cast down or otherwise transform this array into an array of some specific Swift type. Here's an Objective-C class containing a method whose return type of NSArray hasn't been marked up with an element type:

```
@implementation Pep
- (NSArray*) boys {
    return @[@"Manny", @"Moe", @"Jack"];
}
@end
```

To call that method and do anything useful with the result, it will be necessary to cast that result down to an array of String. If I'm sure of my ground, I can force the cast:

```
let p = Pep()
let boys = p.boys() as! [String]
```

As with any cast, though, be sure you don't lie! An Objective-C array can contain more than one type of object. Don't force such an array to be cast down to a type to which not all the elements can be cast, or you'll crash when the cast fails; you'll need a more deliberate strategy (possibly involving `compactMap`) for eliminating or otherwise transforming the problematic elements.

## Dictionary

A dictionary (`Dictionary`, a struct) is an unordered collection of object pairs. In each pair, the first object is the *key*; the second object is the *value*. The idea is that you use a key to access a value.

Keys are usually strings, but they don't have to be; the formal requirement is that they be types that conform to the Hashable protocol. For a type to be Hashable, three things are required:

- The type must be Equatable.
- The type must implement an `Int hashValue` property.
- The type's implementation of equality and `hashValue` must be such that *equal keys have equal hash values*. The protocol itself cannot formally insist upon this rule, but that is what is needed for hashability to be useful and well-behaved.

The hash values can then be used behind the scenes for rapid key access. Most Swift standard types are Hashable; I'll talk in [Chapter 5](#) about how to make your own object types Hashable.



Do not use mutable objects as keys. Mutating a key while it is in use will break the dictionary (lookup will no longer work correctly).

As with arrays, the types of a given Swift Dictionary must be uniform. The key type and the value type don't have to be the same as one another, and they often will not be. But within any dictionary, all keys must be of the same type, and all values must be of the same type.

Formally, a dictionary is a generic, and its placeholder types are its key type and its value type: `Dictionary<Key, Value>`. As with arrays, Swift provides syntactic sugar for expressing a dictionary's type, and that is what you'll usually use: `[Key: Value]`. That's square brackets containing a colon (and optional spaces) separating the key type from the value type. This code creates an empty dictionary whose keys (when they exist) will be Strings and whose values (when they exist) will be Strings:

```
var d = [String:String]()
```

The colon is used also between each key and value in the literal syntax for expressing a dictionary. The key–value pairs appear between square brackets, separated by a comma, just like an array. This code creates a dictionary by describing it literally (and the dictionary's type of `[String:String]` is inferred):

```
var d = ["CA": "California", "NY": "New York"]
```

But if a dictionary variable is declared and initialized to a literal with many elements, it's a good idea to declare the variable's type explicitly. This saves the compiler from

having to examine the entire dictionary to decide its type, and makes compilation faster.

The literal for an empty dictionary is square brackets containing just a colon: `[:]`. That notation can be used provided the dictionary's type is known in some other way. This is another way to create an empty `[String:String]` dictionary:

```
var d : [String:String] = [:]
```

You can also initialize a dictionary from a sequence of key–value tuples. This is useful particularly if you're starting with two sequences. Suppose we happen to have state abbreviations in one array and state names in another:

```
let abbrevs = ["CA", "NY"]
let names = ["California", "New York"]
```

We can combine those two arrays into a single array of tuples and call `init(uniqueKeysWithValues:)` to generate a dictionary:

```
let tuples = (abbrevs.indices).map {(abbrevs[$0],names[$0])}
let d = Dictionary(uniqueKeysWithValues: tuples)
// ["NY": "New York", "CA": "California"]
```

There is actually a simpler way to form those tuples — the global `zip` function, which takes two sequences and yields a sequence of tuples:

```
let tuples = zip(abbrevs, names)
let d = Dictionary(uniqueKeysWithValues: tuples)
```

A nice feature of `zip` is that if one sequence is longer than the other, the extra elements of the longer sequence are ignored — tuple formation simply stops when the end of the shorter sequence is reached. For example, one of the zipped sequences can be a partial range; in theory the range is infinite, but in fact the end of the other sequence ends the range as well:

```
let r = 1...
let names = ["California", "New York"]
let d = Dictionary(uniqueKeysWithValues: zip(r,names))
// [2: "New York", 1: "California"]
```

If the keys in the tuple sequence are not unique, you'll crash at runtime when `init(uniqueKeysWithValues:)` is called. To work around that, you can use `init(_:uniquingKeysWith:)` instead. The second parameter is a function taking two values — the existing value for this key, and the new incoming value for the same key — and returning the value that should actually be used for this key.

Another way to form a dictionary is `init(grouping:by:)`. This is useful for forming a dictionary whose values are *arrays*. You start with a sequence of the *elements* of the arrays, and the initializer clumps them into arrays for you, in accordance with a function that generates the corresponding key from each value.

Suppose we have a list (`states`) of the 50 U.S. states in alphabetical order as an array of strings, and we want to group them by the letter they start with. Here's a verbose strategy. We loop through the list to construct two arrays (an array of `String` and an array of arrays of `String`); we then zip those arrays together to form the dictionary:

```
var sectionNames = [String]()
var cellData = [[String]]()
var previous = ""
for aState in states {
    // get the first letter
    let c = String(aState.prefix(1))
    // only add a letter to sectionNames when it's a different letter
    if c != previous {
        previous = c
        sectionNames.append(c.uppercased())
        // and in that case also add new subarray to our array of subarrays
        cellData.append([String]())
    }
    cellData[cellData.count-1].append(aState)
}
let d = Dictionary(uniqueKeysWithValues: zip(sectionNames, cellData))
// ["H": ["Hawaii"], "V": ["Vermont", "Virginia"], ...]
```

With `init(grouping:by:)`, however, that becomes effectively a one-liner:

```
let d = Dictionary(grouping: states) {$0.prefix(1).uppercased()}
```

## Dictionary subscripting

Access to a dictionary's contents is usually by subscripting. To fetch a value by key, use the key as a subscript:

```
let d = ["CA": "California", "NY": "New York"]
let state = d["CA"]
```

If you try to fetch a value through a nonexistent key, there is no error, but Swift needs a way to report failure; to do so, by default, it returns `nil`. This, in turn, implies that the value returned when you successfully access a value through a key must be an `Optional` wrapping the real value. After that code, therefore, `state` is not a `String` — it's an `Optional` wrapping a `String`! Forgetting this is a common beginner mistake.

You can change that behavior by supplying your own default value as part of the subscript. If the key isn't found in the dictionary, the default value is returned, and so there is no need for the returned value to be wrapped in an `Optional`:

```
let d = ["CA": "California", "NY": "New York"]
let state = d["MD", default:"N/A"] // state is a String (not an Optional)
```

If the reference to a dictionary is mutable, you can also assign into a key subscript expression. If the key already exists, its value is replaced. If the key doesn't already exist, it is created and the value is attached to it:

```
var d = ["CA": "California", "NY": "New York"]
d["CA"] = "Casablanca"
d["MD"] = "Maryland"
// d is now ["MD": "Maryland", "NY": "New York", "CA": "Casablanca"]
```

Instead of assigning into a subscript expression, you can call `updateValue(_:for-Key:)`; it has the advantage that it returns the old value.

As with fetching a value by key, you can supply a default value when assigning into a key subscript expression. This can be a source of great economy of expression. Consider the common task of collecting a histogram: we want to know how many times each element appears in a sequence:

```
let sentence = "how much wood would a wood chuck chuck"
let words = sentence.split(separator: " ").map {String($0)}
```

Our goal is now to make a dictionary pairing each word with the number of times it appears. A manual approach would be rather laborious, along these lines:

```
var d = [String:Int]()
for word in words {
    let ct = d[word]
    if ct != nil {
        d[word]! += 1
    } else {
        d[word] = 1
    }
}
// d is now ["how": 1, "wood": 2, "a": 1, "chuck": 2, "would": 1, "much": 1]
```

With a default value, it's effectively a one-liner:

```
var d = [String:Int]()
words.forEach {d[$0, default:0] += 1}
```

By a kind of shorthand, assigning `nil` into a key subscript expression removes that key–value pair if it exists:

```
var d = ["CA": "California", "NY": "New York"]
d["NY"] = nil // d is now ["CA": "California"]
```

Alternatively, call `removeValue(forKey:)`; it has the advantage that it returns the removed value before it removes the key–value pair.

## Dictionaries have no order

Dictionaries are *unordered*. Whenever you probe a dictionary's entire contents — when you print them, when you cycle through them with `for...in`, and so forth — each entry arrives in a completely unpredictable order. If you run the same code as I do (indeed, even if you run the same code as yourself on two different occasions), your results may be ordered differently. This makes no difference to the actual contents of the dictionary, which consists of particular keys, each associated with a

particular value. `[2: "New York", 1: "California"]` is actually the same dictionary as `[1: "California", 2: "New York"]`.

If you needed order to be meaningful, you may have been thinking of an array, not a dictionary. For an ordered array of key-value pairs — with no subscripting by key, no hashability requirement, and no guaranteed uniqueness of keys — you can use a `KeyValuePairs` object, which is essentially an array of tuples with labels `key` and `value`; it can be initialized from a dictionary literal:

```
let pairs : KeyValuePairs = ["CA": "California", "NY": "New York"]
print(pairs.count) // 2
print(pairs[0]) // (key: "CA", value: "California")
// to access by key, cycle through the array
if let pair = pairs.first(where: {$0.key == "NY"}) {
    let val = pair.value // New York
}
```

On the other hand, there is an `OrderedDictionary` struct in the Swift Collections package; I'll talk about it later.

## Dictionary casting and comparison

As with arrays, a dictionary type is legal for casting down, meaning that the individual elements will be cast down. Typically, only the value types will differ:

```
let dog1 : Dog = NoisyDog()
let dog2 : Dog = NoisyDog()
let d = ["fido": dog1, "rover": dog2]
let d2 = d as! [String : NoisyDog]
```

As with arrays, `is` can be used to test the actual types in the dictionary, and `as?` can be used to test and cast safely.

Dictionary equality is like array equality. Key types are necessarily `Equatable`, because they are `Hashable`. Value types are not necessarily `Equatable`, but if they are, the `==` and `!=` operators work as you would expect.

## Basic dictionary properties and enumeration

A dictionary has a `count` property reporting the number of key-value pairs it contains, and an `isEmpty` property reporting whether that number is 0.

A dictionary has a `keys` property reporting all its keys, and a `values` property reporting all its values. These are effectively opaque structs providing a specialized view of the dictionary itself. You can't assign one to a variable, or print it out, but you can work with them as collections. For example, you can enumerate them with `for...in` (though you should not expect them to arrive in any particular order, as a dictionary is unordered):

```
var d = ["CA": "California", "NY": "New York"]
for s in d.keys {
    print(s) // NY, then CA (or vice versa)
}
```

You can coerce them to an array:

```
var d = ["CA": "California", "NY": "New York"]
var keys = Array(d.keys) // ["NY", "CA"] or ["CA", "NY"]
```

You can sort them, filter them, or map them (yielding an array); you can take their `min` or `max`; you can reduce them; you can compare keys of different dictionaries for equality:

```
let d : [String:Int] = ["one":1, "two":2, "three":3]
let keysSorted = d.keys.sorted() // ["one", "three", "two"]
let arr = d.values.filter {$0 < 2} // [1]
let min = d.values.min() // Optional(1)
let sum = d.values.reduce(0, +) // 6
let ok = d.keys == ["one":1, "three":3, "two":2].keys // true
```

You can also enumerate a dictionary itself. Each iteration provides a key–value tuple (arriving in no particular order, because a dictionary is unordered):

```
var d = ["CA": "California", "NY": "New York"]
for (abbrev, state) in d {
    print("\(abbrev) stands for \(state)")
}
```

The tuple members have labels `key` and `value`, and `forEach` works on a dictionary, so the preceding example can be rewritten like this:

```
var d = ["CA": "California", "NY": "New York"]
d.forEach { print("\(d[key].key) stands for \(d[key].value)") }
```

You can extract a dictionary’s entire contents at once as an array of key–value tuples (in an unpredictable order) by coercing the dictionary to an array:

```
var d = ["CA": "California", "NY": "New York"]
let arr = Array(d)
// [(key: "NY", value: "New York"), (key: "CA", value: "California")]
```

When you apply `filter` to a dictionary, what you get is a dictionary. In addition, there’s a `mapValues` method that yields a dictionary with its values changed according to your map function:

```
let d = ["CA": "California", "NY": "New York"]
let d2 = d.filter {$0.value > "New Jersey"}.mapValues {$0.uppercased()}
// ["NY": "NEW YORK"]
```

There’s also a `compactMapValues` method that applies a map function yielding an `Optional` and filters out any keys for which the resulting value is `nil`.



You can combine two dictionaries with the `merging(_:uniquingKeysWith:)` method — or, if your reference to the first dictionary is mutable, you can call `merge` to modify it directly. The second parameter is like the second parameter of `init(_:uniquingKeysWith:)`, saying what the value should be in case the second dictionary has a key matching an existing key in the first dictionary:

```
let d1 = ["CA": "California", "NY": "New York"]
let d2 = ["MD": "Maryland", "NY": "New York"]
let d3 = d1.merging(d2) {orig, _ in orig}
// ["MD": "Maryland", "NY": "New York", "CA": "California"]
```

## Swift Dictionary and Objective-C NSDictionary

The Foundation framework dictionary type is `NSDictionary`, and Swift Dictionary is bridged to it. The untyped API characterization of an `NSDictionary` in Swift will be `[AnyHashable:Any]`. (`AnyHashable` is a *type eraser* struct, to cope with the possibility, legal in Objective-C, that the keys may be of different Hashable types.)

Like `NSArray` element types, `NSDictionary` key and value types can be marked in Objective-C using a lightweight generic. The most common key type in a real-life Cocoa `NSDictionary` is `NSString`, so you might well receive an `NSDictionary` typed as `[String:Any]`. Specific typing of an `NSDictionary`'s values is rare, because dictionaries that you pass to and receive from Cocoa will often have values of multiple types; it is not surprising to have a dictionary whose keys are strings but whose values include a string, a number, a color, and an array. For this reason, you will usually *not* cast down the entire dictionary's type; instead, you'll work with the dictionary as having `Any` values, and cast when fetching an *individual value* from the dictionary. Since the value returned from subscripting a key is itself an `Optional`, you will typically unwrap and cast the value as a standard single move.

Here's an example. A Cocoa Notification object comes with a `userInfo` property. It is an `NSDictionary` that might itself be `nil`, so the Swift API characterizes it as `[AnyHashable:Any]?`. Let's say I'm expecting this dictionary to be present and to contain a "progress" key whose value is an `NSNumber` containing a `Double`. My goal is to extract that `NSNumber` and assign the `Double` that it contains to a property, `self.progress`. Here's one way to do that safely, using optional unwrapping and optional casting (`n` is the Notification object):

```
let prog = n.userInfo?["progress"] as? Double
if prog != nil {
    self.progress = prog!
}
```

The variable `prog` is implicitly typed as an `Optional` wrapping a `Double`. The code is safe, because if there is no `userInfo` dictionary, or if it doesn't contain a "progress" key, or if that key's value isn't a `Double`, nothing happens, and `prog` will be `nil`.

I then test `prog` to see whether it *is nil*; if it isn't, I know that it's safe to force-unwrap it, and that the unwrapped value is the `Double` I'm after.

(In [Chapter 5](#) I'll describe another syntax for accomplishing the same goal, using conditional binding.)

Conversely, here's a typical example of creating a dictionary and handing it off to Cocoa. This dictionary is a mixed bag: its values are a `UIFont`, a `UIColor`, and an `NSShadow`. Its keys are all strings, which I obtain as constants from Cocoa. I form the dictionary as a literal and pass it, all in one move, with no need to cast anything:

```
UINavigationBar.appearance().titleTextAttributes = [
    .font: UIFont(name: "ChalkboardSE-Bold", size: 20)!,
    .foregroundColor: UIColor.darkText,
    .shadow.: {
        let shad = NSShadow()
        shad.shadowOffset = CGSize(width:1.5,height:1.5)
        return shad
    }()
]
```

As with `NSArray` and `NSMutableArray`, if you want Cocoa to mutate a dictionary, you must coerce to `NSDictionary`'s subclass `NSMutableDictionary`:

```
var d1 = ["NY": "New York", "CA": "California"]
let d2 = ["MD": "Maryland"]
let mutd1 = NSMutableDictionary(dictionary:d1)
mutd1.addEntries(from:d2)
d1 = mutd1 as! [String:String]
// d1 is now ["MD": "Maryland", "NY": "New York", "CA": "California"]
```

## Set

A set (`Set`, a struct) is an *unordered* collection of *unique* objects. Its elements must be all of one type; it has a `count` and an `isEmpty` property; it can be initialized from any sequence; you can cycle through its elements with `for...in` (where the order of elements is unpredictable).

The uniqueness of set elements is implemented by constraining their type to be `Hashable` (and hence `Equatable`), just like the keys of a dictionary, so that the hash values can be used behind the scenes for rapid access. Checking whether a set contains a given element, which you can do with the `contains(_)` instance method, is *very* efficient — far more efficient than doing the same thing with an array. Therefore, if element uniqueness is acceptable (or desirable) and you don't need indexing or a guaranteed order, a set can be a much better choice of collection than an array. I'll talk in [Chapter 5](#) about how to make your own types `Hashable`.



The warnings in the preceding section apply: don't store a mutable value in a Set. Also, don't expect Set values to be reported to you in any particular order. (An OrderedSet struct is available from the Swift Collections package; I'll talk about it later.)

There are no set literals in Swift, but you won't need them because you can pass an array literal where a set is expected. There is no syntactic sugar for expressing a set type, but the Set struct is a generic, so you can express the type by explicitly specializing the generic:

```
let set : Set<Int> = [1, 2, 3, 4, 5]
```

In that particular example there was no real need to specialize the generic, as the Int type can be inferred from the array. However, when setting a Set variable from a literal, it is more efficient to specialize the generic. This saves the compiler the trouble of reading the whole literal.

It sometimes happens (more often than you might suppose) that you want to examine one element of a set as a kind of sample. Order is meaningless, so it's sufficient to obtain *any* element. For this purpose, use the `first` instance property; it returns an Optional, just in case the set is empty.

The distinctive feature of a set is the uniqueness of its objects. If an object is added to a set and that object is already present, it isn't added a second time. Conversion from an array to a set and back to an array is a quick and reliable way of *uniquing* the array — though of course order is not preserved:

```
let arr = [1,2,1,3,2,4,3,5]
let set = Set(arr)
let arr2 = Array(set) // [5, 2, 3, 1, 4], perhaps
```

A set is a Collection and a Sequence. Like Array, Set has a `map(_:)` instance method; it returns an array, but of course you can turn that right back into a set if you need to:

```
let set : Set = [1,2,3,4,5]
let set2 = Set(set.map {$0+1}) // Set containing 2, 3, 4, 5, 6
```

On the other hand, applying `filter` to a Set yields a Set directly:

```
let set : Set = [1,2,3,4,5]
let set2 = set.filter {$0 > 3} // Set containing 4, 5
```

If the reference to a set is mutable, you can add an object to it with `insert(_:)`; there is no penalty for trying to add an object that's already in the set, but the object won't be added. `insert(_:)` also returns a result, a tuple whose `inserted` element will be `false` if an equivalent object was already present in the set. This result is usually disregarded, but it can sometimes be useful; here, we use it to unique an array while preserving its order:

```
var arr = ["Manny", "Manny", "Moe", "Jack", "Jack", "Moe", "Manny"]
var temp = Set<String>()
arr = arr.filter { temp.insert($0).inserted }
```

It might be preferable, though, to use the `unique` or `unique(on:)` method from the `Swift Algorithms` package.

The other element of the tuple returned by `insert(_:)` is `memberAfterInsert`. If `inserted` is `true`, this is simply the parameter of `insert(_:)`. If `inserted` is `false`, however, it is the existing member of the set that caused the insertion to fail because it is regarded as equal to the parameter of `insert(_:)`; this may be of interest because it tells you *why* the insertion was rejected.

Instead of `insert(_:)`, you can call `update(with:)`; the difference is that if you're trying to add an object that already has an equivalent in the set, the former doesn't insert the new object, but the latter *always* inserts, replacing the old object (if there is one) with the new one.

You can remove an object and return it by specifying an equivalent object with the `remove(_:)` method; it returns the object from the set, wrapped in an `Optional`, or `nil` if the object was not present. You can remove and return an arbitrary object from the set with `removeFirst`; it crashes if the set is empty, so take precautions — or use `popFirst`, which is safe.

Equality comparison (`==`) is defined for sets as you would expect; two sets are equal if every element of each is equal to an element of the other.

If the notion of a set evokes visions of Venn diagrams from elementary school, that's good, because sets have instance methods giving you all those set operations you remember so fondly. The parameter can be a set, or it can be any sequence, which will be converted to a set; it might be an array, a range, or even a character sequence:

`intersection(_:)`, `formIntersection(_:)`

Yields the elements of this set that also appear in the parameter. The first forms a new Set; the second is mutating.

`union(_:)`, `formUnion(_:)`

Yields the elements of this set along with the (unique) elements of the parameter. The first forms a new Set; the second is mutating.

`symmetricDifference(_:)`, `formSymmetricDifference(_:)`

Yields the elements of this set that don't appear in the parameter, plus the (unique) elements of the parameter that don't appear in this set. The first forms a new Set; the second is mutating.

`subtracting(_:), subtract(_:)`

Yields the elements of this set except for those that appear in the parameter. The first forms a new Set; the second is mutating.

`isSubset(of:), isStrictSubset(of:)`

`isSuperset(of:), isStrictSuperset(of:)`

Returns a Bool reporting whether the elements of this set are respectively embraced by or embrace the elements of the parameter. The “strict” variant yields false if the two sets consist of the same elements.

`isDisjoint(with:)`

Returns a Bool reporting whether this set and the parameter have no elements in common.

Here’s a real-life example of Set usage from one of my apps. I have a lot of numbered pictures, of which we are to choose one randomly. But I don’t want to choose a picture that has recently been chosen. Therefore, I keep a list of the numbers of all recently chosen pictures. When it’s time to choose a new picture, I convert the list of all possible numbers to a Set, convert the list of recently chosen picture numbers to a Set, and call `subtracting(_:)` to get a list of unused picture numbers! Now I choose a picture number at random and add it to the list of recently chosen picture numbers:

```
let ud = UserDefaults.standard
let recents = ud.object(forKey: Defaults.recents) as? [Int] ?? []
var forbiddenNumbers = Set(recents)
let legalNumbers = Set(1...PIXCOUNT).subtracting(forbiddenNumbers)
let newNumber = legalNumbers.randomElement()!
forbiddenNumbers.insert(newNumber)
ud.set(Array(forbiddenNumbers), forKey:Defaults.recents)
```

## Option sets

An *option set* (OptionSet struct) is Swift’s way of treating a certain type of Cocoa enumeration as a Swift struct. It is not, strictly speaking, a Set; but it is deliberately set-like, sharing common features with Set through the SetAlgebra protocol. An option set has `contains(_:)`, `insert(_:)`, and `remove(_:)` methods, along with all the various set operation methods.

The purpose of option sets is to help you grapple with Objective-C *bitmasks*. A bitmask is an integer whose bits are used as switches when multiple options are to be specified simultaneously. Bitmasks are very common in Cocoa. In Objective-C, bitmasks are manipulated through the arithmetic bitwise-or and bitwise-and operators. Such manipulation can be mysterious and error-prone. But in Swift, thanks to option sets, bitmasks can be manipulated easily through set operations instead.

For example, when specifying how a `UIView` is to be animated, you are allowed to pass an `options:` argument whose value comes from the `UIView.AnimationOptions` enumeration, whose definition (in Objective-C) begins:

```
typedef NSUInteger (UIViewAnimationOptions) {  
    UIViewAnimationOptionLayoutSubviews          = 1 << 0,  
    UIViewAnimationOptionAllowUserInteraction   = 1 << 1,  
    UIViewAnimationOptionBeginFromCurrentState  = 1 << 2,  
    UIViewAnimationOptionRepeat                 = 1 << 3,  
    UIViewAnimationOptionAutoreverse            = 1 << 4,  
    // ...  
};
```

Pretend that an `NSUInteger` is 8 bits (it isn't, but let's keep things simple and short). Then this enumeration means that (in Swift) the following name-value pairs are defined:

<code>UIView.AnimationOptions.layoutSubviews</code>	<code>0b00000001</code>
<code>UIView.AnimationOptions.allowUserInteraction</code>	<code>0b00000010</code>
<code>UIView.AnimationOptions.beginFromCurrentState</code>	<code>0b00000100</code>
<code>UIView.AnimationOptions.repeat</code>	<code>0b00001000</code>
<code>UIView.AnimationOptions.autoreverse</code>	<code>0b00010000</code>

These values can be combined into a single value — a *bitmask* — that you pass as the `options:` argument for your animation. All Cocoa has to do to understand your intentions is to look to see which bits in the value that you pass are set to 1. So, for example, `0b00011000` would mean that `UIView.AnimationOptions.repeat` and `UIView.AnimationOptions.autoreverse` are both true (and that the others are all false).

The question is how to *form* the value `0b00011000` in order to pass it. You could form it directly as a literal and set the `options:` argument to `UIView.AnimationOptions(rawValue:0b00011000)`; but that's not a very good idea, because it's error-prone and makes your code incomprehensible. In Objective-C, you'd use the arithmetic bitwise-or operator, analogous to this Swift code:

```
let val =  
    UIView.AnimationOptions.autoreverse.rawValue |  
    UIView.AnimationOptions.repeat.rawValue  
let opts = UIView.AnimationOptions(rawValue: val)
```

That's rather ugly! However, help is on the way: the `UIView.AnimationOptions` type is an option set struct in Swift (because it is marked as `NS_OPTIONS` in Objective-C), and therefore can be treated much like a `Set`. Given a `UIView.AnimationOptions` value, you can add an option to it using `insert(_:)`:

```
var opts = UIView.AnimationOptions.autoreverse  
opts.insert(.repeat)
```

Alternatively, you can start with an array literal, just as if you were initializing a Set:

```
let opts : UIView.AnimationOptions = [.autoreverse, .repeat]
```



To indicate that no options are to be set, pass an empty option set ([]) or, where permitted, omit the options: parameter altogether.

Sometimes Cocoa hands *you* a bitmask, and you want to know whether a certain bit is set. In this example from a UITableViewCell subclass, the cell's state comes to us as a bitmask; we want to know about the bit indicating that the cell is showing its edit control. The Objective-C way is to extract the raw values and use the bitwise-and operator:

```
override func didTransition(to state: UITableViewCell.StateMask) {
    let editing = UITableViewCell.StateMask.showingEditControl.rawValue
    if state.rawValue & editing != 0 {
        // ... the ShowingEditControl bit is set ...
    }
}
```

That's a tricky formula, all too easy to get wrong. But in Swift this is an option set, so the contains(\_: ) method tells you the answer:

```
override func didTransition(to state: UITableViewCell.StateMask) {
    if state.contains(.showingEditControl) {
        // ... the ShowingEditControl bit is set ...
    }
}
```

## Swift Set and Objective-C NSSet

Swift's Set type is bridged to Objective-C NSSet. The untyped medium of interchange is Set<AnyHashable>. Coming back from Objective-C, if Objective-C doesn't know what this is a set of, you would probably cast down as needed. As with NSArray, however, NSSet can be marked up using lightweight generics to indicate its element type, in which case no casting will be necessary:

```
override func touchesBegan(_ touches: Set<UITouch>, with event: UIEvent?) {
    let t = touches.first // an Optional wrapping a UITouch
    // ...
}
```

## OrderedSet and OrderedDictionary

The Swift Collections package provides an OrderedSet struct and an OrderedDictionary struct. These, as their names imply, allow a Set or a Dictionary to have a fixed order.

## OrderedSet

OrderedSet is basically implemented as an array plus a hash table. Like an array, an OrderedSet has an order, and you can refer to elements consistently by index number. Unlike an array, elements of an OrderedSet must be unique.

Lookup in an OrderedSet, such as `firstIndex(of:)` and `contains`, is fast because it uses the hash table rather than having to walk the array examining every element. So if you were thinking of using an array and you need fast lookup, and if the uniqueness requirement is not a barrier, you might prefer an OrderedSet:

```
let pep = OrderedSet(["Manny", "Moe", "Jack"])
let first = pep.first! // Manny
let ix = pep.firstIndex(of: "Moe") // Optional(1), fast
if pep.contains("Jack") { // true, fast
```

OrderedSet conforms to the Collection and Sequence protocols, so it can do other array-like things, even if you don't get any special benefits. For example, `firstIndex(where:)` works fine, because OrderedSet is partly an array; but it doesn't work any differently than if it *were* an array.

Unlike a Set, you can't just insert into an OrderedSet; it has an order, like an array, so you must also provide an index saying *where* you want to insert this element, or you can append to the end. But it's still a Set, so if the proposed new element already exists, it won't be added! The `insert` and `append` methods return a tuple saying whether the element was added and, if so, at what index; if the element was not added, the index reports where the matching element is.

OrderedSet also has two properties that constitute special views of the data:

### elements

An OrderedSet's `elements` property is an Array, and is useful primarily when you need to pass the OrderedSet data where an array is expected. Direct operations upon the `elements` affect the OrderedSet (with the proviso that operations that would violate the Set's uniqueness contract will not be performed).

### unordered

An OrderedSet's `unordered` property is not a Set, but it acts like one; in particular, it obeys all the set algebra commands applicable to a Set, because it conforms to the SetAlgebra protocol.



When you assign the `elements` or `unordered` property of an `OrderedSet` to another variable, or pass it as a parameter, you have effectively made a copy. There's nothing wrong with that, but keep in mind that mutations on the resulting object will *not* affect the original ordered set:

```
var arr = myOrderedSet.elements
arr.append(100) // does not affect myOrderedSet
```

On the whole, you probably won't be mutating an `OrderedSet`'s `elements` or `unordered` properties in the first place. Mutate the `OrderedSet` itself! Mutating operations on an `OrderedSet` are faster than the same operations on its `elements` property.

An `OrderedSet` can help solve a problem that frequently arises in connection with arrays: how to *cosort* an array — that is, sorting one array in an order dictated by another array. Suppose we have a `model` array with its elements in the desired order:

```
let model = ["Manny", "Moe", "Jack"]
```

And we have another array whose elements are drawn from the `model` array:

```
let arr = ["Jack", "Manny"]
```

The question is: how can we sort the second array so that its elements are ordered like the first array?

A naïve solution might involve a sort function that looks up the index of each element in the `model` array:

```
let result = arr.sorted {
  model.firstIndex(of:$0)! < model.firstIndex(of:$1)!
}
```

But `firstIndex` on a normal array is horribly inefficient, as we must walk the array one element at a time — and if these arrays are big, sorting could involve calling `firstIndex` many times, including multiple times on the same element.

Without `OrderedSet`, the standard solution is to start by making a dictionary of model element values and positions, to facilitate rapid lookup. But an `OrderedSet` makes calling `firstIndex` just as efficient as dictionary lookup:

```
let model = OrderedSet(["Manny", "Moe", "Jack"])
```

When the arrays are large, even that becomes needlessly slow, because we are *still* calling `firstIndex` many times on each element. We can vastly improve efficiency if we start by mapping each element of the target array to a tuple of positions and values, so that we fetch each element's `firstIndex` only once. We then sort the tuples and map back to the original elements:

```
let result = arr.map {(model.firstIndex(of:$0)!, $0)}.sorted(by:<).map {$0.1}
```

## OrderedDictionary

OrderedDictionary has most of the capabilities of a normal Dictionary, along with ordering of its key–value pairs. Its `keys` property is an immutable OrderedSet. Its `elements` property looks a lot like what you get when you coerce a Dictionary to an Array — it's a list of tuples with labels `key` and `value`, indexable by number (because it's a RandomAccessCollection).

Think of an OrderedDictionary as something that you sometimes treat as a dictionary and sometimes treat as an array:

### *As a dictionary*

You can index by key in the normal way. But unlike a normal dictionary, if you assign into a key that doesn't exist, the new pair is appended to the end by default; alternatively, you can call `updateValue(_:forKey:insertingAt:)` to dictate where the pair should be inserted if the key doesn't already exist.

### *As an array*

To access a key–value pair by index number, pass through the `elements` property so that the index number is not mistaken for a key. But for an obviously array-like operation, such as `sort`, `shuffle`, or `remove(at:)`, you don't need to use the `elements` property; the OrderedDictionary knows what you mean, and exposes its elements as key–value pairs directly.

To illustrate, here are some example commands (we assume the existence of a simple Planet struct):

```
var d : OrderedDictionary<String,Planet> = [:]
d["Mercury"] = Planet(distance: 57_900_000, diameter: 4_878, gravity: 0.38)
d["Venus"] = Planet(distance: 108_160_000, diameter: 12_104, gravity: 0.9)
d["Earth"] = Planet(distance: 149_600_000, diameter: 12_756, gravity: 1)
let names = d.keys // OrderedSet: ["Mercury", "Venus", "Earth"]
let thirdPlanet = d.elements[2] // tuple with `key` and `value`
let name = thirdPlanet.key // "Earth"
let mercuryGravity = d["Mercury"]?.gravity // Optional, 0.38
let planetX = Planet(distance: 100_000_000, diameter: 8_000, gravity: 0.8)
d.updateValue(planetX, forKey: "PlanetX", insertingAt: 2)
```

OrderedDictionary also has some ways of updating a value that don't exist for a normal Dictionary, but ought to:

```
modifyValue(forKey:default:_:)
```

```
modifyValue(forKey:insertingDefault:at:_:)
```

The last parameter is a function that takes the existing value as an `inout` parameter.

I'll rewrite the earlier histogram example to use that syntax:

```
var histogram = OrderedDictionary<String, Int>()
let sentence = "how much wood would a wood chuck chuck"
let words = sentence.split(separator: " ").map {String($0)}
for word in words {
    histogram.modifyValue(forKey: word, default: 0) {$0 += 1}
}
// [how: 1, much: 1, wood: 2, would: 1, a: 1, chuck: 2]
```

And if we prefer our keys in alphabetical order, we would now say:

```
histogram.sort {$0.key < $1.key}
```



---

# Flow Control and More

This chapter is a miscellany. I'll start by describing Swift's flow control constructs for branching, looping, and jumping. Then, I'll summarize Swift's privacy and introspection features, and talk about how to override operators and how to create your own operators. Next, I'll explain some specialized aspects of Swift memory management. Finally, I'll survey some relatively recent Swift language features: synthesized protocol implementations, key paths, instance as function, dynamic members, property wrappers, custom string interpolation, reverse generics, result builders, and Result.

## Flow Control

A computer program has a *path of execution* through its code statements. Normally, this path follows a simple rule: execute each statement in succession. But there is another possibility. *Flow control* can be used to make the path of execution skip some statements, or go back and repeat some statements.

Flow control is what makes a computer program “intelligent.” By testing in real time the truth value of a *condition* — an expression that evaluates to a Bool and is thus true or false — the program decides *at that moment* how to proceed. Flow control based on testing a condition may be divided into two general types:

### *Branching*

The code is divided into alternative chunks, like roads that diverge in a wood, and the program is presented with a choice of possible ways to go; the truth of a condition is used to determine which chunk will actually be executed.

### *Looping*

A chunk of code is marked off for possible repetition; the truth of a condition is used to determine whether the chunk should be executed, and then whether it should be executed again. Each repetition is called an *iteration*.

The chunks of code in flow control, which I refer to as *blocks*, are demarcated by curly braces. These curly braces constitute a scope ([Chapter 1](#)). New local variables can be declared here, and go out of existence automatically when the path of execution exits the curly braces ([Chapter 3](#)). For a loop, this means that local variables come into existence and go out of existence on each iteration. As with any scope, code inside the curly braces can see the surrounding higher scope.

Swift flow control is fairly simple, and by and large is similar to flow control in C and related languages. There are two fundamental syntactic differences between Swift and C, both of which make Swift simpler and clearer:

- A condition *does not have to be wrapped in parentheses* in Swift.
- The curly braces *can never be omitted* in Swift.

Moreover, Swift adds some specialized flow control features to help you grapple more conveniently with Optionals, and boasts a particularly powerful form of switch statement.

## Branching

Swift has two forms of branching: the if construct, and the switch statement. I'll also discuss conditional evaluation, a compact form of if construct.

### If construct

The Swift branching construct with `if` is similar to C. Many examples of if constructs have appeared already in this book. The construct may be formally summarized as shown in [Example 5-1](#).

*Example 5-1. The Swift if construct*

```
if condition {  
    statements  
}  
  
if condition {  
    statements  
} else {  
    statements  
}  
  
if condition {  
    statements  
} else if condition {  
    statements  
} else {  
    statements  
}
```

The third form, containing `else if`, can have as many `else if` blocks as needed, and the final `else` block may be omitted.

Here's a real-life if construct that lies at the heart of one of my apps:

```
// okay, we've tapped a tile; there are three cases
if self.selectedTile == nil { // no selected tile: select and play this tile
    self.select(tile:tile)
    self.play(tile:tile)
} else if self.selectedTile == tile { // selected tile tapped: deselect it
    self.deselectAll()
    self.player?.pause()
} else { // there was a selected tile, another tile was tapped: swap them
    self.swap(self.selectedTile, with:tile, check:true, fence:true)
}
```

## Conditional binding

In Swift, `if` can be followed immediately by a variable declaration and assignment — that is, by `let` or `var` and a new local variable name, possibly followed by a colon and a type declaration, then an equal sign and a value:

```
if let variable = value {
    // the block
}
```

This syntax, called a *conditional binding*, is actually a shorthand for *conditionally unwrapping an Optional*. The assigned value (*value*) is expected to be an Optional — the compiler will stop you if it isn't — and this is what happens:

- If the Optional (*value*) is `nil`, the condition fails and the block is skipped, with execution resuming after the block.
- If the Optional is *not* `nil`, then:
  1. The Optional is unwrapped.
  2. The unwrapped value is assigned to the declared local variable (*variable*).
  3. The block is executed with the local variable in scope. The local variable is *not* in scope outside the block.

So a conditional binding safely passes an unwrapped Optional into a block. The Optional is unwrapped, and the block is executed, only if the Optional *can* be unwrapped.

It is perfectly reasonable for the local variable in a conditional binding to have the same name as an existing variable in the surrounding scope. It can even have the same name as the Optional being unwrapped! There is then no need to make up a new name, and inside the block the unwrapped value of the Optional neatly over-shadows the original Optional so that the latter can't be accessed accidentally.

Recall this code from [Chapter 4](#), where I optionally unwrap a Notification’s userInfo dictionary, attempt to fetch a value from the dictionary using the "progress" key, and proceed only if that value turns out to be an NSNumber that can be cast down to a Double:

```
let prog = n.userInfo?["progress"] as? Double
if prog != nil {
    self.progress = prog!
}
```

We can rewrite that code more elegantly and compactly as a conditional binding:

```
if let prog = n.userInfo?["progress"] as? Double {
    self.progress = prog
}
```

It is also possible to nest conditional bindings. To illustrate, I’ll rewrite the previous example to use a separate conditional binding for each Optional in the chain:

```
if let ui = n.userInfo {
    if let prog = ui["progress"] as? Double {
        self.progress = prog
    }
}
```

The result, if the chain involves many optional unwrappings, can be somewhat verbose and the nest can become deeply indented; Swift programmers like to call this the “pyramid of doom.” To help avoid the indentation, nested conditions can be expressed as a *condition list*. Imagine that each left curly brace, together with the following `if`, is replaced by a comma:

```
if let ui = n.userInfo, let prog = ui["progress"] as? Double {
    self.progress = prog
}
```

The conditions are evaluated in left-to-right order. Each condition depends upon the preceding ones; a binding introduced in an earlier condition is in scope in a later one, and if a condition fails the entire list fails immediately. In the example code, the assignment to `prog` won’t even be attempted if `n.userInfo` is `nil`; the assignment to `ui` fails and that’s the end.

Condition lists do not have to consist solely of conditional bindings. They can include ordinary conditions. It would be possible (though not as elegant) to rewrite the previous example like this:

```
if let ui = n.userInfo, let prog = ui["progress"], prog is Double {
    self.progress = prog as! Double
}
```

If the list is too long for a single line, it can be conveniently broken up after each comma:



```

if let ui = n.userInfo,
    let prog = ui["progress"],
    prog is Double {
    self.progress = prog as! Double
}

```

Personally, I am not fond of this kind of extended condition list. I actually prefer the pyramid of doom, where the structure reflects perfectly the successive stages of testing. If I want to avoid the pyramid of doom, I can usually use a sequence of guard statements (**“Guard” on page 303**):

```

guard let ui = n.userInfo else {return}
guard let prog = ui["progress"] as? Double else {return}
self.progress = prog

```

## Switch statement

A switch statement is a neater way of writing an extended `if...else if...else` construct. In C (and Objective-C), a switch statement contains hidden traps; Swift eliminates those traps, and adds power and flexibility. As a result, switch statements are commonly used in Swift (whereas they are rare in my Objective-C code).

In a switch statement, the condition involves the comparison of different possible values, called *cases*, against a single value, called the *tag*. The case comparisons are performed *successively in order*. As soon as a case comparison succeeds, that case’s code is executed and the entire switch statement is exited. The schema is shown in **Example 5-2**; there can be as many cases as needed, and the default case can be omitted (subject to restrictions that I’ll explain in a moment).

*Example 5-2. The Swift switch statement*

```

switch tag {
case pattern1:
    statements
case pattern2:
    statements
default:
    statements
}

```

Here’s an actual example:

```

switch i {
case 1:
    print("You have 1 thingy!")
case 2:
    print("You have 2 thingies!")
default:
    print("You have \(i) thingies!")
}

```

In that code, an `Int` variable `i` functions as the tag. The value of `i` is first compared to the value 1. If it is 1, that case's code is executed and that's all. If it is *not* 1, it is compared to the value 2. If it is 2, *that* case's code is executed and that's all. If the value of `i` matches neither of those, the default case's code is executed.

In Swift, a switch statement must be *exhaustive*. This means that *every* possible value of the tag must be covered by a case. The compiler will stop you if you try to violate this rule. If you don't want to write every case explicitly, you must add a “mop-up” case that covers all other cases; a common way to do that is to add a default case. It's easy to write an exhaustive switch when the tag is an enum with a small number of cases, but when the tag is an `Int`, there is an infinite number of possible cases, so a “mop-up” case *must* appear.

Each case's code can consist of multiple statements; it doesn't have to be a single statement, like the cases in the preceding example. However, it must consist of *at least* a single statement; it is illegal for a Swift switch case to be empty. It is legal for the first (or only) statement of a case's code to appear on the same line as the case, after the colon; I could have written the preceding example like this:

```
switch i {
case 1: print("You have 1 thingy!")
case 2: print("You have 2 thingies!")
default: print("You have \(i) thingies!")
}
```

The minimum single statement of case code is the keyword `break`; used in this way, `break` acts as a placeholder meaning, “Do nothing.” It is very common for a switch statement to include a default (or other “mop-up” case) consisting of nothing but the keyword `break`; in this way, you exhaust all possible values of the tag, but if the value is one that no case explicitly covers, you do nothing.

Now let's focus on the comparison between the tag value and the case value. In the preceding example, it works like an equality comparison (`==`); but that isn't the only possibility. In Swift, a case value is actually a special expression called a *pattern*, and the pattern is compared to the tag value using a “secret” pattern-matching operator, `~=`. The more you know about the syntax for constructing a pattern, the more powerful your case values and your switch statements will be.

A pattern can include an underscore (`_`) to absorb all values without using them. An underscore case is thus an alternative form of “mop-up” case:

```
switch i {
case 1:
    print("You have 1 thingy!")
case _:
    print("You have many thingies!")
}
```

A pattern can include a declaration of a local variable name (an unconditional binding) to absorb all values and use the actual value. This is yet another alternative form of “mop-up” case:

```
switch i {
case 1:
  print("You have 1 thingy!")
case let n:
  print("You have \<n> thingies!")
}
```

When the tag is a Comparable, a case can include a Range; the test involves sending the Range the contains message:

```
switch i {
case 1:
  print("You have 1 thingy!")
case 2...10:
  print("You have \<i> thingies!")
default:
  print("You have more thingies than I can count!")
}
```

A Range pattern can be an opportunity to use partial range syntax:

```
switch i {
case ..<0:
  print("i is negative, namely \<i>")
case 1...:
  print("i is positive, namely \<i>")
case 0:
  print("i is 0")
default:break
}
```

When the tag is an Optional, a case can test it against nil. Moreover, appending ? to a case pattern safely unwraps an Optional tag. Presume that i is an Optional wrapping an Int:

```
switch i {
case 1?:
  print("You have 1 thingy!")
case let n?:
  print("You have \<n> thingies!")
case nil: break
}
```

When the tag is a Bool, a case can test it against a condition. Thus, by a clever perversion, you can use the cases to test *any* conditions you like by using true as the tag; a switch statement becomes a genuine substitute for an extended if...else if construct. In this example from my own code, I could have used if...else if, but a switch statement seems cleaner:

```
func position(for bar: UIBarPositioning) -> UIBarPosition {
    switch true {
    case bar == self.navbar: return .topAttached
    case bar == self.toolbar: return .bottom
    default:
        return .any
    }
}
```

A pattern can include a `where` clause adding a condition to limit the truth value of the case. This is often, though not necessarily, used in combination with a binding; the condition can refer to the variable declared in the binding:

```
switch i {
case let j where j < 0:
    print("i is negative, namely \(j)")
case let j where j > 0:
    print("i is positive, namely \(j)")
case 0:
    print("i is 0")
default: break
}
```

A pattern can include the `is` operator to test the tag's type. In this example, we have a `Dog` class and its `NoisyDog` subclass, and `d` is typed as `Dog`:

```
switch d {
case is NoisyDog:
    print("You have a noisy dog!")
case _:
    print("You have a dog")
}
```

A pattern can include a cast with the `as` (not `as?`) operator. Typically, you'll combine this with a binding that declares a local variable; despite the use of unconditional `as`, the cast is conditional, and if it succeeds, the local variable carries the cast value into the case code. Again, `d` is typed as `Dog`, which has a `NoisyDog` subclass; assume that `Dog` implements `bark` and that `NoisyDog` implements `beQuiet`:

```
switch d {
case let nd as NoisyDog:
    nd.beQuiet()
case let d:
    d.bark()
}
```

You can also use `as` (not `as?`) to cast down the tag (and possibly unwrap it) conditionally as part of a test against a specific match. In this example, `i` might be an `Any` or an `Optional` wrapping an `Any`:

```
switch i {
case 0 as Int:
    print("It is 0")
default:break
}
```

You can perform multiple tests at once by expressing the tag as a tuple and wrapping the corresponding tests in a tuple. The case passes only if every test in the case tuple succeeds against the corresponding member of the tag tuple. In this example, we start with a dictionary `d` typed as `[String:Any]`. Using a tuple, we can safely attempt to fetch and cast two values at once:

```
switch (d["size"], d["desc"]) {
case let (size as Int, desc as String):
    print("You have size \(size) and it is \(desc)")
default:break
}
```

When a tag is an enum, the cases can be cases of the enum. A switch statement is thus an excellent way to handle an enum. Here’s the `Filter` enum from [Chapter 4](#):

```
enum Filter {
    case albums
    case playlists
    case podcasts
    case books
}
```

And here’s a switch statement, where the tag, `type`, is a `Filter`; no mop-up is needed, because I’ve exhausted the cases:

```
switch type {
case .albums:
    print("Albums")
case .playlists:
    print("Playlists")
case .podcasts:
    print("Podcasts")
case .books:
    print("Books")
}
```



If an enum comes from Objective-C (or C) or the Swift standard library, an exhaustive switch over it might get you a warning from the compiler that the enum “may have additional unknown values.” I’ll explain what that means, and what to do about it, in the [Appendix](#).

A switch statement provides a way to extract an associated value from an enum case. Recall this enum from [Chapter 4](#):

```
enum MyError {
    case number(Int)
    case message(String)
    case fatal
}
```

If a case of the enum has an associated value, a tuple of patterns after the matched case name is applied to the associated value. If a pattern is a binding variable, it captures the associated value. The `let` (or `var`) can appear inside the parentheses or after the case keyword; this code illustrates both alternatives:

```
switch err {
case .number(let theNumber):
    print("It is a number: \(theNumber)")
case let .message(theMessage):
    print("It is a message: \(theMessage)")
case .fatal:
    print("It is fatal")
}
```

If the `let` (or `var`) appears after the case keyword, I can add a where clause:

```
switch err {
case let .number(n) where n > 0:
    print("It's a positive error number \(n)")
case let .number(n) where n < 0:
    print("It's a negative error number \(n)")
case .number(0):
    print("It's a zero error number")
default:break
}
```

If I don't want to extract the error number but just want to match against it, I can use some other pattern inside the parentheses:

```
switch err {
case .number(1...):
    print("It's a positive error number")
case .number(..<0):
    print("It's a negative error number")
case .number(0):
    print("It's a zero error number")
default:break
}
```

This same pattern also gives us yet another way to deal with an `Optional` tag. An `Optional`, as I explained in [Chapter 4](#), is in fact an enum. It has two cases, `.none` and `.some`, where the wrapped value is the `.some` case's associated value. But now we know how to extract the associated value! We can rewrite yet again the earlier example where `i` is an `Optional` wrapping an `Int`:

```

switch i {
case .none: break
case .some(1):
    print("You have 1 thingy!")
case .some(let n):
    print("You have \n thingies!")
}

```

To combine switch case tests (with an implicit logical-or), separate them with a comma:

```

switch i {
case 1,3,5,7,9:
    print("You have a small odd number of thingies")
case 2,4,6,8,10:
    print("You have a small even number of thingies")
default:
    print("You have too many thingies for me to count")
}

```

In this example, `i` is declared as an `Any`:

```

switch i {
case is Int, is Double:
    print("It's some kind of number")
default:
    print("I don't know what it is")
}

```

A comma can even combine patterns that declare binding variables, provided they declare the same variable of the same type (`err` is our `MyError` once again):

```

switch err {
case let .number(n) where n > 0, let .number(n) where n < 0:
    print("It's a nonzero error number \n")
case .number(0):
    print("It's a zero error number")
default:break
}

```

Another way of combining cases is to jump from one case to the next by using a `fallthrough` statement. When a `fallthrough` statement is encountered, the current case code is aborted immediately and the next case code runs *unconditionally*. The test of the next case is not performed, so the next case can't declare any binding variables, because they would never be set. It is not uncommon for a case to consist entirely of a `fallthrough` statement:

```

switch pep {
case "Manny": fallthrough
case "Moe": fallthrough
case "Jack":

```

```

        print("\(pep) is a Pep boy")
    default:
        print("I don't know who \(pep) is")
}

```

## If case

When all you want to do is extract an associated value from one enum case, a full switch statement may seem a bit heavy-handed. The lightweight `if case` construct lets you use in a condition the same sort of pattern syntax you'd use in a case of a switch statement. The structural difference is that, whereas a switch case pattern is compared against a previously stated tag, an `if case` pattern is followed by an equal sign and then the tag. In this code, `err` is our `MyError` enum once again:

```

if case let .number(n) = err {
    print("The error number is \(n)")
}

```

The condition starting with `case` can be part of a longer comma-separated condition list:

```

if case let .number(n) = err, n < 0 {
    print("The negative error number is \(n)")
}

```

## Conditional evaluation

An interesting problem arises when you'd like to decide on the fly what value to use — for example, what value to assign to a variable. This seems like a good use of a branching construct. You can, of course, declare the variable first without initializing it, and then set it from within a subsequent branching construct. It would be nice, however, to use a branching construct *as* the variable's value. Here, I try (and fail) to write a variable assignment where the equal sign is followed directly by a branching construct:

```

let title = switch type { // compile error
case .albums:
    "Albums"
case .playlists:
    "Playlists"
case .podcasts:
    "Podcasts"
case .books:
    "Books"
}

```

There are languages that let you talk that way, but Swift is not one of them. However, an easy workaround does exist — use a define-and-call anonymous function, as I suggested in [Chapter 2](#):



```

let title : String = {
    switch type {
    case .albums:
        return "Albums"
    case .playlists:
        return "Playlists"
    case .podcasts:
        return "Podcasts"
    case .books:
        return "Books"
    }
}()

```

In the special case where a value can be decided by a two-pronged condition, Swift provides the C ternary operator (`? :`). Its scheme is:

```
condition ? exp1 : exp2
```

If the condition is true, the expression *exp1* is evaluated and the result is used; otherwise, the expression *exp2* is evaluated and the result is used. You can use the ternary operator while performing an assignment, using this schema:

```
let myVariable = condition ? exp1 : exp2
```

What `myVariable` gets initialized to depends on the truth value of the condition.

I use the ternary operator heavily in my own code. Here's an example:

```
cell.accessoryType =
    ix.row == self.currow ? .checkmark : .disclosureIndicator
```

The context needn't be an assignment; here, we're deciding what value to pass as a function argument:

```
context.setFillColor(self.hilite ? purple.cgColor : beige.cgColor)
```

The ternary operator can also be used to determine the receiver of a message. In this example, one of two `UIViews` will have its background color set:

```
(self.firstRed ? v1 : v2).backgroundColor = .red
```

In Objective-C, there's a collapsed form of the ternary operator that allows you to test a value against `nil`. If it is `nil`, you get to supply a substitute value. If it *isn't* `nil`, the tested value itself is used. In Swift, the analogous operation would involve testing an `Optional`: if the tested `Optional` is `nil`, use the substitute value; if it *isn't* `nil`, *unwrap* the `Optional` and use the unwrapped value. Swift has such an operator — the `??` operator (called the *nil-coalescing* operator).

Here's a real-life example from my own code:

```

func tableView(_ tv: UITableView, numberOfRowsInSection sec: Int) -> Int {
    return self.titles?.count ?? 0
}

```

In that example, `self.titles` is of type `[String]?`. If it's not `nil`, I want to unwrap the array and return its count. But if it *is* `nil`, there is no data and no table to display — but I *must* return *some* number, so clearly I want to return zero. The nil-coalescing operator lets me express all that very neatly.

The nil-coalescing operator together with the Optional `map(_ :)` method neatly solves a class of problem where your goal is to *process* the wrapped value of an Optional or, if it is `nil`, to assign some default value. Suppose our goal is to produce a string expressing the index of `target` within `arr` if it is present, or "NOT FOUND" if it is not. This works, but it's ugly:

```
let arr = ["Manny", "Moe", "Jack"]
let target = // some string
let pos = arr.firstIndex(of:target)
let s = pos != nil ? String(pos!) : "NOT FOUND"
```

Here's a more elegant way:

```
let arr = ["Manny", "Moe", "Jack"]
let target = // some string
let s = arr.firstIndex(of:target).map {String($0)} ?? "NOT FOUND"
```

Expressions using `??` can be chained:

```
let someNumber = i1 as? Int ?? i2 as? Int ?? 0
```

That code tries to cast `i1` to an `Int` and use that `Int`. If that fails, it tries to cast `i2` to an `Int` and use *that* `Int`. If *that* fails, it gives up and uses `0`.

## Loops

The usual purpose of a loop is to repeat a block of code with some simple difference on each iteration. This difference will typically serve also as a signal for when to stop the loop. Swift provides two basic loop structures: while loops and for loops.

### While loops

A while loop comes in two forms, schematized in [Example 5-3](#).

*Example 5-3. The Swift while loop*

```
while condition {
    statements
}

repeat {
    statements
} while condition
```

The chief difference between the two forms is the timing of the test. In the second form, the condition is tested after the block has executed — meaning that the block will be executed at least once.

Usually, the code inside the block will change something that alters the environment and hence the value of the condition, eventually bringing the loop to an end. Here's a typical example from my own code (`movenda` is an array):

```
while self.movenda.count > 0 {
  let p = self.movenda.removeLast()
  // ...
}
```

Each iteration removes an element from `movenda`, so eventually its `count`, evaluated in the condition, falls to 0 and the loop is no longer executed; execution then proceeds to the next line after the closing curly braces.

In its first form, a `while` loop's condition can involve a conditional binding of an `Optional`. This provides a compact way of safely unwrapping an `Optional` and looping until the `Optional` is `nil`; the local variable containing the unwrapped `Optional` is in scope inside the curly braces. My previous code can be rewritten more compactly:

```
while let p = self.movenda.popLast() {
  // ...
}
```

Here's an example of `repeat...while` from my own code. In my `LinkSame` app, if there are no legal moves, we pick up all the cards, shuffle them, and redeal them into the same layout. It's possible that when we do that, there will *still* be no legal moves. So we do it again until there *is* a legal move:

```
repeat {
  var deck = self.gatherUpCards()
  deck.shuffle()
  self.redeal(deck)
} while self.legalPath() == nil
```

Similar to the `if case` construct, `while case` lets you use a switch case pattern. In this rather artificial example, we have an array of various `MyError` enums:

```
let arr : [MyError] = [
  .message("ouch"), .message("yipes"), .number(10), .number(-1), .fatal
]
```

With `while case`, we can extract the `.message` associated string values from the start of the array:

```
var i = 0
while case let .message(message) = arr[i] {
  print(message) // "ouch", then "yipes"; then the loop stops
  i += 1
}
```

## For loops

The Swift for loop is schematized in [Example 5-4](#).

*Example 5-4. The Swift for loop*

```
for variable in sequence {  
    statements  
}
```

With a for loop, you cycle through (*enumerate*) a sequence. The sequence must be an instance of a type that adopts the Sequence protocol. An Array is a Sequence. A Dictionary is a Sequence. A Set is a Sequence. A String is a Sequence. A Range is a Sequence (as long as it is a range of something that comes in discrete steps, like Int). Those, and sequences derived from them, are the things to which you will regularly apply `for...in`.

On each iteration, a successive element of the sequence is used to initialize the variable. The variable is local to the block; it is in scope inside the curly braces, and is not visible outside them. The variable is implicitly declared with `let`; it is immutable by default. If you need to assign to or mutate the variable within the block, write `for var`.

A common use of for loops is to iterate through successive numbers. This is easy in Swift, because you can readily create a sequence of numbers on the fly — a Range:

```
for i in 1...5 {  
    print(i) // 1, 2, 3, 4, 5  
}
```

A for loop is secretly a while loop. Sequence has a `makeIterator` method that yields an iterator object adopting `IteratorProtocol`. According to this protocol, the iterator has a mutating `next` method that returns the next object in the sequence wrapped in an `Optional`, or `nil` if there is no next object. Under the hood, `for...in` is repeatedly calling the `next` method in a while loop. The previous code actually works like this:

```
var iterator = (1...5).makeIterator()  
while let i = iterator.next() {  
    print(i) // 1, 2, 3, 4, 5  
}
```

Sometimes you may find that writing out the while loop explicitly in that way makes the loop easier to control and to customize.

When you cycle through a sequence with `for...in`, what you're actually cycling through is a *copy* of the sequence. That means it's safe to mutate the sequence while you're cycling through it:

```

var s : Set = [1,2,3,4,5]
for i in s {
    if i.isMultiple(of:2) {
        s.remove(i)
    }
} // s is now [1,3,5]

```

That may not be the most elegant way to remove all even numbers from the Set `s`, but it's not illegal or dangerous; removing an element of the Set doesn't mess up the subsequent iterations of the loop.

Not only is the *sequence* a copy; if the variable type is a value type, such as a struct, the *variable* is a copy. So even if you mutate the variable (which is legal if you say `for var`), the original sequence's elements are unaffected. Here's a `Dog` that's a struct:

```

struct Dog {
    var name : String
    init(_ n:String) {
        self.name = n
    }
}

```

We cycle through an array of `Dogs`, uppercasing their names:

```

var dogs : [Dog] = [Dog("rover"), Dog("fido")]
for var dog in dogs {
    dog.name = dog.name.uppercased()
}

```

But nothing useful happens; `dogs` still consists of `Dogs` named "rover" and "fido". If the Sequence is also a Collection, one common workaround is to cycle through its indices instead, so that you can assign back into the original array:

```

var dogs : [Dog] = [Dog("rover"), Dog("fido")]
for ix in dogs.indices {
    dogs[ix].name = dogs[ix].name.uppercased()
}

```

Now `dogs` consists of `Dogs` named "ROVER" and "FIDO".

The sequence `enumerated` method yields a succession of tuples in which each element of the original sequence is preceded by a count (see [“Array enumeration and transformation” on page 244](#)). In this example from my real code, `tiles` is an array of `UIView`s and `centers` is an array of `CGPoint`s saying where those views are to be positioned:

```

for (i,v) in self.tiles.enumerated() {
    v.center = self.centers[i]
}

```

A `for...in` construct can take a `where` clause, allowing you to skip some values of the sequence:

```
for i in 0...10 where i.isMultiple(of:2) {
    print(i) // 0, 2, 4, 6, 8, 10
}
```

Like `if` case and `while` case, there's also `for` case, permitting a switch case pattern to be used in a `for` loop. The tag is each successive value of the sequence, so no assignment operator is used. To illustrate, let's start again with an array of `MyError` enums:

```
let arr : [MyError] = [
    .message("ouch"), .message("yipes"), .number(10), .number(-1), .fatal
]
```

Here we cycle through the whole array, extracting only the `.number` associated values:

```
for case let .number(i) in arr {
    print(i) // 10, -1
}
```

Another common use of `for` case is to cast down conditionally, picking out only those members of the sequence that can be cast down safely. In this real-life code, I want to hide all subviews that happen to be buttons:

```
for case let b as UIButton in self.boardView.subviews {
    b.isHidden = true
}
```

A sequence also has instance methods, such as `map(_:)`, `filter(_:)`, and `reversed`; you can apply these to hone the sequence through which we will cycle. In this example, I count backward by even numbers:

```
let range = (0...10).reversed().filter {$0.isMultiple(of:2)}
for i in range {
    print(i) // 10, 8, 6, 4, 2, 0
}
```

Yet another approach is to generate the sequence by calling global functions such as `stride(from:through:by:)` or `stride(from:to:by:)`. These are applicable to adopters of the `Strideable` protocol, such as numeric types and anything else that can be incremented and decremented. Which form you use depends on whether you want the sequence to include the final value. The `by:` argument can be negative:

```
for i in stride(from: 10, through: 0, by: -2) {
    print(i) // 10, 8, 6, 4, 2, 0
}
```

The Swift Algorithms package supplements that with a `striding(by:)` method on an array. This lets you stride through the array itself rather than striding through index numbers and indexing into the array:

```
let planets = ["Mercury", "Venus", "Earth", "Mars", "Jupiter"]
for planet in planets.striding(by:2) {
    print(planet) // Mercury, Earth, Jupiter
}
```

For maximum flexibility, you can use the global sequence function to generate your sequence by rule. It takes two parameters — an initial value, and a generation function that returns the next value based on what has gone before. In theory, the sequence generated by the sequence function can be infinite in length — though this is not a problem, because the resulting sequence is “lazy,” meaning that an element isn’t generated until you ask for it. In reality, you’ll use one of two techniques to limit the result:

#### *Return nil*

The generation function can limit the sequence by returning `nil` to signal that the end has been reached:

```
let seq = sequence(first:1) {$0 >= 10 ? nil : $0 + 1}
for i in seq {
    print(i) // 1,2,3,4,5,6,7,8,9,10
}
```

#### *Stop requesting elements*

You can request just a piece of the infinite sequence — for example, by cycling through the sequence for a while and then stopping, or by taking a finite prefix:

```
let seq = sequence(first:1) {$0 + 1}
for i in seq.prefix(5) {
    print(i) // 1,2,3,4,5
}
```

The sequence function comes in two forms:

#### `sequence(first:next:)`

Initially hands `first` into the `next:` function and subsequently hands the previous result of the `next:` function into the `next:` function, as illustrated in the preceding examples.

#### `sequence(state:next:)`

This form is more general: it repeatedly hands `state` into the `next:` function as an `inout` parameter; the `next:` function is expected to set that parameter, using it as a scratchpad, in addition to returning the next value in the sequence.

An obvious illustration of the second form is the Fibonacci series:

```
let fib = sequence(state:(0,1)) { (pair: inout (Int,Int)) -> Int in
    let n = pair.0 + pair.1
    pair = (pair.1,n)
    return n
}
for i in fib.prefix(10) {
    print(i) // 1, 2, 3, 5, 8, 13, 21, 34, 55, 89
}
```

## Trailing Closures and Flow Control Blocks

Trailing closures do not play well with subsequent flow control blocks; therefore parentheses are sometimes needed where generally they would not be. The closing curly brace of the trailing closure, followed by the opening curly brace of the block, upsets the compiler:

```
for i in arr.map {$0*2} { // warning
    print(i)
}
```

To silence the warning, wrap the trailing closure in parentheses:

```
for i in arr.map ({$0*2}) {
    print(i)
}
```

In this example, the curly braces are not adjacent, but you get the warning anyway:

```
if arr.map {$0*2}.first == 4 { // warning
```

Again, parentheses are the simplest solution:

```
if arr.map ({$0*2}).first == 4 {
```

Any sequence can be made “lazy” by asking for its `lazy` property. This can be a source of efficiency if you’re going to be looping through the sequence (explicitly or implicitly) and potentially short-circuiting the loop; there’s no point generating more elements of the sequence than the loop will actually process, and that is what `lazy` prevents. Importantly, laziness propagates through a chain of sequence operations. I’ll give an example in the next section.

## Jumping

Although branching and looping constitute the bulk of the decision-making flow of code execution, sometimes they are insufficient to express the logic of what needs to happen next. It can be useful to interrupt your code’s progress completely and *jump* to a different place within it. In this section, I’ll list Swift’s modes of jumping. These are all controlled forms of *early exit* from the current flow of code.

### Return

You already know one form of early exit: the return statement. One function calls another, which may call another, and so on, forming a call stack. When a return statement is encountered, execution of this function is aborted and the path of execution jumps to the point where the call was made in the function one level up the call stack.



## Short-circuiting and labels

Swift has several ways of short-circuiting the flow of branch and loop constructs:

### `fallthrough`

A `fallthrough` statement in a `switch` case aborts execution of the current case code and immediately begins executing the code of the next case.

### `continue`

A `continue` statement in a loop construct aborts execution of the current iteration and proceeds to the next iteration:

- In a `while` loop, `continue` performs the conditional test immediately.
- In a `for` loop, `continue` proceeds immediately to the next iteration if there is one (and aborts the loop there isn't).

### `break`

A `break` statement aborts the current construct and proceeds after the end of the construct:

- In a loop, `break` aborts the loop.
- In a `switch` case, `break` aborts the entire `switch` construct.

When constructs are nested, you may need to specify *which* construct you mean when you say `continue` or `break`. Therefore, Swift permits you to put a *label* before the start of an `if` construct, a `switch` statement, a `while` loop, or a `for` loop (or a `do` block, which I'll describe later). The label is an arbitrary name followed by a colon. You can then use that label name (without the colon) in a `continue` statement or a `break` statement within the labeled construct at any depth, to specify that this is the construct you are referring to.

To illustrate, here's a simple struct for generating prime numbers:

```
struct Primes {
    static var primes = [2]
    static func appendNextPrime() {
        next: for i in (primes.last!+1)... {
            let sqrt = Int(Double(i).squareRoot())
            for prime in primes.lazy.prefix(while: {$0 <= sqrt}) {
                if i.isMultiple(of: prime) {
                    continue next
                }
            }
            primes.append(i)
            return
        }
    }
}
```

The algorithm could be improved, but it's effective and straightforward. The struct maintains a list of the primes we've found so far, and `appendNextPrime` basically just looks at each successive larger integer `i` to see whether any of the primes we've already found (`prime`) divides it. If so, `i` is not a prime, so we want to go on to the next `i`. But there are two nested for loops; if we merely say `continue`, we'll jump to the next `prime` (the inner for loop), not to the next `i` (the outer for loop). The `label` solves the problem.

That example also demonstrates *lazy*. We want to keep `prefix(while:_)` from working harder than it has to; there's no point extracting *all* the primes less than the square root of `i` in advance, because the loop might be short-circuited. So we make primes lazy, which makes `prefix(while:_)` lazy, and so a `prime` is tested as a divisor of `i` only if it has to be.

## Throwing and catching errors

Sometimes a situation arises where further coherent progress is impossible: the entire operation in which we are engaged has failed. It may then be desirable to abort the current scope, and possibly the current function, and possibly even the function that called that function, and so on, exiting to some point where we can acknowledge this failure and proceed in good order in some other way.

For this purpose, Swift provides a mechanism for *throwing and catching errors*. In keeping with its usual insistence on safety and clarity, Swift imposes strict conditions on the use of this mechanism, and the compiler will ensure that you adhere to them.

An *error*, in this sense, is a kind of message, presumably indicating what went wrong. This message is passed up the nest of scopes and function calls as part of the error-handling process, and the code that recovers from the failure can read it. In Swift, an error must be an object of a type that adopts the Error protocol, which has just two requirements: a `String _domain` property and an `Int _code` property. The purpose of those properties is to help errors cross the bridge between Swift and Objective-C; in real life, they are hidden and you will be unaware of them. The Error object will be one of the following:

### *A Swift type that adopts Error*

As soon as a Swift type formally declares adoption of the Error protocol, it is ready to be used as an error object; the protocol requirements are magically fulfilled for you behind the scenes. Typically, this type will be an enum, with different cases distinguishing different kinds of possible failure, perhaps with raw values or associated types to carry further information.

### *NSError*

`NSError` is Cocoa's class for communicating the nature of a problem; Swift extends `NSError` to adopt Error and bridges them to one another. If your call to a

Cocoa method generates a failure, Cocoa will send you an NSError instance typed as an Error.

There are two stages of the error mechanism to consider:

#### *Throwing an error*

Throwing an error aborts the current path of execution and hands an error object to the error mechanism.

#### *Catching an error*

Catching an error receives that error object from the error mechanism and responds in good order, with the path of execution resuming after the point of catching. In effect, we have *jumped* from the throwing point to the catching point.

To *throw an error*, use the keyword `throw` followed by an error object. That's all it takes! The current block of code is immediately aborted, and the error mechanism takes over. However, to ensure that the `throw` command is used coherently, Swift imposes a rule that you can say *throw only in a context where the error will be caught*. What is such a context?

The primary context for throwing and catching an error is the `do...catch` construct. This consists of a `do` block and one or more `catch` blocks. It is legal to throw in the `do` block; an accompanying `catch` block can then be fed any errors thrown from within the `do` block. The `do...catch` construct's schema looks like [Example 5-5](#).

#### *Example 5-5. The Swift `do...catch` construct*

```
do {  
    statements // a throw can happen here  
} catch errortype {  
    statements  
} catch {  
    statements  
}
```

A single `do` block can be accompanied by multiple `catch` blocks. Catch blocks are like the cases of a `switch` statement, and will usually have the same logic: first, you might have specialized `catch` blocks, each of which is designed to handle some limited set of possible errors; finally, you might (and usually will) have a general `catch` block that acts as the default, mopping up any errors that were not caught by any of the specialized `catch` blocks.

In fact, the *syntax* used by a `catch` block to specify what sorts of error it catches is the pattern syntax used by a case in a `switch` statement! Imagine that this is a `switch` statement, and that the tag is the error object. Then the matching of that error object to a particular `catch` block is performed just as if you had written `case` instead of

catch. Typically, when the Error is an enum, a specialized catch block will state at least the enum that it catches, and possibly also the case of that enum; it can have a binding, to capture the enum or its associated type; and it can have a where clause to limit the possibilities still further.

To illustrate, I'll start by defining a couple of errors:

```
enum MyFirstError : Error {  
    case firstMinorMistake  
    case firstMajorMistake  
    case firstFatalMistake  
}  
enum MySecondError : Error {  
    case secondMinorMistake(i:Int)  
    case secondMajorMistake(s:String)  
    case secondFatalMistake  
}
```

And here's a `do...catch` construct designed to demonstrate some of the different ways we can catch different errors in different catch blocks:

```
do {  
    // throw can happen here  
} catch MyFirstError.firstMinorMistake, MyFirstError.firstMajorMistake {  
    // catches MyFirstError.firstMinorMistake  
    // also catches MyFirstError.firstMajorMistake  
} catch let err as MyFirstError {  
    // catches other case(s) of MyFirstError  
} catch MySecondError.secondMinorMistake(let i) where i < 0 {  
    // catches e.g. MySecondError.secondMinorMistake(i:-3)  
} catch {  
    // catches everything else  
}
```

Now let's talk about how the error object makes its way into each of the catch blocks:

#### *Catch block with pattern*

In a catch block with an accompanying pattern, it is up to you to capture in the pattern any desired information about the error. If you want the error itself to travel as a variable into the catch block, you'll need a binding in the pattern.

#### *Catch block with “mop-up” binding*

A catch block whose pattern is *only* a binding catches *any* error under that name; `catch let mistake` is a “mop-up” catch block that catches any error as a variable called `mistake`.

#### *Bare catch block*

In a “mop-up” catch block with *no* accompanying pattern (that is, the bare word `catch` and no more), the error arrives into the block *automatically* as a variable called `error`.

Let's look again at the previous example, but this time we'll examine what arrives into each catch block:

```
do {  
    // throw can happen here  
} catch MyFirstError.firstMinorMistake, MyFirstError.firstMajorMistake {  
    // no error object  
    // but we know it's either MyFirstError.firstMinorMistake  
    // or MyFirstError.firstMajorMistake  
} catch let err as MyFirstError {  
    // MyFirstError.firstFatalMistake arrives as err  
} catch MySecondError.secondMinorMistake(let i) where i < 0 {  
    // only i arrives, but we know it's MySecondError.secondMinorMistake  
} catch {  
    // error object arrives as error  
}
```

So much for the `do...catch` construct. But there's something else that can happen to a thrown error; instead of being caught directly, it can percolate up the call stack, leaving the current function and arriving at the point where this function was called. In this situation, the error won't be caught here, at the point of throwing; it needs to be caught further up the call stack. This can happen in one of two ways:

#### *Throw without a corresponding catch*

A `do...catch` construct might lack a “mop-up” catch block. Then a throw inside the `do` block might *not* be caught here.

#### *Throw outside a do block*

A throw might occur outside of any immediate `do...catch` construct.

However, a thrown error *must* be caught *somehow*. We therefore need a way to say to the compiler: “Look, I understand that it looks like this throw is not happening in a context where it will be caught, but that's only because you're not looking far enough up the call stack. If you do look up far enough, you'll see that a throw at this point *is* eventually caught.” And there is a way to say that! Use the `throws` keyword in a function declaration.

If you mark a function with the `throws` keyword, then its *entire body* becomes a legal place for throwing. The syntax for declaring a `throws` function is that the keyword `throws` appears immediately after the parameter list (and before the arrow operator, if there is one):

```
enum NotLongEnough : Error {  
    case iSaidLongIMeantLong  
}  
func giveMeALongString(_ s:String) throws {  
    if s.count < 5 {
```

```

        throw NotLongEnough.iSaidLongIMeantLong
    }
    print("thanks for the string")
}

```

The addition of `throws` to a function declaration creates a distinct function type. The type of `giveMeALongString` is not `(String) -> ()`, but rather `(String) throws -> ()`. If a function receives as parameter a function that can throw, that parameter's type needs to be specified accordingly:

```

func receiveThrower(_ f:(String) throws -> ()) {
    // ...
}

```

That function can now be called with `giveMeALongString` as argument:

```

func callReceiveThrower() {
    receiveThrower(giveMeALongString)
}

```

An anonymous function, if necessary, can include the keyword `throws` in its in expression, in the same place where it would appear in a normal function declaration. But this is not necessary if, as is usually the case, the anonymous function's type is known by inference:

```

func receiveThrower(_ f:(String) throws -> ()) {
    // ...
}
func callReceiveThrower() {
    receiveThrower {
        s in // can say "s throws in", but not required
        if s.count < 5 {
            throw NotLongEnough.iSaidLongIMeantLong
        }
        print("thanks for the string")
    }
}

```

New in Swift 5.5, the getter of a computed property or a subscript can be marked `throws`, provided there is no setter (in other words, this must be a read-only computed property or subscript). You have to write `get` explicitly so that there is a place to put the `throws` keyword. The getter becomes effectively a `throws` function.

To illustrate, this is a `Dog` with a private `Optional` name that starts life as `nil`; the public interface is a `setName(_:)` method along with a `name` property that `throws` if the private name is still `nil`:

```

class Dog {
    private var _name : String?
    func setName(_ newName: String) {
        self._name = newName
    }
}

```

```

var name : String {
    get throws {
        enum UndefinedError : Error {
            case noName
        }
        guard let name = _name else {
            throw UndefinedError.noName
        }
        return name
    }
}

```

When a `throws` function does throw, it aborts prematurely. This means that if the function is supposed to return a value, it *doesn't* return that value. And that's fine; throwing is an alternate form of legal exit from the function, and the compiler understands that fact.

So now we know that `throws` functions exist. But there's more. Swift imposes some requirements on the *caller* of a `throws` function:

- The caller of a `throws` function must precede the function call with the keyword `try`. This keyword acknowledges, to the programmer and to the compiler, that this function can throw.
- The function call must be made in a place where throwing is legal! A function called with `try` can throw, so saying `try` is just like saying `throw`: you must say it either in the `do` block of a `do...catch` construct or in the body of a `throws` function.

Swift also provides two variants of `try` that you will often use as a shorthand:

`try!`

If you are very sure that a `throws` function will in fact *not* throw, then you can call it with the keyword `try!` instead of `try`. This relieves you of all further responsibility: you can say `try!` *anywhere*, without catching the possible throw.

But be warned: if you're wrong, and this function *does* throw when your program runs, your program can crash at that moment, because you have allowed an error to percolate, uncaught, all the way up to the top of the call stack.

`try?`

Like `try!`, you can use `try?` anywhere; but, like a `do...catch` construct, `try?` catches the throw if there is one, without crashing. The downside is that if there is a throw, *you don't receive any error information*, as you would with a `do...catch` construct. But `try?` does *report* that there was a throw, by returning `nil`.

`try?` is useful particularly in situations where you're calling a throws function that returns a value and all you care about is the value. If there's a throw, `try?` returns `nil`. If there's no throw, `try?` wraps the returned value in an `Optional`. Commonly, you'll unwrap that `Optional` safely in the same line with a conditional binding.

To illustrate, here's an artificial test method that can either throw or return a `String`:

```
func canThrowOrReturnString(shouldThrow:Bool) throws -> String {
    enum Whoops : Error {
        case oops
    }
    if shouldThrow {
        throw Whoops.oops
    }
    return "Howdy"
}
```

We can call that method with `try` inside a `do...catch` construct:

```
do {
    let s = try self.canThrowOrReturnString(shouldThrow: true)
    print(s)
} catch {
    print(error)
}
```

At the other extreme, we can call that method with `try!` anywhere, but if the method throws, we'll crash:

```
let s = try! self.canThrowOrReturnString(shouldThrow: false)
print(s)
```

In between, we can call our method with `try?` anywhere. If the method doesn't throw, we'll receive a `String` wrapped in an `Optional`; if it does throw, we won't crash and we'll receive `nil` (but no error information):

```
if let s = try? self.canThrowOrReturnString(shouldThrow: true) {
    print(s)
} else {
    print("failed")
}
```

Just as with an `Optional` chain, if a throws function returns no value, the return type from `try?` is `Void?` — and you can capture that and compare it against `nil` to learn whether there was an error. In this example, `canThrowButReturnsNoValue` throws but returns no value:

```
let ok : Void? = try? self.canThrowButReturnsNoValue()
```

Now, if `ok` is not `nil`, no error was thrown.



## Rethrows

A function that receives a throws function parameter, and that calls that function (with try), and that doesn't throw for any *other* reason, may itself be marked as rethrows instead of throws. The difference is that when a rethrows function is called, the caller can pass as argument a function that does *not* throw, and in that case the call doesn't have to be marked with try (and the calling function doesn't have to be marked with throws):

```
func receiveThrower(_ f:(String) throws -> ()) rethrows {
    try f("ok?")
}
func callReceiveThrower() { // no throws needed
    receiveThrower { s in // no try needed
        print("thanks for the string!")
    }
}
```

For a read-only computed property that throws, the rules are just the same; you have to say some form of try as you access the property. This is the Dog with the throwing name getter:

```
let d = Dog()
if let name = try? d.name {
    print("dog's name is", name)
} else {
    print("dog has no name yet")
}
```

An initializer can be a throws function. Such an initializer, too, must be called with some form of try. To illustrate, here's a different Dog:

```
class Dog {
    let name : String
    init(name:String) throws {
        enum Invalid : Error { case empty }
        if name.isEmpty {
            throw Invalid.empty
        }
        self.name = name
    }
}
let dog = try? Dog(name:"Fido")
```

As in that example, when such an initializer *does* throw, it may have failed to fulfill the initializer contract of initializing all stored properties. But the compiler doesn't care, because the initializer has failed. The situation is no different from when a failable initializer prematurely returns nil.

In designing an initializer, when should you prefer a failable initializer and when should you prefer a throws initializer? No hard and fast rule can be given; it depends on your overall design goals. In general, `init?` implies simple failure to create an instance, whereas `throws` implies that there is useful information to be gleaned by studying the error.

Even if your own code never uses the keyword `throw` explicitly, you're still very likely, in real life, to call Cocoa methods that are marked with `throws`. (For the details of how the error mechanism works in Objective-C and how this is bridged to the Swift `throws` mechanism, see the [Appendix](#).) Objective-C will be supplying an `NSError`; this class is bridged to Swift `Error`. Swift helps you cross the bridge by giving `Error` a `localizedDescription` property, allowing you to read `NSError`'s `localizedDescription`. Moreover, you can catch a specific `NSError` by its name. The name you'll use is the `NSError` domain, and optionally (with dot-notation) the Cocoa name of its code.

For example, `NSString initWithContentsOfFile:encoding:error:` appears to Swift as a throwing initializer:

```
init(contentsOfFile path: String, encoding enc: String.Encoding) throws
```

So let's say we call that initializer, and we want specifically to catch the error thrown when there is no such file. This `NSError`'s domain, according to Cocoa, is `"NSCocoa-ErrorDomain"`. Its code is 260, for which Cocoa provides the name `NSFileReadNoSuchFileError` (I found that out by looking in the *FoundationErrors.h* header file in Objective-C). The Swift Foundation overlay translates those into `CocoaError` and `.fileReadNoSuchFile` respectively, so we can catch the error like this:

```
do {
    let f = // path to some file, maybe
    let s = try String(contentsOfFile: f)
    // ... if successful, do something with s ...
} catch CocoaError.fileReadNoSuchFile {
    print("no such file")
} catch {
    print(error)
}
```

Objective-C sees a Swift error coherently as well. By default, it receives a Swift error as an `NSError` whose domain is the name of the Swift object type. If the Swift object type is an enum, the `NSError`'s code is the index number of its case; otherwise, the code is 1. When you want to provide Objective-C with a fuller complement of information, make your error type adopt one or both of these protocols:

### *LocalizedError*

Adopts `Error`, adding three optional properties: `errorDescription` (`NSError localizedDescription`), `failureReason` (`NSError localizedFailureReason`), and `recoverySuggestion` (`NSError localizedRecoverySuggestion`). Observe that these are `String?` properties; declaring them as simple `String` rather than `Optional` fails to communicate the information to Objective-C, and is a common mistake.

### *CustomNSError*

Adopts `Error`, adding three properties with default implementations: `errorDomain`, `errorCode`, and `errorUserInfo`, which Objective-C will see as the `NSError`'s domain, code, and userInfo.

## **Nested scopes**

When a local variable needs to exist only for a few lines of code, you might like to define an artificial scope — a custom nested scope, at the start of which you can introduce your local variable, and at the end of which that variable will be permitted to go out of scope, destroying its value automatically. Swift does not permit you to use bare curly braces to do this. Instead, use a bare `do` block without a `catch`.

Here's a rewrite of our earlier code ([Chapter 4](#)) for uniquing an array while keeping its order:

```
var arr = ["Manny", "Manny", "Moe", "Jack", "Jack", "Moe", "Manny"]
do {
    var temp = Set<String>()
    arr = arr.filter { temp.insert($0).inserted }
}
```

The only purpose of `temp` is to act as a “helper” for this one filter call. So we embed its declaration and the filter call in a bare `do` block; that way, `temp` is in a lower scope that doesn't clutter up our local namespace, and as soon as the filter call is over, we exit the block and `temp` is destroyed.

Another use of a bare `do` block is to implement the simplest form of early exit. The block gives you a scope to jump out of; now you can label the `do` block and `break` to that label:

```
out: do {
    // ...
    if somethingBadHappened {
        break out
    }
    // we won't get here if somethingBadHappened
}
```

## Defer statement

A defer statement applies to the scope in which it appears, such as a function body, a while block, an if construct, a do block, and so on. Wherever you say defer, curly braces surround it somehow; the defer block will be executed *when the path of execution leaves those curly braces*. Leaving the curly braces can involve reaching the last line of code within the curly braces, or any of the forms of early exit described earlier in this section.

To see one reason why this is useful, consider the following property:

`self.view.window?.isUserInteractionEnabled`

A Bool. When set to `false`, prevents all user touches from reaching any view within the window (which usually means any view of the whole app). When set to `true`, restores the ability of user touches to reach those views.

It can be valuable to turn off user touch interactions at the start of some slightly time-consuming operation and then turn them back on after that operation, especially when, during the operation, the interface or the app’s logic will be in some state where the user’s tapping a button, say, could cause things to go awry. It is not uncommon for a method to be constructed like this:

```
func doSomethingTimeConsuming() {
    self.view.window?.isUserInteractionEnabled = false
    // ... do stuff ...
    self.view.window?.isUserInteractionEnabled = true
}
```

All well and good — *if* we can guarantee that the only path of execution out of this function will be by way of that last line. But what if we need to return early from this function? Our code now looks like this:

```
func doSomethingTimeConsuming() {
    self.view.window?.isUserInteractionEnabled = false
    // ... do stuff ...
    if somethingHappened {
        return
    }
    // ... do more stuff ...
    self.view.window?.isUserInteractionEnabled = true
}
```

Oops! We’ve just made a terrible mistake. By providing an additional path out of our `doSomethingTimeConsuming` function, we’ve created the possibility that our code might never encounter the call to set `isUserInteractionEnabled` to `true`. We might leave our function by way of the return statement — and the user will then be left unable to interact with the interface.

Obviously, we need to add another `isUserInteractionEnabled = true` call inside the if construct, just before the return statement. But as we continue to develop our code, we must remember, if we add *further* ways out of this function, to add *yet another* `isUserInteractionEnabled = true` call for *each* of them. This is madness!

The defer statement solves the problem. It lets us specify *once* what should happen when we leave this scope, *no matter how*. Our code now looks like this:

```
func doSomethingTimeConsuming() {
    self.view.window?.isUserInteractionEnabled = false
    defer {
        self.view.window?.isUserInteractionEnabled = true
    }
    // ... do stuff ...
    if somethingHappened {
        return
    }
    // ... do more stuff ...
}
```

The `isUserInteractionEnabled = true` call in the defer block will be executed, not where it appears, but before the return statement, or before the last line of the method — whichever path of execution ends up leaving the function. The defer statement says: “Eventually, and as late as possible, be sure to execute this code.” We have *ensured* the necessary balance between turning off user interactions and turning them back on again. Most uses of the defer statement will probably come under this same rubric: you’ll use it to balance a command or recover from a disturbed state.

Observe that in the preceding code, I placed the defer statement very early in its surrounding scope. This placement is important because a defer statement is itself a command. If a defer statement is not actually *encountered* by the path of execution before we exit from the surrounding scope, *its block won’t be executed*. For this reason, always place your defer statement as close to the start of its surrounding block as you can, to ensure that it will in fact be encountered.

When a defer statement changes a value that is returned by a return statement, the return happens first and the defer statement happens second. In other words, defer effectively lets you return a value *and then change it*. This example comes from Apple’s own code (in the documentation, demonstrating how to write a struct that can adopt the Sequence protocol):

```
struct Countdown: Sequence, IteratorProtocol {
    var count: Int
    mutating func next() -> Int? {
        if count == 0 {
            return nil
        } else {
            defer { count -= 1 }
        }
    }
}
```

```

        return count
    }
}

```

That code returns the current value of `count` and *then* decrements `count`, ready for the next call to the `next` method. Without `defer`, we'd decrement `count` and then return the decremented value, which is not what's wanted.

If the current scope has multiple `defer` blocks pending, they will be called in the reverse of the order in which they were originally encountered. In effect, there is a *defer stack*; each successive `defer` statement, as it is encountered, pushes its code onto the top of the stack, and exiting the scope in which a `defer` statement appeared pops that code and executes it.

## Aborting the whole program

Aborting the whole program is an extreme form of flow control; the program stops dead in its tracks. In effect, you have deliberately crashed your own program. This is an unusual thing to do, but it can be useful as a way of raising a very red flag: you don't really *want* to abort, so if you *do* abort, things must be so bad that you've no choice.

One way to abort is by calling the global function `fatalError`. It takes a `String` parameter permitting you to provide a message to appear in the console. I've already given this example:

```

required init?(coder: NSCoder) {
    fatalError("init(coder:) has not been implemented")
}

```

That code says, in effect, that execution should *never* reach this point. We have declared `init(coder:)` just because it is required, and we need to satisfy the compiler; but we have no real implementation of `init(coder:)`, and we do not expect to be initialized this way. If we *are* initialized this way, something has gone very wrong, and we *want* to crash, because our program has a serious bug.

Like throwing an error, a `fatalError` call aborts, and the compiler understands that fact. An initializer can call `fatalError` without having initialized stored properties. Similarly, a function that returns a value does not have to return any value if a `fatalError` call is encountered.

You can abort conditionally by calling the `assert` function. Its first parameter is a condition — something that evaluates as a `Bool`. If the condition is `false`, we will abort; the second parameter is a `String` message to appear in the console if we *do* abort. The idea here is that you are making a bet (an *assertion*) that the condition is true — a bet that you feel so strongly about that if the condition is `false`, there's a

serious bug in your program and you want to crash so you can learn of this bug and fix it.

By default, `assert` works only when you're developing your program. When your program is to be finalized and made public, you throw a build switch that tells the compiler (among other things) that `assert` should be ignored. In effect, the conditions in your `assert` calls are then disregarded; they are all seen as true. This means that you can safely leave `assert` calls in your code. By the time your program ships, of course, none of your assertions should be failing; any bugs that caused them to fail should already have been ironed out.

The disabling of assertions in shipping code is performed in an interesting way. The condition parameter is given an extra layer of indirection by declaring it as an `@autoclosure` function. This means that, even though the parameter is *not* in fact a function, the compiler will wrap it in a function; the runtime won't call that function unless it has to. In shipping code, the runtime will *not* call that function. This mechanism averts expensive and unnecessary evaluation: an `assert` condition test may involve side effects, but the test won't even be performed when assertions are turned off in your shipping program.

In addition, Swift provides the `assertionFailure` function. It's like an `assert` that always fails — and, like an `assert`, it *doesn't* fail in your shipping program where assertions are turned off. It's a convenient synonym for `assert(false)`, as a way of assuring yourself that your code never goes where it's never supposed to go.

Finally, `precondition` and `preconditionFailure` are similar to `assert` and `assertionFailure`, except that they *do* fail even in a shipping program.

## Guard

When your code needs to decide whether to exit early, Swift provides a special syntax — the guard construct. In effect, a guard construct is an if construct where you exit early if the condition fails. Its form is shown in [Example 5-6](#).

*Example 5-6. The Swift guard construct*

```
guard condition else {  
    statements  
    exit  
}
```

A guard construct consists solely of a condition and an else block. The else block *must* jump out of the current scope, by any of the means that Swift provides, such as `return`, `break`, `continue`, `throw`, or `fatalError` — anything that guarantees to the compiler that, in case of failure of the condition, execution absolutely will not proceed within the block that contains the guard construct.

Because the guard construct guarantees an exit on failure of the condition, the compiler knows that the condition has succeeded after the guard construct if we do *not* exit. An elegant consequence is that a conditional binding in the condition is in scope *after* the guard construct, without introducing a further nested scope:

```
guard let s = optionalString else {return}
// s is now a String (not an Optional)
```

A guard construct’s conditional binding can’t use, on the left side of the equal sign, a name already declared in the same scope. This is illegal:

```
let s = // ... some Optional
guard let s = s else {return} // compile error
```

The reason is that `guard let`, unlike `if let` and `while let`, doesn’t declare the bound variable for a *nested* scope; it declares it for *this* scope. We can’t declare `s` here because `s` has already been declared in the same scope.

In my own code, it’s not uncommon to have a series of guard constructs, one after another. This may seem a rather clunky and imperative mode of expression, but I’m fond of it nevertheless. It’s a nice alternative to a single elaborate `if` construct, or to the “pyramid of doom” that I discussed earlier; and it looks like exactly what it is, a sequence of gates through which the code must pass in order to proceed further. Here’s an actual example from my real-life code:

```
@objc func tapField(_ g: Any) {
    // g must be a gesture recognizer
    guard let g = g as? UIGestureRecognizer else {return}
    // and the gesture recognizer must have a view
    guard g.view != nil else {return}
    // okay, now we can proceed...
}
```

It’s often possible to combine multiple guard statement conditions into a single condition list:

```
@objc func tapField(_ g: Any) {
    // g must be a gesture recognizer
    // and the gesture recognizer must have a view
    guard let g = g as? UIGestureRecognizer, g.view != nil
        else {return}
    // okay, now we can proceed...
}
```

A guard construct will also come in handy in conjunction with `try?`. Let’s presume we can’t proceed unless `String(contentsOfFile:)` succeeds. Then we can call it like this:

```
let f = // path to some file, maybe
guard let s = try? String(contentsOfFile: f) else {return}
// s is now a String (not an Optional)
```



There is also a `guard case` construct, forming the logical inverse of `if case`. To illustrate, we'll use our `MyError` enum once again:

```
guard case let .number(n) = err else {return}
// n is now the extracted number
```

`guard case` helps to solve an interesting problem. Suppose we have a function whose returned value we want to check in a guard statement:

```
guard howMany() > 10 else {return}
```

All well and good; but suppose also that in the *next* line we want to *use* the value returned from that function. We don't want to call the function *again*; it might be time-consuming and it might have side effects. We want to *capture* the result of calling the function and pass that captured result on into the subsequent code. But we can't do that with `guard let`, because that requires an `Optional`, and our function `howMany` doesn't return an `Optional`. `guard case` to the rescue:

```
guard case let output = howMany(), output > 10 else {return}
// now output is in scope
```

## Privacy

Privacy (also known as *access control*) refers to the explicit modification of the normal scope rules. I gave an example in [Chapter 1](#):

```
class Dog {
    var name = ""
    private var whatADogSays = "woof"
    func bark() {
        print(self.whatADogSays)
    }
}
```

The intention here is to limit how other objects can see the `Dog` property `whatADogSays`. It is a private property, intended primarily for the `Dog` class's own internal use: a `Dog` can speak of `self.whatADogSays`, but other objects should not be aware that it even exists.

Swift has five levels of privacy:

### `internal`

The default rule is that declarations are *internal*, meaning that they are globally visible *within the containing module*. That is why Swift files within the same module can see one another's top-level contents automatically, with no effort on your part. (That's different from C and Objective-C, where files can't see each

other at all unless you explicitly show them to one another through `include` or `import` statements.)

`fileprivate` (*narrower than internal*)

A thing declared `fileprivate` is visible *only within its containing file*. Two object types declared in the same file can see one another's members declared `fileprivate`, but code in other files cannot see those members.

`private` (*even narrower than fileprivate*)

A thing declared `private` is visible *only within its containing curly braces*. In effect, the visibility of an object type's member declared `private` is limited to code within this type declaration. (A `private` declaration at the top level of a file is equivalent to `fileprivate`.)

`public` (*wider than internal*)

A thing declared `public` is visible *even outside its containing module*. Another module must first import this module before it can see anything at all. But even when another module *has* imported this module, it *still* won't be able to see anything in this module that hasn't been explicitly declared `public`. If you don't write any modules, you might never need to declare anything `public`. If you do write a module, you *must* declare *something* `public`, or your module is useless.

`open` (*even wider than public*)

If a class is declared `open`, code in another module can subclass it; it can't do that if the class is declared merely `public`. If an open class member is declared `open`, code in another module that subclasses this class can override this member; it can't do that if the member is declared merely `public`.

## Private and Fileprivate

Declaring something `private` restricts its visibility. In this way, you specify by inversion what the public API of this object is. Here's an example from my own code:

```
class CancelableTimer: NSObject {
    private var q = DispatchQueue(label: "timer")
    private var timer : DispatchSourceTimer!
    private var firsttime = true
    private var once : Bool
    private var handler : () -> ()
    init(once:Bool, handler:@escaping () -> ()) {
        // ...
    }
    func start(withInterval interval:Double) {
        // ...
    }
}
```

```

    func cancel() {
        // ...
    }
}

```

The initializer `init(once:handler:)` and the `start(withInterval:)` and `cancel` methods, which are *not* marked `private`, are this class's public API. They say, "Please feel free to call me!" The properties, however, are all `private`; no other code can see them, either to get them or to set them. They are purely for the internal use of the methods of this class. They maintain state, but it is not a state that any other code needs to know about.

Privacy is not magically violated by the existence of a special object relationship. Even a subclass cannot see its superclass's private members. (This comes as a surprise to those coming from a language with a protected privacy level.) You can work around this by declaring the class and its subclass in the same file and declaring those members `fileprivate` instead of `private`.

A nested type can see the private members of the type in which it is nested. This makes sense, because the outer type is a surrounding scope; the nested type sees what everything else inside this type sees.

An extension can see the private members of the type it extends, provided the type and the extension are in the same file:

```

class Dog {
    private var whatADogSays = "woof"
}
extension Dog {
    func speak() {
        print(self.whatADogSays) // ok
    }
}

```

In effect, an extension sees its type's `private` as meaning `fileprivate`. This lets you break up a type into extensions without being forced to raise the type's private members to `fileprivate` just so the extensions can see them.

It may be that on some occasions you will want to draw a distinction between the privacy of a variable regarding setting and its privacy regarding getting. To draw this distinction, place the word `set` in parentheses after its own privacy declaration. `private(set) var myVar` means that the *setting* of this variable is restricted, but says nothing about the *getting* of this variable, which is left at the default. Similarly, you can say `public private(set) var myVar` to make getting this variable public, while setting this variable is kept private.

The existence of Objective-C adds complications. Things marked `@objc` can be marked `private` without harm; Objective-C can still see them. (That includes things

marked `@IBAction` and `@IBOutlet`, which imply `@objc`.) But your implementation of a member defined by an Objective-C protocol cannot be marked `private` without hiding it from Objective-C. In particular, optional methods defined by a Cocoa protocol must be at least `internal` (the default), or Cocoa won't be able to find them and won't call them. You are forced to expose these methods to other files in your module, as if they were part of this class's public API, even though you would probably prefer not to.

## Public and Open

If you write a module, you'll need to specify at least some object type declaration as `public`; otherwise, code that imports your module won't be able to see that type. Other declarations that are not declared `public` are `internal`, meaning that they are private to the module. Judicious use of `public` declarations configures the public API of your module.

The members of a public object type are not, themselves, automatically public. If you want a method to be public, you have to declare it `public`. This is an excellent default behavior, because it means that these members are not shared outside the module unless you want them to be. (As Apple puts it, you must “opt in to publishing” object members.)

In my *Zotz* app, which is a card game, the files declaring object types for creating and portraying cards and for combining them into a deck are bundled into a framework called *ZotzDeck*. A framework is a module. The idea is for these files to be able to see one another freely while limiting access from the rest of my app. Many of the *ZotzDeck* types, such as *Card* and *Deck*, are declared `public`. Many utility object types, however, are not; the classes within the *ZotzDeck* module can see and use them, but code outside the module doesn't need to be aware of them. Moreover, the *Card* class is declared `public` but its initializer is not, because the public way to get cards is by initializing a *Deck*; the initializer for *Deck* is declared `public`, so you can do that.



If the only initializer for a public type is implicit, code in another module can't see it and cannot create an instance of this type. If you want other code to be able to create an instance of this type, you must declare the initializer explicitly and make it `public`.

The open access level draws a further distinction. It is applicable only to classes and to members of open classes. A public class can't be subclassed in another module that can see this class; an open class can. A public member of an open class that has been subclassed in another module can't be overridden in that subclass; an open member can.

## Privacy Rules

There is an extensive set of rules for ensuring that the privacy level of related things is coherent. Here are some of them:

- A variable can't be public if its type is private, because other code wouldn't be able to use such a variable.
- A subclass can't be public unless the superclass is public.
- A subclass can change an overridden member's access level, but it cannot even *see* its superclass's private members unless they are declared in the same file together.

And so on. I could proceed to list all the rules, but I won't. There is no need for me to enunciate them formally. They are spelled out in great detail in the Swift manual, which you can consult if you need to. In general, you probably won't need to; the privacy rules make intuitive sense, and you can rely on the compiler to help you with useful error messages if you violate one.

## Introspection

Swift provides limited ability to *introspect* an object, letting an object display the names and values of its properties. This feature is intended for debugging, not for use in your program's logic. For example, you can use it to modify the way your object is displayed in the Xcode Debug pane.

To introspect an object, use it as the `reflecting:` parameter when you instantiate a `Mirror`. The `Mirror`'s children will then be name-value tuples describing the original object's properties. Here's a `Dog` class with a `description` property that takes advantage of introspection. Instead of hard-coding a list of the class's instance properties, we introspect the instance to obtain the names and values of the properties. This means that we can later add more properties without having to modify our `description` implementation:

```
struct Dog : CustomStringConvertible {
    var name = "Fido"
    var license = 1
    var description : String {
        var desc = "Dog ("
        let mirror = Mirror(reflecting:self)
        for (k,v) in mirror.children {
            desc.append("\(k!): \(v), ")
        }
        return desc.dropLast(2) + ")"
    }
}
```

If we now instantiate `Dog` and print that instance, this is what we see in the console:

```
Dog (name: Fido, license: 1)
```

The main use of Mirror is to generate the console output for the Swift dump function (or the po command when debugging). By adopting the CustomReflectable protocol, we can take charge of what a Mirror's children are. To do so, we implement the customMirror property to return our own custom Mirror object whose children property we have configured as a collection of name-value tuples.

In this (silly) example, we implement customMirror to supply altered names for our properties:

```
struct Dog : CustomReflectable {
    var name = "Fido"
    var license = 1
    var customMirror: Mirror {
        let children : [Mirror.Child] = [
            ("ineffable name", self.name),
            ("license to kill", self.license)
        ]
        let m = Mirror(self, children:children)
        return m
    }
}
```

The outcome is that when our code says dump(Dog()), our custom property names are displayed:

```
* Dog
- ineffable name : "Fido"
- license to kill : 1
```

## Operators

Swift operators such as + and > are not magically baked into the language. They are, in fact, functions; they are explicitly declared and implemented just like any other function. That is why, as I pointed out in [Chapter 4](#), the term + can be passed as the second parameter in a reduce call; reduce expects a function taking two parameters and returning a value whose type matches that of the first parameter, and + is in fact the name of such a function. It also explains how Swift operators can be overloaded for different types of operand. You can use + with numbers, strings, or arrays — with a different meaning in each case — because Swift functions can be overloaded; there are multiple declarations of the + function, and Swift is able to determine from the parameter types *which* + function you are calling.

These facts are not merely an intriguing behind-the-scenes implementation detail. They have practical implications for you and your code. You are free to overload existing operators to apply to *your* object types. You can even invent *new* operators! In this section, we'll do both.

First we'll talk about how operators are declared. Clearly there is some sort of syntactical hanky-panky (a technical computer science term), because you don't *call* an operator function in the same way as a normal function. You don't say `+(1,2)`; you say `1+2`. Even so, 1 and 2 in that second expression *are* the parameters to a `+` function call. How does Swift know that the `+` function uses this special syntax?

To see the answer, look in the Swift header:

```
infix operator + : AdditionPrecedence
```

That is an operator declaration. An operator declaration announces that this symbol *is* an operator, and specifies how many parameters it has and what the usage syntax will be in relation to those parameters. The really important part is the stuff before the colon: the keyword `operator`, preceded by an operator *type* — here, `infix` — and followed by the name of the operator. The types are:

`infix`

This operator takes two parameters and appears between them.

`prefix`

This operator takes one parameter and appears before it.

`postfix`

This operator takes one parameter and appears after it.

The term after the colon in an operator declaration is the name of a precedence group. Precedence groups dictate the order of operations when an expression contains multiple operators. I'm not going to go into the details of how precedence groups are defined. The Swift header declares about a dozen precedence groups, and you can easily see how those declarations work. You will probably have no need to declare a new precedence group; you'll just look for an operator similar to yours and copy its precedence group (or omit the colon and the precedence group from your declaration).

An operator is also a function, so you also need a function declaration stating the type of the parameters and the result type of the function. Again, the Swift header shows us an example:

```
func +(lhs: Int, rhs: Int) -> Int
```

That is one of many declarations for the `+` function in the Swift header. In particular, it is the declaration for when the parameters are both `Int`. In that situation, the result is itself an `Int`. (The local parameter names `lhs` and `rhs`, which don't affect the special calling syntax, presumably stand for "left-hand side" and "right-hand side.")

An operator declaration must appear at the top level of a file. The corresponding function declaration may appear either at the top level of a file or at the top level of a type declaration; in the latter case, it must be marked `static`. If the operator is a

prefix or postfix operator, the function declaration must start with the word prefix or postfix; the default is infix and can be omitted.

We now know enough to override an operator to work with an object type of our own! As a simple example, imagine a Vial full of bacteria:

```
struct Vial {
    var numberOfBacteria : Int
    init(_ n:Int) {
        self.numberOfBacteria = n
    }
}
```

When two Vials are combined, you get a Vial with all the bacteria from both of them. So the way to add two Vials is to add their bacteria:

```
extension Vial {
    static func +(lhs:Vial, rhs:Vial) -> Vial {
        let total = lhs.numberOfBacteria + rhs.numberOfBacteria
        return Vial(total)
    }
}
```

And here's code to test our new + operator override:

```
let v1 = Vial(500_000)
let v2 = Vial(400_000)
let v3 = v1 + v2
print(v3.numberOfBacteria) // 900000
```

In the case of a compound assignment operator, the first parameter is the thing being assigned to. Therefore, to implement such an operator, the first parameter must be declared inout. Let's do that for our Vial class:

```
extension Vial {
    static func +=(lhs:inout Vial, rhs:Vial) {
        let total = lhs.numberOfBacteria + rhs.numberOfBacteria
        lhs.numberOfBacteria = total
    }
}
```

Here's code to test our += override:

```
var v1 = Vial(500_000)
let v2 = Vial(400_000)
v1 += v2
print(v1.numberOfBacteria) // 900000
```

Next, let's invent a completely new operator. As an example, I'll inject an operator into Int that raises one number to the power of another. As my operator symbol, I'll use ^^ (I'd like to use ^ but it's already in use for something else). For simplicity, I have omitted error-checking for edge cases (such as exponents less than 1):



```

infix operator ^^
extension Int {
    static func ^^ (lhs: Int, rhs: Int) -> Int {
        var result = lhs
        for _ in 1..

```

That's all it takes! Here's some code to test it:

```

print(2^^2) // 4
print(2^^3) // 8
print(3^^3) // 27

```

Here's another example. I've already illustrated the use of Range's `reversed` method to allow iteration from a higher value to a lower one. That works, but I find the notation unpleasant. There's an asymmetry with how you iterate up; the endpoints are in the wrong order, and you have to remember to surround a literal range with parentheses:

```

let r1 = 1..<10
let r2 = (1..<10).reversed()

```

Let's define a custom operator that calls `reversed()` for us:

```

infix operator >>> : RangeFormationPrecedence
func >>><Bound>(maximum: Bound, minimum: Bound)
    -> ReversedCollection<Range<Bound>>
    where Bound : Strideable {
    return (minimum..

```

Now our expressions can be more symmetrical and compact:

```

let r1 = 1..<10
let r2 = 10>>>1

```

The Swift manual lists the special characters that can be used as part of a custom operator name:

```

/ = - + ! * % < > & | ^ ? ~

```

An operator name can also contain many other symbol characters (that is, characters that can't be mistaken for some sort of alphanumeric) that are harder to type; see the manual for a formal list.

## Memory Management

Swift memory management is handled automatically, and you will usually be unaware of it. Objects come into existence when they are instantiated and go out of

existence as soon as they are no longer needed. Nevertheless, there are some memory management issues of which you must be conscious.

## Memory Management of Reference Types

Memory management of reference type objects (“[Value Types and Reference Types](#)” on page 157) is quite tricky under the hood; I’ll devote [Chapter 13](#) to a discussion of the underlying mechanism. Swift normally does all the work for you, but trouble can arise when two class instances have references to one another. When that’s the case, you can have a *retain cycle* which will result in a *memory leak*, meaning that the two instances *never* go out of existence. Some computer languages solve this sort of problem with a periodic “garbage collection” phase that detects retain cycles and cleans them up, but Swift doesn’t do that; you have to fend off retain cycles manually.

One way to test for and observe a memory leak is to implement a class’s `deinit`. This method is called when the instance goes out of existence. If the instance never goes out of existence, `deinit` is never called. That’s a bad sign, if you were expecting that the instance *should* go out of existence.

Here’s an example. First, I’ll make two class instances and watch them go out of existence:

```
func testRetainCycle() {
    class Dog {
        deinit {
            print("farewell from Dog")
        }
    }
    class Cat {
        deinit {
            print("farewell from Cat")
        }
    }
    let d = Dog()
    let c = Cat()
}
testRetainCycle() // farewell from Cat, farewell from Dog
```

When we run that code, both “farewell” messages appear in the console. We created a Dog instance and a Cat instance, but the only references to them are automatic (local) variables inside the `testRetainCycle` function. When execution of that function’s body comes to an end, all automatic variables are destroyed; that is what it means to be an automatic variable. There are no other references to our Dog and Cat instances that might make them persist, and so they are destroyed in good order.

Now I’ll change that code by giving the Dog and Cat objects references to each other:

```

func testRetainCycle() {
    class Dog {
        var cat : Cat?
        deinit {
            print("farewell from Dog")
        }
    }
    class Cat {
        var dog : Dog?
        deinit {
            print("farewell from Cat")
        }
    }
    let d = Dog()
    let c = Cat()
    d.cat = c // create a...
    c.dog = d // ...retain cycle
}

testRetainCycle() // nothing in console

```

When we run that code, *neither* “farewell” message appears in the console. The Dog and Cat objects have references to one another. Those are *strong* references (also called *persisting* references). A strong reference sees to it that as long as our Dog has a reference to a particular Cat, that Cat will not be destroyed, and vice versa. That’s a good thing, and is a fundamental principle of sensible memory management. The bad thing is that the Dog and the Cat have strong references *to one another*. That’s a retain cycle! Neither the Dog instance nor the Cat instance can be destroyed, because neither of them can “go first” — it’s like Alphonse and Gaston who can never get through the door because each requires the other to precede him. The Dog can’t be destroyed first because the Cat has a strong reference to it, and the Cat can’t be destroyed first because the Dog has a strong reference to it.

These objects are now *leaking*. Our code is over; both *d* and *c* are gone. There are *no* further references to either of these objects; neither object can ever be referred to again. No code can mention them; no code can reach them. But they live on, floating, useless, and taking up memory.



The term “retain cycle” is based on the `retain` command, which is used in Objective-C to form a strong reference. You can’t say `retain` in Swift, so Apple often refers to this kind of cycle as a *strong reference cycle*. But a strong reference cycle *is* a retain cycle — the compiler is in fact inserting `retain` commands under the hood — and I’ll continue calling it a retain cycle.

## Weak references

One solution to a retain cycle is to mark the problematic reference as *weak*. This means that the reference is *not* a strong reference. It is a *weak reference*. The object referred to can now go out of existence even while the referrer continues to exist. Of

course, this might present a danger, because now the object referred to may be destroyed behind the referrer’s back. But Swift has a solution for that, too: only an Optional reference can be marked as weak. That way, if the object referred to *is* destroyed behind the referrer’s back, the referrer will see something coherent, namely `nil`. Also, the reference must be a `var` reference, precisely because it can change spontaneously to `nil`.

This code breaks the retain cycle and prevents the memory leak:

```
func testRetainCycle() {
    class Dog {
        weak var cat : Cat?
        deinit {
            print("farewell from Dog")
        }
    }
    class Cat {
        weak var dog : Dog?
        deinit {
            print("farewell from Cat")
        }
    }
    let d = Dog()
    let c = Cat()
    d.cat = c
    c.dog = d
}
testRetainCycle() // farewell from Cat, farewell from Dog
```

I’ve gone overboard in that code. To break the retain cycle, there’s no need to make *both* Dog’s cat and Cat’s dog weak references; making just *one* of the two a weak reference is sufficient to break the cycle. That, in fact, is the usual solution when a retain cycle threatens. One of the pair will typically be more of an “owner” than the other; the one that is *not* the “owner” will have a weak reference to its “owner.”

Value types are not subject to the same memory management issues as reference types, but a value type can still be *involved* in a retain cycle with a class instance. In my retain cycle example, if Dog is a class and Cat is a struct, we still get a retain cycle. The solution is the same: make Cat’s dog a weak reference. (You can’t make Dog’s cat a weak reference if Cat is a struct; only a reference to a class type can be declared weak.)

Do *not* use weak references unless you have to! Memory management is not to be toyed with lightly. Nevertheless, there are real-life situations in which weak references are the right thing to do, even when no retain cycle appears to threaten. The delegation pattern ([Chapter 12](#)) is a typical case in point; an object typically has no business owning (retaining) its delegate. And a view controller `@IBOutlet` property is usually weak, because it refers to a subview already owned by its own `superview`.

## Unowned references

There's another Swift solution for retain cycles. Instead of marking a reference as weak, you can mark it as unowned. This approach is useful in special cases where one object absolutely cannot exist without a reference to another, but where this reference need not be a strong reference.

Let's pretend that a Boy may or may not have a Dog, but every Dog must have a Boy — and so I'll give Dog an `init(boy:)` initializer. The Dog needs a reference to its Boy, and the Boy needs a reference to his Dog if he has one; that's potentially a retain cycle:

```
func testUnowned() {
    class Boy {
        var dog : Dog?
        deinit {
            print("farewell from Boy")
        }
    }
    class Dog {
        let boy : Boy
        init(boy:Boy) { self.boy = boy }
        deinit {
            print("farewell from Dog")
        }
    }
    let b = Boy()
    let d = Dog(boy: b)
    b.dog = d
}
testUnowned() // nothing in console
```

We can solve this by declaring Dog's boy property unowned:

```
func testUnowned() {
    class Boy {
        var dog : Dog?
        deinit {
            print("farewell from Boy")
        }
    }
    class Dog {
        unowned let boy : Boy // *
        init(boy:Boy) { self.boy = boy }
        deinit {
            print("farewell from Dog")
        }
    }
    let b = Boy()
```

```

        let d = Dog(boy: b)
        b.dog = d
    }
    testUnowned() // farewell from Boy, farewell from Dog

```

An advantage of an unowned reference is that it doesn't have to be an Optional and it can be a constant (let). But an unowned reference is also *genuinely* dangerous, because the object referred to can go out of existence behind the referrer's back, and an attempt to use that reference will cause a crash, as I can demonstrate by this rather forced code:

```

var b = Optional(Boy())
let d = Dog(boy: b!)
b = nil // destroy the Boy behind the Dog's back
print(d.boy) // crash

```

Clearly you should use unowned only if you are absolutely certain that the object referred to will outlive the referrer.

### Stored anonymous functions

A particularly insidious kind of retain cycle arises when an instance property holds a function referring to the instance:

```

class FunctionHolder {
    var function : (() -> ())?
    deinit {
        print("farewell from FunctionHolder")
    }
}
func testFunctionHolder() {
    let fh = FunctionHolder()
    fh.function = {
        print(fh)
    }
}
testFunctionHolder() // nothing in console

```

Oops! I've created a retain cycle, by referring, inside the anonymous function, to the object that is holding a reference to it. Because functions are closures, the FunctionHolder instance fh, declared outside the anonymous function, is captured by the anonymous function as a strong reference when the anonymous function says print(fh). But the anonymous function has also been assigned to the function property of the FunctionHolder instance fh, and that's a strong reference too. So that's a retain cycle: the FunctionHolder persistently refers to the function, which persistently refers to the FunctionHolder.

In this situation, I *cannot* break the retain cycle by declaring the function property as weak or unowned. Only a reference to a class type can be declared weak or unowned,

and a function is not a class. I must declare the captured value `fh` *inside the anonymous function* as `weak` or `unowned` instead.

To do so, use the anonymous function's capture list ("[Capture Lists](#)" on page 60). In the square brackets, put a comma-separated list of any problematic references that would be captured from the surrounding environment, each preceded by `weak` or `unowned`:

```
class FunctionHolder {
    var function : (() -> ())?
    deinit {
        print("farewell from FunctionHolder")
    }
}
func testFunctionHolder() {
    let fh = FunctionHolder()
    fh.function = {
        [weak fh] in // *
        print(fh)
    }
}
testFunctionHolder() // farewell from FunctionHolder
```

That syntax solves the problem. But marking a reference as `weak` in a capture list has a side effect: the reference passes into the anonymous function as an `Optional`. This is good, because it means that if the object referred to goes out of existence behind our back, the value of the `Optional` is `nil`. But of course you must also adjust your code accordingly, unwrapping the `Optional` as needed in order to use it. The usual technique is to perform the *weak-strong dance*: you unwrap the `Optional` once, right at the start of the function, in a conditional binding:

```
fh.function = {
    [weak fh] in // weak
    guard let fh = fh else { return }
    print(fh)    // strong (and not Optional)
}
```

The conditional binding `let fh = fh` elegantly accomplishes three goals:

- It unwraps the `Optional` version of `fh` that arrived into the anonymous function.
- It declares another `fh` that is a normal (strong) reference. So if the unwrapping succeeds, this new `fh` will persist for the rest of this scope.
- It causes the second `fh` to overshadow the first `fh` (because they have the same name). So it is impossible after the `guard` statement to refer accidentally to the weak `Optional` `fh`.

Now, it happens that, in this particular example, there is no way the `FunctionHolder` instance `fh` can go out of existence while the anonymous function lives on. There are

no other references to the anonymous function; it persists only as a property of `fh`. Therefore I can avoid some behind-the-scenes bookkeeping overhead, as well as the weak–strong dance, by declaring `fh` as `unowned` in my capture list instead of `weak`. In real life, my own most frequent use of `unowned` is precisely in this context. Very often, the reference marked as `unowned` in the capture list will be `self`.



Recall, from [Chapter 2](#), that the compiler forces you to say `self` explicitly when you refer to a property or method of `self` within the function body of an escaping closure. Now we can see why: you are threatening to form a retain cycle involving `self`, and the compiler wants to make sure you realize that.

Above all, don't panic. Beginners may be tempted to backstop *all* their anonymous functions with `[weak self]`. That's wrong. Only a *stored* function can raise even the possibility of a retain cycle. Merely passing a function does *not* introduce such a possibility, especially if the function being passed will be called immediately. And even if a function *is* stored, if it is stored *elsewhere*, it might not imply a retain cycle. Always confirm that you actually *have* a retain cycle before concerning yourself with how to prevent it.

Consider the standard expression of an animation, which I discussed in [Chapter 2](#):

```
UIView.animate(withDuration:0.4) {  
    self.myButton3.frame.origin.y += 20  
} completion: { _ in  
    self.someMethod()  
}
```

No one should be using `[weak self]` in these anonymous functions. There's no retain cycle, because the anonymous functions are not being retained by `self` (the view controller). Moreover, the view controller is *not* going to go out of existence while the animation is proceeding. In fact, capturing the view controller as `self` in the body of the anonymous function actually *prevents* it from going out of existence while the animation is proceeding — and that's *good*! Extending the lifetime of an object, such as `self`, long enough for an anonymous function to be called at some future time, is a *useful* thing to do. (In fact, it's so useful that Swift provides a way to do it *without* explicitly capturing the object in the anonymous function: there's a global function, `withExtendedLifetime`, for precisely that purpose.)

## Memory management of protocol-typed references

Only a reference to an instance of a class type can be declared `weak` or `unowned`. A reference to an instance of a struct or enum type cannot be so declared, because its memory management doesn't work the same way (and is not subject to retain cycles). A reference that is declared as a protocol type, therefore, has a problem. A reference typed as a protocol that might be adopted by a struct or an enum cannot be declared `weak` or `unowned`. You can only declare a protocol-typed reference `weak` or `unowned` if



the compiler knows that only a class can adopt it. You can assure the compiler of that by making the protocol a class protocol.

In this code, `SecondViewControllerDelegate` is a protocol that I've declared. This code won't compile unless `SecondViewControllerDelegate` is declared as a class protocol:

```
class SecondViewController : UIViewController {
    weak var delegate : SecondViewControllerDelegate?
    // ...
}
```

Here's the actual declaration of `SecondViewControllerDelegate`; it *is* declared as a class protocol, and that's why the preceding code is legal:

```
protocol SecondViewControllerDelegate : AnyObject {
    func accept(data:Any)
}
```

A protocol declared in Objective-C is implicitly marked as `@objc` and is a class protocol. This declaration from my real-life code is legal:

```
weak var delegate : WKScriptMessageHandler?
```

`WKScriptMessageHandler` is a protocol declared by Cocoa (in particular, by the Web Kit framework), so only a class can adopt `WKScriptMessageHandler`, and the compiler is satisfied that the `delegate` variable will be an instance of a class — and the reference can be treated as weak.

## Exclusive Access to Value Types

Even value types can have memory management issues. In particular, a struct and its members might be directly accessed simultaneously, which could lead to unpredictable results. Fortunately, the compiler will usually stop you before such an issue can arise.

To illustrate, imagine that we have a `Person` struct with a settable `firstName` string property. Now let's write a function that takes both a `Person` and a string as `inout` parameters:

```
func change(_ p:inout Person, _ s:inout String) {}
```

So far so good; but now imagine calling that function with both a `Person` and that same `Person`'s `firstName` as the parameters:

```
var p = Person(firstName: "Matt")
change(&p, &p.firstName) // compile error
```

The compiler will stop you from doing that, with this message: “Overlapping accesses to `p`, but modification requires exclusive access.” The problem is that the single function `change` is being given direct access to the memory of both the struct itself and a

member of that struct, simultaneously. We are threatening to alter the struct in some unpredictable way. This dangerous situation is forbidden; the compiler enforces *exclusive access* when a struct is being modified.

You may encounter that error message from the compiler under some surprising circumstances:

```
let c = UIColor.purple
var components = Array(repeating: CGFloat(0), count: 4)
c.getRed(&components[0], green: &components[1],
    blue: &components[2], alpha: &components[3]) // compile error
```

In that code, no exclusive access problem is evident to the untrained eye; you just have to take the compiler's word for it. One workaround is to take control of memory access yourself, silencing the compiler:

```
components.withUnsafeMutableBufferPointer { ptr -> () in
    c.getRed(&ptr[0], green: &ptr[1], blue: &ptr[2], alpha: &ptr[3])
}
```

It might be better to write a `UIColor` extension that assembles the array without any simultaneous memory access to multiple elements of the array:

```
extension UIColor {
    func getRedGreenBlueAlpha() -> [CGFloat] {
        var (r,g,b,a) = (CGFloat(0),CGFloat(0),CGFloat(0),CGFloat(0))
        self.getRed(&r, green: &g, blue: &b, alpha: &a)
        return [r,g,b,a]
    }
}
```

Sometimes the compiler can't see the issue coming, and you'll crash when the app runs instead:

```
var i = 0
func tweak(_ ii:inout Int) {
    print(i) // legal, but crash
}
tweak(&i)
```

In that code, `tweak` is accessing `i` in two ways simultaneously. On the one hand, `i` is being passed into `tweak` as an `inout` parameter. On the other hand, `tweak` is reaching out directly to `i` (which is in scope). Even though `tweak` never actually modifies `i` and never mentions its own `inout` parameter `ii`, that's a simultaneous access, and is forbidden by the runtime.

# Miscellaneous Swift Language Features

This chapter is a miscellany, and this section is a miscellany within a miscellany. It surveys some “advanced” Swift language features that have been added relatively recently. The reason for postponing the discussion to this point is in part to avoid cluttering up the earlier exposition and in part to ensure that you know enough to understand the subject matter.

## Synthesized Protocol Implementations

A few protocols built into the Swift standard library have the ability to synthesize implementations of their own requirements. Such a protocol can supply code behind the scenes so that an object that adopts the protocol will satisfy the protocol’s requirements *automatically*. This feature was introduced in Swift 4.1.

### Equatable

Equatable is one such protocol. That’s good, because making your custom type adopt Equatable is often a really useful thing to do. Equatable adoption means that the `==` operator can be used to check whether two instances of this type are equal. The only requirement of the Equatable protocol is that you do, in fact, define `==` for your type. Using our Vial struct from earlier in this chapter, let’s first do that manually:

```
struct Vial {
    var numberOfBacteria : Int
    init(_ n:Int) {
        self.numberOfBacteria = n
    }
}
extension Vial : Equatable {
    static func ==(lhs:Vial, rhs:Vial) -> Bool {
        return lhs.numberOfBacteria == rhs.numberOfBacteria
    }
}
```

Now that Vial is an Equatable, not only can it be compared with `==`, but also lots of methods that need an Equatable parameter spring to life. For example, Vial becomes a candidate for use with methods such as `firstIndex(of:)`:

```
let v1 = Vial(500_000)
let v2 = Vial(400_000)
let arr = [v1,v2]
let ix = arr.firstIndex(of:v1) // Optional wrapping 0
```

What’s more, the complementary inequality operator `!=` has sprung to life for Vial automatically! That’s because it’s already defined for *any* Equatable in terms of the `==` operator.

Our implementation of `==` for `Vial` was easy to write, but that’s mostly because this struct has just one property. As soon as you have multiple properties, implementing `==` manually, though theoretically trivial, becomes tedious and possibly hard to maintain. This is just the kind of task computers are good at! You’re likely going to want to define `==` in terms of the equality of all your type’s properties simultaneously; well, Swift will implement `==` *automatically* in exactly that way. All we have to do is declare adoption of `Equatable`, like this:

```
struct Vial : Equatable {
    var numberOfBacteria : Int
    init(_ n:Int) {
        self.numberOfBacteria = n
    }
}
```

That code compiles, even though we now have no implementation of `==`. That’s because the implementation has been synthesized for us. Behind the scenes, two `Vial` objects are now equal just in case their `numberOfBacteria` are equal — which is exactly the implementation we supplied when we wrote the code explicitly.

For `Equatable` synthesis to operate, the following requirements must be met:

- Our object type is a struct or an enum.
- We have adopted `Equatable`, *not* in an extension.
- We have *not* supplied an implementation of the `==` operator.
- All of our struct’s stored property types are themselves `Equatable`.

For an enum, the requirement here is that, if the enum has associated values, the types of those associated values must be `Equatable`. The synthesized `==` implementation will then say that two instances of our enum are equal if they are the same case and, if that case has an associated value, the associated values are equal for both instances. Recall that our `MyError` enum in [Chapter 4](#) couldn’t be used with the `==` operator until we explicitly declared it `Equatable`:

```
enum MyError : Equatable {
    case number(Int)
    case message(String)
    case fatal
}
```

(If an enum has *no* associated values, then it is already effectively `Equatable` and there is no need to adopt `Equatable` explicitly.)

If you don’t like the synthesized implementation of `==` (perhaps because there is a property that you don’t want involved in the definition of equality), all you have to do is write your own, explicitly. You lose the convenience of automatic synthesis, but you’re no worse off than you were before automatic synthesis existed.

Let's say we have a `Dog` struct with a `name` property and a `license` property and a `color` property. And let's say we think two `Dogs` are equal just in case they have the same name and license; we don't care whether the colors are the same. Then we just have to write the implementation of `==` ourselves, omitting `color` from the calculation:

```
struct Dog : Equatable {
    let name : String
    let license : Int
    let color : UIColor
    static func ==(lhs:Dog, rhs:Dog) -> Bool {
        return lhs.name == rhs.name && lhs.license == rhs.license
    }
}
```

## Hashable

Another protocol that performs synthesis of its own implementation is `Hashable`. Recall that a type must be `Hashable` to be used in a `Set` or as the key type of a `Dictionary`. A struct whose properties are all `Hashable`, or an enum whose associated values are all `Hashable`, can conform to `Hashable` merely by declaring that it adopts `Hashable`.

`Hashable` requires that its adopter, in addition to being `Equatable`, have a `hashValue` `Int` property; the idea is that two equal objects should have equal hash values. The implicit implementation combines the `hashValue` of the `Hashable` members to produce a `hashValue` for the object itself. That's good, because *you* would surely have no idea how to do that for yourself. Writing your own hash function is a very tricky business! Thanks to this feature, you don't have to.

But suppose you don't like the synthesized implementation of `hashValue`. Then you *will* have to calculate the `hashValue` yourself. Luckily, Swift gives you a way to do that. You ignore `hashValue`, and instead implement the `hash(into:)` method. There is then no need to implement `hashValue`, because it is autogenerated based on the result of `hash(into:)`. In this method, you are handed a `Hasher` object; you call `hash(into:)` with that object on every property that you want included in the hash calculation — and omit the ones you don't. For hashability to work properly, these should be the very same properties you've included in the `Equatable` calculation of `==`.

So, for our `Dog` struct, we could write:

```
struct Dog : Hashable { // and therefore Equatable
    let name : String
    let license : Int
    let color : UIColor
    static func ==(lhs:Dog, rhs:Dog) -> Bool {
        return lhs.name == rhs.name && lhs.license == rhs.license
    }
}
```

```

        func hash(into hasher: inout Hasher) {
            name.hash(into:&hasher)
            license.hash(into:&hasher)
        }
    }
}

```

## Comparable

Other protocols, alas, do not provide the same convenience. If we want our `Vial` struct to be `Comparable`, we must implement `<` explicitly. (And when we do, the other three comparison operators spring to life automatically as well.)

In Swift 5.3 and later, however, the `Comparable` protocol does provide a synthesized implementation — but only for an enum, and only if the enum has no raw value. The order of the cases is the order in which they are declared; if a case has an associated value, it must be of a `Comparable` type, so that if two instances of the enum have the same case, they can be ordered by their associated value:

```

enum Planet : Comparable {
    case mercury
    case venus
    case earth
    case mars
    case asteroid(String)
    case jupiter
}
// let's test it!
let test1 = Planet.mercury < Planet.venus // true
let test2 = Planet.jupiter > Planet.asteroid("Ceres") // true
let test3 = Planet.asteroid("Ceres") < Planet.asteroid("Vesta") // true

```

## Key Paths

Key paths, a language feature introduced in Swift 4, effectively stand in relation to properties the way function references stand in relation to function calls — they are a way of storing a reference to a property without actually accessing the property.

Suppose we have a `Person` struct with a `firstName` `String` property and a `lastName` `String` property, and that we want to access one of these properties on a `Person` `p`, without knowing until runtime *which* property we are to access. We might write something like this:

```

var getFirstName : Bool = // ...
let name : String = {
    if getFirstName {
        return p.firstName
    } else {
        return p.lastName
    }
}()

```

That's not altogether atrocious, but it's hardly elegant. If we do the same sort of thing in several places, the same choice must somehow be repeated in each of those places — and the more choices there are, the more elaborate our code must be each time.

Key paths solve the problem by permitting us to encapsulate the *notion* of accessing a particular property of a type, such as `Person's firstName` or `lastName`, without actually *performing* the access. That notion is expressed as an instance; therefore, we can store it as a variable, or pass it as a function parameter. That instance then acts as a token that we can use to access the actual property on an actual instance of that type at some future time.

The literal notation for constructing a key path is:

```
\Type.property.property...
```

We start with a backslash. Then we have the name of a type, which may be omitted if the type can be inferred from the context. Then we have a dot followed by a property name — and this may be repeated if that property's type itself has a property that we will want to access, and so on.

In our simple case, we might store the notion of accessing a particular property as a key path variable, like this:

```
var prop = \Person.firstName
```

To perform the actual access, start with a reference to a particular instance and fetch its `keyPath: subscript`:

```
let whatname = p[keyPath:prop]
```

If `p` is a `Person` with a `firstName` of "Matt" and a `lastName` of "Neuburg", then `whatname` is now "Matt". Moreover, `whatname` is inferred to be a `String`, because the key path carries within itself information about the type of the property that it refers to (it is a generic).

Now imagine substituting a different key path for the value of `prop`:

```
var prop = \Person.firstName
// ... time passes ...
prop = \.lastName // inferred as \Person.lastName
```

That substitution is legal, because both `firstName` and `lastName` are `Strings`. Instantly, throughout our program, all occurrences of the `Person [keyPath:prop]` subscript take on a new meaning!

If the property referenced by a key path is writable and you have a writable object reference, then you can also set *into* the `keyPath: subscript` on that object, changing the value of the property:

```
p[keyPath:prop] = "Ethan"
```

Here's a practical example where my own code takes advantage of key paths. One of my apps is a version of a well-known game involving a deck of 81 cards, where every card has four attributes (color, number, shape, and fill), each of which can have three possible values. (81 is  $3^4$ .) The player's job is to spot three cards obeying the following rule: each attribute has either the *same* value for *all* three cards or a *different* value for *each* of the three cards. The problem is to express that rule succinctly.

For the four card attributes, I use enums with Int raw values. This allows me to represent any attribute as a common type (Int). I express those raw values as computed properties, and I vend a list of all four computed properties as an array of key paths (attributes):

```
struct Card {
    let itsColor : Color
    let itsNumber : Number
    let itsShape : Shape
    let itsFill : Fill
    var itsColorRaw : Int { return itsColor.rawValue }
    var itsNumberRaw : Int { return itsNumber.rawValue }
    var itsShapeRaw : Int { return itsShape.rawValue }
    var itsFillRaw : Int { return itsFill.rawValue }
    static let attributes : [KeyPath<Card, Int>] = [
        \.itsColorRaw, \.itsNumberRaw, \.itsShapeRaw, \.itsFillRaw
    ]
    // ...
}
```

Now I can express the rule clearly and elegantly:

```
func isValidTriple(_ cards:[Card]) -> Bool {
    func evaluateOneAttribute(_ n:[Int]) -> Bool {
        let allSame = (n[0] == n[1]) && (n[1] == n[2])
        let allDiff = (n[0] != n[1]) && (n[1] != n[2]) && (n[2] != n[0])
        return allSame || allDiff
    }
    return Card.attributes.allSatisfy {attribute in
        evaluateOneAttribute(cards.map {$0[keyPath:attribute]}) // wow!
    }
}
```

Starting in Swift 5.2, a keypath literal can be used wherever a function is expected that takes that object's type as its sole parameter and produces that property's type as its result. That sentence is enough to make one's head swim, but the idea is quite simple. Consider our Person with a `firstName` and a `lastName` String property. If you have an array of Person, you can extract a list of first names using `map`, like this:

```
let names = arrayOfPersons.map {$0.firstName}
```

Well, now you can use a keypath literal instead:

```
let names = arrayOfPersons.map (\.firstName)
```



That’s more than mere syntactic sugar; the point is that `\.firstName` acts as *the name of a function*. Here’s a more surprising case in point:

```
let f : (Person) -> String = \Person.firstName
```

## Instance as Function

Sometimes a type’s primary job is to contain or represent a function. In those situations, it makes for cleaner code if we can treat an instance of that type *as* a function. The ability to do that was introduced in Swift 5.2.

Before I explain, I’ll give an example. (This particular example comes more or less directly from Apple.) Imagine I have a struct `Adder`, whose job is to store a base value and add it to any addend we care to supply:

```
let add3 = Adder(3)
let sum = add3(4)
print(sum) // 7
```

That code, and indeed the entire concept of `Adder`, should remind you of the notion of a function as a factory for other functions (see “[Function Returning Function](#)” on [page 54](#)). In the second line, we treat `add3` as a function that takes an `Int` and returns another `Int`, namely the first `Int` with 3 added to it. But here’s the thing: `add3` is *not* a function! It is an instance of a struct. We are treating an instance as a function.

The implementation, behind the scenes, is simple. If a type declares an instance method named `callAsFunction`, you can “call” an instance of that type as if it *were* a function: the “call” is routed to the `callAsFunction` method. Here’s `Adder`:

```
struct Adder {
    let base: Int
    init(_ base: Int) {
        self.base = base
    }
    func callAsFunction(_ addend: Int) -> Int {
        return self.base + addend
    }
}
```

So when we create an `Adder` instance named `add3` and then say `add3(4)`, it is *exactly* the same as if we had said `add3.callAsFunction(4)`.

The function notation in `add3(4)` is mere syntactic sugar. But it’s very nice syntactic sugar, because it reflects the truth more compactly. To be sure, we could have given `Adder` an `add` method that performs the addition, or a `makeAdder` method that produces a function that performs the addition:

```

struct Adder {
    let base: Int
    init(_ base: Int) {
        self.base = base
    }
    func add(_ addend: Int) -> Int {
        return self.base + addend
    }
    // or:
    func makeAdder() -> (Int) -> Int {
        return { addend in self.base + addend }
    }
}

```

Either of those would have been just fine. But the job of `Adder` is to act like a function, so rather than having it contain or produce that function, we can use `callAsFunction` to let an `Adder` effectively *be* that function.

You can give your type multiple `callAsFunction` overloads, distinguished in the usual way by parameter types, parameter labels, or both. In this way, a single instance can behave as if it were itself an overloaded function.

## Dynamic Membership

Dynamic membership was introduced in Swift 4.2, with additional features in Swift 5. It allows you to do two things:

- Access a nonexistent property (a *dynamic* property) of an instance or type.
- Treat a reference to an instance as the name of a nonexistent function (a *dynamic* function).

Before I explain, I'll give an example. Imagine I have a class `Flock` that acts as a gate-keeper to a dictionary. I proceed to talk to a `Flock` instance like this:

```

let flock = Flock()
flock.chicken = "peep"
flock.partridge = "covey"
// flock's dictionary is now ["chicken": "peep", "partridge": "covey"]
if let s = flock.partridge {
    print(s) // covey
}
flock(remove:"partridge")
// flock's dictionary is now ["chicken": "peep"]

```

That's surprising, because `Flock` has no `chicken` property and no `partridge` property, and it is not the name of a function with a `remove:` parameter. So why am I able to talk that way?

Here's how the implementation works:

### *Dynamic properties*

The type must be marked `@dynamicMemberLookup`, and must declare a subscript taking a single parameter that is either a string or a key path and has an external name `dynamicMember`. The subscript return type is up to you, and you can have multiple overloads distinguished by the return type. When other code accesses a nonexistent property of this type, the corresponding subscript function — the getter or, if there is one, the setter — is called with the name of the property as parameter.

### *Dynamic functions*

The type must be marked `@dynamicCallable`, and must declare either or both of these methods, where the type `T` is up to you:

`dynamicallyCall(withArguments:[T])`

Other code uses an instance as a function name and calls it with a variadic parameter of type `T`. The variadic becomes an array. If `T` is `Int`, and the caller says `myObject(1,2)`, then this method is called with parameter `[1,2]`.

`dynamicallyCall(withKeywordArguments:KeyValuePairs<String, T>)`

Other code uses an instance as a function name and calls it with labeled arguments of type `T`. The label–value pairs become string–`T` pairs; if a label is missing, it becomes an empty string. If `T` is `String`, and the caller says `myObject(label:"one", "two")`, then this method is called with parameter `["label":"one", "":"two"]`.

So here's the implementation of `Flock`. Its dynamic properties are turned into dictionary keys, and it can be called as a function with a "remove" label to remove a key:

```
@dynamicMemberLookup
@dynamicCallable
class Flock {
    var d = [String:String]()
    subscript(dynamicMember s:String) -> String? {
        get { d[s] }
        set { d[s] = newValue }
    }
    func dynamicallyCall(withKeywordArguments kvs:KeyValuePairs<String, String>) {
        if kvs.count == 1 {
            if let (key,val) = kvs.first {
                if key == "remove" {
                    d[val] = nil
                }
            }
        }
    }
}
```

As originally conceived, dynamic membership is not intended for general use; its primary purpose is to prepare Swift for future interoperability with languages like Ruby, and perhaps to permit domain-specific languages. It is, after all, constitutionally opposed to the spirit of Swift: dynamism means that the compiler's validity checking is thrown away.

On the other hand, `@dynamicMemberLookup` with a subscript that takes a key path *is* Swift-like, because the validity of a given key path is checked at compile time. This feature is good particularly for forwarding messages to a wrapped value. Here's a `Kennel` struct that wraps a `Dog`:

```
struct Dog {
    let name : String
    func bark() { print("woof") }
}
@dynamicMemberLookup
struct Kennel {
    let dog : Dog
    subscript(dynamicMember kp:KeyPath<Dog,String>) -> String {
        self.dog[keyPath:kp]
    }
}
```

If `k` is a `Kennel` instance, we can now fetch `k.name` as a way of fetching `k.dog.name`. An attempt to say `k.nickname`, however, won't even compile; key paths maintain validity checking.

## Property Wrappers

The idea of property wrappers, as you'll recall from [Chapter 3](#), is that commonly used computed property getter and setter patterns can be encapsulated into a type with a `wrappedValue` computed property:

```
@propertyWrapper struct MyWrapper {
    // ...
    var wrappedValue : SomeType {
        get { /*...*/ }
        set { /*...*/ }
    }
}
```

You can then declare your computed property using the property wrapper type name as a custom attribute:

```
@MyWrapper var myProperty
```

The result is that, behind the scenes, a `MyWrapper` instance is created for you, and when your code gets or sets the value of `myProperty`, it is the getter or setter of this `MyWrapper` instance that is called.

In real life, your property wrapper's purpose will almost certainly be to act as a façade for access to a stored instance property, declared inside the property wrapper's type. This alone makes the property wrapper worth the price of admission, because now your main code is not cluttered with private stored properties acting as the backing store for computed properties; the stored properties are hidden in the property wrapper instances.

To introduce the syntax, I'll start with a property wrapper that acts as a façade for storage, and no more:

```
@propertyWrapper struct Facade<T> {
    private var _p : T
    init(wrappedValue:T) {
        self._p = wrappedValue
    }
    var wrappedValue : T {
        get {
            return self._p
        }
        set {
            self._p = newValue
        }
    }
}
```

That's a fairly normal-looking struct. It's a generic so that our property declaration can be of any type. The only special feature here is the initializer. The rule is that if you declare an `init(wrappedValue:)` initializer, it will be called automatically with the value to which the property is initialized:

```
@Facade var p = "test"
```

Here, the property wrapper's generic is resolved to `String`, and its `init(wrappedValue:)` initializer is called with parameter `"test"`. You can call other initializers instead, by treating the custom attribute name as a type name (which, of course, is just what it is) and putting parentheses after it. Suppose our property wrapper declares an initializer with no external parameter name:

```
init(_ val:T) {
    self._p = val
}
```

Then we can call that initializer by declaring our property like this:

```
@Facade("test") var p
```

More practically, here's a generalized version of the `Clamped` property wrapper from [Chapter 3](#); we accept any `Comparable` type (so that `min` and `max` are available), and we accept (and require) initialization with a minimum and maximum to clamp to:

```

@propertyWrapper struct Clamped<T:Comparable> {
    private var _i : T
    private let min : T
    private let max : T
    init(wrappedValue: T, min:T, max:T) {
        self._i = wrappedValue
        self.min = min
        self.max = max
    }
    var wrappedValue : T {
        get {
            self._i
        }
        set {
            self._i = Swift.max(Swift.min(newValue,self.max),self.min)
        }
    }
}

```

And here's how to use it:

```

@Clamped(min:-7, max:7) var i = 0
@Clamped(wrappedValue:0, min:-7, max:7) var ii

```

Those declarations are equivalent, but the first is more natural; behind the scenes, the value with which we initialize the property is routed to the `wrappedValue:` parameter of the property wrapper initializer.

As I've said, when you declare a property with a property wrapper attribute, an actual property wrapper instance is generated. That instance is accessible to our code under the same name as the computed property with underscore (`_`) prefixed to it. In the case of our `@Facade` property `p`, if we set `p` to "howdy" and then say `print(_p)`, the console says `Facade<String>(_p: "howdy")`. You might use this feature for debugging, or to expose additional public members of the struct. This underscore-prefixed variable is declared with `var`, so you can even assign to it a property wrapper instance that you've initialized manually.

The property wrapper may also vend a value that can be referred to elsewhere by prefixing a dollar sign (`$`) to the property name. It does this by declaring a `projectedValue` property (this will usually be a computed property). You might use this to expose some useful secondary object.

That's how the SwiftUI `@State` attribute works. It is a property wrapper (one of several that are commonly used in SwiftUI). The `State` property wrapper struct has a `projectedValue` computed property whose getter returns the `State` struct's binding property. That property is a `Binding`, so when you use your `@State` property's `$` name, you get a `Binding` (see [Chapter 14](#)).



Be careful not to cause a name clash! If you declare a `@Facade` property `p`, you can't declare a property `_p` in the same scope, because that's the name of the synthesized property wrapper instance. (The same issue does not arise for the `$` name, because a variable name can't start with `$`.)

New in Swift 5.5, property wrappers can be applied to function parameters. To see what I mean, let's start with a simple property wrapper that crashes if an assigned string is empty:

```
@propertyWrapper struct Nonempty {
    var wrappedValue : String = "" {
        didSet {
            if wrappedValue == "" {
                fatalError("Not allowed to assign empty string")
            }
        }
    }
}
```

Now we can have an instance property declared like this:

```
@Nonempty var name = "Matt"
```

If we assign "Neuburg" to that property, all is well. If we assign "" to that property, we crash.

You can imagine that it would be nice to extend this sort of validation to a function parameter: if an empty string is passed in as the argument to this parameter, we crash. Starting in Swift 5.5, you can do that:

```
func say(@Nonempty _ what: String) {
    print(what)
}
```

That compiles; but when we call `say` with an empty string, we *don't* crash. The reason is that, while setting a property-wrapped property sets the property wrapper's `wrappedValue` and therefore triggers the `wrappedValue` property's `didSet` observer, passing a value to a property-wrapped parameter *initializes* the property wrapper struct. So for this to work, we need to extend the same crashing behavior to the property wrapper struct's `init(wrappedValue:)` initializer:

```
@propertyWrapper struct Nonempty {
    var wrappedValue : String = "" {
        didSet {
            if wrappedValue == "" {
                fatalError("Not allowed to assign empty string")
            }
        }
    }
    init(wrappedValue: String) {
        self.wrappedValue = wrappedValue
    }
}
```

```

        if wrappedValue == "" {
            fatalError("Not allowed to assign empty string")
        }
    }
}

```

Inside the function that has a property-wrapped parameter, the local parameter value is just like a property-wrapped property. If you use its name, that's the `wrappedValue`. But if you use its name preceded by a dollar sign, that's the `projectedValue`.

To illustrate, imagine we have an extension on `String` defining a method, `rot13`, that applies ROT13 encipherment to the string. ROT13 encipherment advances each character through the alphabet by 13 characters, starting over at "a" if we come to "z"; it has the pleasant feature that applying ROT13 to an enciphered string decipheres it (because the alphabet has 26 letters). Here's a property wrapper that vends both the original string and the enciphered string:

```

@propertyWrapper struct Rot13 {
    var wrappedValue : String
    var projectedValue : String {
        wrappedValue.rot13()
    }
}

```

Now we can write a function that prints both the original string and the enciphered string:

```

func cipher(@Rot13 string: String) {
    print("the original string is", string)
    print("the enciphered string is", $string)
}

```

But we can go further. I'm imagining here that we're calling our `cipher` method like this:

```

cipher(string: "hello")

```

However, it is also permitted to call it like this:

```

cipher($string: "uryyb")

```

The dollar sign indicates that the argument here represents *the projected value*. In order to accommodate this, the property wrapper needs to have an `init(projectedValue:)` initializer. I'll rewrite our property wrapper struct so that it does have one:

```

@propertyWrapper struct Rot13 {
    let orig : String
    let ciph : String
    init(wrappedValue:String) {
        self.orig = wrappedValue
        self.ciph = wrappedValue.rot13()
    }
}

```



```

    init(projectedValue:String) {
        self.ciph = projectedValue
        self.orig = projectedValue.rot13()
    }
    var wrappedValue : String { self.orig }
    var projectedValue : String { self.ciph }
}

```

The result is that we can call the `cipher` function both ways, and we get *the same answer* each time:

```

cipher(string: "hello") // the original string is hello
                        // the enciphered string is uryyb
cipher($string: "uryyb") // the original string is hello
                        // the enciphered string is uryyb

```

That’s because the presence or absence of the dollar sign in the call tells the property wrapper whether to call `init(projectedValue:)` or `init(wrappedValue:)`, and so it can distinguish whether the argument we’re supplying represents the enciphered string or the original string.

## Custom String Interpolation

Starting in Swift 5, string interpolation syntax can be customized. The example I suggested in [Chapter 3](#) is an expression such as `"You have \(n, roman:true) widgets"`, where `n` is an `Int`; the idea is that, if `n` is 5, this would yield `"You have V widgets"`, expressing the `Int` in Roman numerals instead of Arabic notation. This would be an odd goal to accomplish through string interpolation, but it demonstrates the syntax; so let’s implement that example.

To implement string interpolation, you need an adopter of the `ExpressibleByStringLiteral` protocol that also adopts the `ExpressibleByStringInterpolation` protocol. This might be some custom type of your own, but for this example we’ll just use the built-in type that already adopts both of these protocols — `String`. `"You have \(n, roman:true) widgets"` is a `String`, and it already implements string interpolation.

That makes our job easy: all we have to do is customize `String`’s already existing implementation of string interpolation. That implementation hinges on two methods, `appendInterpolation` and `appendLiteral`. The overall string is broken into segments, the interpolations (`appendInterpolation`) and the other parts (`appendLiteral`), and those methods are called; our job is to assemble them into a single object. `String` is already doing that job, and we don’t need to modify the way it implements `appendLiteral`; we just need to modify the way it implements `appendInterpolation`.

To help us do that, there’s another protocol, `DefaultStringInterpolation`. We extend this protocol to inject a version of `appendInterpolation` that takes our interpolated

type — in this case, `Int` — along with any additional parameters. Our implementation should perform any necessary transformations to get a `String`, and then call the default `appendInterpolation(_:)`.

Here's an `Int` method `toRoman()` that yields an Optional `String` (`Int` values of 0 or less will return `nil`, to indicate that they can't be expressed in Roman numerals):

```
extension Int {
    func toRoman() -> String? {
        guard self > 0 else { return nil }
        let rom = ["M", "CM", "D", "CD", "C", "XC", "L", "XL", "X", "IX", "V", "IV", "I"]
        let ar = [1000, 900, 500, 400, 100, 90, 50, 40, 10, 9, 5, 4, 1]
        var result = ""
        var cur = self
        for (c, num) in zip(rom, ar) {
            let div = cur / num
            if (div > 0) {
                for _ in 0..

Our interpolated type is Int, and we want to add one parameter, roman:, a Bool. So our extension of DefaultStringInterpolation will inject an implementation of appendInterpolation like this:



```
extension DefaultStringInterpolation {
    mutating func appendInterpolation(_ i: Int, roman: Bool) {
        if roman {
            if let r = i.toRoman() {
                self.appendInterpolation(r)
                return
            }
        }
        self.appendInterpolation(i)
    }
}
```



For a practical example of custom string interpolation in action, take a look at the Logger struct, introduced in Swift 5.3 as a Swifty wrapper for OSLog (Chapter 10). Its methods take string literals, but the parameter here is not a String; it is a special OSLogMessage struct that adopts ExpressibleByStringLiteral and ExpressibleByStringInterpolation and performs the interpolation at runtime, with custom interpolation parameters, by way of an OSLogInterpolation struct that adopts StringInterpolationProtocol.



---



338 | Chapter 5: Flow Control and More


```

## Reverse Generics

Starting in Swift 5.1 and iOS 13, a function return type can be specified as a subtype of some supertype without stating *what* subtype it is. The syntax is the keyword `some` followed by the supertype. Suppose we have a protocol `P` and a struct `S` that adopts it:

```
protocol P {}
struct S : P {}
```

Then we can declare a function that returns a `P` adopter without specifying what adopter it is, by saying `some P`:

```
func f() -> some P {
    return S()
}
```

A computed property getter (or a subscript getter) is a function, so a computed property can also be declared a `some P`:

```
var p : some P { S() }
```

A stored variable cannot be declared a `some P` explicitly, but it can be a `some P` by inference:

```
var p2 = f() // now p2 is typed as some P
```

In those examples, the type *actually* being returned is `S` — and the compiler knows this by inference. But users of `f` and `p` know only that the type is an unspecified adopter of `P`. For this reason, this is sometimes called a *reverse generic* (or an *opaque type*). Instead of you declaring a placeholder and helping the compiler resolve it, the compiler has already resolved it and hides that resolution behind the placeholder.

A reverse generic `some P` is different from declaring the returned type as `P`. For one thing, in some situations you *can't* declare the returned type as `P` — as when `P` is a generic protocol. (A generic protocol, you remember, can be used only as a type constraint.) But more important, if `f` declared its return type as `P`, then it could return *any* `P` adopter on any occasion. That's not the case with `some P`; `f` returns an `S` and can return *only* an `S`. The compiler uses strict typing to enforce this — but the external declaration hides what exactly the compiler is enforcing. If there are two `P` adopters, `S` and `S2`, then a `some P` resolved to `S` has the same underlying type as another `some P` resolved to `S`, but it does not have the same type as a `some P` resolved to `S2`. This should remind you of a regular generic: an `Optional<String>` is a different type from an `Optional<Int>`.

As a result, a `some` type plays well with a generic in a way that an ordinary supertype would not. Suppose we have a Named protocol and an adopter of that protocol:

```
protocol Named {
    var name : String {get set}
}
struct Person : Named {
    var name : String
}
```

And suppose we have a generic function that uses this protocol as a type constraint:

```
func haveSameName<T:Named>(_ named1:T, _ named2:T) -> Bool {
    return named1.name == named2.name
}
```

Obviously, you can hand two `Person` objects to this generic function, because they resolve the generic placeholder `T` the same way:

```
let matt = Person(name: "Matt")
let ethan = Person(name: "Ethan")
let ok = haveSameName(matt,ethan) // fine
```

But you couldn't do that with two `Named` objects, because they might or might not represent the same adopting type:

```
let named1 : Named = Person(name: "Matt")
let named2 : Named = Person(name: "Ethan")
let ok = haveSameName(named1, named2) // compile error
```

Now suppose we have a function `namedMaker` that makes a `some Named` out of a `String`:

```
func namedMaker(_ name: String) -> some Named {
    return Person(name:name)
}
```

You, the user of `namedMaker`, do not necessarily know what `Named` adopter is produced by `namedMaker`. But you *do* know that every call to `namedMaker` produces the *same* type of `Named` adopter! The compiler knows this too, and it also knows *what* type of `Named` adopter `namedMaker` produces. Therefore you might write this, and the compiler will allow it:

```
let named1 = namedMaker("Matt")
let named2 = namedMaker("Ethan")
let ok = haveSameName(named1, named2) // fine
```

The main place you are likely to encounter some is when using SwiftUI or some other domain-specific language or library that wants to vend specific types while masking them under some common identity. (You are less likely to use `some` in your own code, though I suppose it could be useful for masking types in one area of your code from visibility in another area.)

For example, in SwiftUI a `View`'s body is typed as `some View`. In this way you are shielded from the underlying complexities of compound view types, such as:

```
VStack<TupleView<(Text, HStack<TupleView<(Image, Image)>>>>>>
```

At the same time, the compiler knows that *that* is the type of this View's body, and therefore behind the scenes SwiftUI can reason coherently about this view.

## Result Builders

Swift 5.1 introduced the ability to intercept a function passed to another function, capture its parameters and content, and transform them by way of a *result builder* to get a different function that is actually passed. This complex and highly specialized feature is aimed at enabling Swift to embrace domain-specific languages — the chief such language, at the moment, being SwiftUI. You can say this in SwiftUI:

```
VStack {  
    Text("Hello")  
    Text("World")  
}
```

That doesn't look like legal Swift, so what's going on? Well, `VStack` is a type, and we are creating an instance of that type. We call an initializer to instantiate `VStack`. This particular initializer takes a function as its `content:` parameter. We could write this as `VStack(content:f)`, but instead we use trailing closure syntax; the curly braces embrace the body of an anonymous function. This body is now handed off to a result builder, which detects its structure and transforms it into something that *is* legal Swift (and that creates a `VStack` instance consisting of two `Text`s). The entire look and feel of SwiftUI code rests on this mechanism.

(If you're interested in more details about result builder syntax, there's an excellent WWDC 2021 video on the topic.)

## Result

The `Result` enum expresses the notion of data-or-error in a single object. It's a generic, with a *success* case and a *failure* case, each carrying an associated value which is the data or error respectively.

One of `Result`'s primary uses case is a *completion handler* function. The idea is that, because our code is asynchronous, we cannot directly return a result or throw an error; but we can *call* a function that has been handed to us as a parameter, and as we do, we can pass a parameter to that function. We might want to tell the function that we successfully obtained data, or that we failed because of an error. So we pass a `Result` object, which expresses both:

```
func doSomeNetworking(completion:@escaping (Result<Data,Error>) -> ()) {  
    URLSession.shared.dataTask(with: myURL) { data, _, err in  
        if let data = data {  
            completion(.success(data))  
        }  
    }
```

```

        if let err = err {
            completion(.failure(err))
        }
    }.resume()
}

```

I'll have much more to say about that sort of code in [Chapter 6](#), so if you don't know what a completion handler is or what "asynchronous" means, don't worry; you soon will, and for now you can just appreciate the syntax.

In fact, Result syntax is even cooler than that; it provides an initializer that lets us return the data or throw the error inside the initializer function, as a way of forming the Result object:

```

func doSomeNetworking(completion:@escaping (Result<Data,Error>) -> ()) {
    URLSession.shared.dataTask(with: myURL) { data, _, err in
        let result = Result<Data,Error> {
            if let err = err {
                throw err
            }
            return data!
        }
        completion(result)
    }.resume()
}

```

And things work the same way in reverse at the caller's end, when we need to find out what this Result object consists of. We call the Result object's `get` method, which is a `throws` function. Either this gives us the data or else it throws:

```

self.doSomeNetworking { result in
    do {
        let data = try result.get()
        // do something with the data
    } catch {
        // respond to the error
    }
}

```

The advent of Swift structured concurrency ([Chapter 6](#)) will eventually obviate that particular use of Result, but there are many situations where it remains handy.

---

# Structured Concurrency

The term *concurrency* refers to the ability of a computer program to do more than one thing at the same time. When you're programming iOS, the runtime uses concurrency constantly; if it didn't, your app would be less responsive to the user — perhaps completely unresponsive.

For the most part, the various Cocoa frameworks use concurrency behind the scenes on your behalf; you don't have to worry about concurrency because the frameworks are worrying about them for you.

For instance, suppose your app is downloading something from the network. This download doesn't happen all by itself; somewhere, someone is running code that interacts with the network and obtains data. Yet none of that interferes with your code, or prevents the user from tapping and swiping things in your interface. The networking code runs “in the background.” That's concurrency in action.

Nevertheless, sometimes you need to be concerned with concurrency explicitly. For example:

## *Receiving a communication from background code*

Let's say your app has asked to download something from the network. Presumably, that's because you *want* that thing. If you're downloading an image, the goal might be to display that image in your interface, or to store that image as a file saved to disk. The runtime, in code that you can't see, does the downloading in the background, but eventually it will finish; it has obtained the image. Now *your* code needs a way to *receive* that image so that it can do something with it. How is the background code going to talk to your code? You need a way to receive a message from the background code, at whatever time the image may happen to become available.

### *Running your own code in the background*

Suppose your code performs some time-consuming calculations. You don't want your app to grind to a halt while it waits for these calculations to be performed. So you need a way to request explicitly that some of *your* code be performed “in the background.” And then when the calculations have finished, you'll probably want to do something with the results, such as display them in the interface. Now you need a way to receive a message from *your own* background code, at whatever time the calculations may happen to complete.

In order to do those things, you are going to need to deal directly with concurrency.

Earlier editions of this book didn't talk about concurrency, because it was purely a feature of application architecture. But Swift 5.5 introduces a revolutionary new way of interacting with and expressing concurrent operations. Concurrency is now implemented by way of Swift itself, and there are new syntactical devices and object types for that purpose. These are *language* features that are new in Swift 5.5. Apple refers to this suite of language features as *structured concurrency*.

This chapter discusses these new language features. I'll start by talking a bit more about concurrency in general. Then I'll say something about how concurrency was expressed using Swift 5.4 and before, so you can see what's “wrong” with the old concurrency model. After that, I'll discuss the new Swift 5.5 language features that constitute structured concurrency.

## Multithreading

Concurrency is traditionally envisioned in terms of *threads*. Concurrency implies that your app, or the Cocoa framework that runs it, has subprocesses that can execute even while other subprocesses are in the middle of executing. Threads are the low-level expression of simultaneous subprocess execution. When your app has more than one thread, it is said to be *multithreaded*.

## The Main Thread

Distinguish between the *main* thread and all other threads. There is only one main thread; all other threads are background threads. The singular nature of the main thread means that while a piece of your code is running on the main thread, no other piece of code can run on the main thread. Moreover, the main thread is the interface thread; any code that affects or is triggered by the user interface has to run on the main thread.

Your app's code generally runs on the main thread. The result, in effect, is that while your app's code is running, the interface is frozen. For instance, suppose the user taps a button in your app's interface, and this button tap causes a method in your code to run. While that method is running, the user can't interact with your app at all,



because user interaction takes place on the main thread — and the main thread is busy.

Now, you may ask: “Why have I never observed this when using apps on my iPhone? I tap buttons in apps all the time, and the interface never freezes.” Ah, but that’s because code runs really fast. The interface *is* frozen while an app’s code runs on the main thread, but that state of affairs lasts for only a very short time. The freezing of the interface is so brief that it’s imperceptible.

Conversely, if your code were so time-consuming that it *would* perceptibly freeze the interface while running on the main thread, you *wouldn’t* let that code run on the main thread. If you did, the user *would* perceive your app’s interface as frozen, and that would be bad. In fact, freezing the interface in that way is so bad that if you do it for long enough, a built-in iOS process called the WatchDog will come charging in and kill your app dead as punishment for behaving badly: your app will crash before the user’s very eyes.

When code running on a thread prevents any *other* code from running on that thread, that’s called *blocking*. Code running on the main thread blocks the main thread and therefore blocks the interface. But that, of itself, isn’t necessarily bad. In fact, it’s good! Your code, in response to what the user does, might update the interface; if the user could do something else in the interface while you’re in the middle of updating it, that could be a very bad thing, as it might put the interface, and your code, into an incoherent state. So the blocking behavior of the main thread is perfectly fine — just so long as you don’t misuse the main thread to run any time-consuming code.

## Background Threads

If the main thread were your app’s only thread, things would be very simple. But in real life, your app might have code that can run on a background thread. In that case, your code is multithreaded. Multithreaded code can be difficult to write, difficult to read, and difficult to reason about.

What’s the problem with multithreaded code? Well, the one certain thing about computer code is that it just clunks along the path of execution, one statement at a time. Successive lines of code are performed in the order in which they appear, and nothing else happens between them.

With multithreaded code, that certainty goes right out the window. If you have code that can be performed on a background thread, then *you don’t know* when your code will be performed. Moreover, you don’t know the *order* in which pieces of code will be performed. Any line of your background-thread code could be interleaved between any two lines of your other code. Indeed, under certain circumstances, the same background-thread code might be called multiple times on multiple

background threads simultaneously; in that case, any line of your background-thread code could be interleaved between any two lines of *itself*.

This situation is problematic particularly because of *shared data*. There are variables in your app, such as instance properties, that persist and can be accessed from multiple places. Background threads mean that such variables can be accessed at unexpected moments. That is a really scary thought. Suppose, while code running on one thread is in the middle of using a variable, code running on another thread changes that variable. Who knows what horrors might result?

Consider the following simple example:

```
class Dog {  
    private(set) var name: String? = nil  
    func giveName(_ newName:String) {  
        if self.name == nil { ❶  
            self.name = newName ❷  
        }  
    }  
}
```

The logic in that code appears straightforward enough:

- ❶ We check to see whether this Dog already has a name (by checking whether `self.name` is `nil`).
- ❷ If and only if this Dog *doesn't* already have a name, we give this Dog a name.

Now imagine that `giveName(_:)` might be called on different background threads. Then *between* the line where we check to see whether `self.name` is `nil` (step 1) and the line where we set `self.name` (step 2), this very same code might come along on another thread and set `self.name` — and so we will end up setting `self.name` even though it is *not* `nil`, violating our own logic!

It is possible to request assistance at a deeper level to ensure that a section of code is not run by two threads simultaneously. For example, you can implement a *lock* around a section of code. But locks generate an entirely new level of potential pitfalls. In general, a lock is an invitation to forget to use the lock, or to forget to remove the lock after you've set it. And threads can end up contending for a lock in a way that permits neither thread to proceed. If terms like *race condition* and *deadlock* don't strike fear into your veins, look them up on Wikipedia.

In short, writing safe, dependable multithreaded code is *hard*. It's easy to make a mistake, and difficult to debug it when you do.

## Asynchronous Code

When multiple threads are involved, you don't know exactly when your code will run. This might be because your code is *called* by background thread code, or because it *is* background thread code. Code that might be called at some unknown future time is said to be *asynchronous*.

In this section, I'm going to describe what asynchronous code looks like in Swift 5.4 and before. This will help you appreciate the benefits of the new Swift 5.5 structured concurrency syntax.

As a case in point, I'll use the example I've already referred to — what happens after you ask for something to be downloaded from the network. The download will be completed at some time in the future; at that unknown future time, the runtime will call your code to hand you the downloaded data. The download took place on a background thread, and now it's calling your code. Your code is asynchronous.

### What asynchronous code looks like

In Swift 5.4 and before, a typical asynchronous code architecture is a *completion handler*. When you ask Cocoa to download something, you also provide a *function* that Cocoa can call when the downloading is complete. That function expects a parameter that is a Data object. The idea is that when the downloading *is* complete, Cocoa *will* call that function, passing in whatever was downloaded as a Data object, and now your function can do something with that Data object.

Let's try it. Here's the signature of a method of the Cocoa `URLSession.shared` global object that you can call to get an object that will perform the downloading:

```
dataTask(
    with: URL,
    completionHandler: @escaping (Data?, URLResponse?, Error?) -> Void)
-> URLSessionDataTask
```

The `dataTask(with:completionHandler:)` method expects two parameters: the URL that is to be downloaded, and a completion handler function that will be called after the download has finished. As you can see, the completion handler function has three parameters, all of them Optional so that any of them can be `nil`. Ignore the `URLResponse` and concentrate on the `Data` and the `Error`. Exactly one of those two will be `nil`:

- If the download succeeds, the `Data` will have a value and the `Error` will be `nil`.
- If the download fails due to an error, the `Error` will have a value and the `Data` will be `nil`.

So we call this method, supplying a function that serves as a completion handler. We get back a *data task* object — a `URLSessionDataTask`. That's the object that's going to

do the actual downloading, but it doesn't start doing so until we tell it to `resume`. So here's the structure of some actual code that asks for some downloading to be performed. I've wrapped our call to the `dataTask` method in a `download(url:)` function that downloads something (or tries to) from a URL that we provide, and I've numbered some of the lines *in the order in which they run*:

```
func download(url: URL) {  
    let task = URLSession.shared.dataTask(with: url) { data, __, error in ❶  
        if let data = data { ❷  
            // do something with downloaded data  
        }  
    }  
    task.resume() ❸  
} ❹
```

Let's analyze the structure of that code:

- ❶ We obtain the data task, supplying as the second parameter in the call to `dataTask(with:completionHandler:)` a completion handler function (as an anonymous function, using trailing closure syntax).
- ❷ We tell the data task to start downloading by calling `resume`.
- ❸ Our `download(url:)` method comes to an end, and returns. All our code has finished running for now!
- ❹ Some time later — perhaps quite a long time later — the downloading finishes, and our completion handler function is called. If the downloading succeeded, we'll receive a `Data` object (which we're calling `data`), and we can do something with it.

The salient feature of that code is that it runs *out of order*. We call `task.resume` in the last line of the method, but at that time the material in the middle of our code (step 4) — the trailing closure containing the body of our completion handler function — hasn't run yet. That material will run *later*, at some unknown time. It is *asynchronous* code.

That's confusing. For one thing, nothing about the syntax tells you, the programmer, that some of the code *is* asynchronous. Material in a trailing closure is not necessarily asynchronous. This example, adapted from [Chapter 2](#), uses a trailing closure, but it's not asynchronous:

```
let arr = [2, 4, 6, 8] // 1  
let arr2 = arr.map {  
    return $0*2 // 2, not asynchronous  
}  
print(arr2) // 3
```

That code runs in the order in which it is written. Asynchronous code doesn't. Our `dataTask` code has the same apparent structure as the `map` example, but its pieces don't run in the same order as the `map` example:

```
let task = URLSession.shared.dataTask(with: url) { data, _, error in // 1
    if let data = data { // 3, asynchronous
        // do something with downloaded data
    }
}
task.resume() // 2
```

In the `map` example, the last line, `print(arr2)`, runs *after* the trailing closure. In the `dataTask` example, the last line, `task.resume()`, runs *before* the trailing closure. Our `dataTask` code contains a *time inversion*: the last line runs before the middle lines.

There is in fact a clue to the fact that `dataTask(with:completionHandler:)` runs its completion handler function asynchronously: the completion handler function type is marked `@escaping` in the declaration. This suggests that the completion handler function that we supply now may be stored in order to be called later. But the code is not marked `@escaping` at the call site, so we still might not realize that our code is asynchronous.

## Returning a value

Even if we do realize that our code is asynchronous, the implications of that fact can be difficult for beginners to grasp. Code containing a time inversion is hard to reason about, and misleads beginners into making all sorts of mistakes.

To see what I mean, consider our code once again:

```
func download(url: URL) {
    let task = URLSession.shared.dataTask(with: url) { data, _, error in
        if let data = data {
            // do something with downloaded data
        }
    }
    task.resume()
}
```

What about the comment, “do something with download data”? *How* might we actually do something with the `data` object representing the downloaded material? How, in particular, might we hand this `data` object back to the code that *called* our `download(url:)` method?

Here's an initial naïve attempt; we modify our `download(url:)` declaration to return a `Data` object, and in the anonymous function, we *do* return it:

```
func download(url: URL) -> Data {
    let task = URLSession.shared.dataTask(with: url) { data, _, error in
        if let data = data {
            return data // compile error
        }
    }
    task.resume()
}
```

Well, that didn't work; there's a compile error: "Unexpected non-void return value in void function." And this makes sense; we're trying to return *data* from inside the anonymous function, but the anonymous function doesn't return a value. We want to return *data* from *our* function, `download(url:)`.

At this point, the beginner programmer has a brilliant idea. We'll pass the *data* object up out of the anonymous function into our function, and return it from there. We'll do that by declaring a *Data* variable *before* our anonymous function, so that it's in scope from within the anonymous function:

```
func download(url: URL) -> Data {
    var result: Data = Data()
    let task = URLSession.shared.dataTask(with: url) { data, _, error in
        if let data = data {
            result = data
        }
    }
    task.resume()
    return result
}
```

That compiles, and our beginner programmer is filled with hope — only to have that hope dashed when the app runs and the returned *result* is always a zero-length empty *Data*!

And you can see why that is, if you just remember the time inversion. We return from the `download(url:)` method, and the method ends, *before* the asynchronous code even gets started. The line `return result` runs *before* the line `result = data`!

The beginner programmer is now desperate, and starts thinking illicit thoughts about somehow making the return statement “wait” until the asynchronous part of the code has had a chance to run. That sort of thing is just wrong. You can't make this code “wait” like that (although, as we shall see, that's just what the new Swift 5.5 concurrency syntax *does* let you do).

The fact is that our programmer's hopes and aspirations are just wrong. This kind of function *cannot* return a value that is set by asynchronous code, because the function returns before the asynchronous code sets that value.

So what *is* the viable way for our `download(url:)` method to communicate the *Data* resulting from the download back to whoever called the `download(url:)` method?

It's the very same device that `dataTask(with:completionHandler:)` is using to communicate the output of the download to us — a completion handler!

Of course, our `download(url:)` method doesn't accept a completion handler parameter; but we can change that. Instead of trying in vain to *return* our `Data`, we will *pass* our `Data` to the completion handler:

```
func download(url: URL, completionHandler: @escaping (Data) -> ()) {
    let task = URLSession.shared.dataTask(with: url) { data, _, error in
        if let data = data {
            completionHandler(data)
        }
    }
    task.resume()
}
```

Brilliant! That revision of the code compiles, and it works.

### Throwing an error

The preceding code works if, and only if, there is data. If there is no data — if there's an error instead, so that the incoming `data` parameter is `nil` — we never call the `completionHandler`. We simply leave whoever called us without any result at all. That's not very nice.

So what should we do if there's an error? We could return an empty `Data`:

```
func download(url: URL, completionHandler: @escaping (Data) -> ()) {
    let task = URLSession.shared.dataTask(with: url) { data, _, error in
        if let data = data {
            completionHandler(data)
        } else {
            completionHandler(Data())
        }
    }
    task.resume()
}
```

That works, and now we've covered every possibility; but we're not being very communicative. We're just misusing an empty `Data` object as a stand-in for the fact that there was an error. What we should be doing is communicating the error back to the caller.

Well, thinks our beginner programmer, I know how to communicate an error back to the caller: throw it! Here's an attempt to do that:

```

func download(url: URL, completionHandler: @escaping (Data) -> ()) throws {
    let task = URLSession.shared.dataTask(with: url) { data, _, error in
        if let data = data {
            completionHandler(data)
        } else if let error = error {
            throw error // compile error
        } else {
            fatalError("Should be impossible to get here")
        }
    }
    task.resume()
}

```

It looks promising, but guess what? There’s a compile error again! The compiler says: “Invalid conversion from throwing function of type (Data?, URLResponse?, Error?) throws -> Void to non-throwing function type (Data?, URLResponse?, Error?) -> Void.”

That means we’re throwing *in the wrong place*. The throws function here is *our* function, `download(url:completionHandler:)`. But the throw appears in the *anonymous* function, which isn’t a throws function. And even if it *were* a throws function, throwing inside it wouldn’t do any good, because that wouldn’t communicate anything back to the caller of *our* function; by the time we need to throw the error, our download function has ended and no longer has a caller.

So what’s the correct solution to *this* little conundrum? The answer, once again, is that you have to do the same thing that `dataTask(with:completionHandler:)` did: you have to pass the data *or* the error into the completion handler!

Fortunately, we can do that a little more elegantly than the `dataTask` method does it. Instead of having multiple Optional parameters, a Data and an Error, we can pass *one* parameter that *combines* a Data (in the case of success) and an Error (in the case of failure). That parameter would be a Result enum (“**Result**” on page 341); indeed, this is exactly the sort of use case for which the Result type was invented. Here we go:

```

typealias MyCompletionHandler = (Result<Data, Error>) -> ()
func download(url: URL, completionHandler: @escaping MyCompletionHandler) {
    let task = URLSession.shared.dataTask(with: url) { data, _, error in
        if let data = data {
            completionHandler(.success(data))
        } else if let error = error {
            completionHandler(.failure(error))
        } else {
            fatalError("Should be impossible to get here")
        }
    }
    task.resume()
}

```



That code, at long last, is correct. But it took us ages to arrive at it, and it isn't at all the sort of thing a beginning programmer is likely to construct without considerable assistance.

## Summary

Asynchronous code is confusing, and it's difficult to work with. In particular, we have seen that asynchronous code has these issues:

### *Confusing order*

Asynchronous code represents a time inversion. Code at the end of the method runs before code in the middle of the method. This can be hard for beginning programmers to realize, and the asynchronous code is not marked in any special way to alert them.

### *Can't return a value*

We can't return the data that we got from the internet, because even when we change the `download(url:)` method to return a `Data` object, our method ends and returns a value *before* the downloaded data even arrives into the completion handler.

### *Can't throw an error*

We can't signal failure to the caller by throwing, because the completion handler is not a throws function type, and even if it were, by the time we are ready to throw the error, our `download(url:)` method has already ended and there is no caller any more.

## Structured Concurrency Syntax

Having illustrated and summarized some of the chief difficulties with asynchronous code in Swift 5.4 and earlier, we are now in a position to appreciate the new structured concurrency syntax introduced by Swift 5.5. Here's how we'd write our `download(url:)` method in Swift 5.5:

```
func download(url: URL) async throws -> Data {
    let result = try await URLSession.shared.data(from: url)
    return result.0 // the data
}
```

In that example, we're calling a different `URLSession.shared` method, `data(from:)`. That method is new in iOS 15, and requires the new Swift 5.5 concurrency syntax; that new syntax is used in the first two lines. Here are some things to notice:

### *Asynchronous code is marked*

The `data(from:)` method that we're calling in the second line *is asynchronous*. That fact is explicitly called out in our code, by the use of the keyword `await`.

Moreover, our method `download(url:)` is *asynchronous*. That fact is explicitly called out in our code as well, by the use of the keyword `async`.

#### *Asynchronous code runs in order*

There is no time inversion in our code; the code runs in the order in which the lines appear. In the second line, we call the asynchronous method `data(from:)` and get a result, `result`. It's a tuple whose first element is the data. In the next line, we extract that data from the tuple.

#### *Asynchronous code can return a value*

Our `download(url:)` method can (and does) *return* a value to its caller, even though it is asynchronous. Here, it returns the `Data` part of the value that it got back from the call to `data(from:)`. That, in turn, is possible because the call to `data(from:)` itself *returns* a value to us, directly, even though it is asynchronous.

#### *Asynchronous code can throw an error*

Our `download(url:)` method can (and does) *throw* to signal an error to its caller, even though it is asynchronous. Here, `data(from:)` itself *can throw*, even though it is asynchronous; and if it does, we allow the error to be rethrown out of the `download(url:)` method.

The point of the new structured concurrency syntax introduced in Swift 5.5 is that it helps make multithreaded code easy to write, easy to read, and easy to reason about. Those advantages are demonstrated in this one simple example. There are no completion handlers anywhere in our code! The difficulties that I summarized at the end of the previous section have evaporated completely.

## **async/await**

The heart of the example is its use of two keywords, new in Swift 5.5: `async` and `await`. These two keywords go together to form a language construct designated by a single term — `async/await`. The `async/await` construct is not unique to Swift; it has a long history in other languages. Now it has been integrated into Swift. That innovation is a game-changer.

The keyword `async` is used to *mark* an asynchronous method. Here's the declaration of the `data(from:)` method that we're calling:

```
func data(from url: URL) async throws -> (Data, URLResponse)
```

That method declaration is marked `async`. The `async` keyword appears in the same place where we would mark a method declaration with `throws`. And in fact in this example the method declaration *is* also marked with `throws`, though that is a different matter. You can also mark the getter of a read-only computed property or subscript as `async`, just like `throws`.

(We have also marked our own `download(url:)` method `async`, for reasons that I'll explain later.)

The keyword `await` is used to *call* an asynchronous method. When we call an `async` method, we *must say await*. Delightfully, the compiler will enforce that rule; you can't possibly get it wrong:

```
let result = try await URLSession.shared.data(from: url)
```

The `await` keyword is used in the same way, and in the same place, as we would say `try`. And in fact in this code we *do* also say `try`, though that is a different matter.

The use of `await` when calling an `async` method is not a mere formality. The keyword `await` has, and signals, an actual effect: it causes our code to *pause and wait* until the call to the `async` method finishes. This is exactly what I said earlier is impossible and illegal when dealing with asynchronous code! The `async/await` construct makes waiting possible and legal.

How can that be? Under the hood, the pause created by the `await` keyword does not prevent other code from running; technically, we say that it does not *block*. The code containing the `await` keyword pauses, but other code does not. Once the `async` method that we are waiting for has finished, our code can *resume* right where it left off. This pause-and-resume architecture is the reason why an `async` function can return a value and can throw, even though it is asynchronous.

The pause-and-resume architecture is thread-agnostic, at least as far as the programmer is concerned. You can say `await` on a background thread, but it is also perfectly legal to say `await` on the main thread — because `await` does not block. Your code running on the main thread can pause at `await` and the main thread can perform other work. When the `async` method that we're calling has finished, then when the main thread is free, your code can resume on the main thread.

## Async Contexts

Here's another similarity between `try` and `await`: Just as you can say `try` only in a context that can throw, you can say `await` *only in an async context*.

Here's my `download(url:)` method again:

```
func download(url: URL) async throws -> Data {
    let result = try await URLSession.shared.data(from: url)
    return result.0
}
```

My `download(url:)` function is marked `async` in its declaration (the first line). That makes the body of the `download(url:)` function an `async` context. Otherwise, I could not say `await` (the second line).

Once again, the compiler will help you get this right. If you omit the keyword `async` from the `func` declaration in the first line of that code, there's a compile error, which says: "async call in a function that does not support concurrency." If you see that error message, declaring the surrounding function as `async` solves the problem.

That rule, however, raises an interesting problem, one that every programmer encounters early on in the course of experimenting with `async/await`. There appears to be a danger of infinite regress! If I can never call an `async` function without saying `await`, and if I can never say `await` except from within an `async` context, how can I ever call an `async` method from a *normal* method? How will this chain of calls ever get started?

For instance, suppose I want to call my own `download(url:)` method from my view controller's `viewDidLoad` method. It appears that I can't do it! The compiler wants me to make `viewDidLoad` an `async` method. But a view controller's `viewDidLoad` method is *not* an `async` method, and it's never going to be one. This is an override of an existing `UIViewController` method. It's a longstanding method, going back to a time long before `async/await` existed. It isn't `async`, and you can't declare it as `async` (if you do, the compiler will complain that your override doesn't override any inherited method).

Naturally, structured concurrency provides a solution to this problem. At any point in your code, you can declare a `Task` object, as I'll explain in the next section.

## Tasks

A `Task` object represents the notion of a *task*. In structured concurrency, tasks are the basis of all asynchronous activity. An `async` function can be called only from within some task. Anywhere you can say `await` is a task. When an `async` function is called, it runs as part of the task from which it was called.

Tasks are also the atoms of structured concurrency — meaning that a task itself has *no* concurrency. While a task is running on one thread, that same task cannot be running simultaneously on another thread. But two different tasks can run concurrently; and if a task doesn't run on the main thread, it can run concurrently with the main thread. (I'll say more about that later.)

The `Task` struct is a generic, parameterized on two placeholder types, `Success` and `Failure`; but in general you won't have to worry about that, because the placeholders will be resolved implicitly by the compiler. It has two initializers, both of which take these two parameters:

`priority:`

A `TaskPriority`. It's an `Optional`, and the default is `nil`, so that you usually won't bother to include it. I'll talk more about priorities later.

operation:

An `async` function that expects no parameters and returns an object of type `Success`. The difference between the two `Task` initializers is merely whether the `operation:` function also throws or not.

Initializing a `Task` object is tantamount to requesting that the `operation:` function be called asynchronously. You do not have to retain the `Task` object returned from the initializer! Typically, you won't do so. Here is a perfectly legal and effective way to call our `download(url:)` method from a non-`async` context:

```
let url = URL(string: "https://www.apeth.com/pep/manny.jpg")!
Task {
    do {
        let data = try await self.download(url: url)
        // do something with data
    } catch {
        print(error)
    }
}
```

When initializing a `Task` object, its `operation:` function is asynchronous. We did not say `await` before our `Task` initializer call, and we cannot say it; the initializer is not asynchronous, and in any case we're not in an `async` context. That puts us back in the very same time-inversion situation as before, and there's nothing we can do about it. For example:

```
override func viewDidLoad() {
    super.viewDidLoad()
    let url = URL(string: "https://www.apeth.com/pep/manny.jpg")!
    Task {
        do {
            let data = try await self.download(url: url)
            print(data)
        } catch {
            print(error)
        }
    }
    print(url)
}
```

In that code, the `url` value is printed, and our `viewDidLoad` method itself comes to an end and returns, *before* the downloaded data arrives and the `data` value is printed.

## Wrapping a Completion Handler

Sometimes you may have old-fashioned asynchronous code based on a completion handler, and you'll want to adopt structured concurrency while keeping the completion handler code.

A typical use case is that the code with the completion handler isn't your own. Perhaps you're using a third-party library (see [Chapter 10](#)) and you can't alter the source code. But you still want to incorporate a call to that code into your Swift 5.5 structured concurrency workflow.

For example, let's go back to our completion handler version of `download(url:)`, which went like this:

```
typealias MyCompletionHandler = (Result<Data, Error>) -> ()
func download(url: URL, completionHandler: @escaping MyCompletionHandler) {
    let task = URLSession.shared.dataTask(with: url) { data, _, error in
        if let data = data {
            completionHandler(.success(data))
        } else if let error = error {
            completionHandler(.failure(error))
        } else {
            fatalError("Should be impossible to get here")
        }
    }
    task.resume()
}
```

Suppose we can't touch that code; perhaps we can't even see it. All we know is that the public interface is a function declared like this:

```
typealias MyCompletionHandler = (Result<Data, Error>) -> ()
func download(url: URL, completionHandler: @escaping MyCompletionHandler)
```

How can we call that function using structured concurrency? Structured concurrency has an answer:

1. Declare an `async` function with the structured concurrency interface that you prefer. This is the *wrapper* for the call to the function that requires a completion handler.
2. Inside your wrapper function, call one of these global `async` functions:
  - `withUnsafeContinuation(_:)`
  - `withUnsafeThrowingContinuation(_:)`

Which you choose depends on whether or not you want to be able to throw. You're calling an `async` function, so you will have to say `await`; if you are calling `withUnsafeThrowingContinuation`, you will have to say `try`.

3. The `withUnsafe...` function takes as its parameter a function, which you'll probably supply as an anonymous function with trailing closure syntax.
4. The function that you supply takes one parameter — an `UnsafeContinuation` object.

5. In the function that you supply, you call the function that takes a completion handler, and of course you supply the completion handler function, probably as an anonymous function with trailing closure syntax.
6. In the completion handler function, you call a `resume` method of the `UnsafeContinuation` object. This percolates up to the point where you called the `withUnsafe...` function to begin with, and now you can pass the result out of your wrapper.

All of that will be much clearer with an example. First, here's a list of the `UnsafeContinuation` methods you can call (in step 6):

`resume(returning:)`

The value that you pass in to this call will be returned from the `withUnsafe...` function.

`resume(throwing:)`

The `Error` that you pass in to this call will be thrown from the `withUnsafe...` function.

`resume(with:)`

A compact combination of the preceding two methods. The parameter is a `Result` object, so this is convenient if the value you receive in the completion handler is itself a `Result`:

`.success`

If the `Result` that you pass is a `.success`, its associated value will be returned from the `withUnsafe...` function.

`.failure`

If the `Result` that you pass is a `.failure`, its associated error will be thrown from the `withUnsafe...` function.

`resume()`

Call this method if the `withUnsafe...` function doesn't need to return a value or throw.

The rule is that you *must* call *exactly one* of those methods, no matter what path of execution your code may take. The compiler cannot help you enforce that requirement; that's one reason this is described as `unsafe`.

Our wrapper function might have a structure like this:

```

func myDownload(url:URL) async throws -> Data {
    return try await withUnsafeThrowingContinuation { continuation in
        download(url:url) { result in
            // ???
        }
    }
}

```

The parameter that I’ve named `continuation` is the `UnsafeContinuation` object. To be correct, our code must call a method of that object on every possible path. In this instance, our result value comes to us in the `download(url:)` completion handler as a `Result` enum. This covers both getting a valid `Data` result in the `.success` case and getting an error in the `.failure` case. So let’s call the `UnsafeContinuation`’s `resume(with:)` method, which takes a `Result`. Here’s the full implementation:

```

func myDownload(url:URL) async throws -> Data {
    return try await withUnsafeThrowingContinuation { continuation in
        download(url:url) { result in
            continuation.resume(with: result)
        }
    }
}

```

The outcome is exactly what you would wish for. If we get a `.success` `Result`, the associated `Data` is returned from the `withUnsafeThrowingContinuation` call and passes on out as the returned value of `myDownload(url:)`. If we get a `.failure` `Result`, the associated `Error` is thrown, and our `myDownload(url:)` rethrows it.

An `UnsafeContinuation` is basically the same kind of object that forms the basis of the `await` keyword itself. When we wait for an `async` function call using `await`, a continuation object is created and stored behind the scenes; when the `async` function finishes, a method of that continuation object is called, and our code resumes. So what we’re doing in this wrapper method is enacting manually the same sort of wait-and-resume architecture that is performed for us automatically when we say `await`.

The function that we hand to `withUnsafe...` runs immediately and comes to an end, just as in the asynchronous completion handler world I described earlier in this chapter; the difference is that this time we’ve captured an `UnsafeContinuation` object. Until we call `resume` on that object, the surrounding code — the actual call to `myDownload`, and its call to the `withUnsafe...` function — is suspended because of the `await`. Eventually we are called back on the completion handler, and there we *do* call `resume` on the `UnsafeContinuation` object. When we do that, we’re asking the runtime to resume our code. It does so, and `withUnsafe...` returns, and so does `myDownload(url:)`.

A function that calls back on an asynchronous completion handler is not the only sort of construct to which you can apply a `withUnsafe...` function, though it is the



most common. Any construct where you initiate a call and are called back later asynchronously can be incorporated into structured concurrency in a similar manner.

If you're worried that you might not be implementing `withUnsafe...` correctly, you can call `withCheckedContinuation` or `withCheckedThrowingContinuation` instead. This allows the runtime to crash your app if you use the continuation incorrectly — if your path of execution calls a `resume` method twice, for instance, or fails to call it at all. However, that adds a lot of overhead to the call, so when you're satisfied that things are working as expected, you should switch back to using a `withUnsafe...` function.

## Multiple Concurrent Tasks

Suppose we want to download two images and return them both together. We could call our `download(url:)` method twice in succession:

```
func fetchTwoURLs() async throws -> (Data, Data) {
    let url1 = URL(string:"https://www.apeth.com/pep/manny.jpg")!
    let url2 = URL(string:"https://www.apeth.com/pep/moe.jpg")!
    let data1 = try await self.download(url: url1)
    let data2 = try await self.download(url: url2)
    return (data1, data2)
}
```

That works, but it might not be what we want to say. Each successive `await` represents a pause until the `async` method we're calling has finished. So we are downloading one image and waiting for it to arrive; then, when the first download has finished, we start downloading the second image and waiting for *it* to arrive. That seems unnecessarily time-consuming.

Instead of performing two downloads *successively*, perhaps we want to perform them *concurrently*. This seems like a natural thing to want to do. After all, concurrency is what this is all about. And the `URLSession` object, `URLSession.shared`, can handle multiple data tasks at the same time.

The problem is that, as I mentioned before, a task is the unit of concurrency. The whole point of a task is that a single task contains *no* concurrency. If we want to perform multiple concurrent operations, we will need to create multiple concurrent tasks.

Naturally, structured concurrency lets us do that. In fact, this is what puts the “structured” into structured concurrency. We can spawn off multiple *subtasks* of the current task. A task and its subtasks stand in a parent-child relationship. This helps to guarantee appropriate lifetimes for the subtasks, and (as I'll explain later) is crucial for coherent cancellation of the task tree.

## async let

When we have a known finite number of subtasks to perform, Swift structured concurrency provides a simple, elegant syntax: `async let`. Here’s a rewrite of `fetchTwoURLs` that uses `async let`:

```
func fetchTwoURLs() async throws -> (Data, Data) {
    let url1 = URL(string:"https://www.apeth.com/pep/manny.jpg")!
    let url2 = URL(string:"https://www.apeth.com/pep/moe.jpg")!
    async let data1 = self.download(url: url1)
    async let data2 = self.download(url: url2)
    return (try await data1, try await data2)
}
```

The expression `async let` acknowledges that we are calling an `async` function that returns a value; but it doesn’t wait for that value. Behind the scenes, each `async let` creates a subtask of the current task. That subtask is launched immediately, and runs concurrently with the current task and any other subtasks. When you say `async let` and assign the result of an `async` function, you do *not* say `await`; you’re going to say it *later*, when you first access the returned value. Similarly, if the `async` function also throws, you do *not* say `try`; you’re going to say it *later*, when you say `await`.

So in our code, each call to `download(url:)` is wrapped in a subtask. Those two subtasks are launched immediately and run concurrently; we are downloading two images simultaneously.

Our ultimate goal is to return the results of both `download(url:)` calls as the single result of our `fetchTwoURLs` method. So both calls to `download(url:)` need to have finished before we can return from `fetchTwoURLs`. Therefore, before we return the values on the left side of the `async let` assignments (`data1` and `data2`), we `await` them. As a consequence, the surrounding `fetchTwoURLs` method is unable to return until the data from both downloads has arrived — which is exactly what we want.

You can think of this as a “fork and join” architecture. We start with some surrounding task. We spawn off two subtasks that operate independently and simultaneously. That’s the “fork.” Ultimately, we wait until the results of both of those subtasks have been collected before proceeding. That’s the “join.”

In the particular example I’ve used, where we are awaiting all the elements of a tuple, it is permitted to express the `await` (and the `try`) once, distributed over the tuple, rather than multiple times with each element:

```
return try await (data1, data2)
```

There's an interesting logical consequence of the separation of `async let` from the corresponding `try await`: if the `async` function called by an `async let` assignment throws an error, our code is not interrupted:

```
async let data1 = self.download(url: url1)
async let data2 = self.download(url: url2)
```

Even if the first call to `download(url:)` throws an error *immediately*, the second call will still happen and will still be awaited. The thrown error from the subtask doesn't interrupt our code until later, when we say `try`.

Another interesting fact is that the convenient notation of writing an `async let` statement as a simple assignment is actually syntactic sugar for an autoclosure. Behind the scenes, our `async let` assignments are taken as a shorthand for something more like this:

```
async let d1 = { () async throws -> Data in
    let result = try await self.download(url: url1)
    return result
}()
async let d2 = { () async throws -> Data in
    let result = try await self.download(url: url2)
    return result
}()
```

That code is legal and permits you to express your subtask as multiple lines of code. Still, it's not a mode of expression you're likely to use.

## Task Groups

The use of `async let` in the previous example depends upon our knowing in advance that there will be exactly two URLs and exactly two downloads, so there are exactly two `async let` assignments. But suppose instead that we want to perform an *indeterminate* number of downloads simultaneously. How would we do it?

For example, perhaps the URLs arrive as an array that could be of any length. In that case, we can't use `async let`, because we don't know in advance how many `async let` declarations we need. What we want to do is to *loop* through the array, launching a download for *each* item of the array, and then wait until a value has been returned for *all* the items of the array.

The structured concurrency device for dealing with this kind of situation is a *task group*. The standard pattern for using a task group to loop through an array is rather elaborate; in fact, it's probably the most complicated thing you'll need to learn in connection with Swift 5.5 structured concurrency. However, I assure you that with a little practice it will become second nature. I'll develop the code in stages.

First, here's the overall structure of the example:

```
func fetchManyURLs() async throws -> [Data] {
    let urls: [URL] = // ...
    var result = [Data]()
    // ???
    return result
}
```

I'm positing `urls` as a hard-coded array of URLs, for simplicity; but how the `urls` array is populated, and what URLs it consists of, is irrelevant. The important thing is that we want to start with an array of URLs, `urls`, and return an array of `Data`, `result`, obtained by looping through `urls` and downloading from those URLs *concurrently*. We need to spawn off a subtask for *each* element of the `urls` array, downloading each URL and populating the `result` array as each download completes. And we need to *wait* until we have finished populating the `result` array so that we can return it. That's what a task group will let us do.

This approach starts with a call to a global function; it will be one of these:

- `withTaskGroup(of:returning:body:)`
- `withThrowingTaskGroup(of:returning:body:)`

The choice depends on whether or not the `async` function we want to call can throw. The `...TaskGroup` function takes a `body: function` as a parameter, which we'll typically supply as an anonymous function using trailing closure syntax. The `body: function` receives the task group itself as its parameter. From there, we can talk to the task group, telling it to spawn off the desired subtasks and collecting the results of those subtasks.

Let's call this entire architecture a *task group block*. Here's the structure of our task group block:

```
func fetchManyURLs() async throws -> [Data] {
    let urls: [URL] = // ...
    var result = [Data]()
    try await withThrowingTaskGroup(of: Data.self) { group in
        for url in urls {
            group.addTask {
                return try await self.download(url: url)
            }
        }
        // ???
    }
    return result
}
```

In that code, I've called `withThrowingTaskGroup`; in the `body:` function, I've named the task group parameter `group`. We are going to ask this task group to create subtasks, each of which returns a value of some identical type. We have to say in advance what that type is; that's what the `of:` parameter is for when we initially call the `...TaskGroup` method. (The `returning:` parameter is optional; I'll explain later what it's for.)

To request a subtask, we call the task group's `addTask` method. It takes an `operation:` function expressing the subtask, and that function is where we call our `async` function. You can see that I'm doing that in the example code, looping through the `urls` array and adding a download subtask for each URL that it contains.

Each subtask is launched as we add it. Therefore, by the time we reach the `???` comment, all the URLs in the original `urls` array have been processed, meaning that they have each been used to call `download(url:)`, launching a data task that returns a `Data` object. We are now downloading all the URLs simultaneously!

However, we are still not populating the `result` array. To do that, we need to *wait* for each `Data` object returned from each call to `self.download(url:)`, and append it to the `result` array. I've put my `???` comment at the point where we need to do that. How will we do it?

To help with this problem, Swift 5.5 structured concurrency supplies another new bit of syntax: `for await`. It is a `for` loop, but what it loops through is a stream of objects that arrive asynchronously (called, not surprisingly, an *asynchronous sequence*). In other words, this is an asynchronous `for` loop!

It turns out that, by an amazing coincidence, the task group *is* an asynchronous sequence, consisting of the results of its subtasks. So here, at last, is a version of our code that returns a meaningful value:

```
func fetchManyURLs() async throws -> [Data] {
    let urls: [URL] = // ...
    var result = [Data]() ❶
    try await withThrowingTaskGroup(of: Data.self) { group in ❷
        for url in urls {
            group.addTask { ❸
                return try await self.download(url: url) ❹
            }
        }
        for try await data in group { ❺
            result.append(data)
        }
    }
    return result ❻
}
```

That exemplifies the full pattern in action:

- ❶ We start with an empty collection in which we will accumulate our results.
- ❷ We declare a task group block, stating what kind of value will be returned to the task group from each subtask. The task group block is itself asynchronous, so we `await` it; if it can also throw, we also say `try`.
- ❸ Inside the task group block, we receive the task group as the parameter, and we call its `addTask` method repeatedly to launch each subtask.
- ❹ Each subtask calls an `async` method. In this example, that method returns the type of value we declared earlier (in step 2), and we just return that result back to the task group.
- ❺ Using `for await`, we loop through the task group as an asynchronous sequence, retrieving each returned value as it arrives and accumulating it into the collection that we declared earlier (in step 1).
- ❻ When all returned values have arrived, the asynchronous `for` loop ends; the task group has exhausted its tasks, and it comes to an end. This is what the first `await` (in step 2) has been waiting for! The collection has been populated, and we now proceed to the next line after the task group block, secure in the knowledge that we can use that collection.

Our code is now working! We perform multiple downloads simultaneously and then return their results as an array of `Data`.

There's a slight drawback in the way we're doing this: in our array of `Data`, we don't know which `Data` is which. The problem is that our `download(url:)` method is being called multiple times asynchronously and concurrently, so results can arrive *in any order*; the order of the `Data` objects in `result` bears no relationship to the order of the URLs in `urls`. Our `Data` objects have come unmoored, as it were, from the URLs to which they correspond.

To fix that, we can change our approach slightly: for instance, instead of returning an array of `Data`, we might return a dictionary pairing URL keys with `Data` values. That alteration doesn't affect the overall architecture of the pattern:

```
func fetchManyURLs() async throws -> [URL:Data] {
    let urls: [URL] = // ...
    var result = [URL:Data]()
    try await withThrowingTaskGroup(of: [URL:Data].self) { group in
        for url in urls {
            group.addTask {
                return [url: try await self.download(url: url)]
            }
        }
    }
}
```

```

    }
    for try await d in group {
        result.merge(d) {cur,_ in cur}
    }
}
return result
}

```

There is one more possible change that makes for arguably cleaner code. It seems unfortunate that we are compelled to declare our accumulator collection, `result`, outside the task group block. It would be nicer if this variable were local to the block itself. Well, we can do it that way! A task group block can be declared with an additional `returning:` parameter, stating the type of the overall result to be returned from the block. Using that option, we can accumulate `result` *inside* the task group block, return it, and immediately pass it on out as the returned value from our `fetchManyURLs`:

```

func fetchManyURLs() async throws -> [URL:Data] {
    let urls: [URL] = // ...
    return try await withThrowingTaskGroup(
        of: [URL:Data].self,
        returning: [URL:Data].self) { group in
        var result = [URL:Data]()
        for url in urls {
            group.addTask {
                return [url: try await self.download(url: url)]
            }
        }
        for try await d in group {
            result.merge(d) {cur,_ in cur}
        }
        return result
    }
}

```

Moreover, it turns out that if you don't supply the `returning:` parameter, the type defaults to the type of the `of:` parameter. In our case, they *are* the same type, so we can actually omit the `returning:` parameter while keeping the `result` accumulator inside the task group block.

## Asynchronous Sequences

In the previous section, we encountered asynchronous for loops (`for await`) in connection with task groups. An asynchronous for loop loops through an asynchronous sequence. A task group *is* an asynchronous sequence. More generally, an asynchronous sequence is a type that conforms to the `AsyncSequence` protocol. The values of an asynchronous sequence are generated asynchronously; a `for await` loop pauses after each iteration, and resumes when the next value of the sequence *is* generated,

performing another iteration and waiting again, until the sequence signals that it has terminated.

## Built-in Asynchronous Sequences

The only example of an asynchronous sequence we've seen so far is a task group. But there can be other asynchronous sequences. In iOS 15, asynchronous sequences are vended in a number of places, and you can receive them with an asynchronous for loop.

For example, this code reads a file from disk, one byte at a time, asynchronously:

```
if let url = Bundle.main.url(forResource: "test", withExtension: "txt") {
    if let fh = try? FileHandle(forReadingFrom: url) {
        Task {
            for try await byte in fh.bytes {
                // do something with this byte
            }
        }
    }
}
```

The `FileHandle` `bytes` method, new in iOS 15, returns an asynchronous sequence.

The notification center ([Chapter 12](#)) can vend a stream of notifications as an asynchronous sequence. To access such a stream, you call the `NotificationCenter` `notifications(named:object:)` method; it returns an asynchronous sequence. In this way, you can subscribe to notifications of a certain type by launching a task that contains an asynchronous for loop:

```
let notif = NotificationCenter.default.notifications(
    named: UIApplication.didBecomeActiveNotification,
    object: nil)
Task {
    for await notif in notif {
        // if we get here, application just became active
    }
}
```

Similarly, a Combine framework `Publisher` ([Chapter 14](#)) has a `values` property that is the asynchronous sequence of the values it emits. This is a way to be called periodically by a repeating `Timer` ([Chapter 12](#)):

```
let timerpub = Timer.publish(every: 1, on: .main, in: .default).autoconnect()
Task {
    for await value in timerpub.values {
        // called every second
    }
}
```



Those are all common things to do in an iOS app, and this new way of doing them, using an asynchronous sequence, is an intriguing innovation.

## Making an Asynchronous Sequence

It is also possible to make your own asynchronous sequence. The easiest way is to use the `AsyncStream` initializer. The initializer takes a function, to which it passes a continuation object. To emit a value, you tell that object to `yield` the value. If you have no more values to emit, you tell that object to `finish`.

Here's a somewhat silly example. A text field (`UITextField`) displays editable text in the interface. It can have a delegate (`UITextFieldDelegate`; see [Chapter 12](#)). If that delegate implements the `textFieldDidChangeSelection(_:)` method, the text field calls that method every time the text field's own selection changes (because the user is editing the text in the interface, for instance).

I'll create an object that acts a text field delegate and vends an asynchronous sequence that emits a value every time `textFieldDidChangeSelection(_:)` is called:

```
class TextFieldSelectionChangeStreamer: NSObject, UITextFieldDelegate {
    var values : AsyncStream<UITextField>
    var continuation : AsyncStream<UITextField>.Continuation?
    override init() {
        var myContinuation : AsyncStream<UITextField>.Continuation?
        self.values = AsyncStream { continuation in
            myContinuation = continuation
        }
        super.init()
        self.continuation = myContinuation
    }
    func textFieldDidChangeSelection(_ textField: UITextField) {
        self.continuation?.yield(textField)
    }
}
```

That code is rather convoluted because I have to externalize the continuation object out of the `AsyncStream` initializer function so that the `textFieldDidChangeSelection(_:)` implementation can send it the `yield` message. But the outcome is very simple: now my code can subscribe to the stream of messages with an asynchronous for loop. Here's some test code that demonstrates by printing the text field's text every time its selection changes:

```
class ViewController: UIViewController {
    let textFieldSelectionChangeStreamer = TextFieldSelectionChangeStreamer()
    @IBOutlet var textField : UITextField?
    override func viewDidLoad() {
        super.viewDidLoad()
        self.textField?.delegate = self.textFieldSelectionChangeStreamer
        Task {
```

```

        for await tf in self.textFieldSelectionChangeStreamer.values {
            print(tf.text ?? "")
        }
    }
}

```

## Asynchronous Sequence Methods

An asynchronous for loop is not your only option for dealing with an asynchronous sequence. Asynchronous sequences are similar to sequences; in particular, they are similar to *lazy* sequences. Methods such as `prefix`, `first(where:)`, `map`, `filter`, `reduce`, and many others are implemented on asynchronous sequences.

Moreover, an asynchronous for loop can be “unrolled” into a while loop that calls `next()`, just as with a normal for loop (though you might have no reason to do so):

```

let timerpub = Timer.publish(every: 1, on: .main, in: .default).autoconnect()
Task {
    let values = timerpub.values
    var iter = values.makeAsyncIterator()
    while let value = await iter.next() {
        // called every second
    }
}

```

## Actors

Given that structured concurrency is all about multithreaded code, it may seem odd that I haven’t said very much about threads. Where are the threads when you say `async` and `await`?

On the whole, when you’re using structured concurrency, thinking about threads explicitly is a mistake. Threads exist at a far lower level than the structured concurrency features built into the Swift language. Structured concurrency is generally free to assign your code to any thread it chooses. Indeed, structured concurrency is free to *change* what thread your code runs on. In particular, when your code says `await`, the thread on which your code runs *after* waiting and resuming might not be the same thread on which it was running *before* waiting. The decision about what thread to use belongs to a task; a task releases the current thread when it pauses at `await`, freeing it up for other purposes, and can use a different thread when it resumes afterward.

Nonetheless, the distinction between the main thread, on the one hand, and background threads, on the other, remains crucial. In iOS programming, the main thread is the interface thread; any code that touches an interface-related instance needs to run on the main thread. So how does structured concurrency distinguish between the main thread and background threads?

To answer that question, I have to introduce the notion of an *actor*. An actor is a kind of object type — an object type *flavor*, meaning that it is on a par with enums, structs, and classes ([Chapter 4](#)). Like a class, an actor is a reference type; you can have more than one reference to an actor instance.

To specify whether code should run on the main thread or on a background thread, you can associate that code with an actor. By default, an actor's code runs on a background thread. So if you want to say that certain code should always run on a background thread, just put that code into an actor. (I'll talk in a moment about how to say that code should run on the main thread.)

## Actor Isolation

An actor not only helps your code run on a background thread; it helps your multithreaded code run *safely*. The biggest issue with multithreaded code, you'll recall, is the problem of shared state. If a property can be mutated on more than one thread, your code risks falling into an incoherent state. Actors protect against this possibility by *isolating* their properties. Here's how they do that:

- If an actor instance has a mutable property, only that instance can mutate that property. In other words, only `self` can mutate `self.myMutableProperty`; no one can mutate `other.myMutableProperty`.
- Code outside an actor can *fetch* the actor's mutable property, but this access is asynchronous; the code must say `await`.
- Code outside an actor can *call* the actor's methods, but this access is asynchronous; the code must say `await`. That's because the actor might use a method to mutate its own mutable property.

Here's an artificial example that illustrates the main possibilities:

```
actor MyActor {
    let id = UUID().uuidString // random unique identifier
    var myProperty: String
    init(_ myProperty: String) {
        self.myProperty = myProperty
    }
    func changeMyProperty(to newValue: String) {
        self.myProperty = newValue
    }
}

func test() async {
    let act = MyActor("howdy")
    let id = act.id // legal ❶
    let prop = await act.myProperty // legal but requires await ❷
    await act.changeMyProperty(to: "hello") // legal but requires await ❸
    await act.myProperty = "hello" // compile error: illegal ❹
}
```

- ❶ An actor’s constant (`let`) properties are directly accessible from outside the actor. Constant value type properties can’t mutate, so it’s safe to access them from any code running on any thread.
- ❷ An actor’s mutable (`var`) properties can be fetched from outside the actor, but only by saying `await`. This ensures that the actual access takes place asynchronously on the actor’s own thread. (For technical reasons, the same thing is true even for an actor’s constant properties if the access is from a different module.)
- ❸ An actor’s methods can be called from outside the actor, but only by saying `await` — even if, as in this example, it is not an `async` method. Again, this ensures that the call takes place asynchronously on the actor’s own thread.
- ❹ An actor’s mutable properties cannot be mutated from outside the actor, regardless of whether you say `await`.

In that explanation, the phrase “the actor’s own thread” is just a loose bit of hand-waving. An actor doesn’t really have its “own thread.” Threads don’t really matter and are too low-level. What an actor has is an *isolation domain*. The isolation domain ensures that access is performed on a background thread by default, but it doesn’t guarantee anything about *what* background thread is used, and it doesn’t need to.

## Actor Serialization

An actor’s isolation domain makes a further guarantee: while an actor’s code is running, *no other code belonging to the same actor can start*. This is part and parcel of why outside code has to say `await` when talking to the actor. Again, the goal here is to help your code run safely.

For example, suppose `changeMyProperty(to:)` is a time-consuming operation. Well, if code outside the actor has *already* called `changeMyProperty(to:)`, and if that call is currently running, no *other* code outside the actor can proceed with *any* `await` access to that actor’s members; all `await` access must keep waiting until the actor’s code is no longer running.

This solves the problem of simultaneous access: with an actor, there is *no* simultaneous access. Access to an actor is *serialized*. Those familiar with Grand Central Dispatch will recognize this as reminiscent of a GCD serial queue. (But an actor is also *reentrant*, as I will explain later in this chapter.)

## The Main Actor

So what about the main thread? When you create an actor, in general, you’re specifying that its code should run on a background thread. But behind the scenes, there is also an invisible global actor — the *main actor* — called `MainActor`. Its code runs on

the main thread. If you want to ensure that code runs on the main thread, you isolate it to the main actor.

The primary way to do that is with the `@MainActor` attribute. You can attach the `@MainActor` attribute:

- To a *property*, to require that the property should be accessed only on the main thread. This can be an instance property or a static/class property.
- To a *method*, to require that the method should be called only on the main thread. This can be an instance method or a static/class method. If this is an override in a class, if the overridden method is designated as `@MainActor`, this method inherits that designation.
- To an *entire type* — a class, struct, or enum — to require that all of its properties and methods should be accessed only on the main thread. (The type in question can't be an actor; you cannot mark an entire custom actor with `@MainActor`.) If a subclass is explicitly marked `@MainActor`, it must descend from a superclass that is marked `@MainActor`, or else its declared superclass must be `NSObject`.
- To a *global* (top-level) variable or function.

For instance, I could change my actor to look like this:

```
actor MyActor {
    let id = UUID().uuidString // random unique identifier
    @MainActor var myProperty: String
    init(_ myProperty: String) {
        self.myProperty = myProperty
    }
    @MainActor func changeMyProperty(to newValue: String) {
        self.myProperty = newValue
    }
}
```

In that code, I've changed the property `myProperty` so that it is isolated to the main actor. There is no practical reason for this change; I'm just doing it to illustrate the syntax. The consequences are:

- I must change the method `changeMyProperty(to:)` to be isolated to the main actor as well; otherwise, the code won't compile, because `changeMyProperty(to:)` mutates `myProperty`, which is isolated to the main actor.
- Other code, if it is running on the main thread, can now fetch `myProperty` *directly*, without saying `await`. It can also call `changeMyProperty(to:)` directly — but it doesn't need to, because now it can directly *mutate* `myProperty`!

Built-in Cocoa classes associated with the interface are *already* marked with the `@MainActor` attribute, because interface code must run on the main thread. For

instance, the `ViewController viewDidLoad` method runs on the main thread, because `ViewController` is a subclass of `UIViewController`, which is a `@MainActor` class.



According to the documentation, if a class has a superclass marked as `@MainActor`, the subclass inherits that designation and does not have to be marked explicitly. But my experimentation suggests that this is not true: in the subclass, a nonoverride method is *not* automatically isolated to the main actor unless you explicitly mark the method or the subclass as `@MainActor`.

## Context Switching

By *context switching* I mean a change in thread context: code that has been running on the main thread proceeds to run on a background thread, or vice versa. Clearly it is of great importance that this should happen, and that it should happen cleanly and safely; otherwise, multithreaded code would be impossible.

### Implicit Context Switching

Your code can switch between the main thread and a background thread without your even being aware of it. And that's fine; for the most part, you won't *need* to be aware of it.

Consider, for example, the implementation of `fetchManyURLs`. Recall our earlier use of `addTask`:

```
for url in urls { // runs on the main thread
    group.addTask {
        // runs on a background thread
        return (url, try await self.download(url: url))
    }
}
```

In my testing, it happens that the `operation:` function that we supply in our call to `addTask` runs on a background thread, even if `fetchManyURLs` itself is called on the main thread. But nothing about the code calls our attention to that fact, and in this case there's no reason to be conscious of it.

Again, it happens that when you call the `Task` initializer, the task inherits the characteristics of the surrounding context. This means that the `operation:` code in a `Task` initializer in a view controller's `viewDidLoad` method runs on the main thread:

```
class ViewController: UIViewController { // marked @MainActor
    override func viewDidLoad() {
        super.viewDidLoad() // runs on the main thread
        Task {
            // runs on the main thread
            let result = try? await self.fetchManyURLs()
        }
    }
}
```

```

        // ...
    }
}

```

But again, nothing about the code calls our attention to that fact, and here there's no reason to be conscious of it.

Suppose, however, that we *want* a particular method to run on a background thread. Let's say it's our `fetchManyURLs` method. That's a perfectly reasonable thing to want; `fetchManyURLs` runs fine on a background thread, so we needn't use any main thread time running it. Well, that's what an actor is for! To make `fetchManyURLs` run on a background thread, we can isolate it to an actor.

To do that, I'll declare an actor `MyDownloader` and move my methods `download(url:)` and `fetchManyURLs` into that actor. Then I'll declare a property to hold an instance of that actor, and I'll call `fetchManyURLs` on that instance:

```

class ViewController: UIViewController {
    actor MyDownloader {
        func download(url: URL) async throws -> Data {
            // ... as before ...
        }
        func fetchManyURLs() async throws -> [URL:Data] {
            // ... as before ...
        }
    }
    let downloader = MyDownloader()
    override func viewDidLoad() {
        super.viewDidLoad()
        Task {
            // runs on the main thread
            // but fetchManyURLs runs on a background thread
            let result = try? await self.downloader.fetchManyURLs()
            // ...
        }
    }
}

```

The `fetchManyURLs` code runs on a background thread, because `self.downloader` is an actor. This is a very nice architecture, because it associates the thread context with the target object. The `MyDownloader` object itself insists that its methods will run on a background thread. But once again, nothing about the code says anything about what thread it's running on.

## Explicit Context Switching

Sometimes, you will want to specify the type of thread that some code should run on *at the site where that code appears*. How can you do that?

Let's take the two types of thread separately. First, suppose your code is going to be running on the main thread; how can you launch a task while specifying that it should *not* run on the main thread?

We have already seen that if you call the simple Task initializer, you'll get a task that inherits the characteristics of its surroundings. In a view controller's `viewDidLoad` method, the `operation:` function of a Task initializer runs on the main thread. To prevent that, you can call the `Task.detached` static method instead.

`Task.detached` is a factory method; like the Task initializer, the result is a Task object. And like the Task initializer, it takes an `operation:` function parameter, and it launches that function as a task. The difference is that `Task.detached` cuts off any relationship between the resulting Task object and the surrounding context, so the `operation:` function runs on its own background thread:

```
class ViewController: UIViewController { // marked @MainActor
    override func viewDidLoad() {
        super.viewDidLoad() // runs on the main thread
        Task.detached {
            // runs on a background thread
            let result = try? await self.fetchManyURLs()
            // ...
        }
    }
}
```

Now let's consider the opposite situation. Your code will be running on a background thread, and you need to insist that a block of code should run on the main thread. This situation arises a lot in iOS programming, because you're constantly interacting with interface code that is isolated to the main actor and *must* be called on the main thread.

Here's a typical case in point. Let's say we want to download some image data and display that image in our interface. We'd probably use a `UIImageView` to display the image, and if this is a view controller, we'd probably have a property referring to the `UIImageView`. (In real life, this property would likely be an outlet; see [Chapter 8](#).)

Suppose that for some reason we are calling `Task.detached` to run on a background thread, and in its `operation:` function we call our `download(url:)` method. We then proceed to convert the resulting Data object to a UIImage object, and assign it as the `image` property of the `UIImageView`:

```
class ViewController: UIViewController {
    var imageView : UIImageView?
    actor MyDownloader {
        // ...
    }
    let downloader = MyDownloader()
    override func viewDidLoad() {
```



```

super.viewDidLoad()
Task.detached {
    // runs on a background thread
    let url = URL(string: "https://www.apeth.com/pep/manny.jpg")!
    if let data = try? await self.downloader.download(url: url) {
        if let image = UIImage(data: data) {
            self.imageView?.image = image // compile error
        }
    }
}
}
}
}

```

That code doesn't compile. `UIImageView` is an interface class; it is isolated to the main actor. So we can't mutate its `image` property from a background thread, and the compiler stops us with an error: "Property `image` isolated to global actor `MainActor` can not be mutated from a non-isolated context."

What we want to do here is to step out to the main thread just long enough to mutate the image view's `image` property. To do so, we can call the special `MainActor.run` static method, which takes a function parameter:

```
await MainActor.run { self.imageView?.image = image }
```

But a word of warning: that sort of deliberate context switching to the main thread can be expensive. If you have multiple operations to perform on the main thread and you need to call `MainActor.run`, try to clump those operations into a single call to `MainActor.run`, so as not to switch contexts unnecessarily.

## More About Tasks

A `Task` object represents a structured concurrency task. A task is an atom of concurrency. An individual task has no concurrency internally, but it may run concurrently with other tasks or with main actor code. All code where it is legal to say `await`, and all code that is called from such a place, runs within some task. You can create a task by using the `Task` initializer, by calling `Task.detached`, by calling a task group's `addTask`, and by saying `async let`.

## Task Priority

A `Task` can have a *priority*. This priority doesn't need to be specified explicitly, because, by default, it is inherited from the surrounding context. But you *can* specify it if you want to.

All the ways of creating a task, except `async let`, allow you to provide a `priority` parameter. A priority value is a `TaskPriority` struct instance with a raw value; typically you'll specify the priority using a convenient static constant name. Some priority

values have two names, a general name and an iOS-specific name. Names and values as of this writing are:

- `.high`, aka `.userInitiated` (25)
- `.medium` (21)
- `.low`, aka `.utility` (17)
- `.background` (9)

## The Current Task

You can access the current task by calling the global `withUnsafeCurrentTask` function. It takes a function that receives an Optional unsafe reference to the current task as its parameter. If that reference is `nil`, there is no current task.

But there is usually no need to call `withUnsafeCurrentTask`. More often, you'll talk to the current task by means of static `Task` properties and methods; these call `withUnsafeCurrentTask` under the hood, so nothing is gained by calling it yourself. If there is no current task when you call a static `Task` member, a reasonable default value is returned.

For example, the current task's priority is `Task.currentPriority`. If there is no current task, but the code is simply running on the main thread in the normal course of things, the result is a `TaskPriority` whose raw value is 33.

## Sleeping

A useful static `Task` method is `sleep()`. This is an `async` method that pauses your code for a length of time you specify. It takes a `UInt64` representing nanoseconds. A related method, `sleep(nanoseconds:)`, can throw. (I'll explain later why that's useful.) You call these methods using `await`, so this is a *nonblocking pause*; sleeping in this way is safe and legal even on the main thread.

Nanoseconds are tiny; you will often prefer to specify seconds. Eventually the standard library will probably provide a way to do that; until then, it will be useful to have on hand an extension that converts:

```
extension Task where Success == Never, Failure == Never {
    static func sleep(_ seconds:Double) async {
        await self.sleep(UInt64(seconds * 1_000_000_000))
    }
    static func sleepThrowing(_ seconds:Double) async throws {
        try await self.sleep(nanoseconds: UInt64(seconds * 1_000_000_000))
    }
}
```

To illustrate, the following code prints, pauses for one second, and then prints again:

```
print("test1")
Task {
    await Task.sleep(1.0)
    print("test2")
}
```

Anyone who is familiar with Grand Central Dispatch will recognize this as analogous to `asyncAfter`.

Using `sleep`, you can write reliably time-consuming asynchronous functions that can be useful for informal testing or demonstration purposes. For instance, sleeping is a good way to pretend you're performing some kind of asynchronous server communication. Here's an actor vending a couple of utility functions designed to provide feedback in the console:

```
actor Waiter {
    private var randSecs : Double { Double.random(in: 1...3) }
    func wait(_ i:Int) async {
        print("wait start", i)
        await Task.sleep(randSecs)
        print("wait end", i)
    }
    func waitThrowing(_ i:Int) async throws {
        print("wait start", i)
        do {
            try await Task.sleepThrowing(randSecs)
        } catch {
            print("wait throwing", i)
            throw error
        }
        print("wait end", i)
    }
}
```

## Yielding

If a task takes significant time to run, and if it doesn't say `await` regularly, you might like to express a willingness to be suspended momentarily just in case other tasks are queued up waiting for threads to come free. For example, a computation-heavy background task whose basis is a loop, if the result is not needed as soon as possible, might pause at the start of each iteration (or some iterations, at least).

To signify a willingness to be suspended, call the `Task yield` static method. It is `async`; basically, you're sleeping for an unspecified time. The sleep time might turn out to be zero, if no pending tasks need to be granted execution time, but if it isn't, you're not putting any limit on how long you're willing to sleep.

## Cancellation

If a task takes significant time to run, you might discover while the task is still running that you no longer need it to keep doing whatever it's doing. In that case, it may be possible to *cancel* the task.

The way to cancel a task explicitly is to call its `cancel` method. You'll typically want to tell a task to cancel from outside the task, so you'll need a *reference* to the task. You can capture a `Task` object when you create it, and if you do, you can subsequently send messages to the `Task`. That gives you a way to tell the `Task` to `cancel`. This is not an `async` method, so it can be called from anywhere.

Here's an artificial example, useful as a test bed. We launch a time-consuming task and cancel it almost immediately:

```
let myTask = Task {  
    // ...  
}  
Task {  
    await Task.sleep(100)  
    myTask.cancel()  
}
```

Merely saying `cancel` to a task does not necessarily have any automatic effect on your code running inside the task. Stopping work if the task is cancelled is up to you! If you want a task to be effectively cancellable, you have to ensure that that functionality is built into the task somehow. This architecture is deliberate. There's no telling what cancellation might mean for your task, so it's up to you to stop work in good order, in whatever way makes sense given the nature of the task.

### Cancellation strategies

In order to stop work in response to cancellation, you will need to *notice* that the task has been cancelled. The `cancel` method makes this possible by setting the `isCancelled` `Bool` property of the task to `true`. You can check that setting from within the task by examining the `Task.isCancelled` static property.

There are two main ways to respond to the discovery that the task has been cancelled:

#### *Stop looping*

If there's a loop at the heart of your task, you can examine `Task.isCancelled` at the top of the loop and `break` if it is true. The implication here may be that it is meaningful and coherent for your task to return a partial result as the outcome of omitting some iterations of the loop.

## Throw

Throwing an error aborts your code immediately and sends a signal up the call chain. This can work at any depth within the call chain; if the thrown error is not caught, or if it is rethrown every time it is caught, it percolates all the way up to the top level of the task and the entire task is aborted.

As a shortcut, the `Task.checkCancellation` static method throws an error (a `CancellationError`) if the current task has been cancelled. Again, the top of a loop might be a good place to make that call.

Before you put any effort into making your task cancellable, it might be worthwhile to consider whether you are calling any throws methods that already know how to throw on cancellation. If so, you might have no work to do.

To illustrate, here's a toy example. I'll first create a task and make it cancellable; then I'll show that I really didn't need to make the task cancellable in the first place.

Recall the `Waiter` actor that I created earlier. I've stored an instance of that actor as an instance property `self.waiter`. Now I'll launch a task that uses `self.waiter` to wait three times in succession — but I'll cancel that task after a very short delay:

```
let waitTask = Task {
  for i in 1...3 {
    await self.waiter.wait(i)
  }
}
Task {
  await Task.sleep(0.5)
  waitTask.cancel()
}
```

Our `cancel` call has no discernable result. We still wait three times, as if the task had never been cancelled:

```
wait start 1
wait end 1
wait start 2
wait end 2
wait start 3
wait end 3
```

The reason is that I'm not checking for cancellation. Okay, I'll check for cancellation at the top of the loop:

```
let waitTask = Task {
  for i in 1...3 {
    if Task.isCancelled { // *
      break
    }
    await self.waiter.wait(i)
  }
}
```

```

    }
  }
  Task {
    await Task.sleep(0.5)
    waitTask.cancel()
  }
}

```

This time, the result is that we only wait once:

```

wait start 1
wait end 1

```

That worked; our `cancel` call caused the loop to stop after the first iteration, and the task finished in good order.

A more compact approach would be to call `checkCancellation` and simply throw an error if we've been cancelled:

```

let waitTask = Task {
  for i in 1...3 {
    try Task.checkCancellation() // *
    await self.waiter.wait(i)
  }
}

```

But it turns out there's no need for any of that. My `Waiter`'s `waitThrowing` method calls my `Task` extension method `sleepThrowing`, which calls the `Task` static method `sleep(nanoseconds:)`. The `sleep(nanoseconds:)` method *already* knows how to check for cancellation! It throws an error (a `CancellationError`) if we are cancelled. So I can rewrite the task like this:

```

let waitTask = Task {
  for i in 1...3 {
    try await self.waiter.waitThrowing(i)
  }
}

```

Now the output when we cancel the task is:

```

wait start 1
wait throwing 1

```

The call to `sleep(nanoseconds:)` resulted in an error being thrown the moment we were cancelled. This thrown error percolated all the way up the call chain, and the entire task was aborted. So I was able to write a cancellable task without explicitly checking for cancellation.

Our `download(url:)` method works the same way. It calls the `URLSession.shared` method `data(from:)`. This is a `throws` method, and one of the reasons it can throw an error is if it detects that the task has been cancelled. So if a call to `data(from:)` lies at the heart of our task, the task might be cancellable in a satisfactory way with no additional work on our part.

Consider the following task, where we download three URLs sequentially:

```
let downloadTask = Task {
  let urls: [URL] = [
    URL(string: "https://www.apeth.com/pep/manny.jpg")!,
    URL(string: "https://www.apeth.com/pep/moe.jpg")!,
    URL(string: "https://www.apeth.com/pep/jack.jpg")!,
  ]
  for url in urls {
    let data = try await self.downloader.download(url: url)
    // ...
  }
}
```

That task *is cancellable*. There is no need to check `Task.isCancelled` each time through the loop. The `data(from:)` method responds to cancellation by throwing an error, and that thrown error will percolate up to the top of the task and abort it.

A task that revolves around receiving an asynchronous sequence may be cancellable. A well-behaved asynchronous sequence will detect cancellation and will stop emitting values. An `AsyncStream`, such as the one we created earlier, is a well-behaved asynchronous sequence; when the surrounding task is cancelled, a call to the stream iterator's `next()` will yield `nil`, signalling that there are no more values. An asynchronous `for` loop will detect that and will terminate.

## Cancelling subtasks

A subtask is what you create by saying `async let` or by telling a task group to `addTask`. The relationship between a task and its subtasks is what puts the “structured” into structured concurrency. When you’ve got subtasks, the real power of structured concurrency emerges in connection with cancellation. Powerful automatic behaviors suddenly spring to life:

- When a task is told to `cancel`, then if it has subtasks, those subtasks are told to `cancel automatically`.
- When a task group throws an error, the subtasks of that task group are told to `cancel automatically`.

To demonstrate, consider a task group version of the previous example:

```
let downloadTask = Task {
  let urls: [URL] = [
    URL(string: "https://www.apeth.com/pep/manny.jpg")!,
    URL(string: "https://www.apeth.com/pep/moe.jpg")!,
    URL(string: "https://www.apeth.com/pep/jack.jpg")!,
  ]
  try await withThrowingTaskGroup(of: Data.self) { group in
    for url in urls {
      group.addTask {
        return try await self.downloader.download(url: url)
      }
    }
  }
}
```

```

        }
    }
    for try await data in group {
        // ...
    }
}

```

That task *is cancellable*. If you cancel it externally, the cancellation percolates down to the subtasks, where the `data(from:)` method will detect it. So if any of the downloads is incomplete at the time of cancellation, that download will be aborted and the subtask will throw an error, with the error percolating up to the task and aborting it as well.

Moreover, a task with a task group is cancellable *internally* by way of the task group’s subtasks. This can happen in two ways:

#### *The task group throws an error*

When the task group throws an error, its subtasks are told to cancel automatically. The most common use case is that one of the *subtasks* throws an error and the task group *rethrows* it; the other subtasks are thereupon told to cancel.

For example, suppose we change one of the URLs to a bad URL, one whose domain does not exist. Then `data(from:)` will throw an error (“A server with the specified hostname could not be found”), and the `for try await` loop will immediately receive that error and rethrow it. That will be translated into a cancel message sent to the other subtasks. If any of the other downloads is not yet completed at that time, it will be aborted.

#### *You tell the group to cancelAll*

The `cancelAll` method tells the task group to send `cancel` to all of its subtasks. You can call the `cancelAll` method from any place in your code where the task group is in scope. That includes code *inside* an `addTask` call’s operation: function. So any subtask can cancel all the other subtasks.

That doesn’t necessarily cancel the surrounding task (the `downloadTask` in our example); it simply causes the task group to complete in good order, depending on what cancellation means for your subtasks. But of course it *will* cause the surrounding task to abort if any of the subtasks throws an error in response to being cancelled and the thrown error percolates up to the top level.

If you add a subtask to a task group that has already been cancelled, the subtask will launch but then will immediately be cancelled. That’s a coherent response, but if it worries you, you might prefer not to add the subtask in the first place. To implement that, instead of calling `addTask`, you can call `addTaskUnlessCancelled` to create the subtask conditionally. It returns a `Bool`, which is `false` if we *were* cancelled (and the



subtask was not added), so you can detect that and abort trying to add any further subtasks if desired.

What about a subtask created with `async let`? You don't have a reference to that subtask, and multiple `async let` subtasks can't cancel one another. But you do still get the benefit of top-down cancellation: if you cancel the parent task, the child subtasks created with `async let` will be told to cancel.

When an `async let` subtask throws an error, and the error is rethrown by the corresponding `try await` and the outer task aborts, an interesting edge case arises. What if, at that moment, there are other `await` references to `async let` variables that have not yet been encountered? Like this:

```
async let one = // ... this subtask launches and will eventually throw
async let two = // ... this subtask launches as well
await Task.sleep(0.1)
print("I will try to await 1")
_ = try await one // we rethrow the throw, and the code aborts
print("I have just tried to await 1")
await Task.sleep(0.1)
print("I will try to await 2")
_ = try await two
```

Let's say subtask one actually throws an error. Now the console says:

```
I will try to await 1
```

And that's *all* it says! In the next line, we receive and rethrow the error (`try await one`), and the code aborts. So we never got to say `try await two`, which appears later. But subtask two was launched and is still running. So what happens to poor old subtask two now?

The answer is that subtask two is *cancelled and awaited automatically*. Our main task is being aborted, but structured concurrency guarantees that its lifetime must embrace the lifetimes of its subtasks. Therefore, since *we* did not await subtask two, the runtime awaits it. But first, it cancels it; if subtask two is cancellable, so that it stops work or throws an error when it is cancelled, then it can shorten its own lifetime, but if not, it will be permitted to run to completion in good order.

It is also possible to install a cancellation handler on the current task. You call the global function `withTaskCancellationHandler(operation:onCancel:)`, which takes two functions; the `operation:` function is called immediately (asynchronously), while the `onCancel:` function is held in reserve and is called instantly if the surrounding task is cancelled. However, you're less likely to need this than the other cancellation techniques. Note that the `onCancel:` function cannot throw.

## More About Actors

An actor is a reference type that, by default, runs its code on a background thread. It protects its shared state by requiring that outside access to everything except constant properties say `await`, and by denying outside code the ability to mutate a variable property.

An actor is serialized. While an actor's code is running, no other code of that actor can start; once outside code has gained access to an actor member using `await`, no other code can gain access using `await` until the first access comes to an end. This makes it safe for the actor to access its own shared state internally, even in a multi-threaded world; a mutable instance property of the actor won't be accessed on multiple threads simultaneously, because the actor doesn't run multiple threads simultaneously.

## Reentrancy

Actor serialization unfortunately introduces a risk of being overly aggressive, and might even lead to possible deadlock. To mitigate that risk, there's an important exception to actor serialization: actors are *reentrant*. This means that when an actor *itself* says `await`, then *while the actor's code is waiting*, its members *can* be accessed from outside the actor using `await`. As a result, actors that say `await` must be careful in their assumptions about their own internal shared state.

We can use the `MyDownloader` actor to demonstrate why it makes sense for actors to be reentrant. Consider a task group whose subtasks make a call to `MyDownloader`'s `download(url:)` method:

```
for url in urls {
    group.addTask {
        return try await self.downloader.download(url: url)
    }
}
```

The only thing `download(url:)` does, basically, is call the `URLSession.shared` method `data(for:)` to perform the actual downloading. That method is `async`, so it must be called with `await`, and at that point `download(url:)` pauses. If actors were *not* reentrant, then at that point, all the other subtasks would be stuck waiting to call `download(url:)`! The downloads would all become lined up serially, and the entire purpose of the task group, namely to implement concurrency, would be completely undermined. But an actor *is* reentrant; therefore, while one call to `download(url:)` is paused, another call to `download(url:)` is permitted to begin.

But the flexibility provided by reentrancy comes at a price: while actor code is paused at an `await`, shared state can change. Here's a toy example:

```

actor MyDownloader {
  var counter = 0
  func download(url: URL) async throws -> Data {
    counter += 1
    let num = counter
    let result = try await URLSession.shared.data(from: url)
    print(num == counter)
    return result.0 // the data
  }
}

```

The fact that `download(url:)` downloads is irrelevant here; concentrate on the value of `counter` and the value of `num`, before and after the `await` pause. We're used to the idea that after you've said `let num = counter`, the two values `num` and `counter` are equal, and if you don't change `counter`, they stay equal. But the printed `Bool` value `num == counter` is quite likely to be `false`, because during the `await` pause, another call to this same method can increment `counter` again. If code after the `await` pause blithely assumes that the value of `counter` is the same as it was before the `await` pause, it can easily be wrong and the program can misbehave.

## The Keyword `nonisolated`

Earlier, I enumerated the basic default rules for actor isolation. But there are times when those rules are inappropriate. Consider this simple (and silly) actor:

```

actor Counter {
  let id : String
  var total = 0
  init(id:String) {
    self.id = id
  }
  func inc() {
    self.total += 1
  }
  func capID() -> String {
    return self.id.capitalized
  }
}

```

Now let's see what happens when we try to access the members of that actor:

```

let counter = Counter(id:"matt")
let id = counter.id ❶
let total = await counter.total ❷
await counter.inc() ❸
let capID = counter.capID() // compile error ❹

```

- ❶ We can access the `id` property directly; it's a constant.
- ❷ To access the `total` property, we must say `await`; it's a variable property (`var`).

- ❸ To call `inc`, we must say `await`; it's a method.
- ❹ To call `capID`, we must say `await`. But that's ridiculous! The rule is that a method of the actor must be called asynchronously, to guarantee the integrity of shared state, such as the `total` property. But the `capID` method *doesn't* access the `total` property; the only other member of the actor touched by the actor's `capID` method is its `id` property, which is a constant value type. This access is every bit as safe as accessing `id` itself. If we can access `id` from outside without saying `await`, we should be able to call `capID` from outside without saying `await`.

Our reasoning about `capID` is correct, so let's tell the compiler about it. To do so, we declare the `capID` method as `nonisolated`:

```
nonisolated func capID() -> String {  
    return self.id.capitalized  
}
```

Now our code compiles:

```
let capID = counter.capID() // fine
```

The compiler is not completely passive when we declare an actor member `nonisolated`. We declared `capID` to be `nonisolated`, and the compiler permitted it, because it agrees with our reasoning: `id` is indeed the only member referred to by the `capID` method, and fetching its value is safe because it's a constant. But if we were to declare the `inc` method `nonisolated`, the compiler would slap our hand: "Actor-isolated property `total` can not be mutated from a non-isolated context." The `total` property is isolated, because it's a variable property, and you can't lie your way out of that fact by claiming that a method that mutates it is `nonisolated`.

And it isn't just a matter of mutation. Suppose our actor has a method `reportTotal` that merely *fetches* the `total` value:

```
func reportTotal() -> Int {  
    return self.total  
}
```

You can't declare that method `nonisolated` either: "Actor-isolated property `total` can not be referenced from a non-isolated context."

## The Keyword `isolated`

Just as there is `nonisolated`, there is also `isolated`. To see why this is useful, consider this method; it is *not* declared in the `Counter` actor, but it accepts a `Counter` actor instance as its parameter:

```
func inc(counter: Counter) {
    counter.inc() // compile error
}
```

The compiler complains, because the `Counter inc` method is isolated to an actor, `Counter`, whereas we are elsewhere, such as on the main actor. One solution is to declare this an `async` method, with all that follows:

```
func inc(counter: Counter) async {
    await counter.inc()
}
```

But there's another way. We can declare the `Counter` parameter `isolated`. This declaration goes in the same place that `inout` would go, before the name of the type:

```
func inc(counter: isolated Counter) {
    counter.inc()
}
```

The effect is to bind this method to the `Counter` isolation domain. Loosely speaking, you can think of the `inc(counter:)` method as running on `Counter`'s background thread. It is now effectively part of the `Counter` actor, even though it is not declared within the `Counter` actor. So it can call a `Counter` method in the same way that a `Counter` can call a method on `self`, without saying `async` and `await`.

That move, however, merely pushes the need for `async` and `await` back to whatever method calls this one. Some other method in this same object can call `inc(counter:)` only from an `async` context and only by saying `await`, just as it would have to do if it were calling a full-fledged `Counter` method:

```
func callInc() async {
    let counter = Counter(id: "matt")
    await self.inc(counter: counter)
}
```

## Global Actors

I have already said that there is a hidden global actor, the *main actor*, called `MainActor`. You can bind a method, a property, or an entire type to the main actor by saying `@MainActor`.

The mechanism by which the main actor is injected into the environment is open to your use. The main actor is a built-in global actor, but you are also free to make your own global actors. I can't think of a good reason to do this, but the mechanism is interesting, and it's part of the language starting in Swift 5.5, so I'll describe it.

To create a global actor, you declare a struct with the `@globalActor` attribute. Your struct must also conform to the `GlobalActor` protocol. Conformance is easy: you declare a shared static method that returns an instance of an actor as a singleton.

Typically, that actor will be declared internally within your struct; it need not have any members:

```
@globalActor struct MyGlobalActor {  
    actor MyActor {}  
    static let shared = MyActor()  
}
```

In that code, the actor name `MyActor` is scoped internally to the struct, and won't conflict with any names that you declare elsewhere. Meanwhile, the struct name `MyGlobalActor` becomes the name of an attribute `@MyGlobalActor`, parallel to `@MainActor`. So your code elsewhere can be bound to `MyGlobalActor` by marking it with `@MyGlobalActor`:

```
@MyGlobalActor func f() {  
    print("hello")  
}
```

The body of that function is isolated to `MyGlobalActor`; you can think of it as running on `MyGlobalActor`'s thread. If you're on a different actor, such as the main actor, you have to say `await` in order to call `f`. But other code that is also marked `@MyGlobalActor` does not have to say `await` in order to call `f`; they are in the same isolation domain.

## Sendable

One of the goals of Swift structured concurrency is to build thread-safe behavior into the language. To make this possible, the compiler needs to be able to check whether a particular value can be safely communicated between threads in the first place.

This determination is easy for certain broad categories. A simple value type can be safely communicated from one thread to another, because what's communicated is a copy; nothing mutable is being shared. A reference type is likely to be mutable in place and should not be shared between threads. In between are things like structs and collections; if the properties of a struct or the elements of a collection are value types, it is safe for sharing. There are additional subtleties; for example, a reference type that is semantically immutable (like Cocoa's `NSString`) is safe to share.

Swift structured concurrency refers to types that are safe to share across threads as *sendable*. To enforce the requirement that values used in certain ways be sendable, Swift 5.5 introduces the `Sendable` protocol. A type that cannot conform to `Sendable` isn't sendable, and the compiler will stop you from using it as if it were. For example, an isolated actor method cannot take a parameter that isn't `Sendable`.

Similar restrictions apply to function types, especially with regard to anonymous functions behaving as closures. In order to be passed safely across threads, a closure's captured values must be `Sendable` types. Moreover, a closure must not be permitted

to capture a reference to a `Sendable` type value and then mutate it, because that mutation could take place across thread contexts; so the mutation is legal only if the value was copied explicitly by including it in the capture list (“[Capture Lists](#)” on page 60). To enforce these rules, there’s a `@Sendable` attribute on function types; only `@Sendable` functions can be passed across thread contexts.

It’s useful to be aware of the `Sendable` protocol and the `@Sendable` function attribute because you may see those terms pop up, especially in error messages from the compiler. But at the time of this writing, the Swift 5.5 compiler is not yet actively checking for `Sendable` conformance.

This means that structured concurrency code is not being automatically sanitized for thread-safety. The following code is wrongly legal:

```
class Dog {
    var name = "Rover"
}
actor MyActor {
    let dog = Dog()
    func getMyDog() -> Dog? { self.dog }
}
func test() async {
    let act = MyActor()
    let dog1 = await act.dog // should be illegal
    let dog2 = await act.getMyDog() // should be illegal
    // ...
}
```

That code should be illegal; by letting us capture a `Dog` property as `dog1` and `dog2`, the actor is handing out references to a mutable object, which can now be mutated on multiple threads.

You can turn on `sendable` checking experimentally for your iOS project by entering the following in the Other Swift Flags build setting:

```
-warn-concurrency
```

Then choose Product → Clean Build Folder to get your code to recompile ([Chapter 10](#)). This will catch the illegal lines; the compiler warns. If the compiler warns you about things you feel you shouldn’t have to be warned about, there are some tricks you can use to calm the compiler’s fears. Here’s a snippet of code that should be familiar by now:

```
group.addTask {
    return [url: try await self.download(url: url)]
}
```

In order to quiet the warnings from the compiler about those lines, I had to add `self` to the capture list:

```
group.addTask { [self] in
    return [url: try await self.download(url: url)]
}
```

I also had to turn off Sendable checking for the URL and Data types:

```
extension URL: @unchecked Sendable {}
extension Data: @unchecked Sendable {}
```

Eventually, reliable Sendable checking will be baked into the compiler, but that isn't slated to happen until Swift 6 is released. You can find out more about where all this is headed by reading the Sendable proposal at the [Swift Evolution proposals website](#).



## PART II

---

# IDE

By now, you're doubtless anxious to jump in and start writing an app. To do that, you need a solid grounding in the tools you'll be using. The heart and soul of those tools can be summed up in one word: Xcode. In this part of the book we explore Xcode, the *IDE* (integrated development environment) in which you'll be programming iOS. Xcode is a big program, and writing an app involves coordinating a lot of pieces; this part of the book will help you become comfortable with Xcode. Along the way, we'll generate a simple working app through some hands-on tutorials.

- **Chapter 7** tours Xcode and explains the architecture of the *project*, the collection of files from which an app is generated.
- **Chapter 8** is about nibs. A *nib* is a file containing a drawing of your interface. Understanding nibs — how they work and how they relate to your code — is crucial to your use of Xcode and to development of just about any Cocoa app.
- **Chapter 9** pauses to discuss the Xcode documentation and other sources of information on the API.
- **Chapter 10** explains editing your code, testing and debugging your code, and the various steps you'll take on the way to submitting your app to the App Store. You'll probably want to skim this chapter quickly at first, returning to it as a detailed reference later while developing and submitting an actual app.



---

# Anatomy of an Xcode Project

Xcode is the application used to develop an iOS app. An Xcode *project* is the source for an app; it's the entire collection of files and settings used to construct the app. To create, develop, and maintain an app, it helps to know how to manipulate and navigate an Xcode project. You'll want to be familiar with Xcode, and you'll need to know about the nature and structure of Xcode projects and how Xcode shows them to you. That's the subject of this chapter.

Xcode is a powerful, complex, and very large program. Our survey will chart a safe, restricted, and essential path, focusing on aspects of Xcode that you most need to understand immediately, and resolutely ignoring everything else.



The term “Xcode” is used in two ways. It's the name of the application in which you edit and build your app, and it's the name of an entire suite of utilities that accompanies it; in the latter sense, Instruments and the Simulator are part of Xcode. This ambiguity should generally present little difficulty.

## New Project

Even before you've written any code, an Xcode project is quite elaborate. To see this, let's make a new, essentially “empty” project; you'll find that it isn't empty at all.

1. Start up Xcode and choose File → New → Project.
2. The “Choose a template” dialog appears. The *template* is your project's initial set of files and settings. When you pick a template, you're really picking an existing folder full of files; this folder is hidden deep inside the Xcode bundle, and will essentially be copied, with a few values filled in, to create your project.

In this case, select iOS; under Application, select the App template. Click Next.

3. You are now asked to provide a name for your project (Product Name). Let's call our new project *Empty Window*.

As Xcode copies the template folder, it's going to insert the project's name in several places, including using it as the name of the app. Whatever you type at this moment is something you'll be seeing throughout your project. You are not locked into the name of your project forever, though, and there's a separate setting allowing you to change the name of the app that your project produces. (I'll talk later about name changes; see [“Renaming Parts of a Project” on page 434.](#))

Spaces are legal in the project name, the app name, and the various names of files and folders that Xcode will generate automatically; and in the few places where spaces are problematic (such as the bundle identifier, which I'll discuss in a moment), the name you type as the Product Name will have its spaces converted to hyphens. But do *not* use any other punctuation in your project name! Such punctuation can cause Xcode features to break in subtle ways.

4. Ignore the Team pop-up menu for now (I'll discuss its significance in [Chapter 10](#)) and focus on the Organization Identifier field. The first time you create a project, this field will be blank, and you should fill it in. The goal here is to create a unique string identifying you or your organization. The convention is to start the organization identifier with `com.` and to follow it with a string (possibly with multiple dot-components) that no one else is likely to use.

The significance of the organization identifier is its contribution to the bundle identifier, which is shown in gray below the organization identifier. Every app on a device or submitted to the App Store needs a unique bundle identifier. Your app's bundle identifier will consist by default of the organization identifier plus a version of the project's name; if you choose a unique organization identifier and give every project a unique name within your personal world, the bundle identifier will uniquely identify this project and the app that it produces. (You will be able to change the bundle identifier manually later if necessary.)

5. The Interface pop-up menu should say Storyboard, not SwiftUI.
6. Because you chose Storyboard for the Interface pop-up menu, the Language pop-up menu lets you choose between Swift and Objective-C. Choose Swift.

This choice is not positively binding; it dictates the initial structure and code of the project template, but you are free to add Swift files to an Objective-C project, or Objective-C files to a Swift project. You can even start with an Objective-C project and decide later to convert it completely to Swift. (See [“Bilingual Targets” on page 735.](#))

7. For this example project, make sure Use Core Data and Include Tests are *not* checked. Click Next.

8. You’ve now told Xcode how to construct your project. Basically, it’s going to copy a template folder from somewhere deep within the Xcode application bundle. But you need to tell it where to copy this template folder *to*. That’s why Xcode is now presenting a Save dialog with a Create button. You are to specify the location of a folder that is about to be created — the *project folder* for this project. The project folder can go just about anywhere, and you can move it after creating it. I usually create new projects on the Desktop.
9. If you don’t see any additional options, such as Source Control, click the Options button to reveal them. Xcode offers, through a checkbox, to create a Git repository for your project; in real life, this can be a great convenience (see [Chapter 10](#)), but for now, uncheck that checkbox. If you see an Add To pop-up menu, leave it at the default, “Don’t add to any project or workspace.” Click Create.

The *Empty Window* project folder is created on disk (on the Desktop, if that’s the location you just specified), and the project window for the Empty Window project opens in Xcode.

The project we’ve just created is a working project; it really does build an iOS app called Empty Window. To see this, you can actually build the app — and run it! The scheme and destination in the project window’s toolbar will be listed as Empty Window and some model of iPhone. (The scheme and destination are actually pop-up menus, so you can click them to change their values if needed.) Choose Product → Run. After some delay, the Simulator application opens and displays your app running — an empty white screen.



To *build* a project is to compile its code and assemble the compiled code, together with various resources, into the actual app. Typically, if you want to know whether your code compiles and your project is consistently and correctly constructed, you’ll build the project (Product → Build). To *run* a project is to launch the built app, in the Simulator or on a connected device; if you want to know whether your code works as expected, you’ll run the project (Product → Run), which automatically builds first if necessary.

## The Project Window

An Xcode project embodies a lot of information about what files constitute the project and how they are to be used when building the app, such as:

- The source files (your code) that are to be compiled
- Any *.storyboard* or *.xib* files, graphically expressing interface objects to be instantiated as your app runs
- Any resources, such as icons, images, or sound files, that are to be part of the app




Figure 7-1. The project window

- All settings (instructions to the compiler, to the linker, and so on) that are to be obeyed as the app is built
- Any frameworks that the code will need when it runs

A single Xcode project window presents all of this information. It lets you access, edit, and navigate your code. It reports the progress and results of such procedures as building or debugging an app. And it does a lot more than that. This window displays a lot of information and embodies a lot of functionality! A project window is powerful and elaborate; learning to navigate and understand it takes time. Let's pause to survey this window and see how it is constructed.

A project window has four main parts (Figure 7-1):

1. On the left is the Navigator pane. Show and hide it with View → Navigators → Show/Hide Navigator (Command-0) or with the button at the left end of the toolbar.
2. In the middle is the Editor pane (or simply “editor”). This is the main area of a project window. A project window nearly always displays an Editor pane.
3. On the right is the Inspector pane. Show and hide it with View → Inspectors → Show/Hide Inspector (Command-Option-0) or with the button at the right end of the toolbar.
4. At the bottom is the Debug pane. Show and hide it with View → Debug Area → Show/Hide Debug Area (Command-Shift-Y) or with the button at the right end of the debug pane's top bar.



All Xcode keyboard shortcuts can be customized; see the Key Bindings pane of the Preferences window. Keyboard shortcuts that I cite are the defaults.

## The Navigator Pane

The Navigator pane is the column of information at the left of the project window. Among other things, it's your primary mechanism for controlling what you see in the main area of the project window (the editor). An important use pattern for Xcode is: you select something in the Navigator pane, and that thing is displayed in the editor.

It is possible to toggle the visibility of the Navigator pane (View → Navigators → Hide/Show Navigator, or Command-0); you might hide the Navigator pane temporarily to maximize your screen real estate (especially on a smaller monitor). You can change the Navigator pane's width by dragging the vertical line at its right edge. If the project window is being displayed fullscreen with the Navigator pane hidden, you can display the Navigator pane temporarily by hovering the mouse at the left side of the screen.

The Navigator pane can display nine different sets of information; there are actually nine navigators. These are represented by the nine icons across its top; to switch among them, use these icons or their keyboard shortcuts (Command-1, Command-2, and so on). If the Navigator pane is hidden, pressing a navigator's keyboard shortcut both shows the Navigator pane and switches to that navigator.

Depending on your settings in the Behaviors pane of Xcode's preferences, a navigator might show itself automatically when you perform a certain action. For example, when you build your project, if warning messages or error messages are generated, the Issue navigator may appear. This automatic behavior will not prove troublesome, because it is usually the behavior you want, and if it isn't, you can change it; plus you can easily switch to a different navigator at any time.

Let's begin experimenting immediately with the various navigators:

### *Project navigator (Command-1)*

Click [here](#) for basic navigation through the files that constitute your project (**Figure 7-2**). For example, in the Empty Window folder (the folder-like things in the Project navigator are actually called *groups*), click *AppDelegate.swift* to view its code in the editor.

At the top of the Project navigator, with a blue Xcode icon, is the Empty Window project itself; click it to view the settings associated with your project and its targets. Don't change anything here without knowing what you're doing!

The filter bar at the bottom of the Project navigator lets you limit what files are shown; when there are many files, this is great for quickly reaching a file with a known name. For example, try typing "delegate" in the filter bar search field.

Don't forget to remove your filter when you're done experimenting! Once you've filtered a navigator, it stays filtered until you remove the filter — even if you close the project. A common mistake is to filter a navigator, forget that you've done so,




Figure 7-2. The Project navigator

fail to notice the filter (because you’re looking at the navigator itself, not down at the bottom where the filter bar is), and wonder, “Hey, where did all my files go?”



New in Xcode 13, file extensions in the Project navigator (and elsewhere in the Xcode interface) can be suppressed, using a pop-up menu in Xcode’s General preference pane. I like file extensions, and throughout this book I’ll include the extension when I give a file’s name.

#### Source Control navigator (Command-2)

The Source Control navigator helps you manipulate how your project’s files are handled through version control. I’ll discuss version control in [Chapter 10](#).

#### Symbol navigator (Command-3)

A *symbol* is a name, typically the name of a class or method. The Symbol navigator lists symbols available to your code. Among other things, this can be useful for navigating. For example, highlight the first two icons in the filter bar (so that they are filled), twist open the class listings, and see how quickly you can reach your code’s implementation of the `SceneDelegate` class’s `sceneDidBecomeActive(_:)` method.

Try highlighting the filter bar icons in various ways to see how the contents of the Symbol navigator change. Type in the search field in the filter bar to limit what appears in the Symbol navigator; for example, try typing “active” in the search field, and see what happens.

#### Find navigator (Command-4)

This is a powerful search facility for finding text globally in your project. You can also summon the Find navigator with Find → Find in Project (Command-Shift-F). The words above the search field show what options are currently in force; they are pop-up menus, so click one to change the options. This is a powerful intelligent search that can filter on how a term is used. Try searching for






Figure 7-3. The Find navigator

“delegate” among References; then change it to search among Definitions (Figure 7-3). Click a search result to jump to it in your code.

Below the search field, at the left, is the current *search scope*. This limits what files will be searched. Click it to reveal the search scopes. You can create or edit a “smart” scope (for example, search only *.swift* files), and you can limit the search to one or more groups (folders).

You can type in the other search field, the one in the filter bar at the bottom, to limit further which search results are displayed. (I’m going to stop calling your attention to the filter bar now; every navigator has it in some form.)

#### Issue navigator (Command-5)

You’ll need this navigator primarily when your code has issues. This doesn’t refer to emotional instability; it’s Xcode’s term for warning and error messages emitted when you build your project. The Issue navigator can also display certain runtime issues (such as leaks, as I’ll explain in Chapter 10).

To see the Issue navigator in action, let’s give your code a buildtime issue. Navigate to the file *AppDelegate.swift*, and in the blank line after the last comment at the top of the file’s contents, above the `import` line, type `howdy`. Build the project (Command-B). Switch to the Issue navigator if it doesn’t appear automatically; in its Buildtime pane, it displays some error messages, showing that the compiler is unable to cope with this illegal word appearing in an illegal place. Click an issue to see it within its file. In your code, issue banners appear to the right of lines containing issues; the compiler can even underline the troublesome spot within a line. But it’s always a good idea to look at the Issue navigator as well, because it may contain additional useful information.

Now that you’ve made Xcode miserable, select “howdy” and delete it; save and build again, and your issues will be gone. If only real life were this easy!

You can create a custom buildtime issue, either a compile error or a warning, by starting a line with `#error` or `#warning` respectively followed by a string literal in parentheses, like this: `#warning("Fix this!")`. This can be a dramatic way to




Figure 7-4. The Debug layout

leave a note to whoever subsequently tries to compile this code — possibly your future self.

### Test navigator (Command-6)

This navigator lists test files and individual test methods and permits you to run your tests and see whether they succeeded. A test is code that isn't part of your app; rather, it calls a bit of your app's code, or exercises your app's interface, to see whether things behave as expected. I'll talk more about tests in [Chapter 10](#).

### Debug navigator (Command-7)

By default, this navigator will appear when your code is paused while you're debugging it. There is not a strong distinction in Xcode between running and debugging; the milieu is the same. The difference is mostly a matter of whether breakpoints are obeyed (more about that, and about debugging in general, in [Chapter 10](#)).

To see the Debug navigator in action, you'll need to give your code a breakpoint. Navigate once more to the file *AppDelegate.swift*, select in the line that says `return true`, and choose **Debug** → **Breakpoints** → **Create Breakpoint at Current Line** to make a breakpoint marker appear on that line. Run the project. By default, as the breakpoint is encountered, the Navigator pane switches to the Debug navigator, and the Debug pane appears at the bottom of the window. This overall layout ([Figure 7-4](#)) will rapidly become familiar as you debug your projects.

The Debug navigator starts with several numeric and graphical displays of profiling information (at a minimum, you'll see CPU, Memory, Disk, and Network); click one to see extensive graphical information in the editor. This information allows you to track possible misbehavior of your app as you run it, without the

added complexity of running the Instruments utility (discussed in [Chapter 10](#)). To toggle the visibility of the profiling information at the top of the Debug navigator, click the “gauge” icon (to the right of the process’s name).

The Debug navigator also displays the call stack, with the names of the nested methods in which a pause occurs; as you would expect, you can click a method name to navigate to it. You can shorten or lengthen the list with the first button in the filter bar at the bottom of the navigator.

The Debug pane can be shown or hidden at will: choose View → Debug Area → Hide/Show Debug Area, or Command-Shift-Y, or click the button at the far right of its top bar. The top bar, or *debug bar*, contains various buttons. Below it, the debug area consists of two subpanes:

*The variables list (on the left)*

The variables in scope for the selected method in the call stack at the point where we are paused, along with their values.

*The console (on the right)*

Here the debugger displays text messages; that’s how you learn of exceptions thrown by your running app, plus you can have your code deliberately send you log messages describing your app’s progress and behavior. Such messages are important, so keep an eye on the console as your app runs. You can also use the console to enter commands to the debugger. This can often be a better way to explore values during a pause than the variables list.

Either the variables list or the console can be hidden using the two buttons at the bottom right of the pane. The console can also be summoned by choosing View → Debug Area → Activate Console.

*Breakpoint navigator (Command-8)*

This navigator lists all your breakpoints. At the moment you have only one, but when you’re actively debugging a large project with many breakpoints, you’ll be glad of this navigator. Also, this is where you create special breakpoints (such as symbolic breakpoints), and in general it’s your center for managing existing breakpoints. We’ll return to this topic in [Chapter 10](#).

*Report navigator (Command-9)*

This navigator lists your recent major actions, such as building or running (debugging) your project. Click a listing to see (in the editor) the report generated when you performed that action. The report might contain information that isn’t displayed in any other way, and also it lets you dredge up console messages from the recent past (“What was that exception I got while debugging a moment ago?”).




Figure 7-5. The start of a build report

By clicking on the listing for a successful build, we can see the steps by which a build takes place (Figure 7-5). To reveal the full text of a step, click that step and then click the Expand Transcript button that appears at the far right (and see also the menu items in the Editor menu).

## The Inspector Pane

The Inspector pane is the column at the right of the project window. It contains inspectors that provide information about the current selection or its settings; if those settings can be changed, this is where you change them. The Inspector pane's importance emerges mostly when you're editing a *.storyboard* or *.xib* file (Chapter 8). But it can be useful also while editing code, mostly because Quick Help, a form of documentation (Chapter 9), is displayed here as well.

To toggle the visibility of the Inspector pane, choose View → Inspectors → Hide/Show Inspectors (Command-Option-0). You can change the Inspector pane's width by dragging the vertical line at its left edge. If the project window is being displayed fullscreen with the Inspector pane hidden, you can display the Inspector pane temporarily by hovering the mouse at the right side of the screen.

What appears in the Inspector pane depends on what's selected in the current editor:

### *A code file is being edited*

The Inspector pane shows the File inspector, the History inspector, or the Quick Help inspector. Toggle between them with the icons at the top of the Inspector pane, or with their keyboard shortcuts (Command-Option-1, Command-Option-2, Command-Option-3). The File inspector consists of multiple sections, each of which can be expanded or collapsed by clicking its header; I'll give an example of using it in Chapter 10 when I talk about localization. History is about

version control ([Chapter 10](#) as well). Quick Help can be useful because it displays documentation ([Chapter 9](#)).

#### *A .storyboard or .xib file is being edited*

The Inspector pane adds the Identity inspector (Command-Option-4), the Attributes inspector (Command-Option-5), the Size inspector (Command-Option-6), and the Connections inspector (Command-Option-7). These inspectors can consist of multiple sections, each of which can be expanded or collapsed by clicking its header. I'll talk more about them in [Chapter 8](#).

Other forms of editing may cause other inspector combinations to appear here.

## The Editor

In the middle of the project window is the *editor*. This is where you get actual work done, reading and writing your code ([Chapter 10](#)) or designing your interface in a *.storyboard* or *.xib* file ([Chapter 8](#)). The editor is the core of the project window. You can hide the Navigator pane, the Inspector pane, and the Debug pane, but there is basically no such thing as a project window without an editor.

The *jump bar* across the top shows you hierarchically what file is currently being edited. It also allows you to switch to a different file. Each path component in the jump bar is a pop-up menu. These pop-up menus can be summoned by clicking on a path component, or by using keyboard shortcuts (shown in the View → Editor submenu). Control-4 summons a hierarchical pop-up menu, which can be navigated entirely with the keyboard, allowing you to choose a different file in your project to edit. Each pop-up menu in the jump bar also has a filter field; to see it, summon a pop-up menu from the jump bar and start typing. Thus you can navigate your project even if the Project navigator isn't showing.



Command-click a jump bar component to summon a menu showing the corresponding file in the Finder and its hierarchy of enclosing folders.

The symbol at the left end of the jump bar (Control-1) summons the Related Items menu. This helps you navigate to files conceptually related to the current one. Its contents depend on both the current file and the current selection within it. You can navigate to files declaring related types (Superclasses, Subclasses, Siblings, and adopted Protocols) and to methods that call or are called by the currently selected method. The Generated Interface menu displays a file's public interface as seen by Swift or Objective-C (see the [Appendix](#)).

The editor remembers the history of what it has displayed, and you can return to previously viewed content with the Back button in the jump bar, which is also a pop-up menu (Control-2). Alternatively, choose Navigate → Go Back (Command-Control-Left).

## Editor panes

It is likely, as you develop a project, that you'll want to edit more than one file simultaneously, or obtain multiple views of a single file so that you can edit different areas of it simultaneously. For this purpose, the Editor pane area of the project window can be subdivided into smaller editor panes. Each pane can display a different file, or a different area of the same file.

To summon a new editor pane, choose File → New → Editor (Command-Control-T) or click the Add Editor button at the top right of an editor. Alternatively, if there is only one editor pane, Option-click a file listing in the Project navigator to open it in a new editor pane.

The new pane appears to the right of the current editor or below it; choose View → Change Editor Orientation to reverse this default or to move a pane from the right to below (or vice versa). To summon a new editor pane in the other orientation, choose File → New → Editor Below / On Right, or Option-click the Add Editor button.

To close an editor pane, choose File → Close Editor, or click the X button at the top left of an editor pane.

To zoom an editor pane temporarily, so that it takes over the whole editor area without closing any other panes, choose View → Editor → Focus (Command-Control-Shift-Return), or click the outward double-arrow button at the top left of the pane. To unzoom, do the same thing again: choose View → Editor → Hide Focus, or click the inward double-arrow button. While a pane is zoomed, Close Editor and the X button are disabled; you have to unzoom the pane before you can close it.



Zooming a pane, deliberately or accidentally, and then wondering why you can't make additional editor panes, is a common beginner mistake. If the interface appears to be mysteriously “frozen” so that you can't manipulate editor panes, see if View → Editor → Hide Focus is choosable.

When there are multiple editor panes, and you click a file listing in the Project navigator, its destination, by default, is the current editor pane. To specify a different destination, Option-click a file listing. For maximum flexibility, Option-Shift-click a file listing to enter *destination chooser* mode; you can then navigate with arrow keys to specify where you want this file to open — in an existing pane or as a new additional pane, to the right or below — and hit Return to open it there.



I like the destination chooser so much that I have made it the default: in the Navigation preference pane, under Optional Navigation, I've selected Uses Destination Chooser. The outcome is that the Option-click and Option-Shift-click shortcuts are swapped: the destination chooser appears when I hold the Option key while navigating.

If the Project navigator selection gets out of sync with the file displayed in the current editor pane, you can bring it back into sync by choosing Navigate → Reveal in Project Navigator (Command-Shift-J).

## Assistant panes

An assistant pane is a special kind of editor pane tied to a primary editor pane. When you cause the primary pane to display a different file, its assistant pane *automatically* displays a different file to match.

To summon an assistant pane, choose Editor → Assistant (or choose Assistant from the Editor Options pop-up menu at the top right of the editor pane). You'll know you've entered editor-and-assistant mode because both panes will display an icon showing two linked rings. To configure whether the assistant pane divides the editor vertically or horizontally, choose Editor → Layout → Assistant On Right/Bottom (or use the Editor Options pop-up menu).

Exactly what category of file the assistant pane automatically displays depends upon what you've specified as its relationship to the primary pane. You do that with the first pop-up menu in the assistant pane's jump bar, containing the linked rings icon (Control-4). Your choices here are much like the menu items in the Related Items menu.

If more than one file falls into the category in question — for example, you've set the assistant to show Callers and in the primary pane you've selected a method with more than one caller — then a pair of arrow buttons appears at the right end of the assistant's jump bar, with which you can navigate between them, or use the second jump bar component (Control-5).

## Tabs and windows

There are two kinds of tab. This is rather confusing, because menu commands don't always distinguish them. There are *document tabs* and *window tabs*:

### *Document tabs*

A document tab is an alternative way of populating an editor pane with multiple files. Instead of *splitting* the editor pane into two or more smaller panes, *one* editor pane is configured to display any of several files, one at a time, and you switch between those files using tabs.

To make a document tab, choose File → Open in Tab (Command-Option-O), or Control-click on a file listing in the Project navigator and choose Open in Tab. Or, if the document tab bar is already showing, you can drag file listings into it from the Project navigator to open them as tabs. Additionally, in the Navigation preference pane, you can set Optional Navigation or Double-click Navigation to



Uses Tab; I like double-clicking a listing in the Project navigator to open it as a document tab.

Document tabs are of two types: I call them *pinned* and *volatile*. A given editor pane can have at most one volatile tab. A simple click on a file listing in the Project navigator will *replace* the volatile tab if there is one, or will *create* a volatile tab if there isn't one. To promote a volatile tab to be pinned, choose File → Open in Tab, or Control-click the tab and choose Keep Open.

### Window tabs (and windows)

A window tab doesn't just display a file; it displays the *whole project window interface*, and can display it differently from another window tab. Thus one window tab might show the Project navigator, while another might have the Project navigator hidden, or display a different navigator. It's like having a second window on the same project without occupying any additional screen real estate. To make a new window tab, choose File → New → Window Tab (Command-T), revealing the window's tab bar (just below the toolbar) if it wasn't showing already.

Instead of a window tab, you can display a second independent window on the same project. To make a new window, choose File → New → Window (Command-Shift-T), or promote a window tab to be a window by dragging it right out of its current window.



In the Navigation preference pane, you can set Optional Navigation or Double-click Navigation to Uses Separate Window Tab or Uses Separate Window.

## Project File and Dependents

The first item in the Project navigator represents the project itself. (In the Empty Window project that we created earlier in this chapter, it is called Empty Window.) Hierarchically dependent upon it are items that contribute to the building of the project. Many of the listings in the Project navigator correspond to items on disk in the project folder.

To survey this correspondence, let's view our Empty Window project in two ways simultaneously — in the Project navigator in the Xcode project window, and in the project folder in a Finder window. Select the project listing in the Project navigator and choose File → Show in Finder. The Finder displays the contents of your project folder ([Figure 7-6](#)).






Figure 7-6. The Project navigator (Xcode) and the project folder (Finder)

## Contents of the Project Folder

The most important file in the project folder is *Empty Window.xcodeproj*. This is the *project file*, corresponding to the project listed first in the Project navigator. The project window is effectively displaying this file. All Xcode’s knowledge about your project — what files it consists of and how to build the project — is stored in this file. To open a project from the Finder, double-click the project file. (Alternatively, you can drag the project folder onto Xcode’s icon in the Finder, the Dock, or the application switcher; Xcode will locate the project file and open it for you.)

The Project navigator displays groups (folder-like things) and files hierarchically from the project. Let’s consider how these correspond to reality on disk as portrayed in the Finder (Figure 7-6):

- The Empty Window group corresponds directly to the *Empty Window* folder on disk. Groups in the Project navigator don’t always correspond to folders on disk in the Finder, but this one does — it is a *folder-linked group* (as I’ll explain later).
- Code files within the Empty Window group, such as *AppDelegate.swift*, correspond to real files on disk that are inside the *Empty Window* folder. If you were to create additional code files (which, in real life, you would almost certainly do in the course of developing your project), you would likely put them in the Empty Window group in the Project navigator, and they, too, would then be in the *Empty Window* folder on disk. (However, your files can live anywhere and your project will still work fine.)

There is also a configuration file called *Info.plist*, which also appears both in the Empty Window group and the *Empty Window* folder. I’ll talk more about it later in this chapter.

- Two files in the Empty Window group, *Main.storyboard* and *LaunchScreen.storyboard*, appear in the Finder inside a folder that doesn't visibly correspond to anything in the Project navigator, called *Base.lproj*. This arrangement has to do with *localization*, which I'll discuss in [Chapter 10](#).
- The item *Assets.xcassets* in the Project navigator corresponds to a specially structured folder *Assets.xcassets* on disk. This is an *asset catalog*; you add resources to the asset catalog in Xcode, which maintains that folder on disk for you. I'll talk more about the asset catalog later in this chapter and in [Chapter 10](#).

Now that you have inspected the contents of a typical project folder, you should have little need to open a project folder ever again, except in order to double-click the project file to open the project. Generally speaking, you should not manipulate the contents of a project folder by way of the Finder; manipulate the project *in the project window*. The project expects things in the project folder to be a certain way; if you make any alterations to the project folder directly in the Finder, behind the project's back, you can upset those expectations and break the project. When you work in the project window, it is Xcode itself that makes any necessary changes in the project folder, and all will be well.

## Groups

The purpose of groups in the Project navigator is to make the Project navigator work conveniently for you. Feel free to add further groups. If some of your code files have to do with a login screen that your app sometimes presents, you might clump them together in a Login group. If your app is to contain some sound files, you might put them into a Sounds group. And so on.

A group might or might not correspond to a folder on disk in the project folder. There's a visual distinction: a group that corresponds to a folder on disk is a *folder-linked group*, and has a solid folder icon, like the Empty Window group in [Figure 7-6](#); a group plain and simple exists purely within the Project navigator, and its folder icon is marked with a little triangle in its lower left corner. You'll encounter the distinction at various times:

### *Creating a group*

When you make a new group, there's a choice of menu items: in the contextual menu, you might see New Group and New Group Without Folder. (Confusingly, the choice might sometimes be New Group and New Group *With* Folder.) The one without a folder creates a group plain and simple; the other creates a folder-linked group.

### *Using a group*

When you place a file into a folder-linked group, it goes into the corresponding folder on disk (like the contents of the *Empty Window* folder in [Figure 7-6](#)).

When you place a file into a group plain and simple, the group is effectively ignored in determining where the file will go; it generally will go into the same place as files at the same level as the group.

### *Renaming a group*

To rename a group, select it in the Project navigator and press Return to make the name editable. When you rename a folder-linked group, the folder on disk is renamed as well.

## The Target

A *target* is a collection of parts along with rules and settings for how to build a product from those parts. Whenever you build, what you're building is a target (possibly more than one target).

Select the Empty Window project at the top of the Project navigator, and you'll see the project itself along with its targets listed on the left side of the editor. Our Empty Window project comes with one target — the *app target*, called Empty Window (like the project itself). The app target is the target that you use to build and run your app. Its settings are the settings that tell Xcode how your app is to be built; its product is the app itself.

Under certain circumstances, you might add further targets to a project:

- You might want to add unit tests or interface tests to your project. A test bundle is a target.
- You might write an application extension, such as a photo editing extension (a custom photo editing interface to appear in the Photos app). An extension is a target.
- You might write a library, such as a custom framework, as part of your iOS app. A custom framework is a target.

The project name and the list of targets can appear in two ways (**Figure 7-7**): either as a column on the left side of the editor, or, if that column is collapsed to save space, as a pop-up menu at the top left of the editor. If you select the *project*, you *edit the project*; if you select a *target*, you *edit the target*.

## Build Phases

Edit the app target and click Build Phases at the top of the editor (**Figure 7-8**). The *build phases* are the stages by which your app is built.

The build phases are both a report to you on how the target will be built and a set of instructions to Xcode on how to build the target; if you change the build phases, you




Figure 7-7. Two ways of showing the project and targets

change the build process. Click each build phase to see a list of the files in your target to which that build phase will apply.

Two of the build phases in our app target have contents. Their meanings are pretty straightforward:

#### *Compile Sources*

Certain files (your code) are compiled, and the resulting compiled code is copied into the app. This build phase typically applies to all of the target's *.swift* files. Sure enough, it currently contains all three Swift files supplied by the app template when we created the project.

#### *Copy Bundle Resources*

Certain files are copied into the app, so that your code or the system can find them there when the app runs. This build phase currently applies to the asset catalog; any resources you add to the asset catalog will be copied into your app as part of the catalog. It also applies to your launch storyboard file, *LaunchScreen.storyboard*, and your app's interface storyboard file, *Main.storyboard*.

Copying doesn't necessarily mean making an identical copy. Certain types of file are automatically treated in special ways as they are copied into the app bundle. Copying the asset catalog means that icons in the catalog are written out to the top level of the app bundle, while the asset catalog itself is transformed into a *.car* file; copying a *.storyboard* file means that it is transformed into a *.storyboardc* file, which is itself a bundle containing nib files.

You can alter these lists manually, and sometimes you may need to do so. For instance:

- If something in your project, such as a sound file, is not in Copy Bundle Resources and you want it copied into the app during the build process, drag it from the Project navigator into the Copy Bundle Resources list, or (easier) click the Plus button beneath the Copy Bundle Resources list to get a helpful dialog listing everything in your project.



Figure 7-8. The app target’s build phases

- Conversely, if something in your project is in the Copy Bundle Resources list and you *don’t* want it copied into the app, delete it from the list; this will not delete it from your project, from the Project navigator, or from the Finder, but only from the list of things to be copied into your app.

## Build Settings

Build phases are one aspect of how a target knows how to build the app; the other aspect is *build settings*.

To see the build settings, edit the target and click Build Settings at the top of the editor (Figure 7-9). Here you’ll find a long list of settings, most of which you’ll never touch. Xcode examines this list in order to know what to do at various stages of the build process. Build settings are the reason your project compiles and builds the way it does.

You can determine what build settings are displayed by clicking Basic or All. The settings are combined into categories, and you can close or open each category heading to save room. To locate a setting quickly based on something you already know about it, such as its name, use the search field at the top right to filter what settings are shown.

You can determine how build settings are displayed by clicking Combined or Levels; in Figure 7-9, I’ve clicked Levels, in order to discuss what levels are. It turns out that not only does a *target* contain values for the build settings, but the *project* also contains values for the same build settings; furthermore, Xcode has certain built-in



Figure 7-9. Target build settings

default build setting values. The Levels display shows all of these levels at once, so you can trace the derivation of the actual values used for every build setting.

To understand the chart, read from right to left. For example, the iOS default for the Build Active Architecture Only setting's Debug configuration (far right) is No. But then the project comes along (second column from the right) and sets it to Yes. The target (third column from the right) doesn't change that setting, so the result (fourth column from the right) is that the setting resolves to Yes.

You will rarely have occasion to manipulate build settings directly, as the defaults are usually acceptable. Nevertheless, you *can* change build setting values, and this is where you would do so. You can change a value at the project level or at the target level. You can select a build setting and show Quick Help in the Inspector pane to learn more about it.

## Configurations

There are actually multiple lists of build setting values — though only one such list applies when a particular build is performed. Each such list is called a *configuration*.

Multiple configurations are needed because you build in different ways at different times for different purposes, and you'll want certain build settings to take on different values under different circumstances.

By default, there are two configurations:

### Debug

This configuration is used throughout the development process, as you write and run your app.

### Release

This configuration is used for late-stage testing, when you want to check performance on a device, and for archiving the app to be submitted to the App Store.



Figure 7-10. Configurations




Figure 7-11. How configurations affect build settings

Configurations exist at all because the project says so. To see where the project says so, edit the project and click Info at the top of the editor (Figure 7-10). Note that these configurations are just names. You can create additional configurations, and when you do, you’re just adding to the list of names.

The importance of configurations emerges only when those names are coupled with build setting values. Configurations can affect build setting values both at the project level and at the target level.

For example, return to the target build settings (Figure 7-9) and type “optim” into the search field. Now you can look at the Optimization Level build setting for Swift, at the very bottom of the window (Figure 7-11):

- The Debug configuration value for Optimization Level is No Optimization: while you’re developing your app, you build with the Debug configuration, so your code is just compiled line by line in a straightforward way.
- The Release configuration value for Optimization Level is Optimize for Speed. When your app is ready to ship, you build it with the Release configuration, so the resulting binary is optimized for speed, which is great for your users running the app on a device, but would be no good while you’re developing the app because breakpoints and stepping in the debugger wouldn’t work properly. Compilation may take longer when the compiler must optimize for speed, but you won’t mind the delay, because you won’t do a Release build very often.



Figure 7-12. The scheme editor

## Schemes and Destinations

So far, I have not said how Xcode knows *which* configuration to use during a particular build. This is determined by a *scheme*.

A scheme unites a target (or multiple targets) with a build configuration, with respect to the purpose for which you’re building. A new project comes by default with a single scheme, named after the project. The Empty Window project’s single scheme is currently called Empty Window. To see it, choose Product → Scheme → Edit Scheme. The scheme editor dialog opens (Figure 7-12).

On the left side of the scheme editor are listed various actions you might perform from the Product menu. Click an action to see its corresponding settings in this scheme.

The first action, the Build action, is different from the other actions, because it is common to all of them — the other actions all implicitly involve building. The Build action merely determines what target(s) will be built when each of the other actions is performed. For our project this means that the app target is always to be built, regardless of the action you perform.

The second action, the Run action, determines the settings that will be used when you build and run. The Build Configuration pop-up menu (in the Info pane) is set to Debug. That explains where the current build configuration comes from: whenever you build and run (Product → Run, or click the Run button in the toolbar), you’re using the Debug build configuration and the build setting values that correspond to it, because you’re using this scheme, and that’s what this scheme says to do when you build and run.





Figure 7-13. The Scheme pop-up menu

You can edit an existing scheme, and this can be useful especially as a temporary measure for doing certain kinds of specialized debugging. For example, the Run action's Diagnostics tab contains checkboxes that let you turn on the Address Sanitizer or the Thread Sanitizer, useful for tracking down certain types of obscure runtime error. You'd check the checkbox, build and run, work on the error, and then uncheck the checkbox again.

You can also add a scheme. A typical approach is to duplicate an existing scheme and then modify the duplicate. Instead of changing your main scheme to turn on the Address Sanitizer temporarily, you might have a second scheme where the Address Sanitizer is always turned on; you would then use the Address Sanitizer by switching schemes.

Handy access to schemes and their management is through the Scheme pop-up menu in the project window toolbar (Figure 7-13).

The Scheme pop-up menu is something you're going to be using a lot. Your schemes are listed here, so if you have multiple schemes, this is where you'll switch between them. Also, hierarchically appended to each scheme are the *destinations*.

A destination is effectively a machine that can run your app. On any given occasion, you might want to run the app on a physical device or in the Simulator — and, if in the Simulator, you might want to specify that a particular type of device should be simulated. To make that choice, pick a destination in the Scheme pop-up menu.

Destinations and schemes have nothing to do with one another. The presence of destinations in the Scheme pop-up menu is just a convenience, letting you choose a scheme or a destination or both in a single move. To switch easily among destinations without changing schemes, click the destination name in the Scheme pop-up menu. To switch among schemes, possibly also determining the destination (as shown in Figure 7-13), click the scheme name in the Scheme pop-up menu.

You can open the Scheme pop-up menu with Control-0 (zero), and the Destination pop-up menu with Control-Shift-0; the menu can then be navigated with the keyboard, and is also filterable in the same way as the jump bar (discussed earlier in this chapter).

Each simulated device has a system version that is installed on that device. At the moment, all our simulated devices are running iOS 15; there is no distinction to be drawn, and the system version is not shown. But you can download earlier SDKs (systems) in Xcode's Components preference pane. If you do, and if your app can run under more than one system version, you might also see a system version listed in the Scheme pop-up menu as part of a Simulator destination name.

To manage destinations, choose Window → Devices and Simulators. Switch to the Simulators pane if necessary. This is where you govern what simulated devices exist. Here you can create, delete, and rename simulated devices, and specify whether a simulated device actually appears as a destination in the Scheme pop-up menu.

## From Project to Built App

Now that you know what's in a project, I'm going to summarize how Xcode builds that project into an app. Let's first jump ahead and examine the end product — the built app itself.

What *is* an app anyway? It's actually a special kind of folder called a *package* (and a special kind of package called a *bundle*). The Finder normally disguises a package as a file and does not dive into it to reveal its contents to the user, but you can bypass this protection and investigate an app bundle with the Show Package Contents command. By doing so, you can study the internal structure of your built app bundle.

We'll use the Empty Window app that we built earlier as a sample minimal app to investigate. Choose Product → Show Build Folder in Finder. Inside the *Products* folder, inside the *Debug-iphonesimulator* folder, you'll find the Empty Window app. Control-click it and choose Show Package Contents. Here you can see the results of the build process (Figure 7-14).

Think of the app bundle as a transformation of the project folder. Here are some of the things it contains, and how they relate to what's in the project folder:

### *Empty Window*

Our app's compiled code. The build process has compiled all our Swift files into this single file, our app's binary. This is the heart of the app, its actual executable material.

### *Main.storyboardc*

Our app's interface storyboard file. The project's *Main.storyboard* is currently where our app's interface comes from — in this case, an empty white view



Figure 7-14. Contents of the app package

occupying the entire window. The build process has compiled *Main.storyboard* into a tighter format, resulting in a *.storyboardc* file, which is actually a bundle of nib files to be loaded as required while the app runs. One of these nib files, loaded as our app launches, will be the source of the hitherto empty view displayed in the interface. *Main.storyboardc* sits in the same *Base.lproj* subfolder as *Main.storyboard* does in the project folder; as I said earlier, this folder structure has to do with localization (to be discussed in [Chapter 10](#)).

#### *LaunchScreen.storyboardc*

This is the compiled version of *LaunchScreen.storyboard*, containing the interface that will be displayed briefly during the time it takes for our app to launch (the *launch screen*).

#### *Assets.car*, *AppIcon60x60@2x.png*

An asset catalog and an icon file. In preparation for this build, I added an icon image to the original asset catalog, *Assets.xcassets*. The build process has compiled this file, resulting in a compiled asset catalog file (*.car*) containing any resources that have been added to the catalog; at the same time, the icon file has been written out to the top level of the app bundle.

#### *Info.plist*

A configuration file in a strict text format (a *property list* file). It is derived from various sources:

- The project’s *Info.plist*. New in Xcode 13, this is effectively empty.
- Settings shown in the Info pane when you edit the target.
- Build settings that those settings refer to.
- Values injected by the build process.

For example, when you edit the target and look in the Info pane, you’ll see that the “Bundle name” entry has a calculated value referring to the `$(PRODUCT_NAME)`

environment variable. That value is set in an app target build setting, Product Name, whose value is “Empty Window”. In the built app’s *Info.plist*, this calculation has been performed, and the “Bundle name” entry value is “Empty Window” — which is why our app is labeled “Empty Window” on the device.

Also, in conjunction with the asset catalog writing out our icon file to the app bundle’s top level, a setting has been added to the built app’s *Info.plist* telling the system the name of that icon file, so that the system can find it and display it as our app’s icon.

In real life, an app bundle may contain more files, but the difference will be mostly one of degree, not kind. Our project might have additional *.storyboard* or *.xib* files, additional resources such as sound files, or frameworks that we’ve added. All of these would make their way into the app bundle. Also, an app bundle built to run on a device will contain some security-related files.

You are now in a position to appreciate, in a general sense, how the components of a project are treated and assembled into an app, and what responsibilities accrue to you, the programmer, in order to ensure that the app is built correctly. The rest of this section outlines what goes into the building of an app from a project.

## Build Settings

We have already talked about how build settings are determined. Xcode itself, the project, and the target all contribute to the resolved build setting values, some of which may differ depending on the build configuration. You, the programmer, will have specified a scheme before building; the scheme determines the build configuration, meaning the specific set of build setting values that will apply as this build proceeds.

## Property List Settings

The built app’s *Info.plist* is used to store information that the destination device’s system can read directly when the app is installed and before it runs, such as its name, its version, its icons, its main storyboard’s name, its executable binary’s name, and so on. In Xcode 12 and before, it is derived primarily from an extensive *Info.plist* file that was part of the project; but new in Xcode 13, that file is basically empty.

Instead, in Xcode 13, you view and edit *Info.plist* settings primarily by editing the target and switching to the Info pane. Here you will find a list of keys and their corresponding values. By default, most of the key names (and some of the values) are displayed descriptively, in terms of their functionality; for example, it says “Bundle name” instead of the actual key, which is `CFBundleName`. To view the actual keys, look in the Quick Help inspector, or choose Raw Keys & Values from the contextual menu.

Some settings have a more friendly interface elsewhere. For instance, when you edit the target and switch to the General pane, some of the settings you perform here are effectively ways of editing the *Info.plist*. When you click a Device Orientation checkbox, you are actually changing the value of the “Supported interface orientations” key in the *Info.plist*.

New in Xcode 13, the way this works is that behind the scenes, the *Info.plist* entries are actually *build settings*. For example, the bundle display name comes from the Bundle Display Name build setting. At build time, these build settings are used to help construct the built app’s *Info.plist* because the Generate Info.plist File build setting is Yes.

As I mentioned earlier, some values in the project’s *Info.plist* refer to other build settings, and are processed at build time to transform them into their final values in the built app’s *Info.plist*; and some additional key–value pairs are injected into the *Info.plist* during build processing.

For a list of the possible keys and their meanings, consult Apple’s *Information Property List Key Reference* in the documentation archive (see [Chapter 9](#)). I’ll talk more in [Chapter 10](#) about some *Info.plist* settings that you’re particularly likely to edit.

## Nib Files

A nib file is a file with the extension *.nib* containing a description of a piece of user interface in a compiled format. You edit a *.xib* or *.storyboard* file graphically, as in a drawing program. Your *.xib* and *.storyboard* files are then transformed into nib files by compilation during the build process. This compilation takes place by virtue of the *.storyboard* or *.xib* file being listed in the app target’s Copy Bundle Resources build phase. A *.xib* file results in a single nib file; a *.storyboard* file results in a *.storyboardc* bundle containing multiple nib files.

Our Empty Window project generated from the iOS App template contains an interface *.storyboard* file called *Main.storyboard*. This is our app’s *main storyboard* — not because of its name, but because the *Info.plist* file says so, under the key “Main storyboard file base name” (`UIMainStoryboardFile`). I’ll talk more about the main storyboard later in this chapter; in [Chapter 8](#) I’ll explain how nib files create instances when your code runs.

## Resources

*Resources* are ancillary files embedded in your app bundle to be extracted as needed while the app runs. At some point during your app’s lifetime you might want to display some images, or play some sound files; to do so, you can include these files in your app bundle. In effect, your app bundle is being treated as a folder full of extra stuff that will be available to your app when it runs.



Figure 7-15. Options when adding a resource to a project

There are two different places to add resources to your project in Xcode:

#### *The Project navigator*

If you add a resource to the Project navigator, it is copied by the build process to the top level of your app bundle (assuming that it is also listed in the Copy Bundle Resources build phase).

#### *An asset catalog*

If you add a resource to an asset catalog, then when the asset catalog is copied and compiled by the build process to the top level of your app bundle, the resource's data will be embedded inside it.

### Resources in the Project navigator

To add a resource to your project through the Project navigator, choose File → Add Files to [Project], or drag the resource from the Finder into the Project navigator. A dialog appears (Figure 7-15):

#### *Copy items if needed*

Check this checkbox so that the resource is copied into the project folder. Otherwise, your project will depend on a file that's outside the project folder. That's legal, but keeping all of your project's contents inside the project folder is far safer; otherwise, you might delete or change the file unintentionally.

#### *Added folders*

If what you're adding to the project is a folder, these choices determine how the project references the folder contents:

##### *Create groups*

The folder's name becomes the name of a folder-linked group within the Project navigator, and its contents appear in this group; but the folder contents are listed individually in the Copy Bundle Resources build phase and are copied individually to the top level of the app bundle.

##### *Create folder references*

The folder becomes a *folder reference*. It is shown in blue in the Project navigator, and the folder itself is listed in the Copy Bundle Resources build phase. The build process will copy *the folder itself*, along with its contents,




Figure 7-16. Slots for an image set in the asset catalog

into the app bundle; the resources won't be at the top level of the app bundle, but rather in a subfolder within the app bundle. Your code for accessing those resources will have to specify the subfolder.

#### *Add to targets*

This checkbox determines whether the resource is added to a target's Copy Bundle Resources build phase. If your purpose is to make this resource available to the app when it runs, the app target checkbox should be checked. If your purpose is merely to use the project folder as convenient storage for something that isn't part of your app, the checkbox should *not* be checked. If you get this wrong, you can change this setting later by editing the target's Copy Bundle Resources build phase.

### Resources in an asset catalog

Asset catalogs were invented originally to accommodate image files; they can now contain any kind of data file. Keeping your resources in an asset catalog provides certain advantages over keeping them at the top level of the app bundle.

For example, you might need two or three versions of an image file, corresponding to the single-, double-, and triple-resolution screens of target devices; the asset catalog provides resolution slots to make that easy (Figure 7-16). The asset catalog can perform certain transformations on an image as it is loaded. And asset catalog images load more efficiently, because they are stored in a special format.

Asset catalogs can also hold named colors, Sprite Kit textures, and general data objects. Different versions of the same asset can load in response to device type, light or dark mode, and localization. An asset catalog can contain “folders” that subdivide the assets between namespaces, and multiple asset catalogs can be distinguished by putting them in different bundles (such as frameworks).

### Code Files

The build process compiles a code file into the app's binary if it is listed in the app target's Compile Sources build phase. The Swift files provided by the app template are listed under Compile Sources already. As you develop a real app, you'll create new Swift files by choosing File → New → File; a Save dialog will appear, offering to make

this file part of the app target, and if you accept, the file will be added to the app target's Compile Sources build phase. If you get this wrong, your code probably won't compile, because the compiler won't see the newly added Swift file; you can fix things by editing the Compile Sources build phase.

When you create a new file using the Cocoa Touch Class template, you get some boilerplate code for free. A file template might import the UIKit framework and write the initial class declaration for you, and in the case of some commonly subclassed superclasses, such as UIViewController and UITableViewController, it even provides stub declarations of some of that class's methods.

## Frameworks and SDKs

A *framework* is a library of compiled code used by your code. Most of the frameworks you are likely to use when programming iOS will be Apple's built-in frameworks. These frameworks are the locus of all the stuff that every app might need to do; they are Cocoa. That's a lot of stuff, and a lot of compiled code. Your app gets to share in the goodness and power of the frameworks because it is hooked up to them. Your code works as if the framework code were incorporated into it. Yet your app is relatively tiny; it's the frameworks that are huge.

The Cocoa frameworks are already part of the system on the device where your app will run; they live in `/System/Library/Frameworks` on the device, though you can't tell that because there's no way (normally) to inspect a device's file hierarchy directly.

Your compiled code also needs to be hooked up to those frameworks when the project is being built and run on your computer. To make this possible, the iOS device's `/System/Library/Frameworks` is duplicated on your computer, inside Xcode itself. This duplicated subset of the device's system is called an *SDK* (for "software development kit"). Which SDK is used depends upon what destination you're building for.

The process of hooking up your compiled code with the frameworks that it needs, whether on your computer or on an actual device, is called *linking*. Linking takes care of connecting your compiled code to any needed frameworks, but your code also needs to be able to compile in the first place. The frameworks are full of classes and methods that your code will call. To satisfy the compiler, the frameworks publish their API in header files, which your code can import. For instance, your code can speak of `NSString` and can call `range(of:)` because it imports the `NSString` header. Actually, what your code imports is the `UIKit` header, which in turn imports the `Foundation` header, which in turn imports the `NSString` header, which declares the `range(of:)` method.

Using a framework is therefore a two-step process. Your code must *import* the framework's header in order to compile and build, and then when building it must *link* to



the framework’s binary so that your code can communicate with the framework’s code at runtime.

Luckily, Swift’s use of modules simplifies the importing and linking process (as well as improving compilation times). A Swift `import` statement takes care of everything. The `import UIKit` statement at the top of our project’s code files imports the UIKit framework’s header files and allows your code to compile; then, at build time, it also enables linkage with the UIKit framework.

You can write your own frameworks. A custom framework can be a useful way to subdivide your code into modules, allowing your code to be compartmentalized through privacy and shared between other modules. Also, a framework is a bundle, so it can include resources that are referenced by specifying that bundle. Here’s how to create a framework in your project:

1. Edit the target and choose Editor → Add Target.
2. Select iOS. Under Framework & Library, select Framework. Click Next.
3. Give your framework a name; let’s call it *MyCoolFramework*. You can pick a language, but I’m not sure this makes any difference, as no code files will be created. The Project and Embed in Application pop-up menus should be correctly set by default. Click Finish.

A new *MyCoolFramework* target is created in your project. If you now add a Swift file to the *MyCoolFramework* target, and inside it define an object type and declare it public, then, back in one of your main app target’s files, such as *AppDelegate.swift*, your code can `import MyCoolFramework` and will then be able to see that object type and its public members. In the built app, the app bundle contains a *Frameworks* folder which, in turn, contains a *MyCoolFramework.framework* package containing your framework’s code and resources — a secondary bundle embedded in your app.

## Swift Packages

Sharing frameworks between apps is not simple; it can be rather tricky to use a framework in more than one app of your own, and it’s even harder to distribute your code to others as a framework, and for others to embed your framework in their own app. Starting in Xcode 11, a far more convenient mechanism is available: *Swift packages*. The primary purpose of a Swift package is to share your code as open source. A package is simpler and more efficient than a framework, because it is basically just a bunch of source code.

### Adding a package

Let’s start with how to *use* a package. To use a package in your project, you *add* the package. Packages are available over the internet; typically, they live at GitHub. As an example, we’ll download Apple’s Swift Algorithms package ([Chapter 4](#)):

1. In the Empty Window project window, in the Project navigator, select the Empty Window project at the top of the navigator.
2. Choose File → Add Packages. The Add Package dialog opens.
3. Apple’s Swift packages are already listed in the dialog. But let’s pretend they aren’t! In the search field at the upper right, enter `https://github.com/apple/swift-algorithms` and press Return.
4. The dialog displays information about this package. Click Add Package.
5. After some validation and downloading, a second dialog appears confirming that we want to add this package to our Empty Window app target. Click Add Package.
6. The Swift Algorithms package is listed in the Project navigator, under Package Dependencies.

The Swift Algorithms package code files are listed in the Project navigator, but they are not added to our project folder. Instead, a Swift package that you add to a project in this way is installed in your project’s build folder.

In addition to the Swift Algorithms package, the Swift Numerics package has also been installed. That’s because the Swift Algorithms package *depends* on the Swift Numerics package. This illustrates one of the most important features of Swift packages: dependencies are managed automatically. If one package needs another, installing the first installs the second. If a needed package is later updated at the source, Xcode downloads the update.

The code from the Swift Algorithms package is now available to the project’s code. It’s a module, so all you have to do is say `import Algorithms`. Now you can write code like this:

```
let arr = [1,2,3,4]
let windows = arr.windows(ofCount: 2)
windows.forEach { print($0) } // [1, 2] [2, 3] [3, 4]
```

Actually, we didn’t need to enter the GitHub URL in order to install this particular package. That’s because, new in Swift 5.5, there’s a way to create lists of packages, called *package collections*. New in Xcode 13, package collections are supported, and an Apple package collection, listing some of Apple’s own Swift packages, is already installed. So in the Add Package dialog, you can just select Apple Swift Packages on the left, and there’s the Swift Algorithms package listed; to install it, simply select it and click Add Package.

In fact, since Xcode already knows about this package collection, there’s an even simpler way: just say `import Algorithms` at the top of a Swift code file, *without* having installed the package. That’s a compile error, but Xcode also offers to search package




Figure 7-17. Adding a local package to the app target

collections for you, in case this is a known package. It is, so Xcode finds the package and now you can click Add Package.

## Creating a package

Now let's talk about how to create a package of your own:

1. In the Empty Window project, choose File → New → Package.
2. Give the package a name, such as *MyCoolPackage*. At the bottom of the Save dialog, specify that you want to add this package to the existing project (Empty Window), and make sure you're adding it to the Empty Window project itself, *not* inside the Empty Window group. You're creating a folder, so you also need to say where to save it; it doesn't have to be in your project folder (the Desktop is a perfectly good place). Click Create.
3. The initial package files appear in the Project navigator, but this module is not yet available to the app target. Edit the app target; in the General pane, under Frameworks, Libraries, and Embedded Content, click Plus and choose the package library in the dialog (Figure 7-17). Click Add.

In your app target's code, you can now `import MyCoolPackage` to access public types declared in the package. There is already one source file, *MyCoolPackage.swift*, ready for you to play with. It has a public struct, *MyCoolPackage*, with a public initializer and a public text property. Let's try accessing it:

```
import UIKit
import MyCoolPackage
class ViewController: UIViewController {
    override func viewDidLoad() {
        super.viewDidLoad()
        // Do any additional setup after loading the view.
        let p = MyCoolPackage()
        print(p.text)
    }
}
```

Build and run the project, and watch the console. "Hello, World!" appears. It works!

## Customizing a package

A package is in many ways similar to a target, but it isn't formally a target, so it doesn't have build settings, build phases, or *Info.plist* settings. Instead, instructions about the package must be written as executable Swift code. That code appears in a file called *Package.swift*, and is called the *package manifest*. The template has provided a working package manifest for this basic package; but if you customize the package, you might need to customize the manifest.

As long as your modifications to the package consist only of editing code and adding further code files, you don't need to edit the manifest. Put your additional code files into the *MyCoolPackage* group, where the *MyCoolPackage.swift* file is now; they will automatically be seen and compiled into your app target. (But don't forget that the package is a module; whatever you want your app target code to be able to see must be explicitly made `public`.)

You can also add bundle resources to a Swift package (starting in Xcode 12). To demonstrate, let's add an asset catalog:

1. Select the existing source file, *MyCoolPackage.swift*, and choose File → New → File.
2. In the template chooser, choose iOS → Resource → Asset Catalog.
3. An asset catalog called *Media.xcassets* is created. Edit it and drag an image file into it.

The result is that now the built app will contain an extra bundle, called *MyCoolPackage\_MyCoolPackage.bundle*, created at top level, containing this asset catalog. Code within the package can access an image in the asset catalog by specifying the bundle; the easiest way to do that is with the convenience variable `Bundle.module`, which is implemented for you by the build process.

To prove it, let's have the package vend the image. Suppose the image set in the asset catalog is called *MyCoolImage*. Then we might say, in package code:

```
public struct ImageVendor {
    public static func image(named name:String) -> UIImage? {
        return UIImage(named: name, in: Bundle.module, compatibleWith: nil)
    }
}
```

And our app target, having said `import MyCoolPackage`, can now say:

```
let image = ImageVendor.image(named:"MyCoolImage")
```

You can also include individual files or folders as resources in your package. But in that case the package build mechanism needs to be told what to do with them; you have to customize the package manifest. In particular, you would edit the `.target` value:

- A file that you *don't* want to add to the target would be added to the target's `excludes:` array.
- A file that you *do* want to add to the target would be added to the target's `resources:` array as a `.process` Resource object; for an entire folder (similar to a folder reference, discussed earlier), it would be a `.copy` Resource object.

(For more details, there's a good WWDC 2020 video on this topic.)

## Sharing a package

To share your package online, you place your package folder under Git control (see [Chapter 10](#)) and upload it to an online remote Git repository, such as GitHub. When you upload your own package, or when you update your package, you need to declare its version number. You do this by attaching a Git tag, in the form of a version string, to the most recent commit, similar to this:

```
% git tag "0.0.1"
% git push --tags
```

Xcode's package management mechanism works fine with private repositories, so you can share your code without making it public; you can upload your package and share it *with yourself*. This is a great way to factor out common code and use it in different projects.

# The App Launch Process

You now know how your app gets built. But why are you building it in the first place? Probably so that the app can be installed to a destination — a simulator, or an actual device — and run. So how does *that* work?

When the user launches your app, or when you launch it by building and running it in Xcode, a lot needs to happen. Your app needs some initial instances and an initial interface, and at least some of your code needs an opportunity to run.

In this section, I'll describe the procedure whereby the system on the destination launches the built app.

## The Entry Point

When the app launches, the system needs to know where to find the compiled binary inside the app's bundle. It does know this, because the built app bundle's *Info.plist* file

has an “Executable file” key (`CFBundleExecutable`) whose value is the name of the binary. By default, the binary’s name comes from the `EXECUTABLE_NAME` environment variable, whose value is derived from, and usually identical to, the Product Name build setting.

The system locates and loads the binary and links any needed frameworks. Now it must call into the binary’s code to start it running. But where?

If this app were an Objective-C program, the answer would be clear. Objective-C is C, so the entry point is the `main` function. Our project would typically have a *main.m* file containing the `main` function, like this:

```
int main(int argc, char *argv[]) {
    @autoreleasepool {
        return UIApplicationMain(argc, argv, nil,
                               NSStringFromClass([AppDelegate class]));
    }
}
```

That `main` function does two things:

- It sets up a memory management environment — the `@autoreleasepool` and the curly braces that follow it.
- It calls the built-in `UIApplicationMain` function, which helps your app pull itself up by its bootstraps and get running.

Our app, however, is a Swift program. It has no `main` function! Instead, Swift has a special attribute: `@main`. You can see it in the *AppDelegate.swift* file, attached to the declaration of the `AppDelegate` class:

```
@main
class AppDelegate: UIResponder, UIApplicationDelegate {
```

This attribute essentially does everything that the Objective-C *main.m* file was doing: it creates an entry point that calls `UIApplicationMain` to get the app started.



The term `@main` was introduced in Swift 5.3; formerly, this attribute was called `@UIApplicationMain`.

It would be very unusual for you to give your Swift app project an actual *main* file. But you are free to do so. You would delete the `@main` attribute and instead create a *main.swift* file, making sure it is added to the app target. The name is crucial, because a file called *main.swift* gets a special dispensation: it is allowed to put executable code at the top level of the file ([Chapter 1](#))! The file should contain essentially the Swift equivalent of the Objective-C call to `UIApplicationMain`, like this:

```
import UIKit
UIApplicationMain(
    CommandLine.argc, CommandLine.unsafeArgv, nil,
    NSStringFromClass(AppDelegate.self)
)
```

Starting in Swift 5.3 and Xcode 12, there's another way. Instead of writing a *main.swift* file, you can designate one of your own types as `@main` and give it a static `main` function, where you do whatever you would have done in the *main.swift* file. Behind the scenes, the *main.swift* file is synthesized for you. Here's a minimal implementation:

```
@main
struct MyMain {
    static func main() -> Void {
        UIApplicationMain(
            CommandLine.argc, CommandLine.unsafeArgv, nil,
            NSStringFromClass(AppDelegate.self)
        )
    }
}
```

(That use of the `@main` attribute is also key to the SwiftUI app architecture, where your code doesn't need to refer to any UIKit classes in order to bootstrap the app.)

Regardless of whether you rely on the Swift `@main` attribute or write your own *main.swift* file, you are now calling the `UIApplicationMain` function. This one function call is the primary thing your app does. In fact, your entire app is really nothing but a single gigantic call to `UIApplicationMain`!

Moreover, `UIApplicationMain` is responsible for solving some tricky problems as your app gets started. Where will your app get its initial instances? What instance methods will initially be called on those instances? Where will your app's initial interface come from? `UIApplicationMain` takes care of all that.

## How an App Gets Going

Let's trace the sequence of events as `UIApplicationMain` is called when your app launches. The opening sequence varies somewhat, depending on the circumstances. So let's focus on what happens for a new project created in Xcode 13, such as the Empty Window project we created earlier in this chapter. The project template has given our project these key features:

- The app supports scenes, in two ways:
  - The *Info.plist* contains an "Application Scene Manifest" dictionary (Figure 7-18).
  - The code mentions classes and protocols whose names begin with `UIScene`.

- The app has a main storyboard.

When an app with that structure launches (in iOS 13 or later), here's what happens:

1. `UIApplicationMain` creates the shared application instance, subsequently accessible to your code as `UIApplication.shared`. The default class is `UIApplication`; it is possible to specify a different class, but it is unlikely that you'd need to do so.
2. `UIApplicationMain` creates the application instance's *delegate*. With an explicit call to `UIApplicationMain`, the fourth argument specifies, as a string, what the class of the app delegate instance should be; in the *main.swift* file I described earlier, that specification is `NSStringFromClass(AppDelegate.self)`. When we use the `@main` attribute in the `AppDelegate` class declaration in *AppDelegate.swift*, it means: "This is the app delegate class!"
3. `UIApplicationMain` now turns to the app delegate and, for the first time, runs some of your code: it calls `application(_:didFinishLaunchingWithOptions:)`. This is a place for you to perform certain initializations.
4. `UIApplicationMain` creates a `UISceneSession`, a `UIWindowScene`, and your app's window scene *delegate*. The *Info.plist* typically specifies, as a string, what the class of the window scene delegate instance should be. In the app template, it is the `SceneDelegate` class, which is declared in *SceneDelegate.swift*; in the "Application Scene Manifest" entry in the *Info.plist*, this value is written as `$(PRODUCT_MODULE_NAME).SceneDelegate` to take account of Swift "name mangling" (Figure 7-18).
5. If there is a storyboard associated with this scene, as specified by the *Info.plist*, `UIApplicationMain` loads it and looks inside it to find the view controller designated as this storyboard's *initial view controller* (or *storyboard entry point*); it instantiates this view controller, a `UIViewController` subclass. In our app template, the app's main storyboard, *Main.storyboard*, is the initial scene's storyboard; in that storyboard, the initial view controller is an instance of the `ViewController` class, which is declared in *ViewController.swift*.
6. `UIApplicationMain` creates your app's *window*. This window is assigned to the scene delegate's `window` property. `UIApplicationMain` then assigns the initial view controller instance to the window instance's `rootViewController` property. This view controller is now the app's *root view controller*.
7. More of your code now has a chance to run: `UIApplicationMain` calls the scene delegate's `scene(_:willConnectTo:options:)` method.
8. `UIApplicationMain` causes your app's interface to appear, by calling the `UIWindow` instance method `makeKeyAndVisible`.



Information Property List	Dictionary	(1 item)
Application Scene Manifest	Dictionary	(2 items)
Enable Multiple Windows	Boolean	NO
Scene Configuration	Dictionary	(1 item)
Application Session Role	Array	(1 item)
Item 0 (Default Configuration)	Dictionary	(3 items)
Configuration Name	String	Default Configuration
Delegate Class Name	String	\$(PRODUCT_MODULE_NAME).SceneDelegate
Storyboard Name	String	Main

Figure 7-18. The “Application Scene Manifest” entry in the *Info.plist*

9. The window is about to appear. This causes the window to turn to the root view controller and tell it to obtain its main view. If this view controller gets its view from a nib file, that nib is loaded and its objects are instantiated and initialized (as I’ll describe in [Chapter 8](#)). The view controller’s `viewDidLoad` is then called — another early opportunity for your code to run. Finally, the root view controller’s main view is placed into the window, where it and its subviews are visible to the user.

More of your code can run at this time (some further app delegate and scene delegate methods are called if they are implemented), but basically the app is now up and running, with an initial set of instances and a visible interface. `UIApplicationMain` is *still* running (like Charlie on the M.T.A., `UIApplicationMain` never returns), and is just sitting there, watching for the user to do something, maintaining the *event loop*, which will respond to user actions as they occur. Henceforth, your app’s code will be called only in response to Cocoa events (as I’ll explain in [Chapter 12](#)).

## App Without a Storyboard

The preceding description of the app launch process assumes that the app has a main storyboard. It is possible, however, *not* to have a main storyboard. Without a main storyboard, things like creating a window instance, assigning it to the scene delegate’s window property, creating an initial view controller, assigning that view controller to the window’s `rootViewController` property, and calling `makeKeyAndVisible` on the window to show the interface, must be done by your code. This architecture is useful when your intention is to create the entire interface in code.

Let’s try it. Make a new project starting with the iOS App template; call it Truly Empty. Now follow these steps:

1. Edit the target. In the General pane, select “Main” in the Main Interface field and delete it (and press Tab to set this change).
2. Switch to the Info pane so you can edit the *Info.plist*. Select the “Storyboard Name” entry in the “Application Scene Configuration” dictionary ([Figure 7-18](#)) and press Delete.

3. Optionally, in the Project navigator, delete *Main.storyboard* from the project. You don't have to do this, because even if *Main.storyboard* remains, it will now be ignored.
4. In *SceneDelegate.swift*, edit `scene(_:willConnectTo:options:)` to look like [Example 7-1](#).

*Example 7-1. A scene delegate with no storyboard*

```
func scene(_ scene: UIScene,
           willConnectTo session: UISceneSession,
           options connectionOptions: UIScene.ConnectionOptions) {
    if let windowScene = scene as? UIWindowScene {
        let window = UIWindow(windowScene: windowScene)
        window.backgroundColor = .white
        window.rootViewController = ViewController()
        self.window = window
        window.makeKeyAndVisible()
    }
}
```

The result is a minimal working app with an empty white window. You can prove to yourself that the app is working normally by editing *ViewController.swift* so that its `viewDidLoad` method changes the main view's background color:

```
override func viewDidLoad() {
    super.viewDidLoad()
    self.view.backgroundColor = .red
}
```

Run the app again; sure enough, the background is now red.

In between an app with a main storyboard and an app without a main storyboard, there is a hybrid architecture where there's a main storyboard (you omit steps 1, 2, and 3 in the earlier example) but you sometimes ignore it at launch time (step 4). A common use case would be an app with a sign-in screen that should appear when the user first launches the app (you create the sign-in view controller manually), but once the user has signed in, that screen shouldn't appear on any future launch (you let the main storyboard construct the interface).

## Renaming Parts of a Project

The name you give your project at creation time is used in many places throughout the project. Beginners may worry that they can never rename a project without breaking something. But in fact it can be done.

Keep in mind, however, that you probably don't *need* to rename the project. The project name isn't something the user will ever see, so what does it matter? Typically,

what you want to change is the name of the *app* — the name that the user sees on the device, associated with this app’s icon. To do that, change (or create) the “Bundle Display Name” value in the *Info.plist*; you can do this most easily by editing the Display Name text field at the top of the General pane when you edit the target (see “Property List Settings” on page 563).

If you really *do* want to rename the project, select the project listing at the top of the Project navigator, press Return to make its name editable, type the new name, and press Return again. Xcode presents a dialog proposing to change some other names to match, including the app target and the built app and, by implication, various relevant build settings.

Everything that needs to change changes coherently when you rename the project in this way. The only thing that isn’t changed is the scheme name; there is no particular need to change it, but you can do so: choose Product → Manage Schemes and click the scheme name to make it editable.

You can change the name of the project folder in the Finder at any time, and you can move the project folder in the Finder at will, because all build setting references to file and folder items in the project folder are relative.



When you change the name of a folder-linked group, Xcode automatically changes the name of the corresponding folder on disk, but does *not* change build settings that depend upon the name of that folder, such as the Info.plist File build setting. I regard this as a bug, because it means that changing a group’s name can prevent your project from building. However, it usually isn’t hard to fix the problem by changing manually any build settings that have broken.



When you're programming iOS with Cocoa, your app's visible interface consists entirely of *views*. A view (UIView) is an interface object, which draws itself into a rectangular area. A view can contain (and own) other views, its *subviews*, forming a view hierarchy. All views, in turn, are ultimately placed on the screen by a *view controller*. A view controller owns one view — its *main view* — along with that view's subviews, and their subviews, and so forth. At every moment, some view controller's main view occupies the entire screen. Whatever that view and its subviews look like when they draw themselves, that is what the user will see.

Where do all these views come from? Well, UIView is a class; an individual UIView is an instance of that class. And you know how to make an instance of a class — you call that class's initializer:

```
let v = UIView()
```

So you could create all your interface views in code, one by one. For each view, you would *instantiate* it; then you would *configure* it. You'd say where it should go on the screen, what size it should have, what color it should be. If the view is a button or a label, you'd say what text it should display. And so on.

But that could be a lot of code. Wouldn't it be nice if, instead, you could *draw* your desired interface, just as in a drawing application, and have the runtime build the interface for you, based on your drawing? Well, you can — using a nib.

A *nib* is a file, in a special format, consisting of instructions for creating and configuring instances — primarily UIView instances. You “write” those instructions graphically, by drawing. You design your app's interface visually. Under the hood, Xcode encodes that design. When the app runs and it's time for those UIView instances to appear visibly to the user, the runtime *loads* the nib. It decodes the instructions and

obeys them: it actually creates and configures the view instances that the nib describes.

Xcode includes a graphical design environment so that you can draw your interface into a nib file. I call this the *nib editor*. Long ago, the files on which the nib editor operated were literally nib files — that is, they had a *.nib* file extension. Nowadays, you’ll use the nib editor to edit a *.storyboard* file or a *.xib* file. However, they *will* be turned into actual *.nib* files when you build your project (“**Nib Files**” on page 421), so I still refer to them loosely as nibs or nib files.



The name *nib* has nothing to do with fountain pens or bits of chocolate. The nib editor used to be a separate application called Interface Builder. The operating system for which it was originally developed was called NeXTStep. The files created by Interface Builder were given the *.nib* file extension as an acronym for “NeXTStep Interface Builder.”

Beginners often use nibs, to take advantage of their power and convenience, without knowing what they really are, how they really work, or how to manipulate them in code — as if nibs were some kind of impenetrable magic. But nibs are *not* magic, and they are not hard to understand. Failure to understand nibs and nib loading opens the door to some elementary, confusing mistakes that can be avoided or corrected merely by grasping the basic facts outlined in this chapter.

Note that you don’t *have* to use nibs to create your interface objects. The loading of a nib does nothing that you could not have done directly, in code. You still have the alternative of using code: you can programmatically instantiate a `UIView`, you can configure it, you can place that view into your interface — manually, step by step, one line of code at a time. You are free to mix and match; you can generate some views in code and design other views in the nib editor, or design a view in the nib editor but complete its configuration in code.



One of the salient features of SwiftUI is that it avoids nibs completely. By condensing the notation needed to create views programmatically, it lets you describe your interface clearly and compactly using Swift code alone. Part of the goal is multiplatform reusability: the same code can construct an interface destined for an Apple Watch, an iPhone, an Apple TV, or a desktop Mac.

## The Nib Editor Interface

Let’s explore Xcode’s nib editor. This is where you’ll draw your app’s interface graphically. In **Chapter 7**, we created a simple project, Empty Window, directly from the iOS App template; it contains a storyboard file, so we’ll use that. In Xcode, open the Empty Window project, locate *Main.storyboard* in the Project navigator, and click to edit it.




Figure 8-1. Editing a nib file

Figure 8-1 shows part of the project window after selecting *Main.storyboard* in the Project navigator. The interface may be considered in four pieces:

1. The bulk of the editor is devoted to the *canvas*, where you physically design your app's interface. The canvas portrays views graphically. View controllers are also represented in the canvas; a view controller isn't a view, so it isn't drawn in your app's interface, but it *has* a view, which *is* drawn.
2. At the left of the editor is the *document outline*, listing the storyboard's contents hierarchically by name.
3. To the right of the editor, the inspectors in the Inspector pane let you edit details of the currently selected object.
4. The Objects Library, available as a floating window (View → Show Library, Command-Shift-L, or click the Plus button in the toolbar), is your source of interface objects to be added to the canvas or the document outline.

## Document Outline

The document outline portrays hierarchically the relationships between the objects in the nib. To show or hide the document outline, choose Editor → Document Outline, or choose Document Outline from the Editor Options pop-up menu at the top right of the canvas. The document outline can also be hidden by dragging its right edge,




Figure 8-2. A view controller selected in a storyboard

and it can be shown or hidden by clicking the button at the bottom left corner below the canvas.

The structure of what's displayed in the document outline differs slightly depending on whether you're editing a *.storyboard* file or a *.xib* file.

In a storyboard file, the primary constituents are *scenes*. A scene is, roughly speaking, a single view controller, along with some ancillary material; every scene has a single view controller at its top level.

A view controller isn't an interface object, but it manages an interface object, a view that serves as its *main view*. A scene's view controller is displayed in the canvas with its main view inside it. In [Figure 8-1](#), the large rectangle in the canvas is a view controller's main view, and is actually inside a view controller. The view controller itself can be seen and selected in the document outline. When anything in this scene is selected, the view controller is also represented by an icon in the *scene dock*, which appears above the view controller in the canvas ([Figure 8-2](#)).

In the document outline, all the scenes are listed. Each scene is the top level of a hierarchical list. Hierarchically down from each scene are the objects that also appear in the view controller's scene dock: the view controller itself, along with two *proxy objects*, the First Responder token and the Exit token. They are the scene's *top-level objects*. Then, hierarchically down from the view controller, we have the view controller's main view, along with the main view's subviews (if any) appearing hierarchically down from that, reflecting the interface hierarchy of superviews and subviews.

Objects listed in the document outline are of two kinds:

#### *Nib objects*

The view controller, along with its main view and its subviews, will be turned into actual instances when the nib is loaded by the running app. They are called *nib objects*.






Figure 8-3. A *.xib* file containing a view

### Proxy objects

The First Responder and Exit tokens will *not* be turned into instances when the nib is loaded. They are *proxy objects*. They represent objects that *already* exist. They are displayed in the nib in order to facilitate communication between nib objects and those already existing objects; I'll give examples later in this chapter.

The document outline also contains the Storyboard Entry Point. This isn't an object of any kind. It's an indicator that this view controller is the storyboard's initial view controller (because *Is Initial View Controller* is checked in the view controller's Attributes inspector); it corresponds to the right-pointing arrow seen at the left of this view controller in the canvas in [Figure 8-1](#).

In a *.xib* file, there are no scenes. What would be, in a *.storyboard* file, the top-level objects of a scene become, in a *.xib* file, the top-level objects of the nib itself; and the top-level interface object of a *.xib* file is usually a view. (A *.xib* file *can* contain a view controller, but it usually doesn't.) A *.xib* file's top-level view might well be a view that is to serve as a view controller's main view, but that's not a requirement. [Figure 8-3](#) shows a *.xib* file with a structure parallel to the single scene of [Figure 8-2](#).

The document outline in [Figure 8-3](#) lists three top-level objects. Two of them are proxy objects, termed Placeholders in the document outline: the File's Owner, and the First Responder. The third is a nib object, a view; it will be turned into a `UIView` instance when the nib is loaded as the app runs.

At present, the document outline may seem unnecessary, because there is very little hierarchy; all objects in [Figures 8-2](#) and [8-3](#) are readily accessible in the canvas. But when a storyboard contains many scenes, and when a view contains many levels of hierarchically arranged objects, some of which are difficult to see or select in the canvas, you're going to be very glad of the document outline, which lets you survey the contents of the nib in a nice hierarchical structure, and where you can locate and select the object you're after. You can also rearrange the hierarchy here; if you've made a view a subview of the wrong superview, you can reposition it within this outline by dragging its name.

You can also select objects using the jump bar at the top of the editor: the last jump bar path component is a hierarchical pop-up menu similar to the document outline.

If the names of nib objects in the document outline seem generic and uninformative, you can change them. The name is technically a *label*, and has no special meaning, so feel free to assign nib objects labels that are useful to you. Select a nib object's label in the document outline and press Return to make it editable, or select the object and edit the Label field in the Document section of the Identity inspector.

## Canvas

The canvas provides a graphical representation of a view and its subviews, similar to what you're probably accustomed to in any drawing program. The canvas is scrollable and automatically accommodates however many graphical representations it contains, and can also be zoomed (Option-scroll, or choose Editor → Zoom, or use the contextual menu or the zoom buttons at the bottom of the canvas). You can also display the *minimap*, which shows you the whole content of the canvas in miniature and lets you scroll around it by dragging; choose Editor → Minimap or choose Minimap from the Editor Options pop-up menu at the top right of the canvas.

Our simple Empty Window project's *Main.storyboard* contains just one scene, so the only thing it represents in the canvas is that scene's view controller with its main view inside it. When the app runs, this view controller will become the window's *rootViewController*; therefore its view will occupy the entire window, and will effectively be our app's initial interface. That gives us an excellent opportunity to experiment: any visible changes we make within this view should be visible when we subsequently build and run the app! To prove it, let's add a subview:

1. Start with the nib editor looking more or less like **Figure 8-1**.
2. Summon the Objects Library (Command-Shift-L, or click the Library button in the project window toolbar). Make sure it's displaying objects (not images or colors). If it's in icon view (a grid of icons without text), switch to list view. Click in the search field and type "button" so that only button objects are shown in the list. The Button object we're after is listed first.
3. Drag the Button object from the Library into the view controller's main view in the canvas, and let go of the mouse.

A button is now present in the view in the canvas. The move we've just performed — dragging from the Library into the canvas — is extremely characteristic; you'll do it often as you design your interface.



By default, the Library floating window is temporary; it vanishes as soon as you drag something out of it. To make it remain onscreen after the drag, hold Option when summoning the Library or when dragging out of it; the Library window's toolbar then contains a close button, and the window will remain open until you click that button.

Much as in a drawing program, the nib editor provides features to aid you in designing your interface. Here are some things to try:

- Select the button: resizing handles appear.
- Using the resizing handles, resize the button to make it wider: dimension information appears.
- Drag the button near an edge of the view: a guideline appears, showing standard spacing. Similarly, drag the button near the center of the view: a guideline shows you when the button is centered.
- With the button selected, hold Option (but *not* the mouse button) and hover the mouse outside the button: arrows and numbers appear showing the distance between the button and the edges of the view.
- Control-Shift-click the button: a menu appears, letting you select the button or whatever is behind it or up the hierarchy from it. This is useful particularly when views overlap.
- Double-click the button's title. The title becomes editable. Give it a new title, such as "Hello." Press Return to set the new title.

To prove that we really are designing our app's interface, we'll run the app:

1. Drag the button to a position near the *top left* corner of the canvas. (If you don't do this, the button could be off the screen when the app runs.)
2. Examine the Debug → Activate / Deactivate Breakpoints menu item. If it says Deactivate Breakpoints, choose it; we don't want to pause at any breakpoints you may have created while reading the previous chapter.
3. Make sure the destination in the Scheme pop-up menu is an iPhone simulator.
4. Choose Product → Run (or click the Run button in the toolbar).

After a heart-stopping pause, the Simulator opens, and presto, our empty window is empty no longer; it contains a button! You can tap this button with the mouse, emulating what the user would do with a finger; the button highlights as you tap it.

## Inspectors

In addition to the File, History, and Quick Help inspectors, four inspectors appear in conjunction with the nib editor, and apply to whatever object is selected in the document outline, dock, or canvas:

#### *Identity inspector (Command-Option-4)*

The first section of this inspector, Custom Class, is the most important. Here you can learn — and can change — the selected object’s class.

#### *Attributes inspector (Command-Option-5)*

Settings here correspond to properties and methods that you might use to configure the object in code. For instance, selecting a view and choosing from the Background pop-up menu in the Attributes inspector corresponds to setting the view’s `backgroundColor` property in code.

The Attributes inspector has sections corresponding to the selected object’s class inheritance. The UIButton Attributes inspector has three sections: in addition to a Button section, there’s a Control section (because a UIButton is also a UIControl) and a View section (because a UIControl is also a UIView).

#### *Size inspector (Command-Option-6)*

The X, Y, Width, and Height fields determine the object’s position and size within its superview, corresponding to its `frame` property in code; you can equally set these values in the canvas by dragging and resizing, but numeric precision can be desirable.

#### *Connections inspector (Command-Option-7)*

Connections are outlets and actions, as I’ll explain later in this chapter.

## Loading a Nib

A nib file is a collection of potential instances — its nib objects. They become *actual* instances only if, while your app is running, the nib is *loaded*. At that moment, the nib objects described in the nib are effectively transformed into instances that are available to your app. I call this process — the loading of a nib and the resulting creation of instances — the *nib-loading mechanism*. We may speak as if a nib contains literal object instances; we may speak of “loading” or “instantiating” or “fetching” a view controller or a view from a nib. But in fact the nib contains nothing but *instructions* for creating a view controller or view instance. The job of the nib-loading mechanism is to fulfill those instructions.

Using nibs as a source of instances is efficient. Interface is relatively heavyweight stuff, but a nib is small. Moreover, a nib isn’t loaded until it is needed; indeed, it might never be loaded. So this heavyweight stuff won’t come into existence unless it is about to be displayed.

There’s no such thing as “unloading” a nib. A nib is loaded, its nib objects are turned into instances, those instances are handed over to the running app, and that’s all; the nib has done its job. It is then up to the running app to decide what to do with the instances that just sprang to life. It must hang on to them for as long as it needs them,

and will let them go out of existence when they are no longer needed. Typically, it will do this by adding them to the interface, where they will persist until that interface as a whole is removed.

The same nib file can be loaded multiple times, generating a new set of instances each time. A nib is thus a mechanism for reproducing a view controller or a view hierarchy as many times as necessary. A single nib file might represent interface that you intend to use in several places in your app — possibly several places simultaneously — by loading the nib repeatedly.

## Loading a View Controller Nib

When you're programming iOS with Cocoa, every view in your app's visible interface depends, at every moment, on a view controller. So where do view controllers come from? You can instantiate a view controller in code, or you can load it from a nib. A nib containing a view controller will almost certainly come from a storyboard. (A *.xib* file *can* contain a view controller, but it usually won't.)

A storyboard is a collection of scenes. Each scene starts with a view controller. When the app is built and the storyboard is compiled, each view controller in the storyboard ends up in its own individual nib. When the app runs, if that view controller is needed, that nib is loaded.

A view controller may be loaded from a storyboard automatically (by the runtime) or manually (by your code):

### *Automatic creation of a view controller*

There are two main occasions when a view controller is loaded automatically from a nib:

#### *At app launch time*

As your app launches, if it has a main storyboard, the runtime looks for that storyboard's *initial view controller* (entry point) and loads its nib, turning it into a view controller instance to serve as the app's root view controller ([“How an App Gets Going” on page 431](#)).

#### *When a segue is performed*

A storyboard typically contains several scenes connected by segues; when a segue is performed, the destination scene's view controller nib is loaded and turned into an instance.

### *Manual instantiation of a view controller*

In code, to turn a view controller in a storyboard into a view controller instance, you start with a `UIStoryboard` instance, and call one of these methods:

`instantiateInitialViewController`

Loads the storyboard's initial view controller nib and turns it into a view controller instance.

`instantiateViewController(withIdentifier:)`

Loads the nib of the view controller in the storyboard whose Storyboard ID matches the given identifier string, and turns it into a view controller instance.

## Loading a Main View Nib

Every view controller has a main view. But for reasons of efficiency, a view controller, when it is instantiated, *lacks* its main view. It obtains its main view *later*, when that view is needed because it is to be placed into the interface. We say that a view controller loads its view *lazily*. A view controller can obtain its main view in several ways; one way is to load it from a nib. There are two main cases to consider:

### *View controller in a storyboard*

When a view controller and its main view belong to a scene in a storyboard, then when the app is built and the storyboard is compiled, we end up with *two* nibs: the nib containing the view controller, and the nib containing the view. The app runs, and let's say the nib containing the view controller is loaded in order to instantiate the view controller, as I just described; later, when the view controller instance needs its main view, it automatically loads the corresponding view nib and generates its main view from it.

### *View controller instantiated in code*

Another fairly common configuration is that you instantiate a view controller entirely in code, but you've designed its main view in a *.xib* file in your project. In the built app, that *.xib* file will be turned into a nib file. You have to tell the view controller what nib that is, so that at runtime, when the view controller instance needs its main view, it can load that nib and generate its main view from it:

- You might override the view controller's `nibName` property to be the name of the nib file containing its main view.
- You might call the view controller's designated initializer `init(nibName:bundle:)`, using the `nibName:` parameter to tell this view controller instance the name of the nib file containing its main view.
- If you don't provide a `nibName`, but there is a nib with the same name as the view controller (possibly with the suffix `Controller` stripped off), it is assumed to be the nib file containing the view controller's main view.

## Loading a View Nib Manually

Consider a *.xib* file where you've designed a view that is *not* a view controller's main view. When the app is built, this file is turned into a nib. In the running app, to load that nib and create the view instance requires a call to one of these methods:

`loadNibNamed(_:owner:options:)`

A Bundle instance method. Usually, the bundle instance will be `Bundle.main`.

`instantiate(withOwner:options:)`

A UINib instance method. The nib instance will be created by calling the UINib initializer `init(nibName:bundle:)`.

You can make one of those calls to load a nib view directly. That's the best way to explore and exercise the nib-loading mechanism. Let's try it!

First we'll create and configure a *.xib* file in our Empty Window project:

1. In the Empty Window project, choose File → New → File and specify iOS → User Interface → View. This will be a *.xib* file containing a UIView instance. Click Next.
2. In the Save dialog, accept the default name, View, for the new *.xib* file. Click Create.
3. We are now back in the Project navigator; our *View.xib* file has been created and selected, and we're looking at its contents in the editor. Those contents consist of a single UIView.
4. Our view is too large for purposes of this demonstration, so select it and, in the Attributes inspector, change the Size pop-up menu, under Simulated Metrics, to Freeform. Handles appear around the view in the canvas; drag them to make the view smaller. About 240×200 would be a good size.
5. Populate the view with some arbitrary subviews by dragging them into it from the Library. You can also configure the view itself; for example, in the Attributes inspector, change its background color ([Figure 8-4](#)).

Our goal now is to *load* this nib file, manually, in code, when the app runs. There are three tasks you have to perform when you load a nib:

1. Load the nib.
2. Obtain the instances that it creates as it loads.
3. Do something with those instances.

I've already said that to load the nib we can call `loadNibNamed(_:owner:)`. This would be the complete code for loading our nib:

```
Bundle.main.loadNibNamed("View", owner: nil)
```




Figure 8-4. Designing a view in a .xib file

That's the *first* task. But if that's *all* we do, we will load the nib *to no effect*. The view instances will be created and will then vanish in a puff of smoke. In order to prevent that, we need to *capture* those instances. Here's one way to do that. The call to `loadNibNamed(_:owner:)` returns an array of instances created from the nib's top-level nib objects through the loading of that nib. Our nib contains just one top-level nib object — the `UIView` — so it is sufficient to capture the first (and only) element of this array:

```
let arr = Bundle.main.loadNibNamed("View", owner: nil)!
let v = arr[0] as! UIView
```

We have now performed the *second* task: we've captured an instance that we created by loading the nib. The variable `v` now refers to a brand-new `UIView` instance.

Now let's perform the *third* task — doing something with the view we've just instantiated. A useful and dramatic thing to do with it, and probably the reason you'd load a nib in the first place, is to put that view into your interface. Let's do that! Edit *ViewController.swift* and put these lines of code into its `viewDidLoad` method:

```
let arr = Bundle.main.loadNibNamed("View", owner: nil)!
let v = arr[0] as! UIView
self.view.addSubview(v)
```

Build and run the app. There's our view, visible in the running app's interface! This proves that our loading of the nib worked (Figure 8-5).

## Connections

A *connection* is a directional linkage in the nib editor running from one object to another. I'll call the two objects the *source* and the *destination* of the connection. There are two kinds of connection: outlet connections and action connections. The rest of this section describes them, explains how to create and configure them, and discusses the nature of the problems that they are intended to solve.






Figure 8-5. A nib-loaded view appears in our interface

## Outlets

When a nib loads and its instances come into existence, those instances are useless unless you can get a reference to them. In the preceding section, we solved that problem by capturing the array of instances returned from the loading of the nib. But there's another way: use an outlet. This approach requires some advance configuration, which can easily go wrong. But it is also more convenient, especially when nibs are loaded automatically.

An *outlet* is a connection that has a *name*, which is effectively just a string. When the nib loads, something unbelievably clever happens. The source object and the destination object are no longer just potential objects in a nib; they are now real, full-fledged instances. The runtime looks in the outlet's source object for an *instance property* with the *same name* as the outlet, and *assigns the destination object to that property*. The source object now has a reference to the destination object!

To illustrate, suppose that the following three things are true:

1. As defined in code, a Dog has a person instance property which is typed as Person.
2. There's a Dog object and a Person object in a nib.
3. We make an outlet from the Dog object to the Person object in the nib, and we name that outlet "person".

In that case, when the nib loads and the Dog instance and the Person instance are created, that Person instance will be assigned as the value of that Dog instance's person property (Figure 8-6), just as if we had said `dog.person = person` in code.

As you can see, for an outlet to work, preparation must be performed in *two different places*: in the class of the source object, where the instance property is declared, and in the nib, where the outlet is created and configured. This is a bit tricky; Xcode does try to help you get it right, but it is still possible to mess it up. (I will discuss ways of messing it up, in detail, later in this chapter.)




Figure 8-6. How an outlet provides a reference to a nib-instantiated object

## The Nib Owner

Consider once again the view-loading example that we implemented earlier (illustrated in [Figure 8-5](#)). Let's implement that example again; this time, instead of assigning the nib-loaded view to a variable in code, we'll use an outlet connection to capture the nib-loaded view into a property.

There is an important difference between the Dog-and-Person example I just outlined and the view-loading example. In our view-loading example, who is the Dog, and who is the Person? The Person is the view in the nib. But the Dog is the view controller (a `ViewController` instance) — and the view controller is *not in the nib*. Evidently, we need an outlet that runs from an object *outside* the nib (the view controller) to an object *inside* the nib (the view). That seems metaphysically impossible — but it isn't. The nib editor cleverly permits such an outlet to be created, using the *nib owner object*.

Before I explain what the nib owner is, I'll tell you where to find the nib owner object in the nib editor:

### *In a storyboard scene*

In a storyboard scene, the nib owner *is the view controller*. It is the first object listed for that scene in the document outline, and the first object shown in the scene dock.

### *In a .xib file*

In a .xib file, the nib owner *is a proxy object*. It is the first object shown in the document outline, listed under Placeholders as the File's Owner.

So what *is* the nib owner object? It's a proxy representing an instance that *already* exists *outside* the nib at the time that the nib is loaded. When the nib is loaded, the nib-loading mechanism *doesn't* instantiate that object; the nib owner is *already* an instance. Instead, the nib-loading mechanism *substitutes* the real, already existing instance for the nib owner object, using the real instance to fulfill any connections that involve the nib owner.

But wait! How does the nib-loading mechanism *know* what real, already existing instance to substitute for the nib owner object in the nib? It knows because it is told, in one of two ways, at nib-loading time:

### *Your code loads the nib*

If your code loads a nib manually in code by calling either `loadNibNamed(_:owner:options:)` or `instantiate(withOwner:options:)`, you specify an owner object as the `owner:` argument.

### *A view controller loads the nib*

If a view controller instance loads a nib automatically in order to obtain its main view, the view controller instance specifies *itself* as the owner object.

Let's do a thought-experiment with our Dog and Person objects. This time, suppose the following four things are true:

1. As defined in code, a Dog has a person instance property which is typed as Person.
2. There is a Person nib object in our nib, but no Dog nib object. Instead, when the app runs, there will *already* be a Dog instance, and we want this Dog instance to get its person *from the nib*.
3. We configure an outlet in the nib *from the nib owner object* to the Person object, and we name that outlet "person". We can't do that unless the nib owner object's class is Dog, so we'll set its class first if necessary (using the Identity inspector).
4. When we load the nib, we specify the existing Dog instance as owner.

The nib-loading mechanism will then match the Dog nib owner object with the already existing actual Dog instance that we specified as owner, and will assign the newly instantiated Person instance as that Dog instance's person (Figure 8-7)!




Figure 8-7. An outlet from the nib owner object

Back in the real world, let's reconfigure our Empty View nib-loading project to employ that same mechanism. In *ViewController.swift*, we're already loading the View nib in code. This code is running inside a *ViewController* instance. We want to use that instance as the nib owner. This will be a little tedious to configure, but bear with me, because understanding how it works is crucial:

1. We need an instance property in *ViewController*. At the start of the body of the *ViewController* class declaration, insert the property declaration, like this:

```
class ViewController: UIViewController {
    @IBOutlet var coolview : UIView!
```

The var declaration you already understand; we're making an instance property called *coolview*. It is declared as an *Optional* because it won't have a "real" value when the *ViewController* instance is created; it's going to get that value later through the loading of the nib ("**Deferred initialization of properties**" on page



Figure 8-8. Creating an outlet

- 130). The `@IBOutlet` attribute is a hint to Xcode to allow us to create the outlet in the nib editor.
2. Edit *View.xib*. We'd like to make the outlet, but in order to do that, we must ensure that the nib owner object is designated as a `ViewController` instance. Select the File's Owner proxy object and switch to the Identity inspector. In the first text field, under Custom Class, set the Class value as `ViewController`. Tab out of the text field and save.
3. Now we're ready to make the outlet! In the document outline, hold **Control** and *Control-drag* from the File's Owner object to the View; a little line follows the mouse as you drag. Release the mouse when the View is highlighted. A little HUD (heads-up display) appears, listing possible outlets we are allowed to create (Figure 8-8). There are two of them: *coolview* and *view*. Click *coolview* (*not view*!).
4. Finally, we need to modify our nib-loading code. We no longer need to capture the result of our call to `loadNibNamed(_:owner:)`. That's the whole point of this exercise! Instead, we're going to load the nib *with ourselves as owner*. This will cause our *coolview* instance property to be set automatically:

```
Bundle.main.loadNibNamed("View", owner: self)
self.view.addSubview(self.coolview)
```

Build and run. It works! The first line loaded the nib, instantiated the view, *and set our coolview instance property* to that view. The second line can display `self.coolview` in the interface, because `self.coolview` now *is* that view.

Let's sum up what we just did. Our preparatory configuration was a little tricky, because it was performed in two places — in code, and in the nib:

#### *In code*

There must be an *instance property* in the class whose instance will act as owner when the nib loads. It must be marked as `@IBOutlet`; otherwise, Xcode won't permit us to create the outlet in the nib editor.

### *In the nib editor*

The *class of the nib owner object* must be set to the class whose instance will act as owner when the nib loads; otherwise, Xcode *still* won't permit us to create the outlet. We must then *create the outlet*, with the same name as the property, from the nib owner to some nib object.

If all those things are true, then, when the nib loads, *if* it is loaded with an owner of the correct class, that owner's instance property will be set to the outlet destination.



When you configure an outlet to an object in the nib, that object's name as listed in the document outline ceases to be generic (e.g. "View") and takes on the name of the outlet (e.g. "coolview"). This name is still just a label — it has no effect on the operation of the outlet — and you can change it in the Identity inspector.

## Automatically Configured Nibs

Now that we've created a nib owner outlet *manually* and loaded a nib *manually*, we have demystified the nib-loading mechanism. When a view controller gets its main view from a nib *automatically*, everything works exactly like what we just did!

Consider our Empty Window project's *Main.storyboard*, with its single scene consisting of a ViewController and its main view. Everything about that situation is exactly parallel to what we just did:

### *The instance property*

In our manual example, we started with an instance property in our nib owner class.

Well, ViewController is a UIViewController, and UIViewController has an instance property — its *view* property! This is the property that needs to be set in order for the view controller to obtain its main view.

### *The nib owner class*

In our manual example, in the nib editor, we made sure that the nib owner object's class would be the class of the owner when the nib loads.

Well, in our *Main.storyboard* scene, the View Controller object *is* the nib owner, and it *is* of the correct class, namely ViewController (the class declared in the *ViewController.swift* file). Look and see: select the ViewController object in the storyboard and examine its class in the Identity inspector.

### *The outlet*

In our manual example, in the nib editor, we created an outlet with the same name as the owner instance property, leading from the owner to the nib object.

Well, in our *Main.storyboard* scene, the ViewController object *is* the view nib owner, and it *has* an outlet named *view* which *is* connected to the main view.




Figure 8-9. A view controller's view outlet connection

Look and see: select the view controller object in the storyboard and examine its Connections inspector (Figure 8-9).

So the storyboard has *already* been configured in a manner exactly parallel to how we configured *View.xib* in the preceding section. And the result is exactly the same! When the view controller needs its view, it loads the view nib with itself as owner, the nib-loading mechanism sees the connected view outlet, the view at the destination of that outlet is assigned to the view controller's view property, and voilà! The view controller has its main view.

Moreover, the view controller's main view is then placed into the interface. And *that* is why whatever we design in this view in the storyboard, such as putting into it a button whose title is "Hello," actually appears in the interface when the app runs.

## Misconfigured Outlets

Setting up an outlet to work correctly involves several things being true at the same time. You should expect that at some point in the future you will fail to get this right, and your outlet won't work properly — and your app will probably crash. So be prepared! And don't worry; this happens to everyone. The important thing is to recognize the symptoms so that you know what's gone wrong.

In this section, we're deliberately going to make things go wrong, so that we can explore the main ways for an outlet to be incorrectly configured. The crashes I'm about to describe, especially the first two, are extremely common for beginners.

### Outlet–property name mismatch

Start with our working Empty Window example. Run the project to prove that all is well. Now, in *ViewController.swift*, change the property name to *badview*:

```
@IBOutlet var badview : UIView!
```

In order to get the code to compile, you'll also have to change the reference to this property in *viewDidLoad*:

```
self.view.addSubview(self.badview)
```

The code compiles just fine. But when you run it, the app crashes with this message in the console: "This class is not key value coding-compliant for the key coolview."

I'll explain that message in [Chapter 11](#). For now, just think of it as a technical way of saying that the name of the outlet in the nib (which is still `coolview`) doesn't match the name of any property of the nib's owner when the nib loads — because we changed the name of that property to `badview` and wrecked the configuration. In effect, we had everything set up correctly, but then we went behind the nib editor's back and removed the corresponding instance property from the outlet source's class. When the nib loads, the runtime can't match the outlet's name with any property in the outlet's source — the `ViewController` instance — and we crash.

There are other ways to bring about this same misconfiguration. You could change things so that the nib owner is an instance of *the wrong class*. You might do that in the nib editor, by selecting the nib owner and changing its class in the Identity inspector. Alternatively, you might do it in code:

```
Bundle.main.loadNibNamed("View", owner: NSObject())
```

We made the owner a plain vanilla `NSObject` instance. The `NSObject` class has no property with the same name as the outlet, so the app crashes when the nib loads, complaining about the owner not being “key value coding-compliant.”



To change an outlet property's name *without* breaking the connection from the nib, select the property name in code and choose Editor → Refactor → Rename.

## No outlet in the nib

Fix the problem from the previous example by changing both references to the property name from `badview` back to `coolview` in `ViewController.swift`. Run the project to prove that all is well. Now we're going to mess things up at the other end! Edit `View.xib`. Select the File's Owner and switch to the Connections inspector, and disconnect the `coolview` outlet by clicking the X at the left end of the second cartouche. Run the project. We crash with this error message in the console: “Fatal error: unexpectedly found nil while unwrapping an Optional value.”

We removed the outlet from the nib. So when the nib loaded, our `ViewController` instance property `coolview`, which is typed as an implicitly unwrapped `Optional` wrapping a `UIView`, was *never set to anything*. It kept its initial value, which is `nil`. We then tried to *use* the implicitly unwrapped `Optional` by putting it into the interface:

```
self.view.addSubview(self.coolview)
```

Swift tries to obey by unwrapping the `Optional`, but you can't unwrap `nil`, so we crash.



## No view outlet

I can't demonstrate this problem using a *.storyboard* file. What we'd like to do is *disconnect* the view outlet in *Main.storyboard*, but the storyboard editor guards against this. But if you *could* make this mistake, then trying to run the project would result in a crash at launch time, with a console message complaining that “the view outlet was not set.”

A nib that is to serve as the source of a view controller's main view *must* have a connected view outlet from the view controller (the nib owner object) to the view. In a *.xib* file whose view is to function as a view controller's main view, you *can* make this mistake — usually by forgetting to connect the File's Owner view outlet to the view in the first place.

## Deleting an Outlet

Deleting an outlet coherently — that is, without causing one of the problems described in the previous section — involves working in several places at once, just as creating an outlet does. I recommend proceeding in this order:

1. Disconnect the outlet in the nib.
2. Remove the outlet declaration from the code.
3. Attempt compilation and let the compiler catch any remaining issues for you.

Let's suppose that you decide to delete the *coolview* outlet from the Empty Window project. You would follow the same three-step procedure that I just outlined:

1. Disconnect the outlet in the nib. To do so, edit *View.xib*, select the source object (the File's Owner proxy object), and disconnect the *coolview* outlet in the Connections inspector by clicking the X.
2. Remove the outlet declaration from the code. To do so, edit *ViewController.swift* and delete or comment out the `@IBOutlet` declaration line.
3. Now attempt to build the project; the compiler issues an error on the line referring to `self.coolview` in *ViewController.swift*, because there is now no such property. Delete or comment out that line, and build again to prove that all is well.

## More Ways to Create Outlets

Earlier, we created an outlet by control-dragging from the source to the destination in the document outline. Xcode provides many other ways to create outlets — too many to list here. I'll survey some of the most interesting. We'll continue to use the Empty Window project and the *View.xib* file. All of this works exactly the same way for a *.storyboard* file.

To prepare, delete the outlet in *View.xib* as I described in the previous section (if you haven't already done so). In *ViewController.swift*, create (or uncomment) the property declaration, and save:

```
@IBOutlet var coolview : UIView!
```

Now we're ready to experiment:

#### *Drag from source Connections inspector*

You can drag from a circle in the Connections inspector in the nib editor to connect the outlet. In *View.xib*, select the File's Owner and switch to the Connections inspector. The *coolview* outlet is listed here, but it isn't connected: the circle at its right is open. Drag from the circle next to *coolview* to the *UIView* object in the nib. You can drag to the view in the canvas or in the document outline. You don't need to hold Control as you drag from the circle, and there's no HUD because you're dragging from a specific outlet, so Xcode knows which one you mean.

#### *Drag from destination Connections inspector*

Now let's make that same move the other way round. Delete the outlet in the nib. Select the View and look at the Connections inspector. We want an outlet that has this view as its destination: that's a "referencing outlet." Drag from the circle next to New Referencing Outlet to the File's Owner object. The HUD appears: click *coolview* to make the outlet connection.

#### *Drag from source HUD*

Instead of starting by dragging, we can start by Control-clicking to summon a HUD and then drag from that HUD. Again delete the outlet in the Connections inspector. Control-click the File's Owner. A HUD appears, looking a lot like the Connections inspector. Drag from the circle at the right of *coolview* to the *UIView*.

#### *Drag from destination HUD*

Again, let's make that same move the other way round. Delete the outlet in the Connections inspector. Either in the canvas or in the document outline, Control-click the view. There's the HUD showing its Connections inspector. Drag from the New Referencing Outlet circle to the File's Owner. A second HUD appears, listing possible outlets; click *coolview*.

Again, delete the outlet. Now we're going to create the outlet by dragging *between the code and the nib editor*. This will require that you work in two places at once: you're going to need two editor panes (see [Chapter 7](#)). In one editor pane, show *ViewController.swift*. In the other editor pane, show *View.xib*, in such a way that the view is visible.




Figure 8-10. Connecting an outlet by dragging from code to nib editor

#### Drag from property declaration to nib

Next to the property declaration in the code, in the gutter, is an empty circle. Drag from that circle *right across the barrier* to the View in the nib editor (Figure 8-10). You’ve done it! The outlet connection has been formed in the nib; you can see this by looking at the Connections inspector, and also because, back in the code, the circle in the gutter is now filled in.

You can hover over the filled circle, or click it, to learn what the outlet in the nib is connected to. You can click the little menu that appears when you click in the filled circle to navigate to the destination object.

Here’s one more way — the most amazing of all. Keep the two-pane arrangement from the preceding example. Again, delete the outlet (you will probably need to use the Connections inspector or HUD in the nib editor pane to do this). Also delete the `@IBOutlet` line from the code! We’re going to create the property declaration and connect the outlet, *in a single move!*

#### Drag from nib to code

Control-drag from the view in the nib editor across the pane barrier to just inside the body of the class `ViewController` declaration. A HUD offers to Insert Outlet or Outlet Collection (Figure 8-11). Release the mouse. A popover appears, where you can configure the declaration to be inserted into your code. Configure it as shown in Figure 8-12: you want an outlet, and this property should be named `coolview`. Click Connect. The property declaration is inserted into your code, and the outlet is connected in the nib.

Making an outlet by connecting directly between code and the nib editor is cool and convenient, but don’t be fooled: there’s no such direct connection. There are *two distinct and separate things* — an instance property in a class, and an outlet in the nib *with the same name and coming from an instance of that class*. It is the identity of the




Figure 8-11. Creating an outlet by dragging from nib editor to code




Figure 8-12. Configuring an outlet property declaration

names and classes that allows the two to be matched at runtime when the nib loads. Xcode tries to help you get everything set up correctly, but it is *not* in fact magically connecting the code to the nib, and it is still possible to mess up the configuration later, as I've already described.

## Outlet Collections

An *outlet collection* is an *array* instance property (in code) matched (in a nib) by *multiple* connections to objects of the same type.

Suppose a class contains this property declaration:

```
@IBOutlet var coollabels: [UILabel]!
```

The outcome is that, in the nib editor, with an instance of this class selected, the Connections inspector lists `coollabels` — not under Outlets, but under Outlet Collections. This means that you can form multiple `coollabels` outlets, each one connected to a different `UILabel` object in the nib. When the nib loads, those `UILabel` instances become the elements of the `coollabels` array; the order of elements in the array is the order in which the outlets were formed. Your code can then refer to the

labels by number (the index into the array). This can be cleaner than having a separate instance property for each label.

## Action Connections

An action connection, like an outlet connection, is a way of giving one object in a nib a reference to another. But, unlike an outlet connection, it's not a property reference; it's a *message-sending* reference.

An *action* is a message emitted automatically by a Cocoa UIControl interface object (a *control*), sent to another object when the user does something to it, such as tapping the control. The various user behaviors that will cause a control to emit an action message are called *events*. To see a list of possible events, look at the UIControl.Event documentation. For example, in the case of a UIButton, the user tapping the button corresponds to the `.touchUpInside` control event.

For this architecture to work, the control object must know three things:

### *Control event*

What control event to respond to

### *Action*

What message to send (that is, what method to call) when that control event occurs

### *Target*

What object to send that message to

An action connection in a nib builds the knowledge of those three things into itself. It has the control object as its source; its destination is the target; and you tell the action connection, as you form it, what the control event and action message should be. To form the action connection, you need to configure the class of the *destination* object so that it has an instance method suitable as an action message.

To experiment with action connections, we'll need a UIControl object in a nib, such as a button. You may already have such a button in the Empty Window project's *Main.storyboard* file. However, it's probable that, when the app runs, we've been covering the button with the view that we're loading from *View.xib*. So first clear out the ViewController class declaration body in *ViewController.swift*, so that there is no outlet property and no manual nib-loading code; this should be all that's left:

```
class ViewController: UIViewController {  
}
```

Now let's arrange to use the view controller in our Empty Window project as a target for an action message emitted by the button's `.touchUpInside` event (meaning that the button was tapped). We'll need a method in the view controller that will be called

by the button when the button is tapped. To make this method dramatic and obvious, we'll have the view controller put up an alert window. Insert this method into the `ViewController` declaration body:

```
@IBAction func buttonPressed(_ sender: Any) {
    let alert = UIAlertController(
        title: "Howdy!", message: "You tapped me!", preferredStyle: .alert)
    alert.addAction(
        UIAlertAction(title: "OK", style: .cancel))
    self.present(alert, animated: true)
}
```

The `@IBAction` attribute is like `@IBOutlet`: it's a hint to Xcode itself, asking Xcode to make this method available in the nib editor. And indeed, if we look in the nib editor, we find that it *is* now available: edit *Main.storyboard*, select the View Controller object and switch to the Connections inspector, and you'll find that `buttonPressed:`, which is the Objective-C name of our action method, is now listed under Received Actions.

In *Main.storyboard*, in the single scene that it contains, the top-level View Controller's View should contain a Hello button. If it doesn't, add one, and position it in the upper left corner of the view. Double-click it and change its title to "Hello." Our goal now is to connect that button's Touch Up Inside event, as an action, to the `buttonPressed(_:)` method in `ViewController`.

As with an outlet connection, there is a source and a destination. The source here is the button in the storyboard; the destination is the `ViewController` instance acting as owner of the nib containing the button. There are many ways to form this action connection, all of them completely parallel to the formation of an outlet connection. The difference is that we must configure *both* ends of the connection. At the button (source) end, we must specify that the control event we want to use is Touch Up Inside; fortunately, this is the default for a `UIButton`, so we might be able to skip this step. At the view controller (destination) end, we must specify that the action method to be called is our `buttonPressed(_:)` method.

Let's form the action connection by Control-dragging from the button to the view controller in the nib editor:

1. Control-drag from the button (in the canvas or in the document outline) to the View Controller listing in the document outline (or to the view controller icon in the scene dock above the view in the canvas).
2. A HUD listing possible connections appears (Figure 8-13); it lists mostly segues, but it also lists Sent Events, and in particular it lists `buttonPressed:`.
3. Click the `buttonPressed:` listing in the HUD.




Figure 8-13. A HUD showing an action method

The action connection has now been formed. This means that when the app runs, any time the button gets a Touch Up Inside event — meaning that it was tapped — it will call the `buttonPressed(_:)` method in the target, which is the view controller instance. We know what that method should do: it should put up an alert. Try it! Build and run the app, and when the app appears in the Simulator, tap the button. It works!

## More Ways to Create Actions

Other ways to form the action connection in the nib, having created the action method in `ViewController.swift`, include the following:

### *Drag from source Connections inspector*

Select the button and use the Connections inspector. Drag from the Touch Up Inside circle to the view controller. A HUD appears, listing the known action methods in the view controller; click `buttonPressed:`.

### *Drag from source HUD*

Control-click the button. A HUD appears, similar to the Connections inspector. Proceed as in the previous case.

### *Drag from destination HUD*

Control-click the view controller. A HUD appears, similar to the Connections inspector. Drag from `buttonPressed:` (under Received Actions) to the button. Another HUD appears, listing possible control events. Click Touch Up Inside.

### *Drag from action method to nib*

Make two editor panes. Arrange to see `ViewController.swift` in one pane and the storyboard in the other. The `buttonPressed(_:)` declaration in `ViewController.swift` has a circle to its left, in the gutter. Drag from that circle across the pane barrier to the button in the nib.

As with an outlet connection, the most impressive way to make an action connection is to drag from the nib editor to your code, inserting the action method and forming




Figure 8-14. Configuring an action method declaration

the action connection in the nib *in a single move*. To try this, first delete the `buttonPressed(_:)` method in your code and delete the action connection in the nib. Make two editor panes. Arrange to see `ViewController.swift` in one pane and the storyboard in the other. Now:

1. Control-drag from the button in the nib editor to an empty area in the View-Controller class declaration's body. A HUD offering to create an outlet *or an action* appears in the code. Release the mouse.
2. The popover view appears:
  - a. Always look first at the Connection pop-up menu. It might be offering to create an outlet connection. That isn't what you want; you want an action connection! If it says Outlet, change it to Action.
  - b. Enter the name of the action method (here, `buttonPressed`) and configure the rest of the declaration. The defaults are probably good enough: see [Figure 8-14](#).

Xcode forms the action connection in the nib, and inserts a stub method into your code:

```
@IBAction func buttonPressed(_ sender: Any) {  
}
```

The method is just a stub (Xcode can't read your mind and guess what you want the method to do), so in real life, at this point, you'd insert some functionality between those curly braces. As with an outlet connection, the filled circle next to the code in an action method tells you that Xcode believes that this connection is correctly configured, and you can click the filled circle to learn, and navigate to, the object at the source of the connection.

## Misconfigured Actions

As with an outlet connection, configuring an action connection involves setting things up correctly at both ends (the nib and the code) so that they match. And of course you can wreck an action connection's configuration and crash your app. So be



## Should Outlets and Actions Be Private?

In my opinion, every `@IBOutlet` and `@IBAction` attribute should be followed by the keyword `private`, or at least `fileprivate`. There is never any reason for one view controller to access another view controller's outlet properties or action methods directly; to do so would be interfering, in effect, with that view controller's views. An outlet or action marked `private` continues to work correctly, because the attribute exposes it to Objective-C.

prepared! The typical misconfiguration, commonly encountered by beginners, is that the name of the action method as embedded in the action connection in the nib no longer matches the name of the action method in the code.

To see this, change the name of the action method in the code from `buttonPressed` to something else, like `buttonPushed`. Now run the app and tap the button. Your app crashes, displaying in the console this dreaded error message: “Unrecognized selector sent to instance.” A selector is a message — the name of a method ([Chapter 2](#)). The runtime tried to send a message to an object, but that object turned out to have no corresponding method (because we renamed it). If you look a little earlier in the error message, it even tells you the name of this method:

```
-[Empty_Window.ViewController buttonPressed:]
```

The runtime is telling you (using Objective-C notation) that it tried to call the `buttonPressed(_:)` method in your Empty Window module's `ViewController` class, but the `ViewController` class has no such method.



To change an action method's name *without* breaking the connection from the nib, select the method name in code and choose Editor → Refactor → Rename.

## Connections Between Nibs — Not!

You cannot draw an outlet connection or an action connection between an object in a nib and an object in a *different* nib:

- You cannot open nib editors on two different `.xib` files and Control-drag a connection from one to the other.
- In a `.storyboard` file, you cannot Control-drag a connection between an object in one scene and an object in another scene.

The reason is obvious when you consider what a nib *is*. Objects in a nib together will become instances together, at the moment when the nib loads, so it makes sense to connect them in that nib, because we know what instances we'll be talking about

when the nib loads. The two objects may both be instantiated by loading the nib, or one of them may be a proxy object (the nib owner), but they must both be represented *in the same nib*, so that the actual instances can be configured in relation to one another on each particular occasion when this nib loads.

If an outlet connection or an action connection were drawn from an object in one nib to an object in another nib, there would be no way to understand what actual future instances the connection is supposed to connect, because they are different nibs and will be loaded at different times (if ever). The problem of communicating between an instance generated from one nib and an instance generated from another nib is a special case of the more general problem of how to communicate between instances in a program, discussed in [Chapter 14](#).

## Additional Configuration of Nib-Based Instances

After a nib finishes loading, the instances that it describes have been initialized and configured with all the attributes dictated through the Attributes and Size inspectors, and their outlets have been used to set the values of the corresponding instance properties. Nevertheless, you might want to append your own code to the initialization process as an object is instantiated by loading a nib. This section describes some ways you can do that.

A common situation is that a view controller, functioning as the owner when a nib containing its main view loads (and therefore represented in the nib by the nib owner object), has an outlet to an interface object instantiated by the loading of the nib. In this architecture, the view controller can perform further configuration on that interface object, because it has a reference to it after the nib loads — the corresponding instance property. The earliest place where it can perform such configuration is its `viewDidLoad` method. At the time `viewDidLoad` is called, the view controller's view has been instantiated and assigned to its view property, and all its outlets have been connected; but the view is not yet in the visible interface.

Another possibility is that you'd like the nib object to configure itself, over and above whatever configuration has been performed in the nib. Often, this will be because you've got a custom subclass of a built-in interface object class; in fact, you might want to *create* a subclass precisely so as to have a place to put this self-configuring code. The problem you're trying to solve might be that the nib editor doesn't let you perform the configuration you're after, or that you have many objects that need to be configured similarly, so that it makes more sense for them to configure themselves by virtue of sharing a common class than to configure each one individually.

One approach is to implement `awakeFromNib` in your custom class. The `awakeFromNib` message is sent to all nib-instantiated objects just after they are instantiated by

the loading of the nib: the object has been initialized and configured and its connections are operational.

Let's make a button whose background color is always red, regardless of how it's configured in the nib. (This is a nutty example, but it's dramatically effective.) In the Empty Window project, we'll create a button subclass, `RedButton`:

1. In the Project navigator, choose `File → New → File`. Specify `iOS → Source → Cocoa Touch Class`. Click `Next`.
2. Call the new class `RedButton`. Make it a subclass of `UIButton`. Click `Next`.
3. Make sure you're saving into the project folder, in the Empty Window group, and that the Empty Window app target is checked. Click `Create`. Xcode creates *RedButton.swift*.
4. In *RedButton.swift*, inside the body of the `RedButton` class declaration, implement `awakeFromNib`:

```
override func awakeFromNib() {  
    super.awakeFromNib()  
    self.backgroundColor = .red  
}
```

We now have a `UIButton` subclass that turns itself red when it's instantiated from a nib. But we have no instance of this subclass in any nib. Let's fix that. Edit the main storyboard, select the button that's already in the main view, and use the Identity inspector to change this button's class to `RedButton`. Now build and run the project. Sure enough, the button is red!

A further possibility is to take advantage of the User Defined Runtime Attributes in the nib object's Identity inspector. This can allow you to configure, in the nib editor, aspects of a nib object for which the nib editor itself provides no built-in interface. What you're actually doing here is sending the nib object, at nib-loading time, a `setValue(_:forKeyPath:)` message; Cocoa key paths are discussed in [Chapter 11](#). Naturally, the object needs to be prepared to respond to the given key path, or your app will crash when the nib loads.

Here's an example. One of the disadvantages of the nib editor is that it provides no way to configure layer attributes. Let's say we'd like to use the nib editor to round the corners of our red button. In code, we would do that by setting the button's `layer.cornerRadius` property. The nib editor gives no access to this property. Instead, we can select the button in the nib editor and use the User Defined Runtime Attributes in the Identity inspector. We set the Key Path to `layer.cornerRadius`, the Type to Number, and the Value to whatever value we want — let's say 10 ([Figure 8-15](#)). Now build and run; sure enough, the button's corners are now rounded.




Figure 8-15. Rounding a button’s corners with a runtime attribute



Figure 8-16. An inspectable property in the nib editor



If you define your own property, your User Defined Runtime Attributes setting for that property will fail silently unless you mark the property `@objc`.

You can also configure a custom property of a nib object by making that property *inspectable*. To do so, add the `@IBInspectable` attribute to the property’s declaration in your code. This causes the property to be listed in the nib object’s Attributes inspector. (It also implicitly marks it `@objc`.)

Let’s make it possible to configure our button’s border in the nib editor. At the start of the `RedButton` class declaration body, add this code:

```
@IBInspectable var borderWidth : CGFloat {
    get {
        return self.layer.borderWidth
    }
    set {
        self.layer.borderWidth = newValue
    }
}
```

That code declares a `RedButton` property, `borderWidth`, and makes it a façade in front of the layer’s `borderWidth` property. It also causes the nib editor to display that property in the Attributes inspector for any button that is an instance of the `RedButton` class (Figure 8-16). The result is that when we give this property a value in the nib editor, that value is sent to the setter for this property at nib-loading time, and the button border appears with that width.

To intervene with a nib object's initialization even earlier, if the object is a `UIView` (or a `UIView` subclass), you can override `init(coder:)`. A minimal implementation would look like this:

```
required init?(coder: NSCoder) {  
    super.init(coder:coder)  
    // your code here  
}
```



---

# Documentation

*Knowledge is of two kinds. We know a subject ourselves,  
or we know where we can find information upon it.*

—Samuel Johnson,  
*Boswell's Life of Johnson*

No aspect of iOS programming is more important than a fluid and nimble relationship with the documentation. In addition to Swift's own types, there are hundreds of built-in Cocoa classes along with their numerous methods and properties and other details. Apple's documentation, whatever its flaws, is the definitive official word on how you can expect Cocoa to behave, and on the contractual rules incumbent upon you in working with this massive framework whose inner workings you cannot see directly.

Your primary access to the documentation is in Xcode, through the documentation window. But there are other forms of documentation and assistance. Quick Help popovers and the Quick Help inspector provide documentation without leaving the code editor. You can examine the code headers, which provide a useful overview and often contain valuable comments, and you can jump quickly to a symbol declaration. Apple provides sample code, and there are lots of additional online resources.

## The Documentation Window

There are two main categories of documentation provided by Apple:

### *Primary documentation*

The primary documentation (*reference* documentation) for Cocoa classes and other symbols is included entirely within Xcode, and is displayed in the documentation window (Window → Developer Documentation or Help → Developer

Documentation, Command-Shift-0). You can also view the same documentation online, at <https://developer.apple.com/documentation>.

### *Secondary documentation*

Secondary documentation consisting of older guides, sample code, and technical notes and Q&As is available only online, at <https://developer.apple.com/library/archive/navigation>. Apple refers to this material as the *documentation archive*.

Within the documentation window, the primary pathway is a search; press Command-Shift-0 (or Command-L or Command-Shift-F if you're already in the documentation window) and type a search term, typically a class name such as "NSString" or "UIButton." As you type, you're shown the top search results pertaining to the language of your choice (such as Swift or Objective-C). You can choose a result with the mouse, or you can navigate the results with arrow keys and press Return to select the desired hit.

You can also perform a documentation window search starting from within your code. You'll very often want to do this: you're looking directly at a symbol (a type name, a function name, a property name, and so on) at its point of use in your code, and you want to know more about it. Select text in your code (or anywhere else) and choose Help → Search Documentation for Selected Text (Command-Option-Control-/). This is like typing that text into the search field in the documentation window.

The documentation window behaves basically as a sort of web browser. Terms shown in a documentation page are links; click one to navigate to the documentation page about that term. You can then navigate between pages you've already loaded, using Navigate → Go Back and Navigate → Go Forward (or the back and forward buttons in the documentation window). To split your view of the documentation into multiple tabs, choose File → New → Window Tab (Command-T); to open a link in a new tab, hold Command when you click the link.

A hierarchical table of contents for the whole documentation appears in the navigator pane at the left of the documentation window; to see it if it isn't showing, click the Navigator button in the window toolbar. The table of contents can display any of three panes: Swift, Objective-C, or Other. You can switch between them with the pop-up menu at the top of the table of contents, or use the keyboard shortcuts (Command-1 and so on). To select in the table of contents the page you're currently viewing, choose Editor → Reveal in Navigator (or use the contextual menu).

To search for text *within* the current documentation page, use the Find menu commands, such as Find → Find (Command-F). But if, as is usually the case, your goal is to find a certain method or property, filtering in the jump bar is a better way, as I'll show in the next section.






Figure 9-1. The start of the `UIButton` class documentation page

## Class Documentation Pages

When dealing with Cocoa, your target documentation page will most likely be the documentation for a class, such as the page shown in Figure 9-1. Here are some typical features of a class documentation page:

### *Jump bar*

At the top of the page is the jump bar. This has two main purposes:

#### *Breadcrumbs*

The jump bar functions as a kind of “breadcrumbs” display of where you are. The `UIButton` class documentation page is in the Views and Controls section of the `UIKit` division of the documentation. This is the same hierarchy in which the page is displayed in the navigator table of contents.

#### *Navigation*

Each item in the jump bar is a hierarchical menu, displaying the same hierarchy as in the navigator table of contents. Choose a menu item to navigate there. As with the Xcode project window editor’s jump bar, you can type to filter the items of the currently selected menu.

### *Language*

Links let you choose between Swift and Objective-C as the language for display of symbol names.

## Availability

This list tells you two important things:

- What sort of *hardware* you’re programming for when you use this class. That’s important because searches are not filtered by hardware type. If you were to stumble accidentally into the `NSViewController` class documentation page, you might be confused about how this class fits into the rest of iOS programming, unless you notice that iOS is not even listed in this class’s Availability; this is a macOS class (AppKit).
- The lowest *version number* in which this class became available. For example, the `UIGraphicsImageRenderer` page tells you that this class is available in iOS 10.0 and later. So you wouldn’t be able to use it in code intended to run on iOS 9.

## Framework

The framework that vends this class.

## On This Page

The class reference page is divided into sections, and these are links to them, in order:

### Declaration

The formal declaration for this class, showing its superclass.

### Overview

If a page has an Overview section, read it! It explains what this class is for and how to use it. It may also contain valuable links to guides that provide related information.

### Topics

These are primarily the class’s members — its properties and methods — grouped by their purpose. Each member is accompanied by a short description; click the member itself to see further details. (I’ll talk more about that in a moment.) There may also be listings for enums used by this class’s properties and methods, and notifications if this class emits any; the `UIApplication` class documentation page is a case in point.

### Relationships

There are two chief kinds of relationship that a class can have, and you’ll want to keep an eye on both of them; a common beginner mistake is failing to follow the documentation links in this section:

#### *Inherits from*

This class’s superclass. A class inherits from its superclasses, so the functionality or information you’re looking for may be in a superclass. You won’t find `addTarget(_:action:for:)` listed in the `UIButton` class

page; it's in the UIControl class page (UIButton's superclass). You won't find out that a UIButton has a `frame` property from the UIButton class page; that information is in the UIView class page (UIControl's superclass).

#### *Conforms to*

Protocols adopted by this class. Again, the functionality or information you're looking for might be documented for a protocol rather than in this class's own page. For instance, you won't discover the `viewWillTransition(to:with:)` method on the UIViewController class page; you have to look in the documentation for the UICollectionContainer protocol, which UIViewController adopts.

When you click the name of a property or method in a class documentation page, you're taken to a separate page that describes it in detail. This page is laid out similarly to a class documentation page:

#### *Jump bar*

The jump bar provides breadcrumb navigation leading back to the class documentation page.

#### *Language*

The page gives you a choice of languages.

#### *Availability*

The availability for a property or method need not be the same as its class's availability, because a class can acquire (and lose) members over time. The UINavigationController class is as old as iOS itself and is available starting in iOS 2.0, but its `prefersLargeTitles` property didn't appear until iOS 11.0.

#### *On This Page*

There is no separate Overview section, but there is always an initial summary of purpose (the same summary that appears on the class documentation page). The other sections of a method's page are:

#### *Declaration*

The formal declaration for this method, showing its parameters and return type.

#### *Parameters*

Separate explanations for each parameter.

#### *Return Value*

An explicit description of what this method returns.




Figure 9-2. Filtering the jump bar for the UIButton topics

### Discussion

Often contains extremely important further details about how this method behaves. Always pay attention to this section!

### See Also

Links to related methods and properties. Helpful for getting a larger perspective on how this method fits into the overall behavior of this class.

The Topics section of a class documentation page may list many class members, and these can rapidly threaten to become overwhelming. If you know the name of a class member that you're interested in, or you want to get to a particular topic quickly, how are you going to reach it without the tedium of scrolling? *Don't forget the jump bar!* The jump bar lists all the class members listed on the page, grouped by topic. And that list can be filtered by typing. Let's say I know that the class member I'm interested in contains the term "background." I summon the rightmost level of the jump bar, type "back," and am shown a shortened list of just those terms (Figure 9-2). Now it's easy to navigate to the detail page for any of those items.

In addition to the class documentation, the built-in primary documentation includes explanatory guides on overall topics. The existence of these guides is not always obvious. The UIButton class documentation is inside the Views and Controls section; that page, the section page, is an introductory guide to views and controls. Sometimes there are extensive explanatory pages, effectively constituting the chapters of a virtual booklet. The Table of Contents can be a big help in spotting these; such pages are marked with a document icon. The discussion of Swift Packages is a case in point.

## Quick Help

Quick Help is a condensed rendering of the documentation for a particular symbol such as a type, function, or property name. It appears with regard to the current selection or insertion point automatically in the Quick Help inspector (Command-Option-3) if the inspector is showing. For instance, if you're editing code and the insertion point or selection is within the term `viewDidLoad`, documentation for the `viewDidLoad` method automatically appears in the Quick Help inspector if it is visible. Quick Help is also available in the Quick Help inspector for interface objects selected in the nib editor.

Quick Help documentation can also be displayed as a popover window. Select a term in the code editor and choose Help → Show Quick Help for Selected Item (Command-Control-Shift-?). Alternatively, hold Option and hover the mouse over a term until the cursor becomes a question mark; then Option-click the term.



When you're developing Swift code, Quick Help is of increased importance. If you click in the name of a Swift variable whose type is inferred, Quick Help shows the inferred type (see [Figure 3-1](#)). This can help you understand compile errors and other surprises.

The Quick Help documentation contains links. If there's an Open in Developer Documentation link, you can click it to see the full documentation in the documentation window.

You can inject documentation for your own code into Quick Help. To do so, precede a declaration with a comment enclosed in `/**...*/` or with one or more single-line comments starting with `///`.

Within a documentation comment, Markdown formatting can be used (<http://daringfireball.net/projects/markdown/syntax>). The first line of the comment becomes the Summary field for Quick Help; remaining paragraphs become the Description field, except that certain list items (paragraphs beginning with `*` or `-` followed by space) are treated in a special way, such as:

- List items beginning with Parameter *paramname*: are incorporated into the Parameters field.
- A list item beginning with Throws: becomes the Throws field.
- A list item beginning with Returns: becomes the Returns field.
- A list item beginning with Note: becomes a Note field.

Here's a function declaration with a preceding comment:

```
/**
Many people would like to dog their cats. So it is *perfectly*
reasonable to supply a convenience method to do so:

* Because it's cool.
* Because it's there.

* Parameter cats: A string containing cats

* Returns: A string containing dogs
*/

func dogMyCats(_ cats:String) -> String {
    return "Dogs"
}
```




Figure 9-3. Custom documentation injected into Quick Help

The double asterisk in the opening comment delimiter denotes that this is documentation, which is automatically associated with the `dogMyCats` method declaration that follows it.

The point of doing this is that it documents your code, not just at the point of definition, but everywhere. When the symbol `dogMyCats` is selected *anywhere* in my code, such as a call site, its documentation is displayed in Quick Help (Figure 9-3). The first paragraph of the comment becomes the Summary, and is also displayed as part of code completion (see Chapter 10). The word surrounded by asterisks is formatted as italics; the asterisked paragraphs become bulleted paragraphs; and the last two paragraphs become special fields.

You can also generate a documentation comment automatically. Select within the declaration line and choose Editor → Structure → Add Documentation. The comment is inserted before the declaration. The description, plus (if this is a function declaration) the Parameters, Returns, and Throws fields, as applicable, are provided as placeholders.

There are additional special documentation fields. For more information about these, see the “Markup Functionality” page of Apple’s *Markup Formatting Reference*.



To document an enumeration, put a documentation comment before the `enum` declaration and before each individual case declaration.

# Documenting Frameworks and Packages

New in Xcode 13, comment-based documentation in a framework or a Swift package ([Chapter 7](#)) can be assembled into documentation pages injected into the documentation window. Documentation of this sort, similar to Apple’s own documentation, is like a miniature book; in addition to listing types and their members, it can contain clickable cross-references, images, and explanatory pages. This mechanism is called *DocC*.

To illustrate, pretend I have a Coolness framework. Here’s its code; this is the content of a file *Coolness.swift* declaring a Temp enum and a Cool struct, along with documentation comments:

```
/// Degree of coolness.
public enum Temp {
    /// So cool you could plotz.
    case frigid
    /// Kind of cool.
    case lukewarm
    /// Not particularly cool.
    case boiling
}

/// Expression of coolness.
public struct Cool {
    var temp : Temp
    /// Changes our coolness.
    /// - Parameter to: The Temp you'd like it to be.
    public mutating func changeTemp(to newValue: Temp) {
        self.temp = newValue
    }
}
```

To generate the documentation for this framework, I’ll choose Product → Build Documentation. The result is that, in the documentation window, there is now a Workspace Documentation section listing the Coolness framework. Three documentation pages have been automatically generated: the Temp enum page; the Cool struct page; and the Coolness framework *landing page*, which acts as a table of contents containing links to both of those.

Your documentation can contain cross-reference links to other documentation pages. For example, here’s a line of the Cool struct documentation comment that mentions another type:

```
/// - Parameter to: The Temp you'd like it to be.
```

I’ll change it to this:

```
/// - Parameter to: The ``Temp`` you'd like it to be.
```

The double backticks turn the word `Temp`, both in the Quick Help and in the Cool struct documentation page, into a link to the Temp enum documentation page.

You can customize the automatically generated pages, and you can add ancillary pages and resources to the framework's documentation. To get started, you'll need a *documentation catalog*:

1. Select the Coolness group containing the framework files, and choose File → New → File.
2. In the template chooser, choose iOS → Documentation → Documentation Catalog.
3. Create the documentation catalog in the Coolness group, and *make sure it is part of the framework target*. The documentation catalog is called *Documentation* by default; it's fine to accept that name.

The result is that a special group is created in the framework (or package), called *Documentation.docc*. This is the documentation catalog. It contains an initial Markdown file called *Documentation.md*, along with a Resources group.

By editing the initial Markdown file, you can customize the landing page. It contains placeholder text, and is divided into sections by headers: a first-level title header, and two second-level headers called Overview and Topics. Those second-level header titles must be kept as they are; those are the only legal second-level titles. But the section *contents* are yours to modify.

You should start by changing the title to the name of the framework, surrounded by double backticks; that's how the documentation build process knows that this is to be the landing page. The other two sections can be included or omitted. The Topics section is the table of contents, consisting of links to type documentation pages; if you omit this section, the default Topics table of contents will be used.

**Example 9-1** shows the structure of a Markdown file that customizes the landing page. When we now choose Product → Build Documentation to rebuild the documentation, the framework landing page is replaced with the page shown in **Figure 9-4**.

*Example 9-1. Structure of a custom landing page*

```
# ``Coolness``  
  
This framework is extremely cool.  
  
## Overview  
  
How cool can you get?  
  
Very cool!
```






Figure 9-4. Custom framework documentation landing page

```
## Topics
```

```
### Basic
```

```
These are basic.
```

```
- ``Cool``
```

```
### Advanced
```

```
These are advanced.
```

```
- ``Temp``
```

Similarly, it is possible to customize a type's documentation page, by writing an *extension* file. To add an extension file, choose File → New → File and, in the template chooser, choose Extension File. The title, surrounded by double backticks, must be a path to the type's documentation page. To customize the Temp enum documentation page, the title in my extension file would be ``Coolness/Temp``.

To add an explanatory article, choose File → New → File and, in the template chooser, choose Article File. Its structure is similar to the landing page; the main difference is that you can choose your own title, and you get to add your own custom sections. The landing page will automatically include a link to any explanatory articles, using the title as the link text.

The Resources folder can hold images that you want to include in your documentation. An ordinary Markdown image link in a page's text will cause the image to appear in the documentation.

It is also possible to construct interactive tutorials, similar to the ones Apple provides for introducing SwiftUI (<https://developer.apple.com/tutorials/swiftui>). For more about that, and for further technical details about how DocC documentation is constructed, consult the DocC framework documentation in Xcode's documentation window.

## Symbol Declarations

A *symbol* is a declared term, such as the name of a function, variable, or object type. If you can see the name of a symbol in the code editor, you can jump quickly to the declaration of that symbol. Select the term and choose Navigate → Jump to Definition (Command-Control-J); alternatively, hold Command-Control and hover the mouse over a prospective term, until the cursor becomes a pointing finger, and then Command-Control-click the term:

- If the symbol is declared in your code, you jump to its declaration in your code; this can be helpful not only for understanding your code but also for navigation.
- If the symbol is declared in the Swift library or a Cocoa framework, you jump to its declaration in the header file. (I'll talk more about header files in the next section.)



Command-Control-click is the default for jumping to a symbol's declaration, but it can be changed. In the Navigation pane of Xcode's preferences, under Command-click on Code, switch the pop-up menu to Jumps to Definition. Now you can jump to a symbol declaration with a simple Command-click.

To jump to the declaration of a symbol whose name you know, even if you don't see the name in the code before you, choose File → Open Quickly (Command-Shift-O). A search field appears. In it, type key letters from the name, which will be interpreted

intelligently; for example, to search for `application(_:didFinishLaunchingWithOptions:)`, you might type “appdidf.” Possible matches are shown in a scrolling list below the search field; you can navigate this list with the mouse or by keyboard alone. Besides declarations from the framework headers, declarations in your own code are listed as well; so this, too, can be a rapid way of navigating your code.

In addition, a list of available symbols appears in the Symbol navigator ([Chapter 7](#)). If the second icon in the filter bar is highlighted, these are symbols declared in your project; if not, symbols from imported frameworks are listed as well. Click to navigate to a symbol declaration.

## Header Files

A header file can be a useful form of documentation. The header is necessarily accurate, up-to-date, and complete, and it may contain comments telling you things that the documentation doesn’t. Also, a single header file can contain declarations for multiple classes and protocols. So it can be an excellent quick reference.

The previous section describes various ways of jumping to a symbol declaration; since most symbols are declared in header files, these are ways of reaching header files. To reach *NSString.h*, select the term `NSString` wherever it may appear in your code and jump to its declaration, or choose `File → Open Quickly (Command-Shift-O)` and type “`NSString`.” Once you’re in a header file, you can navigate it conveniently through the jump bar at the top of the editor.

When you jump to a header file from your code, the header file, if it is written in Objective-C, can appear in Objective-C or Swift:

- To switch from an Objective-C original to its Swift translation, choose `Generated Interface` from the `Related Items` menu (at the left end of the jump bar, `Control-1`).
- To switch from a Swift translated (generated) header to the Objective-C original, choose `Navigate → Jump to Original Source`, or choose `Original Source` from the `Related Items` menu.

You can learn a lot about the Swift language and the built-in library functions by examining the Swift header file. The special Swift header files for Core Graphics and Foundation are also likely to prove useful. A neat trick is to write an `import` statement just so that you can reach the corresponding header. If you `import Swift` at the top of a Swift file, the word `Swift` itself is a symbol that you can use to jump to the Swift header.

## Sample Code

The documentation archive includes plenty of sample code projects. You can view the code in a browser, but you can see only one file at a time, so it's difficult to get an overview. Instead, click the Download Sample Code button and open the downloaded project in Xcode; with the sample code project open in a project window, you can read the code, navigate it, edit it, and of course run the project.

Some of the primary documentation guides contain links to downloadable sample code as well. This sample code can be difficult to discover. In a few cases, the documentation archive links to it. In other cases, you just have to stumble across it. Again, the table of contents in the documentation window can be a big help here; sample code pages are marked with a curly braces icon.

As a form of documentation, sample code is both good and bad. It can be a superb source of working code that you can often copy and paste and use with very little alteration in your own projects. It is usually heavily commented, because the Apple folks are aware, as they write the code, that it is intended for instructional purposes. Sample code also illustrates concepts that users have difficulty extracting from the documentation. But the logic of a project is often spread over multiple files, and nothing is more difficult to understand than someone else's code (except, perhaps, your own code). Moreover, what learners most need is not the *fait accompli* of a fully written project but the reasoning process that constructed the project, which no amount of commentary can provide.

Apple's sample code is generally thoughtful and instructive, and is definitely a major component of the documentation; it deserves more appreciation and usage than it seems to get. But it is most useful, I think, after you've reached a certain level of competence and comfort. Also, while some of the sample code is astoundingly well-written, some of it is a bit careless or even downright faulty.

## Internet Resources

Programming has become a lot easier since the internet came along and Google started indexing it. It's amazing what you can learn with a Google search. Your problem is very likely one that someone else has faced, solved, and written about on the internet. Often you'll find sample code that you can paste into your project and adapt.

Apple's own online resources go beyond the formal documentation. There are WWDC videos (<https://developer.apple.com/videos>) from the current and previous years. Apple also hosts developer forums (<https://developer.apple.com/forums>); some interesting discussions take place in these forums, and they are patrolled by helpful Apple employees.

Other online resources have sprung up spontaneously as iOS programming has become more popular, and lots of iOS and Cocoa programmers post tutorials or blog about their experiences. Stack Overflow (<http://www.stackoverflow.com>) is a site that I'm particularly fond of; it's a general programming question-and-answer site, not devoted exclusively to iOS programming, but with lots of iOS programmers hanging out there; questions are answered succinctly and correctly, and the interface lets you focus on the right answer quickly and easily.



---

# Life Cycle of a Project

This chapter surveys some of the main stages in the life cycle of an Xcode project, from inception to submission at the App Store. This will provide an opportunity to discuss some additional features of the Xcode development environment as well as various tasks you'll typically perform as you work on your app, including editing, debugging, and testing your code, running your app on a device, profiling, localizing, and releasing to the public.

## Environmental Dependencies

It may be useful to have your app behave differently depending on the environment in which it finds itself when compiling or running:

### *Buildtime dependencies*

These are choices made at build time. They affect the build process, including what the compiler does. Typical dependencies are:

- The version of Swift under which we're compiling.
- The type of destination for which we're compiling — a simulator or a real device.
- A custom compilation condition defined for the current build configuration in the build settings.
- The action that causes the build — for instance, whether we're building to run or to archive.

### *Runtime dependencies*

These are choices made depending on what the app discovers its environment to be when it runs. Typical dependencies are the type of device we turn out to be running on (iPad vs. iPhone) and the system version installed on this device:

- Should the app be permitted to run under this environment?
- Should the app do different things, or load different resources, depending on the environment?
- Should the app respond to the presence of an argument or environment variable injected by Xcode?

## Conditional Compilation

Stretches of code that might or might not be compiled into your built app depending on the compile-time environment are fenced off by `#if...#endif` directives, as shown in [Example 10-1](#).

*Example 10-1. Swift conditional compilation*

```
#if condition
    statements
#elseif condition
    statements
#else
    statements
#endif
```

The `#elseif` and `#else` sections can be omitted, and there can be multiple `#elseif` sections. There are *no curly braces*, and the *statements* will not in fact be indented by the code editor.

The conditions are treated as Booleans, so they can be combined with the usual Boolean logic operators. However, they are not Swift code expressions! They must come from a limited predefined set of reserved words. The ones you are most likely to use are:

`swift(>=5.5)`, `compiler(>=5.5)` (*or some other version number*)

The version of the Swift language or compiler under which we’re building. The only legal operators are `<` and `>=`. The `swift` version depends on the Swift Language Version build setting, but the `compiler` version depends on the Xcode version. Under Xcode 13, if the Swift Language Version build setting is Swift 4.2, then `swift` is less than 5, but `compiler` is not.

`targetEnvironment(simulator)`

Whether we’re building for a simulator or device destination. This can allow an app to run coherently on the simulator even though the simulator lacks certain capabilities, such as the camera.

`canImport(Uikit)` (*or some other module name*)

Whether the module in question is available on the platform for which we’re building.






Figure 10-1. Compilation conditions in the build settings

### Custom compilation condition

A name that you enter in the Active Compilation Conditions build setting will yield true for purposes of conditional compilation.

The *statements* enclosed in each block will not be compiled at all unless the appropriate condition is met, as this (very silly) example demonstrates:

```
#if swift(>=5.5)
print("howdy")
#else
Hey! Ba-Ba-Re-Bop
#endif
```

That code compiles without complaint in a plain vanilla project built from the iOS App template in Xcode 13. The statement Hey! Ba-Ba-Re-Bop is not a legal Swift expression, but the compiler doesn't care, because our Swift version *is* Swift 5.5, so the compiler never even examines the `#else` block.

An `#if` condition can distinguish between build configurations by way of the Active Compilation Conditions build setting. In fact, your project already comes with one such condition by default: the `DEBUG` condition is defined for the Debug configuration but not for the Release configuration (Figure 10-1). This means that for a Debug build, but not for a Release build, the test `#if DEBUG` will succeed.

A useful technique is to define a configuration, define an Active Compilation Conditions setting for that configuration, and make a scheme that uses that configuration for one or more actions.

For instance, if the Run action uses the Debug build configuration but the Test action uses your custom Testing build configuration, any Active Compilation Conditions for the Testing configuration will be present only when testing, and so you can make conditional compilation apply to testing only. I often use this approach to make a private method public during testing only, just so that method can be tested. (I'll talk more about testing later in this chapter.)

## Build Action

The Development Assets build setting (introduced in Xcode 11) lets you specify one or more paths for resources that won't be included in an archive build — meaning a build to be distributed to other users, as I'll explain later in this chapter. In this way

your app can include resources such as default data during development and testing, while guaranteeing that those resources won't pollute the ultimately released built app.

The paths that you specify can designate individual resources, entire asset catalogs, or even folders. A neat approach is a folder-linked group in the Project navigator: put your development-only resources into that group, and specify the path to the corresponding folder in Development Assets.

If you combine the Development Assets build setting with the `targetEnvironment(simulator)` compilation condition, you have the makings of a simulator-only test bed — code that is present only on the simulator, along with ancillary files that won't be present when you ultimately distribute the app to others.

For example, my Albumen app is all about displaying the contents of the user's music library. The Simulator doesn't really have a music library, so I use conditional compilation with `#if targetEnvironment(simulator);` on the simulator, I have the app load some preconfigured data from a text file, and the app displays that data instead. But I don't want that text file to be present in the App Store release, so I list it in the Development Assets.

## Permissible Runtime Environment

Under what environments should this app be permitted to run? The choices are determined by build settings that you can configure through a convenient interface:

### *Device Type*

The device type(s) on which your app will run natively. This is the app target's Targeted Device Families build setting; to set, edit the app target, switch to the General pane, and use the Device checkboxes (under Deployment Info):

#### *iPhone*

The app will run on an iPhone or iPod touch. It can also run on an iPad, but not as a native iPad app; it runs in a reduced enlargeable window (Apple sometimes refers to this as “compatibility mode”).

#### *iPad*

The app will run only on an iPad.

#### *iPhone, iPad*

The app will run natively on both kinds of device; it is a *universal* app.

(There are some additional options, because an iOS app can also run on a Mac.)

### *iOS Deployment Target*

The *earliest* system your app can run on: in Xcode 13, this can be any major iOS system as far back as iOS 9.0. To set, edit the app target, switch to the General

pane, and choose from the Target pop-up menu (under Deployment Info). There is also a drop-down list when you edit the project, in the Info pane.

(But to set the deployment target for a test target, you might have to edit the target's build settings directly.)

## Backward Compatibility

Writing an app whose iOS Deployment Target system version is lower than the current system version — that is, an app that is *backward compatible* to an earlier system — can be challenging. With each new system, Apple adds new features. You'll want to take advantage of these. But your app will *crash* if execution encounters features not supported by the system on which it is actually running!

Fortunately, when the compiler knows that a feature is unsupported by an earlier system, it will prevent you from accidentally using that feature on that system. Here's a line of code where we prepare to draw a small image:

```
let r = UIGraphicsImageRenderer(size:CGSize(width:10,height:10))
```

The `UIGraphicsImageRenderer` class exists only in iOS 10.0 and later. If your deployment target is iOS 9, the compiler will stop you with an error: “`UIGraphicsImageRenderer` is only available on iOS 10.0 or newer.”

How does the compiler know we've got a potential problem here? It's because a term (a type or a member) states its availability in its declaration. The `UIGraphicsImageRenderer` class declaration is preceded (in Swift) with this annotation:

```
@available(iOS 10.0, *)
```

The details of the notation are not very important (if you're interested, consult the Attributes chapter of Apple's *Swift Reference Manual*). The important thing is that the annotation tells the compiler — and you — that this class isn't present until iOS 10 and later.

When you encounter this kind of issue, you cannot proceed until you guarantee to the compiler that this code will run only on a system that supports it. Luckily, Xcode's Fix-it feature (discussed later in this chapter) will help you do exactly that. Here, it offers to surround that line with an *availability check*:

```
if #available(iOS 10.0, *) {  
    let r = UIGraphicsImageRenderer(size:CGSize(width:10,height:10))  
} else {  
    // Fallback on earlier versions  
}
```

The `if #available` condition tests the current system at runtime. It needs to match the `@available` annotation, and Xcode's Fix-it will make sure that it does. You can use `#available` in an `if` construct or a `guard` construct.

You can also annotate your own type and member declarations with an `@available` attribute. If you do, your own code will then have to use an availability check in order to refer to that type or that member. If your method is declared `@available(iOS 15.0, *)`, then when the deployment target is earlier than iOS 15, you can't call that method without an availability check that matches it: `if #available(iOS 15.0, *)`. Within such a method, you don't need the availability check, because you've already guaranteed that this method won't run on a system earlier than iOS 15.

A case in point is the built-in iOS App template. This template is not very backward compatible, because it uses a scene delegate (Chapter 7). Scene delegates and the related classes were introduced in iOS 13; they don't exist in iOS 12 and before, and the launch process is different without them. To make a project generated from the template backward compatible, you need to mark the entire `SceneDelegate` class, and any methods in the `AppDelegate` class that refer to `UISceneSession`, with an availability annotation: `@available(iOS 13.0, *)`.

Your code now compiles, and it runs on iOS 12. But it doesn't actually *work* on iOS 12. To fix that, you also need to declare a window property in the `AppDelegate` class:

```
var window : UIWindow?
```

The result is that when this app runs in iOS 13 or later, the scene delegate has the window, but when it runs in iOS 12 or before, the app delegate has the window — and your other code may then need to take account of *that* in order to be backward compatible.

A more insidious problem arises when the very same method or property *does* exist on different systems, but behaves differently. Often this is because Apple introduces a bug, or fixes a bug, or both. For example, setting `UIProgressView`'s `progressImage` property worked in iOS 7.0, didn't work at all from iOS 7.1 through iOS 8.4, and then started working again in iOS 9 and later. When that sort of thing happens, the compiler can't help you, and you usually have no way of knowing about it other than trial and error (and working around the problem coherently can be tricky).

To *test* your app on an earlier system, you'll need a destination that *runs* that earlier system. Through Xcode's Components preference pane (see Chapter 7), you can download an earlier Simulator SDK going back as far as iOS 11.4. To test on an earlier system than that, you'll need an older version of Xcode, and probably an older device. This can be difficult to configure, and may not be worth the trouble.

## Device Type

An app might need to respond differently depending on the hardware on which it finds itself running. A universal app might need to behave differently depending on whether it is running on an iPad or an iPhone, different devices have different screen resolutions that might call for using different images, and so on.

You can learn in code whether we’re running on an iPhone or an iPad. The current `UIDevice` (`UIDevice.current`), or the `traitCollection` of any `UIViewController` or `UIView` in the hierarchy, will tell you the current device’s type as its `userInterfaceIdiom`, which will be a `UIUserInterfaceIdiom`, either `.phone` or `.pad`.

When it comes to loading resources, there are some built-in shortcuts. Image files to be loaded from the top level of the app bundle can be distinguished automatically by using the same name but different suffixes, such as `@2x` and `@3x` to indicate the screen resolution, or `~iphone` and `~ipad` to indicate the device type. Or you can use an asset catalog (see “[Resources in an asset catalog](#)” on page 423), which allows you to specify different images for different runtime environments just by putting them in the correct slot. Either way, the runtime will automatically choose the image variant appropriate to the current environment.

Certain *Info.plist* settings come with name suffixes as well. For example, it is usual for a universal app to adopt one set of possible orientations on iPhone and another set on iPad: typically, the iPhone version permits a limited set of orientations while the iPad version permits all orientations. You configure this using two groups of “Supported interface orientations” settings in the *Info.plist*:

`UISupportedInterfaceOrientations`

(or `UISupportedInterfaceOrientations~iphone`)

A general set of orientations, or an iPhone-only set.

`UISupportedInterfaceOrientations~ipad`

An iPad-only set of orientations that overrides the general set when the app runs on an iPad.

The clearest and most reliable way to make these configurations is to edit the *Info.plist* directly (in the Info pane when you edit the app target). Alternatively, there are some checkboxes you can use, in the General pane when you edit the target, under Deployment Info:

1. Uncheck iPad, check iPhone, and check the desired Device Orientation checkboxes for the iPhone.
2. Uncheck iPhone, check iPad, and check the desired Device Orientation checkboxes for the iPad.
3. Check both iPad and iPhone. Even though you’re now seeing just one set of orientations, both sets are remembered.

(That is surely one of Xcode’s least intuitive bits of interface!)

Similarly, your app can load different nib files and display different interfaces depending on the device type. If the nib comes from a *.xib* file, use the image file naming convention: a nib file by the same name with `~ipad` appended will load




Figure 10-2. The Arguments tab of the scheme’s Run action

automatically if we are running on an iPad. If you want to have two different main storyboards, use the *Info.plist* naming convention: with window scenes under iOS 13 and later, configure two “Application Scene Manifest” keys, `UIApplicationSceneManifest` and `UIApplicationSceneManifest~ipad`, that specify different `UISceneStoryboardFile` values.

## Arguments and Environment Variables

You can inject key–value pairs into the environment, making them available to your code, when running the app from Xcode. Edit the scheme and go to the Arguments tab of the Run action. There are two categories (Figure 10-2); to add a key–value pair, click the Plus button under the desired category and enter a name and value:

### *Arguments Passed On Launch*

The name of the argument must be preceded by a hyphen, and followed with a space and the value. This allows you to inject key–value pairs into user defaults. If an argument is `-TEST1 1`, then you can say:

```
if UserDefaults.standard.integer(forKey: "TEST1") == 1 {
```

### *Environment Variables*

There’s a Name column and a Value column (which is always a string). To retrieve an environment variable, use the `ProcessInfo` class. If the name is `TEST2` and the value is `2`, then you can say:

```
if let t = ProcessInfo.processInfo.environment["TEST2"], t == "2" {
```

A configured pair can be toggled on or off for subsequent builds by clicking the checkbox to its left. So you don't have to delete a configured pair just because you don't want to use it at the moment.

Arguments and environment variables configured for the Run action are present when you build and run, but not when you are testing. But the Test action has its own arguments and environment variables, which are present only when you are unit testing. That gives your code a way to detect that it is under test. For example, you might conditionally substitute a “mock” version of a class or struct during unit testing.

These arguments and environment variables are present only when you build and run *from Xcode*; a user who launches your app on a device will be unaffected by them. So you can take advantage of this feature during development without worrying that its effects will leak out into the real world.

## Version Control

Sooner rather than later in the life of any real app, you should consider putting your project under version control. Version control is a way of taking periodic snapshots (technically called *commits*) of your project. Its purpose might be:

### *Security*

Version control can store your commits in a repository offsite, so that your code isn't lost in case of a local computer glitch or some equivalent “hit by a bus” scenario.

### *Publication*

You might want to make your project's source publicly available through an online site such as GitHub.

### *Collaboration*

Version control affords multiple developers rational write access to the same code.

### *Confidence*

Progress on your code may require changes in many files, possibly over many days, before a new feature can be tested. Version control tracks and lists those changes, and if things go badly, helps to pinpoint what's gone wrong, and lets you withdraw the changes altogether if necessary. You can confidently embark on a programmatic experiment whose result may not be apparent until much later.

Xcode's version control facilities are geared primarily to Git (<http://git-scm.com>). You can use a different version control system with your projects, but not in an integrated fashion from inside Xcode. Even with Git, it is possible to ignore Xcode's integrated

version control and rely on the Terminal command line or a specialized third-party GUI front end such as Sourcetree (<http://www.sourcetreeapp.com>). In that case, you might turn off Xcode's version control integration by unchecking Enable Source Control in the Source Control preference pane. If you check Enable Source Control, additional checkboxes spring to life so that you can configure what automatic behaviors you want. In this discussion, I'll assume that Enable Source Control is checked.

When you create a new project, the Save dialog includes a checkbox that offers to place a Git repository into your project folder from the outset. If you have no reason to decide otherwise, I suggest that you check that checkbox! If you don't, and if you change your mind later and want to add a Git repository to an existing project, open the project and choose Source Control → New Git Repositories. Conversely, to download a working copy of an existing project from a remote server, choose Source Control → Clone and enter the required information.

When you open an existing project, if that project is already managed with Git, Xcode detects this and displays version control information in its interface. Files in the Project navigator are marked with their status. You can distinguish modified files (M), new untracked files (?), and new files added to the index (A).

Version control management commands are available in these places:

- The Source Control menu
- A file's contextual menu, in the Source Control submenu (Control-click the file's listing in the Project navigator)
- The change bars in a source editor pane
- The Code Review editor in a source editor pane
- The Source Control navigator (Command-2)
- The History inspector (Command-Option-2) and, when appropriate, the Source Control inspector (Command-Option-4)
- The branch pop-down menu in the project window toolbar (new in Xcode 13)

To commit changes, choose Source Control → Commit; or, for a single file, choose Source Control → Commit [Filename] in the contextual menu for that file. A comparison view of the changes appears; each change can be excluded from this commit (or reverted entirely), so related file hunks can be grouped into meaningful commits. You can discard changes, push, and pull using the Source Control menu. Cherry-pick and stashing commands are also present.

Branches, stashes, tags, and remotes are listed in the Source Control navigator. Selecting an item here causes relevant information to be displayed in the Source Control inspector; selecting a branch displays its corresponding remote, and selecting a remote displays its URL. Selecting a branch also shows the log of its commits in the editor. The list of commits is filterable through a search field at the top of the editor.






Figure 10-3. Version comparison

Selecting a commit in the list displays its branches, its commit message, and its involved files in the inspector. Double-click a commit to see its involved files and their differences from the previous commit in a comparison view.

Other relevant commands appear in the contextual menu for items in the Source Control navigator. To add a remote, Control-click the Remotes listing. To make a new branch, check out a branch, tag a branch, delete a branch, or merge a branch, Control-click the branch listing.

To see a comparison view for the file currently being edited, display the Code Review editor: choose View → Show Code Review (Command-Option-Shift-Return), or click the Enable Code Review button at the top right of an editor pane. New in Xcode 13, comparison can be inline or side by side; to specify which, choose Editor → Inline Comparison or Editor → Side By Side Comparison, or use the Editor Options pop-up menu at the top right of the editor pane.

In [Figure 10-3](#), I'm using the inline comparison view (new in Xcode 13) to see the difference between two selected commits. The commits are chosen and listed in the bar at the bottom of the pane. In the text, the older version is displayed first, followed by the newer version; you can see that I've changed my `titleTextAttributes` dictionary keys (because the Swift language changed).

The History inspector (Command-Option-2) lists the commit log from the current branch for the file that's being edited. Click a commit to summon a popover containing the full commit message along with buttons to show the commit and its files, switch to the Code Review editor, or address an email to the commit's author.

For similar information in a source editor pane, choose Editor → Authors, or choose Authors from the Editor Options pop-up menu at the top right of the pane. The file is divided into hunks corresponding to the commits where those lines were most recently changed, along with each commit's author and date. Click a commit to summon the same popover. To get that popover for a given line of code, select it and choose Editor → Show Last Change For Line (or the contextual menu).

If you’ve checked Show Source Control Changes in the Source Control preference pane, change bars appear in the source editor pane, in the gutter at the left, showing what you’ve changed since the last commit. In my opinion, this is Xcode’s most valuable Git integration feature. Choose Navigate → Jump to Next Change to navigate between changes; if you switch to Code Review mode, arrows in the bottom bar let you do the same thing. New in Xcode 13, the Changes tab of the Source Control navigator lists all changed files. Command-click a change bar to display both the old committed text and the new uncommitted text inline. Click a change bar to see a menu that lets you discard that change (be careful not to do that by mistake!).

If you have an account with any of three popular online sites that allow ready management of code submitted through version control — GitHub (<https://github.com>), Bitbucket (<https://bitbucket.org>), and GitLab (<https://gitlab.com>) — you can enter your authentication information into Xcode’s Accounts preference pane. Once you’ve done that:

#### *Create a remote repository*

If your project is already under Git control locally, switch to the Source Control navigator, click Repositories, Control-click Remotes, and choose New [Project Name] Remote. A dialog lets you choose a remote site and upload to it.

#### *Clone a remote repository*

When you choose Source Control → Clone, your repositories on those sites are listed in a dialog and you can clone one of them directly. Also, when you’re in a web browser looking at a GitHub repository consisting of an Xcode project, if you click the Code button, there’s an option to Open with Xcode; the repository is cloned and the project is opened, in a single move.

#### *Manage pull requests*

Pull request integration, new in Xcode 13, is available for GitHub and Bitbucket. To create a pull request, having pushed a branch, choose Source Control → Create Pull Request, edit the title, enter a comment, and click Publish. Existing pull requests can be viewed and edited from the Source Control navigator, under Changes. Pull request comments can appear inline within the relevant code. For more information, there’s a good WWDC 2021 video about the pull request workflow in Xcode.

## Editing and Navigating Your Code

Many aspects of Xcode’s editing environment can be modified to suit your tastes. Your first step should be to go to Xcode’s Themes preference pane and choose a theme and a Source Editor font face and size. Nothing is so important as being able to read and write code comfortably!

I like a pleasant monospaced font. SF Mono is included and is the default; I think it's very nice. Other possibilities might be Menlo or Consolas, or the freeware Inconsolata (<http://levien.com/type/myfonts>) or Source Code Pro (<https://github.com/adobe-fonts/source-code-pro>). I also like a largish size (13, 14, or even 16). You can change the theme and font size on the fly with the Editor → Font Size and Editor → Theme hierarchical menus. You also get a choice of line spacing (leading) and cursor.

## Text Editing Preferences

The exact look and behavior of the source code editor depends upon your settings in the three tabs of Xcode's Text Editing preference pane — Display, Editing, and Indentation. Here are some particularly interesting Text Editing settings.

### Display

With “Line numbers” checked, line numbers appear in the gutter to the left of source code text. Visible line numbers are useful when debugging.

Code folding lets you collapse the text between matching curly braces. With “Code folding ribbon” checked, code folding bars appear to the left of your code (at the right of the gutter), displaying your code's hierarchical structure and allowing you to collapse and expand just by clicking the bars. I'm not fond of code folding, and I don't want to trigger it accidentally, so I leave that checkbox unchecked. If I need code folding, it remains available through the Editor → Code Folding hierarchical menu.

A divider line for a MARK: comment (discussed later in this chapter) can appear in your code, above the comment; check “Mark separators.”

With Editor Overscroll turned on, Xcode pretends that your file ends with some extra whitespace, so that when you scroll to the end, the last line appears in the middle of the editor pane rather than at the bottom. Since the bottom of the editor pane is usually the bottom of your screen, this lets you keep your eyes focused more or less straight ahead as you work; also, you can append lines without the editor constantly scrolling to accommodate them.

### Editing

The first two checkboxes under Editing have to do with code completion; I'll discuss them separately in a moment.

With “Enable type-over completions” checked, Xcode helps balance delimiters. Let's say I intend to make a UIView by calling its initializer `init(frame:)`. I type as far as this:

```
let v = UIView(fr
```

Xcode automatically appends the closing right parenthesis, with the insertion point still positioned before it:

```
let v = UIView(fr)
// I have typed ^
```

When I finish typing the parameter and then type a right parenthesis, I don't end up with two adjacent right parentheses; instead, Xcode moves the insertion point through the existing right parenthesis:

```
let v = UIView(frame:r)
//      I have typed ^
```

With “Enclose selection in matching delimiters” checked, if you select some text and type a left delimiter (such as a quotation mark or a left parenthesis), the selected text is not replaced; rather, it is surrounded with left and right delimiters. I find this natural and convenient.

## Indentation

I like all seven checkboxes under “Indent when typing” to be checked; I find the way Xcode lays out code to be excellent with these settings. If a line of code isn't indenting itself correctly, select the problematic area and choose Editor → Structure → Re-Indent (Control-I). Pasted code is not indented automatically unless you've checked “Re-Indent on paste.”



There's a checkbox letting you decide whether to indent case labels in a switch statement in Swift. This is a subject of semireligious warfare; I'm not about to get involved.

## Multiple Selection

You probably know from experience how to use the mouse and keyboard to select text. In addition to the familiar forms of selection, Xcode lets you set *multiple simultaneous selections* in your code. With a multiple selection, your edits, including typing and keyboard navigation, are performed at each selection site simultaneously, which is useful when you have many parallel changes to make. Some ways to get a multiple selection are:

- Option-click and drag to create a rectangular selection.
- Control-Shift-click (and perhaps drag, double-click, and so on) to add a selection to the existing selection.
- Select a symbol and choose Editor → Selection → Select All Symbols; each occurrence of that symbol is selected simultaneously. (Alternatively, Editor → Edit All In Scope selects all occurrences of the currently selected term within the same scope.)



Figure 10-4. The code completion menu

- Select any text and choose Find → Select Next Occurrence.
- Press Command-F to bring up the search field at the top of the editor, enter a search term, and choose Find → Find and Select Next, or Find → Select All Find Matches.
- Select a stretch of code consisting of multiple lines, and choose Editor → Selection → Split Selection By Lines.

## Code Completion and Placeholders

As you write code, you'll want to take advantage of Xcode's code completion feature. Type names and member names can be astonishingly verbose, and whatever reduces your time and effort typing will be a relief. Code completion behavior is governed by two checkboxes in the Editing pane of the Text Editing preferences:

### *Suggest completions while typing*

If this is checked, code completion is basically on all the time.

### *Use Escape key to show completion suggestions*

If this is checked, you can ask for code completion manually by pressing Esc.

I like to have the first checkbox unchecked and the second checkbox checked. That way, I get code completion on demand.

Suppose I want my code to create an alert. I type as far as `let alert = UIAl` and press Esc. A menu pops up, listing completions, including `UIAlertController`. You can navigate this menu, dismiss it, or accept the selection, using the mouse or the keyboard alone. I like to use the keyboard. I arrow down to `UIAlertController` and hit Return, and `UIAlertController` is entered in my code.

Now I type a left parenthesis, so that I've got `UIAlertController(`, and again I press Esc. Now the menu pops up listing the initializers appropriate to a `UIAlertController` (Figure 10-4). The last one is the one I want, so I arrow down to it and hit Return.

At this point, the template for the method call is entered in my code (I’ve broken it into multiple lines here):

```
let alert = UIAlertController(  
    title: <#T##String?#>,  
    message: <#T##String?#>,  
    preferredStyle: <#T##UIAlertController.Style#>)
```

The expressions in `<#...#>` are *placeholders*, showing the type of each parameter. They appear in Xcode as cartouche-like “text tokens” to prevent them from being edited accidentally. To navigate among placeholders, press Tab or choose Navigate → Jump to Next Placeholder (Control-/). In this way, you can select each placeholder in turn, typing to replace it with the actual argument you wish to pass and then tabbing to the next placeholder. To convert a placeholder to a normal string without the delimiters, select it and press Return, or double-click it.

When you’re entering a declaration for a method that’s inherited from a superclass or defined in an adopted protocol, you don’t need to type the initial func; just type the first few letters of the method’s name. In my app delegate class I might type:

```
app
```

If I then press Esc, I see a list of methods such as `application(_:didFinishLaunchingWithOptions:)`; these are methods that might be sent to my app delegate (by virtue of its being the app delegate, as discussed in [Chapter 12](#)). When I choose one, the entire declaration is filled in for me, including the curly braces:

```
func application(_ application: UIApplication,  
    didFinishLaunchingWithOptions  
    launchOptions: [UIApplication.LaunchOptionsKey : Any]?) -> Bool {  
    <#code#>  
}
```

A placeholder for the code appears between the curly braces, and it is selected, ready for me to start entering the body of the function.

What you type in connection with code completion doesn’t have to be the literal start of a symbol. In the preceding example, I can greatly reduce the number of choices in the completion menu if I start by typing `launching`.

Code completion is intelligent about the context in other ways. If a function you’re declaring needs an override designation, code completion provides it. If the property you’re chaining to with dot-notation is an Optional, code completion inserts a safe-unwrapping question mark as it appends the next item in the chain.

## Snippets

Code completion is supplemented by code snippets. A code snippet is a bit of text with an abbreviation. Code snippets are kept in the Snippets library, which appears

when you summon the Library floating window (Command-Shift-L) while editing code. With the Library showing, you can double-click or drag to insert a snippet into your code. But the real point is that a code snippet's abbreviation is available to code completion, which means you can insert a snippet *without* showing the library: you type the abbreviation and the snippet's name is included among the completions.

For example, to enter a `class` declaration at the top level of a file, I would type `class` and press Esc to get code completion, and choose Class — Subclass. The template for a class declaration appears in my code: the class name and superclass name are placeholders, the curly braces are provided, and the body of the declaration (between the curly braces) is another placeholder.

In the Library, single-click on a snippet to see its details: its expansion, its language, its platform(s), its code completion abbreviation (labeled Completion), and the scope where it applies (labeled Availability). If the details don't appear, click the Details button at the top right of the Library floating window.

You can add your own snippets to the Snippets library. These will be categorized as user snippets and will appear first. Unlike built-in snippets, user snippets can be edited and deleted.

To create a user snippet, select some text and choose Editor → Create Code Snippet. The Library floating window will appear, with the new snippet's details ready for editing. Provide a name, a description, and an abbreviation; the Availability pop-up menu lets you narrow the scope in which the snippet will be available through code completion. In the text of the snippet, use the `<#...#>` construct to form any desired placeholders.

I've created an outlet snippet (Chapter 8), with an availability scope of Class Implementation, defined like this:

```
@IBOutlet private var <#name#> : <#type#>!
```

And I've created an action snippet, defined like this:

```
@IBAction private func <#name#> (_ sender: Any) {  
    <#code#>  
}
```

My other snippets constitute a personal library of utility functions that I've developed over the years.

## Refactoring and Code Actions

Refactoring is an intelligent form of code reorganization. To use it, select within your code and then choose from the Editor → Refactor hierarchical menu, or Control-click and choose from the Refactor hierarchical menu in the contextual menu. Here are some of the refactoring commands you're most likely to use:

### *Rename*

The selected symbol's declaration and all references to it are changed, throughout your code. This also allows you to change the name of an outlet property or action method without breaking the connection from the nib ([Chapter 8](#)).

### *Extract to Method*

Creates a new method and moves the selected lines of code into the body of that method, replacing the original lines with a call to that method. The method name and the new call to it are then selected, ready for you to supply a meaningful name.

### *Extract to Variable*

Creates a new variable and assigns the selected code expression to that variable, replacing the original expression with a reference to the variable. If the same expression appears multiple times and you choose Extract All Occurrences, they are all replaced with a reference to the variable. The variable name and the new reference(s) to it are then selected, ready for you to supply a meaningful name.

### *Add Missing Protocol Requirements*

In a type declaration, when the type name is selected, if the type declares adoption of a protocol and does not in fact conform to the protocol's requirements, inserts stubs declaring the missing required members.

### *Generate Memberwise Initializer*

In a type declaration, when the type name is selected, synthesizes an initializer based on the instance property names. This is a great convenience for classes, because they, unlike structs, have no implicit memberwise initializer. It can also be useful for structs, because if you add an initializer to a struct, you lose the implicit memberwise initializer — so this is a way to regain it.

### *Add Equatable Conformance*

In a type declaration that does *not* declare conformance to Equatable, when the type name is selected, synthesizes an implementation of the static `==` method based on the instance property names.

### *Convert Function to Async*

(New in Xcode 13.) In a function declaration, when the function name is selected, simply inserts the `async` keyword.

But if the function's last parameter is an `@escaping` function returning `Void`, that parameter is assumed to be a completion handler, and the function is rewritten as a true `async` function! If it was passing a value into the completion handler, now it *returns* that value. If it was passing an error into the completion handler, now it *throws* that error. Moreover, two more options appear:



### *Add Async Alternative*

Rewrites the function as two functions with the same name. The second function is `async`. The first function, taking a completion handler, calls the `async` function and passes the result into the completion handler; it is also marked with an availability deprecation. This is suitable when your app doesn't need to be backward compatible; your calling code keeps working, but gets a compiler warning encouraging it to call the `async` version.

### *Add Async Wrapper*

Leaves the function untouched, and adds a second function with the same name. The second function is `async`; it contains a `withCheckedContinuation` block that calls the first function and, in the completion handler, resumes the continuation. This is suitable when your app needs to be backward compatible, which case you'll have to attach an availability annotation to the `async` version (and a Fix-it will help you do that).

### *Convert To Switch Statement*

When an if comparison depends on an equality test, then when the entire if construct is selected, rewrites it as a switch statement.

### *Expand Switch Cases*

In a switch statement where the tag is an enum, when the keyword `switch` is selected, adds any missing cases.

Code actions are another approach to refactoring. You Command-click (or, depending on your Navigation preferences, Command-Control click) in a keyword that introduces curly braces. A popover, called the *action menu*, appears; it contains menu items that let you edit the structure of your code. The same popover can be summoned by selecting the keyword and then choosing Editor → Show Code Actions (Command-Shift-A). Some of the popover menu commands are like the refactoring commands I've just listed.

## Fix-it and Live Syntax Checking

Xcode's Fix-it feature allows the compiler to make *and implement* positive suggestions on how to avert a problem that has arisen as a warning or compile error. In effect, you're getting the compiler to edit your code for you.

Here's an example. [Figure 10-5](#), at the top, shows that I've accidentally forgotten the parentheses after a method call. This causes a compile error. But the stop-sign icon next to the error tells me that Fix-it has a suggestion. I click the stop-sign icon, and [Figure 10-5](#), at the bottom, shows what happens: a dialog pops up, not only showing the full error message but also telling me how Fix-it proposes to fix the problem — by inserting the parentheses. If I click the Fix button in the dialog, Xcode does insert the parentheses — and the error vanishes, because the problem is solved.




Figure 10-5. A compile error with a Fix-it suggestion

The intelligence of Fix-it is sometimes the same as the intelligence of refactoring. If a switch statement’s tag is an enum and you omit cases, Fix-it will add them. If a type adopts a protocol and fails to implement required members, Fix-it will insert stubs for those members.



If you’re confident that Fix-it will do the right thing, you can have it implement *all* suggestions simultaneously: choose Editor → Fix All Issues.

Live syntax checking is like continual compilation, emitting a warning or error even if you don’t actually compile. This feature can be toggled on or off using the “Show live issues” checkbox in Xcode’s General preference pane. I keep it turned off, because I find it intrusive. My code is almost never valid while I’m in the middle of typing, because things are always half-finished; that’s what it means to be typing! Merely typing `let` and pausing will likely cause the live syntax checker to complain.

## Navigation

Developing an Xcode project involves editing code in many files. You’ll need to leap nimbly from file to file; you might want to see multiple files simultaneously. Fortunately, Xcode provides numerous ways to navigate your code, some of which have been mentioned already in Chapters 7 and 9:

### *The Project navigator*

Lists all your project’s files by name. If you know something about the name of a file, you can find it quickly in the Project navigator by typing into the search field in the filter bar at the bottom of the navigator (Edit → Filter → Filter in Navigator, Command-Option-J). For example, type `story` to see just your `.storyboard` files.

### *The Symbol navigator*

If you highlight the first two icons in the filter bar (so that they are filled), the Symbol navigator lists your project’s object types and their members. Click a symbol to navigate to its declaration in the editor. As with the Project navigator, the filter bar’s search field can help get you where you want to go.

### *The jump bar*

Every path component of an editor pane's jump bar is a menu:

#### *The bottom level*

At the jump bar's bottom level (the rightmost menu, Control-6) is a list of your file's object and member declarations, in the order in which they appear. Hold Command while choosing the menu to see them in alphabetical order instead. To filter what the menu displays, start typing while the menu is open.

You can inject text into this menu; to do so, put a comment in your code whose first word is MARK:, TODO:, or FIXME:, followed by the desired text. A MARK: comment is a good way to divide the menu into sections. To make an actual divider line in the menu, put a hyphen:

```
// MARK: - View lifecycle
```

#### *Higher levels*

Higher-level path components are hierarchical menus; you can use any of them to work your way down the file hierarchy and reach any file without using the Project navigator. These menus can also be filtered.

#### *History*

Each editor pane remembers the names of files you've displayed in it. The Back and Forward indicators are buttons as well as pop-up menus (or choose Navigate → Go Back and Navigate → Go Forward, Command-Control-Left and Command-Control-Right).

#### *Related items*

The leftmost button in the jump bar summons the Related Items menu, a hierarchical menu of files related to the current file, such as superclasses and adopted protocols. This list even includes functions that call or are called by the currently selected function.

### *Editor panes*

Using multiple editor panes allows you to work in two places at once.

### *Assistant pane*

The assistant pane lets you walk through all places that relate to your code in a specific way, such as all callers of a selected method.

### *Document tabs*

Using document tabs allows a single editor pane to be switched between specific places where you want to work.



Figure 10-6. The minimap

### Jump to definition

Navigate → Jump to Definition (Command-Control-J, Command-Control-click) lets you jump from a selected or clicked symbol in your code to its declaration.

### Open quickly

File → Open Quickly (Command-Shift-O) summons a dialog where you can search for a symbol in your code and in the framework headers.

### Breakpoints

The Breakpoint navigator lists all breakpoints in your code. Xcode lacks code bookmarks, but you can misuse a breakpoint as a bookmark. Breakpoints are discussed later in this chapter.

### Minimap

The minimap helps you navigate a single large source code file. To see it, choose Editor → Minimap, or use the Editor Options pop-up menu at the top right of the editor pane. The minimap displays the entire file in miniature — too small to read, but indicating the structure of the code, including MARK: comments, along with transients such as warnings and errors, change bars, breakpoints, and Find results. Drag the shaded area to scroll. Hover the mouse to display structure and symbols; hold Command while hovering to display *all* symbols (Figure 10-6). Click a symbol to navigate to it.

## Finding

Finding is a form of navigation. Xcode has both an editor level find and a global find; each is configurable with find options that affect your search:

### *Editor level find (Find → Find, Command-F)*

Appears in a bar at the top of the editor pane. A button at the right end of the search field toggles case-sensitive search; a pop-up menu lets you specify containment, word exact match, word start, word end, or regular expression search.

### *Global find (Find → Find in Project, Command-Shift-F)*

Appears in the Find navigator. The options appear above and below the search field. Above the search field, you can choose between Text, References (where a symbol is used), Definitions (where a symbol is defined), Regular Expression, and Call Hierarchy (tracing call stacks backward); you can search by word contents, word exact match, word start, or word end. Below the search field, you can toggle case sensitivity, and you can specify a scope determining which files will be searched: click the current scope to see the Search Scopes panel, where you can select a different scope or create a custom scope.



Globally finding the Call Hierarchy is one of Xcode's best, yet least-known, features. It displays hierarchically the complete call stack, tracing all the paths by which the search target is accessed. When you're struggling to understand how your code works (or doesn't), this display is magic. There's even a shortcut: select a term and choose Find → Find Call Hierarchy.

To find and replace:

### *Editor level find and replace*

Next to the magnifying glass icon, click Find and choose Replace to toggle the visibility of the With field. You can perform a Find and then click Replace to replace that instance, or click All to replace all occurrences (hold Option to change it to All in Selection).

### *Global find and replace*

Above the left end of the search bar, click Find and choose Replace. You can replace all occurrences (Replace All), or select particular find results in the Find navigator and replace only those (Replace); conversely, you can press Delete to remove a selected find result from the Find navigator, to protect it from being affected by Replace All.

# Running in the Simulator

When you build and run with a simulator as the destination, you run in the Simulator application. A Simulator window represents a specific type of device. Depending on your app target's Deployment Target and Targeted Device Families build settings, and on what SDKs you have installed, you may have choices about the device type and system as you specify your destination before running (see [Chapter 7](#)).

The Simulator can display multiple windows, representing different devices. You can run different projects simultaneously, in the same Simulator window or different Simulator windows. When you choose from the Simulator's File → Open Simulator hierarchical menu, you switch to the window representing the chosen device, launching that device's simulator if needed.

A Simulator window can display the bezel surrounding the device's screen. Choose Window → Show Device Bezels to toggle this feature (for all windows). Displaying the bezel allows you to press hardware buttons (Home button, volume buttons, screen lock button) by clicking with the mouse; also, certain gestures, such as swiping from the screen edge, become easier to perform. On the other hand, hiding the bezel is arguably neater, and all those hardware buttons are still available through menu commands.

A Simulator window can be resized by dragging an edge or corner. You also have a choice of three standard sizes (you might have to uncheck Show Device Bezels to enable them all):

## *Window → Physical Size*

The device screen displayed on your computer monitor is the size of the screen of the physical device. If you hold up the physical device next to the Simulator window on the monitor, the screen dimensions will match perfectly.

## *Window → Point Accurate*

One point on the device screen is one point on the computer monitor. An iPhone 6s screen is 375 points wide, so it occupies 375 points of computer screen width.

## *Window → Pixel Accurate*

One pixel on the device screen is one pixel on the computer monitor. My computer monitor is single-resolution, but an iPhone 6s is double-resolution, so it occupies 750 pixels of computer screen width. If your computer monitor resolution matches the resolution of the device, Pixel Accurate and Point Accurate are the same.

You can also maximize the Simulator window with Window → Fit Screen; you can float the Simulator window in front of all other applications, including Xcode; and

you can tile it into fullscreen mode, which is useful for splitting the screen between just the Simulator and Xcode.

You can interact with the Simulator in some of the same basic ways as you would a device. Using the mouse, you can tap on the device's screen; hold Option to make the mouse represent two fingers moving symmetrically around their common center, and Option-Shift to represent two fingers moving in parallel.

For an iPad simulator, you can also capture the keyboard, or the keyboard and pointer; buttons for toggling this appear above the Simulator window. That means you're simulating a hardware keyboard or mouse being connected. A captured pointer belongs entirely to the Simulator, so now you can't use your mouse to do anything else! To get out of this situation, end capture mode by pressing Esc (or whichever keyboard shortcut you've specified in the Simulator preferences).

Items in the Device menu let you perform hardware gestures such as rotating the device, shaking it, locking its screen, and clicking the Home button; buttons for clicking Home and rotating the device are visible above the simulator window as well.

Items in the Features menu let you test your app by simulating special situations such as the arrival of a phone call or the user switching between light and dark mode (Toggle Appearance).

The Debug menu in the Simulator is useful for detecting problems with animations and drawing. Slow Animations, if checked, makes animations unfold in slow motion so that you can see in detail what's happening. The four menu items whose names begin with Color reveal possible sources of inefficiency in screen drawing. Simulate Memory Warning lets you pretend your app is running low on memory.

The Simulator application supports “side-loading” of apps. This means you can get an app onto a simulator without launching it from Xcode. To do so, drag a built *.app* file from the Finder onto an open simulator window. Various other types of resource, such as images and push notification payloads, can be side-loaded as well.

While running your app from Xcode in the Simulator, you can change certain user settings on the simulated device without passing through the Settings app. In the debug bar, click the Environment Overrides button to summon a popover where you can switch between light and dark modes, change the dynamic text size, and alter various accessibility settings.

Another powerful way to control a simulator is from the command line. In the Terminal, type `xcrun simctl` to see a list of things you can do. Among other things, in addition to side-loading files, you can change your app's privacy permissions, manipulate its keychain, and send it an external URL (such as a universal link).

In Xcode 11 and before, closing a Simulator window stops the corresponding simulator; to use that simulator again later, it must be rebooted. Starting in Xcode 12, the

Simulator application's preferences let you elect to keep simulators running when closed and even when the Simulator app isn't running.

## Debugging

Debugging is the art of figuring out what's wrong with the behavior of your app as it runs. I divide this art into two main techniques: caveman debugging and pausing your running app in the debugger.

### Caveman Debugging

Caveman debugging consists of altering your code, usually temporarily. Typically, you'll add code to log informative messages that you'll read in the Xcode console in the project window's Debug pane as your app runs.

Purists may scoff at caveman debugging, but I use it heavily: it's easy, informative, and lightweight. And sometimes it's the only way. Unlike the debugger, console logging works with any build configuration (Debug or Release) and wherever your app runs (in the Simulator or on a device). It works when pausing is impossible (because of threading issues, for instance). It even works on someone else's device, such as a tester to whom you've distributed your app.



Swift defines four special literals, particularly useful when logging because they describe their own location within the source code: `#file`, `#line`, `#column`, and `#function`.

### Print

The simplest Swift command for sending a message to the Xcode console is the global `print` function. You might print a string saying where the path of execution is:

```
print("view did load")
```

You might output a value:

```
print("i is", i)
```

When you print an object, the output comes from that object's `description` property. Cocoa objects generally have a useful built-in `description` property implementation. Let's print an object in our view controller's `viewDidLoad`:

```
print(self.view)
```

The output in the console reads something like this (I've formatted it for clarity here):

```
<UIView: 0x79121d40;  
  frame = (0 0; 320 480);  
  autoresize = RM+BM;  
  layer = <CALayer: 0x79121eb0>>
```



We learn the object's class, its address in memory (useful for confirming whether two instances are in fact the same instance), and the values of some additional properties. In your own object types, you can adopt `CustomStringConvertible` and implement the description property as desired ([Chapter 4](#)).

## Dump

Instead of `print`, you might like to use `dump`. Its console output describes an object along with its class inheritance and its instance properties, by way of a `Mirror` object:

```
dump(self)
```

If `self` is a view controller of class `ViewController` with a `didInitialSetup` instance property, the console output looks like this:

```
* ViewController
- super: UIViewController
- super: UIResponder
- super: NSObject
- didInitialSetup: true
```

In your own object types, you can adopt `CustomReflectable` and implement the `customMirror` property as desired ([Chapter 5](#)).

## Logger

An important feature of `print` and `dump` is that they produce no output when the app is launched independently of Xcode. That makes sense, because in that situation there's no Xcode console to output to. But what if you *want* to send yourself messages when you're running the app independently of Xcode?

The traditional solution is to import `Foundation` (which, in real-life iOS programming, you're already doing) and call the `NSLog` C function. It takes an `NSString` which operates as a format string, followed by the format arguments. A *format string* is a string containing symbols called *format specifiers*, for which values (the format arguments) will be substituted at runtime; see “String Format Specifiers” in Apple's *String Programming Guide* in the documentation archive. All format specifiers begin with a percent sign (%), so the only way to enter a literal percent sign in a format string is as a double percent sign (%%). The character(s) following the percent sign specify the type of value that will be supplied at runtime. The most common format specifiers are %@ (an object reference), %d (an int), %ld (a long), and %f (a double):

```
NSLog("the view: %@", self.view)
```

In that example, `self.view` is the first (and only) format argument, so its value will be substituted for the first (and only) format specifier, %@, when the format string is printed in the console:

```
2015-01-26 10:43:35.314 Empty Window[23702:809945]
the view: <UIView: 0x7c233b90;
frame = (0 0; 320 480);
autoresize = RM+BM;
layer = <CALayer: 0x7c233d00>>
```

Over the past several years, NSLog has gradually been superseded by a new unified logging system, OSLog. Starting in iOS 14 and Swift 5.3, a Swift native type, `Logger`, acts as a comfortable façade for OSLog. To use `Logger`, `import os` and create a `Logger` object, typically as an instance property or global:

```
import os
let mylog = Logger(subsystem: "com.neuburg.matt", category: "testing")
```

The `subsystem` and `category` strings are arbitrary but useful, because you can refer to them to focus on the particular log messages that interest you. To send a log message, call a method of your `Logger` instance; to start with, you can use `log`:

```
mylog.log("this is a test")
```

The argument has to be a literal string, but it can include string interpolations:

```
mylog.log("this is a test of \(self)")
```

These are actually custom string interpolations ([Chapter 5](#)):

- You don't have to use NSLog format specifiers; you express formatting with string interpolation parameters (I'll demonstrate in a moment).
- Your interpolations are treated as autoclosures, so they aren't evaluated unless they have to be, and when they *are* evaluated, it's done outside of your app's process, without slowing down the app itself.

When you run the app from Xcode, log messages from `Logger` appear in the Xcode console, and are tagged similarly to NSLog with the current time and date along with the process name, process ID, and thread ID (useful for determining whether two logging statements are called on the same thread). The category from your `Logger` configuration is also present, in square brackets; this gives you something to filter on so that only the desired messages appear.

Moreover, these log messages appear *even when the app is running outside of Xcode!* To view them, use the Console application:

1. In the Sources pane at the left, under Devices, are shown all running simulators and any devices currently visible to the computer. Select the desired device and exercise the app, while watching the Console output.
2. To eliminate unwanted output, set up a filter in the toolbar search field. You can filter by the name of the process (that is, the name of your app); even better, you can filter by the subsystem and category you configured when creating your `Logger` object.

3. You can also specify what information to show by choosing the columns that appear, such as the Time, Process, Thread ID, Category, Subsystem, and Type columns.

But perhaps you didn't have the Console application configured and ready at the time you ran your app? Then there's another option: you can read your log messages after the fact. To do so, use the `log` command-line tool. A device doesn't even have to be physically connected to the computer in order to gather its logs; it just has to be visible on the network. Suppose I say this in the Terminal:

```
% sudo log collect --device-name "TheMattPhone" --last 1h
```

The result is that my home directory now contains a file (actually a bundle) called *system\_logs.logarchive*. I can open this file with the Console application and explore it with filtering in exactly the same way as I've just described for a live logging stream. Alternatively, I can filter in the Terminal with another `log` command:

```
% log show --predicate 'category == "testing"' system_logs.logarchive
```

Bear in mind that what you can do, the user can do. The user can see your logging messages just as well as you can. For this reason, string interpolations are *redacted* by default when your app is running independently of Xcode. If you want an interpolation to be always legible in the Console or the system log, you have to specify that it is public, using a custom string interpolation parameter:

```
mylog.log("this is a test of \(self, privacy: .public)")
```

You can also use string interpolation parameters to perform various sorts of string formatting that you would otherwise have had to perform using `NSLog` format specifiers, such as dictating the number of digits after the decimal point and other sorts of padding and alignment:

```
mylog.log("the number is \(i, format: .decimal(minDigits: 5))") // e.g. 00001
```

Another way to mediate between public and private logging is by specifying the logging *level* at which messages are to be sent. To do so, call a `Logger` instance method that specifies the level: the methods are `debug`, `info`, `notice` (same as `log`), `error`, and `fault`. The significance of logging levels is:

#### *Noisiness*

What you're categorizing is how bad the situation is. `fault` means that, if we log this at all, there is an unexpected bug in the program.

#### *Persistence*

A `debug` message is not written into the log file and doesn't propagate to the Console application. So it works more like `print`: only you can see it, and only while running the app from Xcode. The others are written into the log file, and

the level reflects how hard the message will resist being expunged as time elapses and further data is accumulated.

### *Lagginess*

A debug message has the least overhead, because there is no need to talk to the file-writing mechanism, and on the user's device the format specifier arguments won't even be evaluated, so the expense is effectively zero.

### *Interface*

The levels correspond to markings in the Console application. A `fault` message calls attention to itself with a red filled dot.

## **Aborting**

Another useful form of caveman debugging is deliberately aborting your app because something has gone seriously wrong. See the discussion of `assert`, `precondition`, and `fatalError` in [Chapter 5](#).

`precondition` and `fatalError` work even in a Release build. By default, `assert` is inoperative in a Release build, so it is safe to leave it in your code when your app is ready to ship; by that time, of course, you should be confident that the bad situation your `assert` was intended to detect has been debugged and will never actually occur.

## **The Xcode Debugger**

When Xcode is running your app, you can pause in the debugger and use Xcode's debugging facilities. The important thing, if you want to use the debugger, is that the app should be built with the Debug build configuration (the default for a scheme's Run action). The debugger is not very helpful against an app built with the Release build configuration, not least because compiler optimizations can destroy the correspondence between steps in the compiled code and lines in your source code.

### **Breakpoints**

There isn't a strong difference between running and debugging in Xcode; the main distinction is whether breakpoints are effective or ignored. The effectiveness of breakpoints can be toggled at two levels:

#### *Globally (active vs. inactive)*

Breakpoints as a whole are either *active* or *inactive*. If breakpoints are inactive, we won't pause at any breakpoints.

#### *Individually (enabled vs. disabled)*

A given breakpoint is either *enabled* or *disabled*. Even if breakpoints are active, we won't pause at this one if it is disabled. Disabling a breakpoint allows you to




Figure 10-7. A line breakpoint




Figure 10-8. A column breakpoint

leave in place a breakpoint that you might need later without pausing at it every time it's encountered.

In Xcode 12 and before, the only kind of breakpoint is a *line* breakpoint. A line breakpoint applies to a line of code; the purpose of the breakpoint is to pause before that line executes. New in Xcode 13, you can also place a breakpoint in the middle of a line of code; this is called a *column* breakpoint. What you're actually breakpointing is an evaluable expression within this line of code.

To create a line breakpoint, select in the editor the line where you want to pause, and choose Debug → Breakpoints → Create Breakpoint at Current Line (Command-\). Alternatively, a simple click in the gutter adds a line breakpoint. The breakpoint is symbolized by an indicator in the gutter (Figure 10-7, first).

To create a column breakpoint, select in the editor the expression where you want to pause, and choose Debug → Breakpoints → Create Column Breakpoint. Alternatively, Control-click and choose Create Column Breakpoint from the contextual menu, or Command-click and choose it from the action menu. The breakpoint is symbolized by a marker just above the start of the expression (Figure 10-8).

To remove a line breakpoint, select in the line and choose Debug → Breakpoints → Delete Breakpoint at Current Line. To remove a line breakpoint gesturally, drag the indicator out of the gutter. To remove a column breakpoint, select the breakpointed expression and choose Debug → Breakpoints → Delete Column Breakpoint (or use the contextual menu or the action menu). To remove a column breakpoint gesturally, click the indicator and drag until the cursor displays an X.

There are menu items for disabling and then enabling an individual breakpoint, but the simplest way is gestural: just click the breakpoint indicator, or Control-click it and choose Disable Breakpoint from the breakpoint's contextual menu. A dark breakpoint is enabled; a light breakpoint is disabled (Figure 10-7, second).

To toggle the active status of breakpoints as a whole, click the Breakpoints button in the debug bar, or choose Debug → Activate/Deactivate Breakpoints (Command-Y). If breakpoints are inactive, they are simply ignored en masse, and no pausing at breakpoints takes place. Breakpoint markers are a solid color if breakpoints are active, gray if they are inactive (Figure 10-7, third). The active status of breakpoints as a whole doesn't affect the enabled or disabled status of any breakpoints.

Once you have some breakpoints in your code, you'll want to survey and manage them. That's what the Breakpoint navigator is for. Here you can navigate to a breakpoint, enable or disable a breakpoint by clicking on its indicator in the navigator, and delete a breakpoint. The Breakpoint navigator is of increased importance in Xcode 13, because a column breakpoint indicator is tiny, so it's a lot easier to manipulate a column breakpoint in the navigator than in the code editor.

You can also configure a breakpoint's behavior. Control-click the breakpoint indicator, in the code editor or in the Breakpoint navigator, and choose Edit Breakpoint; or double-click the breakpoint indicator. You can have a breakpoint pause only under a certain condition or after it has been encountered a certain number of times, and you can have a breakpoint perform one or more actions when it is encountered, such as issuing a debugger command, logging, playing a sound, speaking text, or running a script. A breakpoint whose behavior has been configured is badged (Figure 10-7, fourth).

A configured breakpoint can be told to continue automatically after performing its action when it is encountered. A breakpoint that logs and continues can be an excellent alternative to caveman debugging. By definition, such a breakpoint operates only when you're actively debugging the project; it won't dump any messages into the console when the app runs independently, because breakpoints exist only in Xcode.

Certain special kinds of breakpoint (*event* breakpoints) can be created in the Breakpoint navigator — click the Plus button at the bottom of the navigator and choose from its pop-up menu — or by choosing from the Debug → Breakpoints hierarchical menu. Here are the ones you're most likely to use:

#### *Swift error breakpoint*

Pauses when your code says throw.

#### *Exception breakpoint*

Pauses when an Objective-C exception is thrown or caught, without regard to whether the exception would crash your app later. An exception breakpoint that pauses on all exceptions when they are thrown gives the best view of the call stack and variable values at the moment of the exception.

(Sometimes Apple’s code will throw an exception and catch it, deliberately. This isn’t a crash, and nothing has gone wrong; but if you’ve created an exception breakpoint, your app will pause at it, which can be confusing. If this happens to you, choose Debug → Continue to resume your app; if it keeps happening, you might need to disable the exception breakpoint.)

### *Symbolic breakpoint*

Pauses when a certain method or function is called, regardless of what object called it. The method doesn’t have to be your method! A symbolic breakpoint can help you probe Cocoa’s behavior. A method may be specified in one of two ways:

#### *Using Objective-C method notation*

The instance method or class method symbol (- or +) followed by square brackets containing the class name and the method name:

```
-[UIApplication beginReceivingRemoteControlEvents]
```

#### *By Objective-C method name*

The Objective-C method name alone. The debugger will resolve this for you into all possible class–method pairs, as if you had entered them using the Objective-C notation that I just described:

```
beginReceivingRemoteControlEvents
```

A symbolic breakpoint needs to be *resolved*, meaning that Xcode figures out what real method you’re referring to. If Xcode can’t do that (perhaps because you entered the method specification incorrectly), there’s no penalty, but the symbolic breakpoint won’t do anything. Note that resolution might not take place until you actually run the project. New in Xcode 13, an unresolved symbolic breakpoint has a dotted-outline indicator; so you’ll know when the breakpoint is resolved, because the indicator will be normal. Also, a symbolic breakpoint resolved to multiple methods will display a list of those methods hierarchically.

### *Runtime Issue breakpoint*

Pauses when a runtime issue is encountered. There are four types; for all but the System Frameworks type, you’ll need to enable the corresponding diagnostic in the Scheme editor.

For example, with the main thread checker turned on, you’ll crash if you attempt to manipulate the user interface on a background thread; but you might prefer to break just before that crash. To do so, make a Main Thread Checker breakpoint.

Breakpoints come in three levels of exposure:

#### *Local to you and a project*

The default. The breakpoint appears in this project on this machine.



Figure 10-9. Paused at a breakpoint

#### *Global to you*

Use the contextual menu to say Move Breakpoint To → User. The breakpoint now appears in all your projects on this machine. Symbolic and exception breakpoints are particularly good candidates for this level.

#### *Shared with others*

Use the contextual menu to say Share Breakpoint. The breakpoint is now visible in this project to others with whom you share the project.

### Paused at a breakpoint

When the app runs with breakpoints active and an enabled breakpoint is encountered (and assuming its conditions are met, and so on), the app pauses. In the project window, the editor shows the file containing the point of execution, which will usually be the file containing the breakpoint. We are paused at the command that is *about* to be executed, which is shown by the *instruction pointer* (Figure 10-9). Depending on the settings for Running → Pauses in the Behaviors preference pane, the Debug navigator and the Debug pane may also appear.

When pausing at a breakpoint, the expression that is about to be executed is underlined (new in Xcode 13), and the instruction pointer displays some useful information:

- The thread number. Thread 1 is the main thread.
- The breakpoint number. This is arbitrarily assigned by the debugger itself; look in the Breakpoint navigator to see the number assigned to each breakpoint.
- The number of times this breakpoint has been encountered (in parentheses; this is new in Xcode 13).

Here are some things you might like to do while paused at a breakpoint:

#### *See where you are*

One common reason for setting a breakpoint is to make sure that the path of execution is passing through a certain line. Functions listed in the call stack in the Debug navigator with a User icon are yours; click one to see where you are paused in that function. (Other listings are functions and methods for which you have no source code, so there would be little point clicking one unless you know something about assembly language.) You can also view and navigate the call stack using the jump bar in the debug bar.






Figure 10-10. A data tip

### Study variable values

In the Debug pane, variable values for the current scope (corresponding to what's selected in the call stack) are visible in the variables list. You can see additional object features, such as collection elements, properties, and even some private information, by opening disclosure indicators.

You can use the search field to filter variables by name or value. If a formatted summary isn't sufficiently helpful, you can send description (or, if this object adopts `CustomDebugStringConvertible`, `debugDescription`) to an object variable and view the output in the console: choose `Print Description of [Variable]` from the contextual menu, or select the variable and click the Info button below the variables list.

You can view a variable's value graphically: select the variable and click the Quick Look button (an eye icon) below the variables list, or press the space bar. For example, in the case of a `CGRect`, the graphical representation is a correctly proportioned rectangle. You can make instances of your own custom class viewable in the same way; declare the following method and return an instance of one of the permitted types (see Apple's *Quick Look for Custom Types in the Xcode Debugger* in the documentation archive):

```
@objc func debugQuickLookObject() -> Any {
    // ... create and return your graphical object here ...
}
```

You can inspect a variable's value in place in your code, by examining its data tip. To see a data tip, hover the mouse over the name of a variable in your code. The data tip is much like the display of this value in the variables list: there's a disclosure indicator that you can open to see more information, plus an Info button that displays the value description here and in the console, and a Quick Look button for showing a value graphically (Figure 10-10).

### *Set a watchpoint*

A watchpoint is like a breakpoint, but instead of depending on a certain line of code it depends on a variable's value: the debugger pauses whenever the variable's value changes. You can set a watchpoint only while paused in the debugger. Control-click the variable in the variables list and choose Watch [Variable]. Watchpoints, once created, are listed and managed in the Breakpoint navigator.

### *Inspect your view hierarchy*

You can study the view hierarchy while paused in the debugger. Click the Debug View Hierarchy button in the debug bar, or choose Debug → View Debugging → Capture View Hierarchy. Views are listed in an outline in the Debug navigator, along with their view controllers and window scenes. The editor displays your views visually; this is a three-dimensional projection that you can rotate. The Object inspector and the Size inspector display information about the currently selected view.

### *Inspect your object graph*

Using the Memory Debugger, you can study the object graph (what objects you've created and how they refer to one another) while paused in the debugger. I'll talk more about that later in this chapter.

### *Manage expressions*

An expression is code to be added to the variables list and evaluated every time we pause. Choose Add Expression from the contextual menu in the variables list. The expression is evaluated within the current context in your code, so be careful of side effects.

### *Talk to the debugger*

You can communicate directly with the debugger through the console. Xcode's debugger interface is a front end to the *real* debugger, LLDB (<http://lldb.lvm.org>); by talking directly to LLDB, you can do everything that you can do through the Xcode debugger interface, and more. Common commands are:

`ty` `loo` (*short for type lookup*)

Followed by a type name, dumps a full declaration for the type, listing all its members (properties and methods). For Cocoa classes, you might get better information by performing the lookup in Objective-C:

```
(lldb) ty loo -l objc -- ClassName
```

`v` (*or fr v, short for frame variable*)

Alone, prints out all variables locally in scope, similar to the display in the variables list. Alternatively, can be followed by the name of a variable you want to examine. Fast and lightweight because it reaches right into the stack and grabs the value, but it has some limitations; for obvious reasons, it doesn't work for computed properties.

*p (or expression, expr, or simply e)*

Compiles and executes, in the current context, any expression in the current language. Be careful of your expression's side effects! This is more heavyweight than *v*.

*po (meaning "print object")*

Like *p*, but displays the value of the executed expression in accordance with its description or `debugDescription` (similar to `Print Description`). It is actually an alias for `expr -0`, meaning "object description." Twice as expensive as *p* because it has to be compiled and executed *twice*.

### *Fiddle with breakpoints*

You are free to create, destroy, edit, enable and disable, and otherwise manage breakpoints even while your app is running, which is useful because where you'd like to pause next might depend on what you learn while you're paused here.

Indeed, this is one of the main advantages of breakpoints over caveman debugging. To change your caveman debugging, you have to stop the app, edit it, rebuild it, and start running the app all over again. But to fiddle with breakpoints, you don't have to be stopped; you don't even have to be paused! An operation that went wrong, if it doesn't crash your app, can probably be repeated in real time, so you can just add a breakpoint and try again. For instance, if tapping a button produces the wrong results, you can add a breakpoint to the action method and tap the button again; you pass through the same code, and this time you pause and can work out what the trouble is.

### *Continue or step*

To proceed with your paused app, you can either resume running or take one step and pause again. The commands are in the `Debug` menu, or you can click the convenient buttons in the debug bar:

#### *Continue*

Resume running (until a breakpoint is encountered).

#### *Step Over*

Pause at the next line.

#### *Step Into*

Pause in your function that the current line calls, if there is one; otherwise, pause at the next line.

#### *Step Out*

Pause when we return from the current function.

*Start over, or abort*

To kill the running app, click Stop in the toolbar (Product → Stop, Command-Period). Clicking the Home button in the Simulator (Hardware → Home) or on the device does *not* stop the running app.

You can make changes to your code while the app is running or paused in the Simulator or on a device, but those changes are *not* magically communicated to the running app. To see your changes in action, you must stop the running app, build, run, and launch the app all over again.

However, you can inject changes into your code by means of an `expr` command, given either at the LLDB console or through a custom-configured breakpoint. Moreover, you can skip a line of code by dragging the instruction pointer down; if you combine that with `expr`, you’ve effectively replaced one line of code with another. So it may be possible to modify your app’s logic and test a proposed change to your code *without* rebuilding and relaunching.



Local variable values can exist even if, at the point where you are paused, those variables have not yet been initialized; but *such values are meaningless*, so ignore them. This applies to the variables list, data tips, and so forth. Forgetting this is a common beginner mistake.

## Testing

A *test* is code that isn’t part of your app target; its purpose is to exercise your app and make sure that it works as expected. Tests can be broadly of two kinds:

### *Unit tests*

A unit test exercises your *code*. A unit test might call some method in your code, handing it various parameters and looking to see if the expected result is returned each time, not just under normal conditions but also when incorrect or extreme inputs are supplied.

### *Interface (UI) tests*

An interface test exercises your *app*. It operates from the point of view of a user, guiding your app through use case scenarios by effectively tapping buttons with a ghost finger and watching to make sure that the interface behaves as expected.

Tests should ideally be written and run constantly as you develop your app. In the case of unit tests, it can even be useful to write tests *before* writing the real code, as a way of developing a working algorithm or designing your app’s business logic. Once your code passes your tests, you continue to run those tests to detect whether a bug has been introduced during the course of development (when that happens, it’s called a *regression*).

Tests are bundled in a separate target (see [Chapter 7](#)). The app templates give you an opportunity to add test targets at the time you create your project. Alternatively, you can create a new test target at any time: make a new target and specify iOS → Test → Unit Testing Bundle or UI Testing Bundle.

A test *class* is a subclass of XCTestCase, which is itself a subclass of XCTest. A test *method* is an instance method of a test class, returning no value and taking no parameters, whose name starts with test. A test method may be marked throws and, new in Xcode 13, it may be marked async.

A test method does not run — indeed, it is not even compiled — until you explicitly ask it to do so. The test target has a dependency upon the main target that it tests (usually, your app target); this means that when a test class is to be compiled and built, the main target will be compiled and built automatically first. But building the main target (with Product → Build, Command-B, or Product → Run, Command-R) does *not* build the test target! To build a test target so as to learn whether its code compiles successfully, but without running a test method, choose Product → Build For → Testing (Command-Shift-U).

Each test method that runs may succeed or fail; more precisely, it succeeds if it *doesn't* fail. A test method can fail in two ways:

#### *Assertions*

A test method may call one or more *assertions*. These are global functions whose names begin with XCTAssert; for a list, see the XCTestCase class documentation. If any assertion fails, the test method fails.

By default, a test method continues running after an assertion fails. That might not be what you want; arguably, failure puts the test method in a bad state. To prevent it, set the `continueAfterFailure` property of your XCTestCase to `false` beforehand.

#### *Throws*

If a test method is declared with throws, throwing an error in the body of the method counts as the test failing. Throwing aborts the test method immediately.

A test method declared with throws, rather than succeeding or failing, may be *skipped*. The idea is that you skip a test based on conditions discovered at runtime (for instance, perhaps this test makes sense only on a certain kind of device). To test those conditions, you can call a global function, either XCTSkipIf or XCTSkipUnless; these are throwing functions, so the call is preceded by try, and what they throw is an XCTSkip error instance. Or you can test the conditions yourself, and construct and throw your own XCTSkip instance. When an XCTSkip instance is thrown, the test method is aborted but neither succeeds nor fails.

Starting in Xcode 12.5, you can call `XCTExpectFailure`, either preceding or wrapping some assertions that you expect to fail or an error that you expect to be thrown. This is useful especially when you want to postpone fixing a failure. When an expected failure *does* fail, the test method doesn't fail, and it continues (unless the failure is an uncaught thrown error). On the other hand, by default, when an expected failure *doesn't* fail, that's a failure! You can change that by turning off `isStrict` in the associated `XCTExpectedFailure.Options` object.

New in Xcode 13, a test method can be declared as `async`. This neatly solves the problem of asynchronous testing, giving your calls to `async` functions a place to start without having to declare a `Task` initializer.

New in Xcode 13, you can ask for a test method or class to run repeatedly. This is intended for situations where your tests are behaving indeterministically (that is, they fail *sometimes* and you don't know why).

A test class may contain utility methods that are called by the test methods; their names do *not* begin with `test`. A utility method can behave like a test method — that is, it can fail through an assertion or by throwing — and the call stack is traced to point the finger at the right spot.

Each test method runs in its own separate test class instance. In fact, your test class is instantiated as many times as there are test methods to be run, *before* any of the test methods is called. This means that if your test class has instance properties, they are separately initialized for each test method. But that doesn't take care of externalities that may need to be configured beforehand or cleaned up afterward. To accompany your test methods, therefore, you can override any of these special methods inherited from `XCTestCase`:

#### `setUp` *class method*

Called once before *all* test methods in the class.

#### `setUp` *instance method*

Called before *each* test method. Starting in Swift 5.2, there's a throwing alternative: `setUpWithError`. If you implement both `setUp` and `setUpWithError`, the error method is executed *first*.

#### `tearDown` *instance method*

Called after *each* test method. Starting in Swift 5.2, there's a throwing alternative: `tearDownWithError`. If you implement both `tearDown` and `tearDownWithError`, the error method is executed *last*.

#### `tearDown` *class method*

Called once after *all* test methods in the class.

As an alternative to the `tearDown` instance method, you can use a *tearDown block*. To do so, call `self.addTearDownBlock(_:)` with a function (typically an anonymous function) to be called at *tearDown* time; `self` here is the  `XCTestCase`  instance. When the *tearDown block* is called depends on where it is added; if you call `addTearDownBlock` within a test method, the block is called only on exit from that method, but if you call it in the `setUp` instance method, the block is called after every test method, because the block was added freshly before every test method.

Running a test also runs the app. The test target's product is a bundle; a unit test bundle is loaded into the app as it launches, whereas an interface test bundle is loaded into a special test runner app generated for you by Xcode. Resources, such as test data, can be included in the bundle. You might use `setUp` to load such resources; you can get a reference to the bundle by way of the test class, by saying `Bundle(for:Self.self)`.

## Unit Tests

Unit tests need to see into the target to be tested, so the test target must import the target to be tested, as a module. To overcome privacy restrictions, the `import` statement should be preceded by the `@testable` attribute; this attribute temporarily changes `internal` (explicit or implicit) to `public` throughout the imported module. A `private` or `fileprivate` method is not directly testable, but you can work around that by providing an `internal` trampoline method that exists only during testing thanks to conditional compilation (as I suggested earlier in this chapter).

As an example of writing and running a unit test method, we can use our `Empty Window` project. Let's give the `ViewController` class a (nonsensical) instance method `dogMyCats`:

```
func dogMyCats(_ s:String) -> String {  
    return ""  
}
```

The method `dogMyCats` is supposed to receive any string and return the string `"dogs"`. At the moment, though, it doesn't; it returns an empty string instead. That's a bug. Now we'll write a test method to ferret out this bug.

First, we'll need a unit test target:

1. In the `Empty Window` project, choose `File → New → Target` and specify `iOS → Test → Unit Testing Bundle`.
2. Call the product `EmptyWindowTests`; observe that the target to be tested is the app target.
3. Click `Finish`.

In the Project navigator, a new group has been created, *EmptyWindowTests*, containing a single test file, *EmptyWindowTests.swift*. It contains a test class *EmptyWindowTests*, along with stubs for two test methods, *testExample* and *testPerformanceExample*. Comment out those two methods. We're going to replace them with a test method that calls *dogMyCats* and makes an assertion about the result:

1. At the top of *EmptyWindowTests.swift*, where we are importing *XCTest*, we must also import the target to be tested, which is the app target:

```
@testable import Empty_Window
```

2. Prepare an instance property in the declaration of the *EmptyWindowTests* class to store our *ViewController* instance:

```
var viewController = ViewController()
```

3. Write the test method. Its name must start with *test!* Let's call it *testDogMyCats*. It has access to the *ViewController* instance as *self.viewController*:

```
func testDogMyCats() {  
    let input = "cats"  
    let output = "dogs"  
    XCTAssertEqual(output,  
        self.viewController.dogMyCats(input),  
        "Failed to produce \ \(output) from \ \(input)")  
}
```

We are now ready to run our test. There are many ways to do this. Switch to the Test navigator, and you'll see that it lists our test target, our test class, and our test method. You can run a test method, or the whole class suite, using the contextual menu or with Run buttons that appear when you hover the mouse over a listing. In addition, in *EmptyWindowTests.swift* itself, there are diamond-shaped indicators in the gutter to the left of the class declaration and the test method name; when you hover the mouse over one of them, it changes to a Run button. You can click that button to run, respectively, all tests in this class or an individual test. Or, to run all tests in all test classes, you can choose **Product** → **Test**.



After running a test, to run just that test again, choose **Product** → **Perform Action** → **Run [Test]** Again. To run multiple individual tests, Command-click in the Test navigator to select just those tests; then choose **Product** → **Perform Action** → **Run [n] Test Methods** (or use the contextual menu).

So now let's run *testDogMyCats*. The app target is compiled and built; the test target is compiled and built. (If any of those steps fails, we can't test, and we'll be back on familiar ground with a compile error or a build error.) The app launches in the Simulator, and the test runs.






Figure 10-11. The Report navigator reports a test failure




Figure 10-12. The Report navigator details a test failure

The test fails! (Well, we knew that was going to happen, didn't we?) The error is described in a banner next to the assertion that failed in our code; moreover, red X marks appear everywhere — at the top of the project window, in the Test navigator next to `testDogMyCats`, and in `EmptyWindowTests.swift` next to the first line of `testDogMyCats`.

The best place to survey what went wrong is the Report navigator. Typically, what you'll want to look at is the summary report; it is what you see in the editor when you select the line that says Test in the Report navigator (Figure 10-11).

The failure is automatically tied to the place in your code where it took place. Hover the mouse over the failure line in the report; a button with an arrow appears at the right. Click it to jump to your code. Alternatively, a button with two linked rings also appears at the right; click it to open your code in an assistant pane, so that you can view the report and the code simultaneously. Select any failure in the report pane to see the corresponding code in the code pane.

Occasionally you might need to view further details. To do so, choose Test → Log from the jump bar at the top of the editor (Figure 10-12); by expanding transcripts, you can see the full console output from the test run, including any caveman debugging messages that you may have sent from your test code (to show them, click the little horizontal lines icon at the far right).

Now let's fix our code. In `ViewController.swift`, modify `dogMyCats` to return "dogs" instead of an empty string. Now run the test again. It passes!

When a test failure occurs, you might like to pause at the point where the assertion is about to fail. To do so, in the Breakpoint navigator, click the Plus button at the bottom and choose Test Failure Breakpoint. This is like an Exception breakpoint,




Figure 10-13. The Report navigator displays code coverage statistics

pausing on the assertion line in your test method just before it reports failure. You could then switch to the method being tested and debug it, examining its variables and so forth, to work out the reason for the impending failure. Don't forget to continue running afterward, so that the test can finish and generate the report.

Xcode's code coverage feature lets you assess how much of your app target's code is being exercised by your unit tests. To switch it on, edit the Test action in your scheme and check Code Coverage in the Options pane. Run your tests. Afterward, the Report navigator has a Coverage section displaying statistics (Figure 10-13); you can also choose Editor → Code Coverage (or use the Editor Options pop-up menu at the top right of the editor pane) to reveal a gutter at the right of your code calling attention to stretches of code that didn't run during the tests.

It's also useful to know about performance testing. This lets you check the performance statistics surrounding a test and make sure that performance is not falling off during development. In addition to measuring elapsed time, performance tests can measure things like CPU and memory usage. A performance test can also exercise launching your app and report whether it launches as quickly as it should.

The modern way to do performance testing is by calling `measure(metrics:)` with an array of `XCTMetric` objects, such as `XCTClockMetric` and `XCTCPUMetric`. The call takes a function where you exercise the code to be tested. The test is automatically run several times, to get a statistically meaningful sample. The first time you run a performance test, you establish a baseline measurement; subsequent runs can alert you if the standard deviation diverges too far from the baseline. For realistic performance testing you should probably run a release build on a device without the debugger attached and with all sanitizers and diagnostics turned off; you can manage that with a custom scheme (and possibly a test plan, as I'll explain a bit later).

Writing unit tests is something of an art, as is writing code designed to be testable. You need to make sure that what your test is testing (the so-called *system under test*, or "sut") is your code, not Apple's code, the network, or any other externality. To prevent an extraneous object from becoming entangled in your test, you might have to use dependency injection to substitute a mock object whose behavior you can

control directly. Actual discussion of the art of testing is outside the scope of this book; in fact, the discussion would require a book of its own, and such books do exist.

As I mentioned earlier, running app target unit tests runs the app. You can avoid that by putting your testable code into a framework ([Chapter 7](#)) and attaching a unit test target to that framework. Those unit tests will run without the extra overhead of launching the app. So if your goal is not to assemble real-world performance statistics, you can run the framework unit tests rather than the app target unit tests.

## Interface Tests

Now let's experiment with interface testing. I'm going to assume that you still have (from [Chapter 8](#)) a button in the Empty Window interface with an action connection to a ViewController method that summons an alert. We'll write a test that taps that button and makes sure that the alert is summoned. Add a UI Testing Bundle to the project; call it *EmptyWindowUITests*.

Interface test code is based on *accessibility*, a feature that allows the screen interface to be described verbally and to be manipulated programmatically. It revolves around three classes: `XCUIElement`, `XCUIApplication` (an `XCUIElement` subclass), and `XCUIElementQuery`. In the long run, it's best to learn about these classes and write your own UI test code; but to help you get started, accessibility actions are *recordable*, meaning that you can generate code automatically by performing the actual actions that constitute the test. Let's try it:

1. In the `testExample` stub method, create a new empty line and leave the insertion point within it.
2. Choose Editor → Start Recording UI Test. (Alternatively, there's a Record button in the debug bar.) The app launches in the Simulator.
3. In the Simulator, tap the button in the interface. When the alert appears, tap OK to dismiss it.
4. Return to Xcode and choose Editor → Stop Recording UI Test. Also choose Product → Stop to stop running in the Simulator.

With luck, the following code, or something similar, has been generated:

```
let app = XCUIApplication()
app.staticTexts["Hello"].tap()
app.alerts["Howdy!"].scrollViews.otherElements.buttons["OK"].tap()
```

The `app` object, obviously, is an `XCUIApplication` instance. Properties such as `staticTexts` and `alerts` return `XCUIElementQuery` objects. Subscripting such an object returns an `XCUIElement`, which can then be sent action methods such as `tap`.

Now run the test by clicking in the diamond in the gutter at the left of the `testExample` declaration. The app launches in the Simulator, and a ghost finger performs



Figure 10-14. The Report navigator displays a failed UI test

the same actions we performed, tapping first the button in the interface and then, when the alert appears, the OK button that dismisses it. The test ends and the app stops running in the simulator. The test passes!

More important, if the interface stops looking and behaving as it does now, the test will *not* pass. To see this, in *Main.storyboard*, select the button and, under Control in the Attributes inspector, uncheck Enabled. The button is still there, but it can't be tapped; we've broken the interface. Run the test. The test fails, and the Report navigator explains why (Figure 10-14): when we came to the Tap “OK” Button step, we first had to Find the “OK” Button, and we failed because there was no alert.

Ingeniously, the report also supplies lots of information about the view hierarchy, along with a screenshot, so that we can inspect the state of the interface during the test. Under Find the “OK” Button, you can double-click Automatic Screenshot to learn what the screen looked like at that moment: it's easy to see the disabled button (and no alert).

## Persisting screenshots

Screenshots such as those taken automatically during the UI test I just described can be useful for other purposes. You might like to retain a more permanent record of how your interface looks under various circumstances — as marketing materials, for submission to the App Store, to help with localization, and so on. In fact, you might construct some of your UI tests for no other purpose than to take screenshots!

To this end, you can have your UI test *deliberately* take a screenshot and make it persist. To do so, call the `XCUIElement` (or `XCUIScreen`) `screenshot` method, turn the resulting `XCUIScreenshot` object into an `XCTAttachment`, and call the `XCTestCase` `add` method to retain the actual screenshot. Along the way, be sure to extend the

lifetime of the attachment so that it persists even if the test succeeds; you can also give the screenshot a convenient name:

```
let screenshot = XCUIApplication().screenshot()
let attachment = XCTAttachment(screenshot: screenshot)
attachment.lifetime = .keepAlways
attachment.name = "OpeningScreen"
self.add(attachment)
```

In the Report navigator, our screenshot is displayed under the name we assigned to it.

## Interface testing and accessibility

During interface testing, your app is in effect being viewed from the outside, as a human being would view it. As I've already said, that depends upon accessibility. Standard interface objects are accessible, but other interface that you create might not be. Select an interface element in the nib editor to view its accessibility characteristics in the Identity inspector. Run the app in the Simulator and choose Xcode → Open Developer Tool → Accessibility Inspector to explore in real time the accessibility characteristics of whatever is under the cursor.

Another useful trick is to put a breakpoint in a UI test method, run the test, pause, and tell the debugger to `po XCUIApplication()` to see the full view hierarchy as accessibility sees it. To see fewer results, form a query specifying the type of entity you're interested in, such as `po XCUIApplication().buttons`.

Referring to an interface object by its visible title, as in our code `app.staticTexts["Hello"]`, is poor practice. If the title changes, or if the app is localized for another language (discussed later in this chapter), the reference breaks. Instead, we should give our button a fixed accessibility identifier, either in code or in the Identity inspector in the nib editor. If the Hello button's accessibility identifier is `GreetingButton`, we can refer to it as `app.buttons["GreetingButton"]` instead.

For more about adding useful accessibility to your interface objects, see Apple's *Accessibility Programming Guide for iOS* in the documentation archive.

## Test Plans

When you've built up several suites of tests, you'll want a way to configure what tests should be run under what conditions on a given occasion. Before Xcode 11, such configuration was confined to a *scheme*. By editing a scheme's Test action, you could determine the complete set of tests that would run when you chose Product → Test. If you wanted more than one set of tests, you needed multiple schemes.

Starting in Xcode 11, this scheme-based architecture is superseded by *test plans*. A test plan is a text file (in JSON format), but you won't have to deal with it as text; you edit it in a dedicated editor, similar to how an *Info.plist* is treated. To create a test

plan, choose Product → Test Plan → New Test Plan. The test plan should not be part of any target, and you'll probably put it at the top level of your project. Edit the new test plan. Click the Plus button and select the targets containing the tests you want to use.

In the Tests pane of the test plan, you can specify individual test classes and test methods to be run. In the Configurations pane, you can specify the behavior of your tests, including various choices you would previously have made in the scheme editor and elsewhere: arguments and environment variables, system language, simulated location, screenshot policy, diagnostics, whether to use code coverage, whether tests should run repeatedly, and whether tests should run in random order (which can help unmask hidden dependencies between tests).

You can make configuration choices on two levels: a set of shared settings, and individual named configurations that inherit the shared settings and can override them. It's important to give each named configuration a meaningful name, because this name is the identifier that will be displayed in the test report.

Having created one or more test plans, you still can't *use* them for anything until you convert your scheme to use test plans. To do so, choose Product → Scheme → Convert Scheme to Use Test Plans. (I presume that some day test plans will be the default and this step will no longer be needed.) The Test action of your scheme will now point to the test plans you've added to it. These should include *every* test plan you might ever want to use with this scheme.

Your scheme may now have multiple test plans, but only one test plan is current at any given moment. When you choose Product → Test, it is the current test plan that runs. Here's how the current test plan is determined:

#### *In the Test navigator*

At the top, the Test navigator has a pop-up menu letting you pick a test plan from among those attached to the current scheme. Whatever test plan is currently displayed here is the current test plan. If the current test plan doesn't include a given test, that test is dimmed and you can't run it from the Test navigator (though of course you can select it and run it from the test source).

#### *In the Product menu*

The Product → Test Plan hierarchical menu lists the test plans attached to the current scheme. Whatever test plan is checked here is the current test plan.



If the current test plan has more than one configuration, then whenever you run a test method, it runs by default under *all* configurations successively. That can come as a surprise. If it isn't what you want, Control-click to summon the contextual menu; it lets you specify a configuration for this run.




Figure 10-15. A test report with an activity

## Massaging the Report

Nothing is more important after running your tests than understanding what happened. Your key source of information is the report. XCTest includes powerful features that give you a lot of control over what goes into the report.

One simple but effective trick is to group the report output into meaningful activities. To do so, in your test method call `XCTestContext.runActivity(named:)`. In addition to the name, which should be some explanatory string, it takes a function; that function is where you'll do your testing and call your assertions. The outcome is that, in the test report summary, the activity name appears as a line in the report, and the test results are grouped hierarchically under that line (Figure 10-15).

Another useful device is attachments. We've already seen that you can attach a screen shot to your report. But an attachment can be *any* kind of data. `XCTAttachment` has initializers for attaching a string, an image, the contents of a file or a directory, a `Data` object, and more. As we've seen, you can call `self.add` (where `self` is the `XCTest`) to get your attachment into the test report. A call to `XCTestContext.runActivity` is also a great place to add an attachment: the function parameter hands you an `XCTActivity` object, and you call `add` with your attachment.

It's possible that a test will hang — perhaps there's a threading deadlock — or just take too long. You don't want to come back from running your tests overnight and discover that they're still incomplete because of a hang. Starting in Xcode 12, an `XCTestCase` or a test plan can declare an *execution time allowance*. If a test takes longer than that, it fails, and a spindump file is attached to the test report.

The entire report mechanism relies upon an `XCTIssue` object that is passed into the `XCTestCase.record` method to contribute to the report. You can intervene in this mechanism! Instead of throwing or calling a built-in assert, you can create your own `XCTIssue`, populate it, and record it, like this:

```
let loc = XCTSourceCodeLocation(filePath: #file, lineNumber: #line)
var issue = XCTIssue(type: .assertionFailure, compactDescription: "oh darn")
issue.add(XCTAttachment(string:"yipes"))
issue.sourceCodeContext = XCTSourceCodeContext(location: loc)
self.record(issue)
```



At an even deeper level, you can override `record` and modify the incoming `XCTIssue` before calling `super` — or *don't* call `super` and thus suppress the failure entirely.

## Clean

From time to time, during repeated testing and debugging, and before making a different sort of build (switching from Debug to Release, or running on a device instead of the Simulator), it's a good idea to *clean* your target. This means that existing builds will be removed and caches will be cleared, so that all code will be considered to be in need of compilation and you can build your app from scratch.

Cleaning removes the cruft, quite literally. Suppose you have been including a certain resource in your app, and you decide it is no longer needed. You can remove it from the Copy Bundle Resources build phase (or from your project as a whole), but that doesn't necessarily remove it from your built app. This sort of leftover resource can cause all kinds of mysterious trouble. The wrong version of a nib may seem to appear in your interface. Code that you've edited may seem to behave as it did before the edit. Cleaning removes the built app and all the intermediate build products that Xcode caches in order to construct it, and very often solves the problem.

You can choose Product → Clean Build Folder, which removes the entire build folder for this project. For an even more extensive cleaning:

1. Choose Product → Show Build Folder in Finder.
2. Quit Xcode.
3. Back in the Finder, press Command-Up Arrow twice. You're now in your user `~/Library/Developer/Xcode/DerivedData` folder. Move all its contents to the trash.

That's a complete clean for every project you've opened recently — plus the module cache. Removing the module cache can reset Swift itself, causing occasional mysterious compilation, code completion, or syntax coloring issues to go away.

In addition to cleaning your project, you should also remove your app from the Simulator. This is for the same reason as cleaning the project: when a new build of the app is copied to the Simulator, existing resources inside the old build may not be removed (in order to save time), and this may cause the app to behave oddly.

To clean out the current simulator while running the Simulator, choose Hardware → Erase All Content and Settings. To clean out *all* simulators, quit the Simulator and then say, in the Terminal:

```
% xcrun simctl erase all
```



## Running on a Device

Eventually, you'll want to progress from running and testing and debugging in the Simulator to running and testing and debugging on a real device. The Simulator is nice, but it's only a simulation; there are many differences between the Simulator and a real device. The Simulator is really your computer, which is fast and has lots of memory, so problems with memory management and speed won't be exposed until you run on a device. User interaction with the Simulator is limited to what can be done with a mouse: you can click, you can drag, you can hold Option to simulate use of two fingers, but more elaborate gestures can be performed only on an actual device. And many iOS facilities, such as the accelerometer and access to the music library, are not present on the Simulator at all, so that testing an app that uses them is possible *only* on a device.

Running your app on a device requires a Developer Program membership, which in turn requires an annual fee. You may balk initially, but sooner or later you're going to get over it and accept that this fee is worth paying. (The temporary ability to run your app on a device *without* a paid Developer Program membership is very limited and I'm not going to discuss it.)

## Obtaining a Developer Program Membership

To obtain a Developer Program membership, go to the Apple Developer Program web page (<https://developer.apple.com/programs>) and initiate the enrollment process. When you're starting out, the Individual program is sufficient. The Organization program costs no more, but adds the ability to privilege additional team members in various roles; you do *not* need the Organization program merely to distribute your built app to other users for testing.

Your Developer Program membership involves two things:

### *An Apple ID*

The user ID that identifies you at Apple's site (along with the corresponding password). You'll use your Developer Program Apple ID for all kinds of things. In addition to letting you prepare an app to run on a device, this same Apple ID lets you post on Apple's development forums, download Xcode beta versions, and so forth.

### *A team name*

You, under a single Apple ID, can belong to more than one *team*. On each team, you will have one or more *roles* dictating your privileges. If you are the head (or sole member) of the team, you are the *team agent*, meaning that you can do everything: you can develop apps, run them on your device, submit apps to the App Store, and receive the money for any paid apps that sell copies there.

Having established your Developer Program Apple ID, you should enter it into the Accounts preference pane in Xcode. Click the Plus button at the bottom left and select Apple ID as the type of account to add. Provide the Apple ID and password. From now on, Xcode will identify you through the team name(s) associated with this Apple ID; you shouldn't need to tell Xcode this password again.

## Signing an App

Running an app on a device is a remarkably complicated business. You will need to *sign* the app as you build it. An app that is not properly signed for a device will not run on that device (assuming you haven't jailbroken the device). Signing an app requires two things:

### *An identity*

An identity represents Apple's permission for a given team to develop, *on this computer*, apps that can run on a device. It consists of two parts:

#### *A private key*

The private key is stored in the keychain on the computer. It identifies a computer where this team can *potentially* develop device-targeted apps.

#### *A certificate*

A certificate is a virtual permission slip from Apple. It contains the public key matching the private key (because you told Apple the public key when you asked for the certificate). With a copy of this certificate, any machine holding the private key can *actually* be used to develop device-targeted apps under the name of this team.

### *A provisioning profile*

A provisioning profile is a virtual permission slip from Apple, uniting four things:

- An *identity*.
- An *app*, identified by its bundle identifier.
- A list of eligible *devices*, identified by their unique device identifiers (UDIDs).
- A list of *entitlements*. An entitlement is a special privilege that not every app needs, such as the ability to talk to iCloud. You won't concern yourself with entitlements unless you write an app that needs one.

A provisioning profile is therefore sufficient for signing an app as you build it. It says that on *this* computer it is permitted to build *this* app such that it will run on *these* devices.

There are two types of identity, and hence two types of certificate and provisioning profile: *development* and *distribution* (a distribution certificate is also called a *production* certificate). We are concerned here with the development identity, certificate, and profile; I'll talk about the distribution side later.

The only thing that belongs entirely to you is the private key in your computer's keychain. Apple is the ultimate keeper of all other information: your certificates, your provisioning profiles, what apps and what devices you've registered. Your communication with Apple, when you need to verify or obtain a copy of this information, will take place through one of two means:

#### *The developer member center*

A set of web pages at <https://developer.apple.com/account>. Having logged in with your Apple ID, you can click Certificates, IDs & Profiles (or go directly to <https://developer.apple.com/account/resources>) to access all features and information to which you are entitled by your membership type and role. (This is the area of Apple's site formerly referred to as the Portal.)

#### *Xcode*

Just about everything you would need to do at the developer member center can be done through Xcode instead. When all goes well, using Xcode is a lot simpler! If there's a problem, you can head for the developer member center to iron it out.

## Automatic Signing

Apple provides two distinct ways of obtaining and managing certificates and profiles in connection with a project — automatic signing, and manual signing. For new projects, automatic signing is the default. This is indicated by the fact that the “Automatically manage signing” checkbox is checked in the Signing & Capabilities pane when you edit your project's app target.

To see just how automatic Xcode's signing management can be, let's start at a stage where as yet you have neither a development certificate in your computer's keychain nor a development profile for any app. But you do have a Developer Program Apple ID, and you've entered it into Xcode's Accounts preference pane. Then, when you create a new project (File → New → Project), you'll see on the second screen (“Choose options for your new project”) a pop-up menu listing all the teams with which your Apple ID is associated. Specify the desired team here.

When you then create the project on disk and the project window opens, *everything happens automatically*. Your computer's keychain creates a private key for a development certificate. The public key is sent to Apple. The actual development certificate is created at the developer member center, and is downloaded and installed into your computer's keychain. With no conscious effort, you've obtained a development identity!




Figure 10-16. Xcode knows of no devices

If you’ve never run on any device before, and if you haven’t manually registered any devices at the developer member center, that might be as far as Xcode can go for now. If so, you’ll see some warnings in the Signing & Capabilities pane, similar to [Figure 10-16](#).

Now connect a device via USB to your computer and select it as the destination, either under Product → Destination or in the Scheme pop-up menu in the project window toolbar. Try to build. This causes a dialog to appear, offering to register the device. It has a Register Device button. Click it!

The problem is resolved; the error vanishes, and a development provisioning profile has been created and downloaded (and has been stored in your `~/Library/MobileDevice/Provisioning Profiles` folder). This is a *universal* iOS Team Provisioning Profile — also known as a *wildcard* or *XC wildcard* profile — and that is all you need in order to run any basic app on any device.

You are now almost ready to run this project on this device. There may, however, be one further step: you might have to disconnect the device from USB and connect it again. This is so that Xcode can recognize the device afresh and prepare for debugging on it. This process is rather time-consuming; a progress indication is shown at the top of the project window, and in the Devices and Simulators window.

The good news is that once you’ve gone through all of that, you won’t have to do it again. You now have a development certificate, and Xcode has generated and downloaded a universal iOS Team Provisioning Profile, and your device is registered with Apple and prepared by Xcode for debugging. So Xcode knows everything it needs to know! From now on you can create a project and run it on this device *immediately*.

To confirm that you have a universal development provisioning profile, edit your project’s app target, switch to the Signing & Capabilities pane, and click the little “i” button at the right of the Provisioning Profile (where it says Xcode Managed Profile). A popover appears, displaying information about the provisioning profile. At the top of that popover, it says: “iOS Team Provisioning Profile”, followed by an asterisk (\*). Below that, the App ID is an asterisk as well. The asterisk is the sign that this is a universal development profile, not restricted to one particular app ID. It allows you

to run *any* app on the targeted device for testing purposes, provided that the app doesn't require special entitlements (such as using iCloud).

If you do eventually turn on some entitlements for an app target (in the Signing & Capabilities pane), Xcode will communicate with the developer member center to attach those entitlements to your registered app; then it will create a new provisioning profile that includes those entitlements, download it, and use it for this project.

## Manual Signing

Automatic signing is great, but sometimes it might not work, or you might have some reason for wanting to manage signing manually. It's useful to know how to do that.

To stop a project's signing from being managed automatically by Xcode, simply uncheck the "Automatically manage signing" checkbox. This causes Xcode to take its hands off completely. Xcode won't automatically generate or choose a development certificate or a provisioning profile; you will have to do it all yourself.

To obtain a development certificate manually, there are two possible approaches:

### *The Accounts preference pane*

This approach is semi-automatic. In Xcode's Accounts preference pane, select your team name and click Manage Certificates to summon the "Signing certificates" dialog. Click the Plus button at the lower left, and choose Apple Development. Xcode will communicate with the developer member center and a development certificate will be created and installed on your computer.

### *Keychain Access and the developer member center*

This approach is completely manual. Go to Certificates at the developer member center, click the Plus button, ask for an Apple Development certificate, click Continue, and follow the instructions that you're given:

1. You begin by generating the private key in your computer's keychain. Launch the Keychain Access application and choose Keychain Access → Certificate Assistant → Request a Certificate From a Certificate Authority. Click the "Saved to disk" radio button and save the certificate signing request file onto your computer.
2. At the developer member center, upload the certificate signing request file that you just created. The actual certificate is generated; download it, and double-click to install it into the keychain. (You can then throw away both the certificate request file and the downloaded certificate.)

Once you have a development certificate, here's how to use the developer member center to create a development profile manually:

1. The device must be registered at the developer member center. Look under Devices to see if it is. If it isn't, click the Plus button and enter a name for this device along with its UDID. You can copy the device's UDID from its listing in Xcode's Devices and Simulators window.
2. The app must be registered at the developer member center. Look under Identifiers to see if it is. If it isn't, add it: Click Plus. Choose App IDs. Choose App. Enter a description for this app (such as its name). Ignore the App ID Prefix field. Copy the Bundle Identifier from your project window's Signing & Capabilities pane and paste it into the bundle identifier field, and register the app.  
  
(If your app uses special entitlements, this step is also where you'd associate those entitlements manually with the app.)
3. Under Profiles, click Plus. Ask for an iOS App Development profile. On the next screen, choose the App ID for this app (presumably the one you just created in the previous step). On the next screen, check your development certificate. On the next screen, select the device(s) you want to run on. On the next screen, give this profile a name, and generate the profile. You are now offered a chance to download the profile, but you don't have to do that, because Xcode can do it for you.
4. In Xcode, in the Signing & Capabilities pane, in the Provisioning Profile pop-up menu, choose Download Profile. The profile you created at the developer member center is listed here! Select it. The profile is downloaded and development provisioning is enabled for this project.

## Running the App

Once you have a development profile applicable to an app and a device, you can connect the device via USB, choose it as the destination in the Scheme pop-up menu, and build and run the app. (If you're asked for permission to access your keychain, you should grant it.)

The app is built, loaded onto your device, and launched. As long as you launch the app from Xcode, everything is just as when running in the Simulator. You can run and you can debug. The running app is in communication with Xcode, so that you can stop at breakpoints, read messages in the console, profile your app with Instruments, and so on. The outward difference is that to interact physically with the app, you use the device, not the Simulator.

You can also configure your device to allow Xcode to build and run apps on it *without* a USB connection. To do so, start with the device connected via USB; locate the device in the Devices and Simulators window and check "Connect via network."

The device can now be used as a build and run destination *wirelessly*, provided it is connected via WiFi to the local network or to some other network that your

computer can access by its IP address. You can build and run from Xcode, pausing at breakpoints and receiving console messages, even though the device is not physically attached to your computer. This would be useful particularly if the app you're testing requires the device to be manipulated in ways that are difficult when the device is tethered by a USB cable.

## Managing Development Certificates and Devices

You're allowed to have more than one development certificate, so there should be no problem running your project on a device from another computer. Just do what you did on the first computer! If you're using automatic signing, a new certificate will be generated for you, and it won't conflict with the existing certificate for the first computer.

When a device is attached to the computer, it appears in Xcode's Devices and Simulators window. If this device has never been prepared for development, you can ask Xcode to prepare it for development. You can then build and run onto the device. If the device isn't registered at the member center, a dialog appears offering to let you register it; click Register Device, and now the device *is* registered. Your automatically generated provisioning profile is modified to include this device, and you are now able to build and run on it.

The Devices and Simulators window can be used to communicate in other ways with a connected device. Using the contextual menu on the device's name, you can copy the device's UDID, and you can view and manage provisioning profiles on the device. In the main part of the window, you can see (and delete) apps that have been installed for development using Xcode, and you can view and download their sandboxes. You can take screenshots. You can view the device's stored logs. You can open the Console application to view the device's console output in real time.

## Profiling

Xcode provides tools for probing the internal behavior of your app graphically and numerically, and you should keep an eye on those tools. The gauges in the Debug navigator allow you to monitor key indicators, such as CPU and memory usage, any time you run your app. Memory debugging gives you a graphical view of your app's objects and their ownership chains, and can even reveal memory leaks. And Instruments, a sophisticated and powerful utility application, collects profiling data that can help track down problems and provide the numeric information you need to improve your app's performance and responsiveness.




Figure 10-17. The Debug gauges

## Gauges

The gauges in the Debug navigator are operating whenever you build and run your app. Click a gauge to see further detail displayed in the editor. The gauges do not provide highly detailed information, but they are extremely lightweight and always active, so they are an easy way to get a general sense of your running app's behavior at any time. If there's a problem, such as a prolonged period of unexpectedly high CPU usage or a relentless unchecked increase in memory usage, you can spot it in the gauges and then use Instruments to help track it down.

There are four basic gauges: CPU, Memory, Disk, and Network. Depending on the circumstances, you may see additional gauges. An Energy Impact gauge appears when running on a device, and for certain devices, a GPU gauge may appear as well.

In [Figure 10-17](#), I've been heavily exercising my app for a few moments, repeating the most calculation- and memory-intensive actions I expect the user to perform. These actions do cause some spikes in energy usage, but that's to be expected; this is a user-initiated action, and the user won't perform it very often. Meanwhile, my app's memory usage remains level. So I don't suspect any issues.



Note that [Figure 10-17](#) is the result of running *on a device*. Running in the Simulator might give completely different — and misleading — results.

## Memory Debugging

Memory debugging lets you pause your app and view a graphical display of your object hierarchy at that moment. This is valuable not only for detecting problems but also for understanding your app's object structure.






Figure 10-18. A memory graph




Figure 10-19. The memory graph displays a leak

To use memory debugging, run the app and click the Debug Memory Graph button in the debug bar. The app pauses, and you are shown a drawing of your app’s objects, linked by their chains of ownership (Figure 10-18).

The Debug navigator lists your objects hierarchically; click an object to see a different part of the graph. Click an object’s double-arrow badge in the graph to show or hide that object’s retaining object chain. Double-click an object in the graph to refocus the graph on that object. A special Memory inspector appears in the Inspector pane; click an object in the graph to learn more about it, or click an arrow to learn how the arrow’s destination is retained by its source.

In my app, the root view controller is a ViewController whose view’s subviews include a MyBoard view whose tiles property is an array of Tile views. Figure 10-18 displays that situation.

At the cost of some additional overhead, you can enable the malloc stack before running your app: edit the scheme’s Run action and under Diagnostics check Malloc Stack Logging with the pop-up menu set to All Allocation and Free History. When you run the app, selecting an object in the memory graph provides a backtrace in the Memory inspector that tells you *how* each object came into being. If the backtrace is collapsed, hover the mouse over the word Backtrace and click the Expand button that appears. Hover over a line of the backtrace and click the right-arrow button to jump to that line of your code.

Memory debugging also detects memory leaks. Such leaks will cause an error icon to appear, and are listed in the Runtime pane of the Issue navigator. Suppose we run the example from Chapter 5 where I have a Dog class instance and a Cat class instance with strong references to one another and no other references to either instance, so they are both leaking. The leaking Cat and Dog are listed in the Issue navigator, and clicking one them displays a graph of the problem: the Cat and the Dog are retaining one another (Figure 10-19).




Figure 10-20. Instruments graphs memory usage over time

## Instruments

To get started with Instruments, first set the desired destination in the Scheme pop-up menu in the project window toolbar. The destination should be a device if possible; Instruments on the Simulator does not reflect the reality you're trying to measure. Now choose Product → Profile. Your app builds using the Profile action for your scheme; by default, this uses the Release build configuration, which is what you want. Instruments launches; if your scheme's Instrument pop-up menu for the Profile action is set to Ask on Launch (the default), Instruments presents a dialog where you choose a template.

Alternatively, click Profile In Instruments in a Debug navigator gauge editor; this is convenient when the gauges have suggested a possible problem, and you want to reproduce that problem under the more detailed monitoring of Instruments. Instruments launches, selecting the appropriate template for you. A dialog offers two options: Restart stops your app and relaunches it with Instruments, whereas Profile keeps your app running and hooks Instruments into it.

Once the Instruments main window appears, if you chose Product → Profile, you'll probably have to click the Record button, or choose File → Record Trace, to get your app running. Now you should interact with your app like a user; Instruments will record its statistics.

Figure 10-20 shows me doing much the same thing in Instruments that I did with the Debug navigator gauges in Figure 10-17. I've set the destination to my device. I choose Product → Profile; when Instruments launches, I choose the Allocations template. With my app running under Instruments, I exercise it for a while and then pause Instruments, which meanwhile has charted my memory usage. Examining the chart, I find that there are spikes up to about 17MB, but the app always settles back down to a much lower level (around 6MB). Those are very gentle and steady memory usage figures, so I'm happy.

The Leaks template can help you detect memory leaks (similar to the memory graph leak detection I discussed earlier). In Figure 10-21, I've again run the retain cycle code from Chapter 5, profiling the app using the Leaks template. Instruments has detected the leak, and has diagrammed the issue.




Figure 10-21. Instruments describes a retain cycle




Figure 10-22. Drilling down into the time profile

In the next example, I'm curious as to whether I can shorten the time it takes my app to load a photo image. I've set the destination to a device, because that's where speed matters and needs to be measured. I choose Product → Profile. Instruments launches, and I choose the Time Profiler template. When the app launches under Instruments on the device, I load new images repeatedly to exercise this part of my code for about ten seconds.

In **Figure 10-22**, I've paused Instruments, and am looking at what it's telling me. Opening the disclosure indicators in the lower portion of the window, I can drill down to my own code, indicated by the user icon.

Drilling down one more level (at the very bottom of the screenshot), I discover that the place we're spending most of our CPU time isn't my code after all; it's the call to `CGImageSourceCreateThumbnailAtIndex`, which is in the `ImageIO` framework. I can't make that run any faster; it doesn't belong to me. It may be, however, that I could load the image another way; at the expense of some temporary memory usage, perhaps I could load the image at full size and scale it down by redrawing it myself. If I'm concerned about speed here, I could spend a little time experimenting. The point is that now I know *what* the experiment should be. This is just the sort of focused, fact-based numerical analysis at which Instruments excels.

Those examples barely scratch the surface. Use of Instruments is an advanced topic; an entire book could be written about Instruments alone. The Instruments application comes with online help that's definitely worth studying. Many WWDC videos from current and prior years are about Instruments; look particularly for sessions with "Instruments" or "Performance" in their names.

## Localization

A device, or an individual app, can be set by the user to prefer a certain language as its primary language. You might like your app's interface to respond to this situation by appearing in that language. This is achieved by *localizing* the app for that language.

Localization operates through *localization folders* with an *.lproj* extension in your project folder and in the built app bundle (Figure 7-6). When your running app reaches into its own bundle to obtain a resource, if it is running on a system whose language corresponds to a localization folder, if that localization folder contains a version of that resource, that's the version that is loaded.

Any type of resource can live in these localization folders; you will be particularly concerned with *text* that is to appear in your interface. Such text must be maintained in specially formatted *.strings* files, which have these default names:

- To localize your *Info.plist* file, use *InfoPlist.strings*.
- To localize your *Main.storyboard*, use *Main.strings*.
- To localize your code strings, use *Localizable.strings*.

Fortunately, you don't have to create or maintain these files manually! Instead, you work with exported XML files in the standard *.xiff* format. Xcode will generate *.xiff* files on demand, based on the structure and content of your project; it will also read them and will turn them automatically into the various localized *.strings* files.

## Creating Localized Content

To experiment with localization, our app needs some localizable content:

1. Edit the target and enter a value in the Display Name text field in the General pane. Our Empty Window app already says “Empty Window” here, but it’s gray, indicating that this is merely an *automatic* display name; enter “Empty Window” explicitly (and press Tab), to make this an *actual* display name.

If you now look in the Info pane, you will see that you have just set the “Bundle display name” key (CFBundleDisplayName) in the *Info.plist* file. That key will be localized.

2. Edit *Main.storyboard* and confirm that it contains a button whose title is “Hello.” That title will be localized. (It will help the example if you also widen the button to about 100 points.)
3. Edit *ViewController.swift*. The code here contains some string literals, such as “Howdy!”:

```
@IBAction func buttonPressed(_ sender: Any) {
    let alert = UIAlertController(
        title: "Howdy!", message: "You tapped me!",
        preferredStyle: .alert)
    alert.addAction(
        UIAlertAction(title: "OK", style: .cancel))
    self.present(alert, animated: true)
}
```

That code *won’t* be localized, unless we modify it. Formerly, the way to do this was to call the global `NSLocalizedString` function. New in iOS 15 and Xcode 13, you can call `String(localized:comment:)` instead. Modify our `buttonPressed` method to look like this:

```
@IBAction func buttonPressed(_ sender: Any) {
    let greeting = String(
        localized: "Howdy!",
        comment: "Alert title: Say hello")
    let message = String(
        localized: "You tapped me!",
        comment: "Alert message: Report a tap")
    let ok = String(
        localized: "OK",
        comment: "Alert button: accept and dismiss")
    let alert = UIAlertController(
        title: greeting,
        message: message,
        preferredStyle: .alert)
    alert.addAction(
        UIAlertAction(title: ok, style: .cancel))
    self.present(alert, animated: true)
}
```




Figure 10-23. An exported xcloc bundle



Calls to `String(localized:comment:)` will not be automatically included when exporting localized strings unless you set the Use Compiler to Extract Swift Strings build setting to Yes.

## Exporting

Now we're going to give our project an actual localization, and we'll export an editable `.xliff` file expressing the details of that localization. This process will generate any needed `.strings` files, automatically.

For my localization language, I'll choose French:

1. Edit the target. Make sure that the Use Compiler to Extract Swift Strings build setting has been set to Yes.
2. Edit the project. In the Info pane, under Localizations, click the Plus button. In the pop-up menu that appears, choose French. In the dialog, click Finish.
3. Still editing the project, choose Editor → Export For Localization. In the dialog that appears, check French. You're about to create a folder, so call it something like Empty Window Localization and save it to the desktop.
4. The result is that inside the folder you've just created is an `.xcloc` bundle called `fr.xcloc` (for French). Control-click it and choose Show Package Contents (Figure 10-23).

The heart of the output is an XML file called `fr.xliff` (inside the *Localized Contents* subfolder). Examining this file, you'll observe that our app's localizable strings have all been discovered and have been clumped into groups as subelements of `<file>` elements. Looking at each `<file>` element's `original` attribute, you can see what file it represents. The files are called *Main.storyboard*, *InfoPlist.strings*, and *Localizable.strings*. As I've already mentioned, the *Main.storyboard* file localizes our main

storyboard; the *InfoPlist.strings* file localizes our *Info.plist*; and the *Localizable.strings* file localizes literal strings in our code.

## Editing

Now let's pretend that you are the French translator, tasked with creating the French localization of this app. Your job is to *modify* the *fr.xliff* file by supplying a `<target>` tag for every `<source>` tag that is to be translated into French. Your edited file might contain, at the appropriate places, translations like this (note that the `id` and `Object-ID` attributes will be different in your actual *fr.xliff* file):

```
<trans-unit id="AZ-1.normalTitle" xml:space="preserve">
  <source>Hello</source>
  <target>Bonjour</target>
  <note>Class = "UIButton"; normalTitle = "Hello"; ObjectID = "AZ-1";</note>
</trans-unit>

<trans-unit id="CFBundleDisplayName" xml:space="preserve">
  <source>Empty Window</source>
  <target>Fenêtre Vide</target>
  <note>Bundle display name</note>
</trans-unit>

<trans-unit id="Howdy!" xml:space="preserve">
  <source>Howdy!</source>
  <target>Salut!</target>
  <note>Alert title: Say hello</note>
</trans-unit>

<trans-unit id="OK" xml:space="preserve">
  <source>OK</source>
  <target>OK</target>
  <note>Alert button: accept and dismiss</note>
</trans-unit>

<trans-unit id="You tapped me!" xml:space="preserve">
  <source>You tapped me!</source>
  <target>Vous m'avez tapé!</target>
  <note>Alert message: Report a tap</note>
</trans-unit>
```

Other types of localizable resources may be exported automatically as well. For example, images in the asset catalog are localizable, and these are exported too (in *Localized Contents*). If an asset catalog was exported for localization, the translator can edit or replace the localized version of an image directly.

In addition, the *original* versions of our localizable material were exported (in *Source Contents*); and your export can include screenshots taken during interface testing (described earlier in this chapter). These can give the translator valuable context as to the usage of the terms to be translated.

Key	English	French	Comment
Howdy!	Howdy!	Bonjour!	Alert title: Say hello
OK	OK	OK	Alert button: accept and dismiss
You tapped me!	You tapped me!	Vous m'avez tapé!	Alert message: Report a tap

Figure 10-24. Editing an *xcloc* bundle in Xcode

New in Xcode 13, an *.xcloc* bundle can be opened directly in Xcode to edit its contents. The editing interface hides the complexity of the *.xcloc* contents layout and the *.xliff* XML and shows you just the translatable material directly (Figure 10-24).

## Importing

The French translator, having edited the *fr.xliff* file and any exported localizable asset catalog images, returns the *fr.xcloc* bundle to us. We proceed to incorporate it back into our project:

1. Edit the project.
2. Choose Editor → Import Localizations; in the dialog, locate and open the *fr.xcloc* bundle.

Xcode parses the *.xcloc* bundle contents, locates the *fr.xliff* file inside it, opens and reads it, and creates the corresponding files in the project. In particular, the project folder now contains a *fr.lproj* folder containing *.strings* files in the correct format, namely key–value pairs like this:

```
/* Optional comments are C-style comments */
"key" = "value";
```

The *.strings* files in our *fr.lproj* folder include the following:

- An *Info.plist.strings* file, localized for French, corresponding to our *Info.plist* file. It reads like this:

```
/* Bundle display name */
"CFBundleDisplayName" = "Fenêtre Vide";
```

- A *Main.strings* file, localized for French, corresponding to *Main.storyboard*. It will be similar to this:

```
/* Class = "UIButton"; normalTitle = "Hello"; ObjectID = "AZ-1"; */
"AZ-1.normalTitle" = "Bonjour";
```

- A *Localizable.strings* file, localized for French, localizing the strings in our code. It looks like this:



```

/* Alert title: Say hello */
"Howdy!" = "Salut!";

/* Alert button: accept and dismiss */
"OK" = "OK";

/* Alert message: Report a tap */
"You tapped me!" = "Vous m'avez tapé!";

```

If the translator has edited any exported asset catalog images, they will be incorporated into the appropriate slots in our asset catalog.

## Testing Localization

Build and run the project in the Simulator. The project runs in English, so the button title is still “Hello,” and the alert that it summons when you tap it still contains “Howdy!”, “You tapped me!”, and “OK.” Stop the project in Xcode.

Now we’re going to transport ourselves magically to France! Edit the scheme. In the scheme’s Run action, under the Options pane, change the Application Language to French. Then build and run again. Presto! The button in the interface has the title Bonjour. When we tap it, the alert contains “Salut!”, “Vous m’avez tapé!”, and “OK.”

To prove that our *Info.plist* localization is working, use the Settings app in the Simulator to change the system language to French (under General → Language and Region). You’ll see that, in the Springboard, our app’s title has changed to French; it is now *Fenêtre Vide*.

In real life, preparing your nib files to deal with localization will take some additional work. In particular, you’ll want to use autolayout, configuring your interface so that interface objects containing text have room to grow and shrink to compensate for the change in the length of their text in different languages.

To view your interface under different localizations, you can preview your localized nib files within Xcode, without running the app. Edit a *.storyboard* or *.xib* file and choose Editor → Preview (or choose Preview from the Editor Options pop-up menu at the top right of the editor pane). In the preview pane, a pop-up menu at the lower right lists localizations; choose from the menu to switch between them. A “double-length pseudolanguage” stress-tests your interface with really long localized replacement text.

Test plans (discussed earlier in this chapter) let you create multiple configurations, each of which can have a different system language and region. When you run a test, it runs under all of the current test plan’s configurations in succession. This provides an automated way to check that your app behaves correctly under all localizations.

## Localized String Keys

In the *.strings* files generated from the French localization in our example app, there's an unfortunate issue: the keys are identical to the English values. Consider, for instance, this entry from our French *Localizable.strings* file:

```
/* Alert message: Report a tap */  
"You tapped me!" = "Vous m'avez tapé!";
```

This is supposed to be a list of key–value pairs; we shouldn't be using the English user-facing text as a key. For one thing, if we now change the English text in our `String(localized:comment:)` call, our French translation will break. Also, we would be unable to have different French translations for the same English text used in different contexts.

I regard this as a bug. Using `NSLocalizedString`, we can supply distinct `key:` and `value:` arguments. But `String(localized:comment:)` wrongly uses the `localized:` argument as both the key and its English value.

As a workaround, instead of entering the English user-facing text as the `localized:` parameter, enter a key string. Then, to prevent the keys from appearing in the user interface, export the English localization and “translate” the keys into the desired English user-facing text. Now import the localization to generate the correct English *.strings* files.

(If your development language isn't English, substitute the development language into those instructions.)

Now when you export a different localization, such as French, the `<trans-unit>` element's `id` value is the key, to which the translator pays no attention, and the `<source>` is the English, which the translator duly translates.

To change the English user-facing text later on, edit the English *Localizable.strings* file — not the code. Nothing will break, because the key remains constant.

## Distribution

*Distribution* means sharing your built app with users for running on their devices. There are two primary kinds of distribution:

### *Ad Hoc distribution*

You are providing a copy of your app to a limited set of known users so that they can try it on specific devices and report bugs, make suggestions, and so forth.

### *App Store Connect distribution*

You are uploading the app to App Store Connect. This could be for one of two reasons:

### *TestFlight testing*

You are providing access to the app temporarily to certain users for testing through TestFlight.

### *App Store sale*

You are providing the app to the App Store to be listed publicly, so that anyone can download it and run it, possibly for a fee.

## Making an Archive

To create a copy of your app for distribution, you need first to build an *archive* of your app. An archive is basically a preserved build. It has three main purposes:

### *Distribution*

An archive will serve as the basis for subsequent distribution of the app; the distributed app will be *exported* from the archive.

### *Reproduction*

Every time you build, conditions can vary, so the resulting app might behave slightly differently. But every distribution from a particular archive contains an identical binary and will behave the same way. If a bug report arrives based on an app distributed from a particular archive, you can distribute that archive to yourself and run it, knowing that you are testing exactly the same app.

### *Symbolication*

The archive includes a *.dSYM* file that allows Xcode to accept a crash log and report the crash's location in your code. This helps you to deal with crash reports from users.

Here's how to build an archive of your app:

1. Set the destination in the Scheme pop-up menu in the project window toolbar to Any iOS Device. Until you do this, the Product → Archive menu item will be disabled. You do *not* have to have a device connected; you are not building to run on a *particular* device, but saving an archive that will run on *some* device.
2. If you like, edit the scheme to confirm that the Release build configuration will be used for the Archive action. This is the default, but it does no harm to double-check.
3. Choose Product → Archive. The app is compiled and built. The archive itself is stored in a date folder within your user *~/Library/Developer/Xcode/Archives* folder. Also, it is listed in Xcode's Organizer window (Window → Organizer) under the app's Products → Archives entry; this window may open spontaneously to show the archive you've just created. You can add a description here; you can also change the archive's name (this won't affect the name of the app).

You’ve just signed your archive with a *development* profile; that’s good, because it means you can run the archived build directly on your device. However, a development profile can’t be used to make an Ad Hoc or App Store Connect build of your app; therefore, when you export the archive to form an Ad Hoc or App Store Connect build, Xcode will embed the appropriate *distribution* profile instead.

So now, in order to export from your archive, you need a distribution profile. And to get *that*, you need a distribution *certificate*.

## The Distribution Certificate

A distribution certificate (sometimes called a *production* certificate) is required for distributing your app to other users.

A distribution certificate is parallel to a development certificate, except for one thing: the number of distribution certificates you can have is very limited. At times, the number has been as low as one; at others, Apple seems to have raised the limit as high as three. In any case, this limit has always been a source of difficulty for developers who collaborate on the same team or who alternate between different computers.

The reason is that a given distribution certificate is generated with a public key corresponding to just one private key. In order to install the same distribution certificate on two different computers, both computers would need a copy of that private key. That’s not easy to arrange, and it’s arguably insecure.

New in Xcode 13, that problem is solved in a completely new way: a *cloud-based certificate*. You don’t have to install your distribution certificate on *any* computer. Instead, Apple maintains it for you. You and anyone else on your team with the appropriate role can access the same distribution certificate from anywhere, as long as you have an internet connection; and the times when you *need* a distribution certificate are usually times when you *do* have an internet connection — because you’re exporting an archived build to App Store Connect, for example.

So the simplest way to get a distribution certificate is *not* to get one! Just export the archive to App Store Connect (as I’ll describe later), and when you come to the screen about signing, opt for automatic signing. The signing will succeed, even though you have no distribution certificate on your computer. And after signing, you *still* won’t have a distribution certificate on your computer! You don’t need one.

But if you *do* need to create a distribution certificate and download it to your computer, you can. There are two ways: you can request it through the Accounts preference pane (ask for an Apple Distribution certificate), or you can obtain it manually using the Keychain Access application and the developer member center, exactly as I described earlier for obtaining a development certificate.

If you still need to transfer an existing distribution certificate from one computer to another, you can do that too. As I said before, this involves sharing your private key. On the computer that has the distribution certificate in its keychain, in the Accounts preference pane, under Manage Certificates, Control-click that certificate and choose Export Certificate from the contextual menu. You'll be asked to save the resulting file, securing it with a password. The password is needed because this file, a *.p12* file, contains the private key from your keychain. Now copy the *.p12* file to the second computer. (You could email it, for instance.) On that computer, open the exported file, using the password. The private key and the certificate are imported into the keychain of the second computer. You can then throw away all copies of the *.p12* file; it has done its job.

## The Distribution Profile

Obtaining a distribution profile is like obtaining a development profile. If you're using automatic signing for this project, Xcode will probably be able to create an appropriate distribution profile for you automatically when you export your archive.

If necessary, you can instead obtain a distribution profile manually, at the developer member center, under Certificates, IDs & Profiles. The procedure is similar to obtaining a development profile manually, with a few slight differences:

1. If this is to be an Ad Hoc distribution profile, collect the UDIDs of all the devices where this build is to run, and make sure you've added each of them at the developer member center under Devices. (For an App Store distribution profile, omit this step.)
2. Make sure that the app is registered at the developer member center under Identifiers, as I described earlier in this chapter.
3. Under Profiles, click the Plus button to ask for a new profile. Choose an Ad Hoc or App Store profile. On the next screen, choose your app from the pop-up menu. On the next screen, choose your distribution certificate. On the next screen, for an Ad Hoc profile only, specify the devices you want this app to run on. On the next screen, give the profile a name.

Be careful about the profile's name, as you might need to be able to recognize it later from within Xcode! My own practice is to assign a name containing the term "AdHoc" or "AppStore" and the name of the app.

4. Click Done. You should subsequently be able to download the profile from within Xcode (and if not, you can click Download at the developer member center).

## Distribution for Testing

There are two ways to distribute your app for testing: Ad Hoc distribution and Test-Flight distribution. I'll briefly describe each of them.

### Ad Hoc distribution

Here are the steps for creating an Ad Hoc distribution file from an archive:

1. In the Organizer window, under Archives, select the archive and click Distribute App at the upper right. A dialog appears. Here, you are to specify a method; choose Ad Hoc. Click Next.
2. In the next screen, you may be offered various options:

#### *App Thinning*

This means that multiple copies of the app can be created, each containing resources appropriate only to one type of device, simulating what the App Store will do when the user downloads the app to a device. There would normally be no need for this, though it might be interesting to learn the size of your thinned app.

#### *Rebuild from Bitcode*

Bitcode allows the App Store to regenerate your app to incorporate future optimizations. If you're going to be using bitcode when you upload to the App Store, you might like to use it when you perform your Ad Hoc build. Personally, I avoid bitcode, so I would uncheck this checkbox.

#### *Include manifest for over-the-air installation*

Over-the-air (OTA) installation allows an end user to download and install the Ad Hoc build over the network. I'm not going to go into the details here.

3. In the next screen, you may be offered a choice between automatic and manual signing:
  - An *automatically* generated Ad Hoc distribution profile will be configured to run on *all* devices registered for your team at the developer member center, and will use a cloud-based distribution certificate (as I described earlier).
  - If you choose *manual* signing, you will need to have installed a distribution certificate on your computer, and you'll need to have generated an Ad Hoc distribution profile. You'll see another screen where you can specify that certificate and choose your Ad Hoc distribution profile, either from the member center or (if you've downloaded the distribution profile already) from your computer.

4. The archive is prepared, and a summary window is displayed. The name of the provisioning profile is shown, so you can tell that the right thing is happening. Click Export.
5. You are shown a dialog for saving a folder. The file will be inside that folder, with the suffix *.ipa* (“iPhone app”), accompanied by property list and log files describing the export process.
6. Locate in the Finder the *.ipa* file you just saved. Provide this file to your users with instructions.

How should a user who has received the *.ipa* file copy it onto a registered device? Starting with macOS 10.15 Catalina, this can be done directly in the Finder. The user attaches the device to the computer (clicking the various Trust buttons if necessary), selects the device in a Finder window sidebar, and just drags the app right onto the device’s window.

Another reliable way is to download the Apple Configurator application from the Mac App Store. Attach the device to the computer and launch Apple Configurator. An image of the device’s screen appears in the Configurator window. Drag the *.ipa* file from the Finder onto that image, and it will be copied onto the device.

## TestFlight distribution

TestFlight beta testing has many advantages over Ad Hoc testing. The number of Ad Hoc testers is limited to 100 devices per year per developer (not per app), and devices used for development are counted against this limit; TestFlight lifts that to a limit of 10000 testers. TestFlight is also far more convenient for your testers than Ad Hoc distribution, because they download and install prerelease versions of your app directly from the App Store onto their devices through the TestFlight app. Communication between you and your testers is handled seamlessly: TestFlight emails invitations to testers, allows testers to provide feedback comments, collects crash logs, notifies testers when you update the app, and so forth.

Here’s how to upload your app for TestFlight testing:

1. Select an archive in the Organizer window and click Distribute App.
2. You are asked for a method of distribution. Select App Store Connect.
3. You are asked for a destination. Select Upload.
4. New in Xcode 13, if you have not previously registered this app at App Store Connect, a screen will appear offering to register it for you. You are asked for Name and SKU entries; for their significance, see the discussion of submission to the App Store later in this chapter.
5. You are presented with three checkboxes. I suggest unchecking the bitcode checkbox and checking the other two.




Figure 10-25. Icon slots in the asset catalog

6. You are given a choice of signing options. If you elect automatic signing, a cloud-based distribution certificate will be obtained and attached to the exported build. If you elect manual signing, you will need to have created a distribution certificate and profile beforehand.

Prerelease versions of your app intended for distribution to beta testers require review by Apple. Basically, the rule is that if your app's minor version number increases, you can expect a delay while Apple performs the review.

On the other hand, *internal* testers (team members who have direct access to your App Store Connect account) can download new versions immediately. That includes you! I often use TestFlight as a way of distributing a build to myself so that I can test on a device under real-world conditions.

## Final App Preparations

As the big day approaches when you're thinking of submitting your app to the App Store, don't become so excited by the prospect of huge fame and massive profits that you rush the all-important final stages of app preparation. Apple has a lot of requirements, and failure to meet them can cause your app to be rejected. Take your time. Make a checklist and go through it carefully. See Apple's *App Store Connect Help* and the "Icons and Images" chapter of the *iOS Human Interface Guidelines*.

### Icons in the app

The best way to provide your app with icons is to use the asset catalog (Figure 10-25). The image sizes needed are listed in the asset catalog itself. To determine which slots should be displayed, use the checkboxes in the Attributes inspector when you select the icon set. To add an image, drag it from the Finder into the appropriate slot.

A resolution of "2x" or "3x" means that the image should be double or triple the listed dimensions for an icon; for example, an iPhone app icon listed with a size of "60" but a scale of "3x" means that this slot needs an image measuring 180×180.

An icon file must be a PNG file, without alpha transparency. It should be a full square; the rounding of the corners will be added for you. Apple seems nowadays to



prefer simple, cartoony images with a few bright colors and possibly a gentle gradient background.

App icon sizes have changed over the years. If your app is to be backward compatible to earlier systems, you may need additional icons in additional sizes, corresponding to the expectations of those earlier systems. Conversely, new devices can come along, bringing with them new icon size requirements (this happened when the iPad Pro appeared on the scene). Again, this is exactly the sort of thing the asset catalog will help you with.

Optionally, you may elect to include smaller versions of your icon to appear when the user does a search on the device, as well as in the Settings app if you include a settings bundle. However, I never include those icons; the system's scaled-down versions of my app icons look fine to me.

## Marketing icon

To submit an app to the App Store, you will need to supply a 1024×1024 PNG or high-quality JPEG icon to be displayed at the App Store (the *marketing icon*). Apple's guidelines say that it should not merely be a scaled-up version of your app's icon; but it must not differ perceptibly from your app's icon, either, or your app will be rejected (I know this from bitter experience).

The marketing icon should be included in the asset catalog. There's a slot for it, along with the slots for the real app icons.

## Launch images

There is an inevitable delay between the moment when the user taps your app's icon to launch it and the moment when your app is up and running and displaying its initial window. To cover this delay and give the user a visible indication that something is happening, a launch image needs to be displayed during that interval.

The launch image needn't be detailed; in fact, it probably should not be. It might be just a blank depiction of the main elements or regions of the interface that will be present when the app has finished launching. In this way, when the app *does* finish launching, those elements or regions appear to be filled in as the launch image fades away to reveal the real app.

To prepare the launch image, you use a *launch nib file* — a *.xib* or *.storyboard* file containing a single view. You construct this view using subviews and autolayout. The view is automatically reconfigured to match the screen size and orientation of the device on which the app is launching, and label and button text can be localized. The launch image will be a snapshot of this view.

By default, a new app project comes with a *LaunchScreen.storyboard* file. This is where you design your launch image. The *Info.plist* points to this file as the value of

its “Launch screen interface file base name” key (`UILaunchStoryboardName`). You can configure the *Info.plist*, if necessary, by editing the target and setting the Launch Screen File field under App Icons and Launch Images in the General pane.

Keep the launch screen simple and minimal. Don’t try to misuse it as some kind of introductory splash screen. If you want a splash screen, configure a real view controller to display its view when the app has finished launching. Code cannot run in association with the display of the launch screen; by definition, your app is launching and its code has not yet started to run.

## Screenshots and Video Previews

When you submit your app to the App Store, you will be asked for one or more screenshots of your app in action to be displayed at the App Store. These screenshots must demonstrate actual user experience of the app, or your app may be rejected by Apple’s review team. You should take them beforehand and be prepared to provide them during the app submission process. You can provide a screenshot corresponding to the screen size and resolution of every device on which your app can run, or you can reuse a larger-size screenshot for smaller sizes.

You can obtain screenshots either from the Simulator or from a device connected to the computer:

### *Simulator*

Run the app in the Simulator with the desired device type as your destination. Choose File → Save Screen. Alternatively, click the Save Screen button above the simulator window. A miniature screenshot window appears; Control-click it to choose an option for disposing of the screenshot. By default, it is saved to the Desktop.

You can also generate a screenshot from the command-line. For instance:

```
% xcrun simctl io booted screenshot myscreenshot.png
```

That command saves a screenshot as *myscreenshot.png* in my home directory (because that’s where I was in the Terminal when I gave the command).

### *Device*

In Xcode, in the Devices and Simulators window, locate your connected device under Devices and click Take Screenshot. The screenshot is saved to the Desktop. Alternatively, with the app running on the device, in the project window, choose Debug → View Debugging → Take Screenshot of [Device].

You can also take a screenshot directly on a device. If the device has a Home button, click the screen lock button and the Home button simultaneously. If not, click the screen lock button and the Volume Up button simultaneously. The

screenshot is saved in the Photos app, and you can communicate it to your computer in any convenient way (such as with AirDrop or by emailing it to yourself).

You probably don't have devices with every size you need in order to submit screenshots to the App Store. The Simulator supplies every needed device size. It may be, however, that your app doesn't run properly on the Simulator, because it uses features that exist only on a device. I frequently solve this problem by supplying artificial data to my app, on the simulator only (as I described earlier, [“Build Action” on page 489](#)), so that its interface works sufficiently to let me capture screenshots.

You can also submit to the App Store a video preview showing your app in action; it can be up to 30 seconds long, in H.264 or Apple ProRes format. For more details about video preview specifications, see the “App preview specifications” section of the Reference chapter of Apple's *App Store Connect Help*.

One way to capture the video preview is with your device and QuickTime Player:

1. Connect the device to the computer and launch QuickTime Player. Choose File → New Movie Recording.
2. Hover the mouse over the QuickTime Player window so that the Record button appears. To the right of that button is a pop-menu indicator. Click it! Choose your device from the Camera section (and, if necessary, from the Microphone section).
3. Start recording, and exercise the app on the device. When you're finished, stop recording and save.

You can also capture a video preview from a Simulator window. (This feature was introduced in Xcode 12.5.) Choose File → Record Screen; exercise the app in the Simulator; choose File → Stop Recording. A miniature screenshot window appears; Control-click it to choose an option for disposing of the screenshot.

The resulting movie file can be edited to prepare it for submission to the App Store.

## Property List Settings

A number of settings in the *Info.plist* are crucial to the proper behavior of your app. You should peruse Apple's *Information Property List Key Reference* for full information. Most of the required keys are created as part of the template, and are given reasonable default values, but you should check them anyway. The following are particularly worthy of attention:

### *Bundle display name* (CFBundleDisplayName)

The name that appears under your app's icon on the device screen; this name needs to be short in order to avoid truncation. I talked earlier in this chapter about how to localize the display name. You can enter this value directly in the General pane when you edit your app target.

### *Supported interface orientations* (UISupportedInterfaceOrientations)

This key designates the totality of orientations in which the app is ever permitted to appear. I talked earlier in this chapter about the interface for making these settings with checkboxes in the General pane of the target editor, but you get better fine tuning by editing the *Info.plist* directly in the Info pane. For example, it might be necessary to reorder the orientations (because on an iPhone the *first* orientation listed may be the one into which the app will actually launch).

### *Required device capabilities* (UIRequiredDeviceCapabilities)

You should set this key if the app requires capabilities that are not present on all devices. But don't do that unless it makes no sense for your app to run *at all* on a device lacking the specified capabilities. The key is not present by default in the Info pane, so if you need it, you will have to add it. It is an array of strings whose possible values appear in a pop-up menu in the Value column.

### *Bundle version*

Your app needs a version number. The best place to set it is the General pane of the target editor. There are two fields:

#### *Version*

Corresponds in the *Info.plist* to “Bundle version string, short” (CFBundleShortVersionString), also known as the *marketing version*. In Xcode 13 it comes from the Marketing Version build setting. This is a user-facing string and needs to be a version string, such as “1.0”. It will be displayed at the App Store, distinguishing one release from another. Failure to increment the version string when submitting an update for release through the App Store will cause the update to be rejected.

#### *Build*

Corresponds in the *Info.plist* to “Bundle version” (CFBundleVersion). In Xcode 13 it comes from the Current Project Version build setting. The user never sees this value; it is purely to distinguish different builds that have the same marketing version string. It can, and probably should, be a simple positive integer, which should be incremented each time you submit a new build to App Store Connect — but you can start over at 1 when you increment the marketing version string.

Programmers have historically found all this rather confusing. New in Xcode 13, you get help; when you upload your app to App Store Connect, your build number is validated, and if necessary you'll be offered a corrected value (which will be attached to the uploaded build without modifying your project or the archive).

The interplay between TestFlight versions and App Store versions is also a little tricky. If you're satisfied with a TestFlight version, you can submit the very same binary, which is already present at App Store Connect, for distribution by the App Store. But once you have submitted a version to the App Store, the next build that you submit, even if it is just for TestFlight, must have a higher marketing version string; upping the build number is not sufficient.



Version strings don't work like decimal numbers! Each component of the string is treated as an *integer*. A short version string "1.4" is not "higher" than a version string "1.32" — because 4 is smaller than 32. As usual, I learned this lesson the hard way.

## Submission to the App Store

When you're satisfied that your app works well, and you've installed or collected all the necessary resources, you're ready to submit your app to the App Store for distribution. To do so, you'll need to make preparations at the App Store Connect site (<https://appstoreconnect.apple.com>).



The first time you visit App Store Connect, you should go to the Contracts section and complete submission of your contract. You can't offer any apps for sale until you do, and even free apps require completion of a contractual form.

I'm not going to recite all the steps you have to go through to tell App Store Connect about your app, as these are described thoroughly in Apple's *App Store Connect Help* document, which is the final word on such matters. But here are some of the main pieces of information you will sooner or later have to supply (and see also <https://developer.apple.com/app-store/product-page>):

### *Your app's name*

This is the name that will appear at the App Store; it need not be identical to the short name that will appear under the app's icon on the device, dictated by the "Bundle display name" setting in your *Info.plist* file. Apple now requires that this name be 30 characters or fewer.

You can get a rude shock when you submit your app's information to App Store Connect and discover that the name you wanted is already taken. There is no reliable way to learn this in advance, and such a discovery can necessitate a certain amount of last-minute scrambling on your part. (Can you guess how I know that?)

### *Subtitle*

A description of the app, 30 characters or fewer, that will appear below the name at the App Store.

### *Description*

You must supply a description of fewer than 4,000 characters; Apple recommends fewer than 580 characters, and the first paragraph is the most important, because this may be all that users see at first when they visit the App Store. It must be pure text, with no HTML or character styling.

### *Promotional text*

Optional; 170 characters or fewer. The significance of the promotional text is that you can change it for an existing app, without uploading a new build.

### *Keywords*

A comma-separated list, shorter than 100 characters. These keywords will be used, in addition to your app's name, to help users discover your app through the Search feature of the App Store.

### *Privacy policy*

The URL of a web page describing your privacy policy.

### *Support*

The URL of a website where users can find more information about your app.

### *Copyright*

Do not include a copyright symbol in this string; it will be added for you at the App Store.

### *SKU*

A string identifier that's unique within the world of your own apps. It's convenient if it has something to do with your app's name or bundle identifier.

### *Price*

You don't get to make up a price. You have to choose from a list of pricing "tiers."

### *Availability Date*

There's an option to make the app available as soon as it is approved, and this will typically be your choice.



As you submit information, click Save often! If the connection goes down and you haven't explicitly saved, all your work can be lost. (Can you guess how I know that?)

Once your app is registered at App Store Connect, then when you have an archived build ready for distribution, you can export and upload it. The export process is basically identical to what I described earlier for Test Flight distribution. I recommend *not* converting to bitcode. You should accept the option to upload symbols, as this will make it easier to analyze subsequent crash reports.

There are two ways to dispose of the signed exported app:

*Upload to App Store Connect*

The upload is performed within Xcode, and the app will be validated at the far end.

*Save to disk*

You can perform the upload later using the Transporter application, available from the Mac App Store.

After uploading the archive, you have one final step to perform. Wait for the binary to be processed at Apple's end. (You should receive an email when processing has completed.) Then return to App Store Connect, where you submitted your app information. You will now be able to select the binary, save, and submit the app for review.

You will subsequently receive notifications from Apple informing you of your app's status as it passes through various stages: "Waiting For Review," "In Review," and finally, if all has gone well, "Ready For Sale" (even if it's a free app). Your app will then appear at the App Store.

Once your app is registered at the App Store, you do *not* need to make further preparations merely to upload a new build. Simply increase the build number or version string, as I described earlier, and upload the build. If this build is for TestFlight, and if this version has already been reviewed for TestFlight, the new build becomes available for testing immediately. If this build is for the App Store, you can upload it first and register the new version at App Store Connect later.





## PART III

---

# Cocoa

The Cocoa Touch frameworks provide the general capabilities needed by any iOS application. Buttons can be tapped, text can be read, screens of interface can succeed one another, because Cocoa makes it so. To use the framework, you must learn to let the framework use you. You must put your code in the right place so that it will be called at the right time. You must fulfill certain obligations that Cocoa expects of you. You master Cocoa by being Cocoa's obedient servant. In this part of the book, that's what you'll learn to do.

- **Chapter 11** describes how Cocoa is organized and structured through such Objective-C language features as subclassing, categories, and protocols. Then some important built-in Cocoa object types are introduced. The chapter concludes with a description of Cocoa key-value coding and a look at how the root `NSObject` class is organized.
- **Chapter 12** presents Cocoa's event-driven model of activity, along with its major design patterns and event-related features — notifications, delegation, data sources, target-action, the responder chain, and key-value observing. The chapter concludes with some words of wisdom about managing the barrage of events Cocoa will be throwing at you, and how to escape that barrage momentarily with delayed performance.
- **Chapter 13** is about Cocoa memory management. I'll explain how memory management of reference types works. Then some special memory management situations are described: autorelease pools, retain cycles, notifications and timers, nib loading, and `CTypeRefs`. The chapter concludes with a discussion of Cocoa

property memory management, and advice on how to debug memory management issues.

- **Chapter 14** discusses the question of how your objects are going to see and communicate with one another within the confines of the Cocoa-based world. It concludes with a look at two relatively new ways of managing object communications, the Combine framework and SwiftUI.

Finally, don't forget to read the **Appendix** for more detail about how Objective-C and Swift interact and cooperate.

# Cocoa Classes

When you program iOS through Foundation and UIKit, you're programming Cocoa. The Cocoa API is written mostly in Objective-C, and Cocoa itself consists mostly of Objective-C classes, derived from the root class, `NSObject`.

This chapter introduces Cocoa's class structure and explains how Cocoa is conceptually organized, in terms of its underlying Objective-C features, along with a survey of some of the most commonly encountered Cocoa utility classes. The chapter then discusses Objective-C instance properties and Cocoa key-value coding, and concludes with a description of the Cocoa root class and its features, which are inherited by all Cocoa classes.

## Subclassing

Cocoa supplies a large repertory of objects already endowed with appropriate behavior. A `UIButton` knows how to draw itself and how to respond when the user taps it. A `UITextField` knows how to display editable text, how to summon the keyboard, and how to accept keyboard input.

When the default behavior or appearance of an object supplied by Cocoa isn't quite what you're after, you might want to customize it. But that does not necessarily mean you need to subclass! In fact, subclassing is one of the rarer ways in which your code will relate to Cocoa. Most built-in Cocoa Touch classes will never need subclassing (and some, in their documentation, downright forbid it).

Instead, Cocoa classes are often heavily endowed with methods that you can call and properties that you can set precisely in order to customize an instance, and these will be your first resort. Always study the documentation for a Cocoa class to see whether instances can already be made to do what you want. The `UIButton` class

documentation shows that you can set a button's title, title color, internal image, background image, and many other features and behaviors, without subclassing.

In addition, many built-in classes use delegation ([Chapter 12](#)) as the preferred way of letting you customize their behavior. You wouldn't subclass UITextField just in order to respond in some special way when the user types text, because the delegate mechanism and the UITextFieldDelegate protocol provide ways to do exactly that.

Nevertheless, sometimes setting properties and calling methods and using delegation won't suffice to customize an instance the way you want to. In such cases, a Cocoa class may provide methods that are called by the runtime at key moments in the life of the instance, allowing you to customize that class's behavior by subclassing and overriding.

Moreover, certain Cocoa Touch classes are subclassed routinely, constituting the exception that proves the rule. A case in point is UIViewController. Every Cocoa app uses view controllers, but a plain vanilla UIViewController, not subclassed, is very rare. A Cocoa iOS app without at least one UIViewController subclass would be practically impossible. Subclassing is how you inject *your* functionality into a view controller. Much of your code will probably revolve around UIViewController subclasses that you have written.

Another case in point is UIView. Cocoa Touch is full of built-in UIView subclasses that behave and draw themselves as needed (UIButton, UITextField, and so on), and you will rarely need to subclass any of them. On the other hand, you might create your *own* UIView subclass, whose job would be to draw itself in some completely new way.

You don't actually draw a UIView; rather, when a UIView needs drawing, its `draw(_:)` method is called so that the view can draw itself. So the way to draw a custom UIView is to subclass UIView and implement `draw(_:)` in the subclass. As the documentation says, "Subclasses that ... draw their view's content should override this method and implement their drawing code there." The documentation is saying that you *need* to subclass UIView in order to draw custom content.

Suppose we want our window to contain a horizontal line. There is no horizontal line interface widget built into Cocoa, so we'll just have to roll our own — a UIView that draws itself as a horizontal line. Let's try it:

1. In our Empty Window example project, choose File → New → File and specify iOS → Source → Cocoa Touch Class, and in particular a subclass of UIView. Call the class `MyHorizLine`. Xcode creates *MyHorizLine.swift*. Make sure it's part of the app target.
2. In *MyHorizLine.swift*, replace the contents of the class declaration with this (without further explanation):

```

required init?(coder: NSCoder) {
    super.init(coder:coder)
    self.backgroundColor = .clear
}
override func draw(_ rect: CGRect) {
    let c = UIGraphicsGetCurrentContext()!
    c.move(to:CGPoint(x: 0, y: 0))
    c.addLine(to:CGPoint(x: self.bounds.size.width, y: 0))
    c.strokePath()
}

```

3. Edit the main storyboard. Find UIView in the Library (it is called simply “View”) and drag it into the View object in the canvas. You may resize it to be less tall.
4. Select the UIView that you just dragged into the canvas and use the Identity inspector to change its class to MyHorizLine.

Build and run the app in the Simulator. You’ll see a horizontal line corresponding to the location of the top of the MyHorizLine instance in the nib. Our view has drawn itself as a horizontal line, because we subclassed it to do so.

In that example, we started with a bare UIView that had no drawing functionality of its own. But you might also be able to subclass a built-in UIView subclass to modify the way it already draws itself. In the UILabel class documentation, the discussions of both `drawText(in:)` and `textRect(forBounds:limitedToNumberOfLines:)` refer explicitly to overriding these methods. The implication is that these are methods that will be called for us, automatically, by Cocoa, as a label draws itself; we can subclass UILabel and implement these methods in our subclass to modify how a particular label draws itself.

In one of my own apps, I subclass UILabel and override `drawText(in:)` to make a label that draws its own rectangular border and has its content inset somewhat from that border. As the documentation tells us: “In your overridden method, you can configure the current context further and then invoke super to do the actual drawing [of the text].” Let’s try it:

1. In the Empty Window project, make a new class file, a UILabel subclass; call the class MyBoundedLabel.
2. In *MyBoundedLabel.swift*, insert this code into the body of the class declaration:

```

override func drawText(in rect: CGRect) {
    let context = UIGraphicsGetCurrentContext()!
    context.stroke(self.bounds.insetBy(dx: 1.0, dy: 1.0))
    super.drawText(in: rect.insetBy(dx: 5.0, dy: 5.0))
}

```

3. Edit the main storyboard, add a UILabel to the interface, and change its class in the Identity inspector to MyBoundedLabel.

Build and run the app. As you can see, the rectangle is drawn and the label’s text is inset within it.

## Categories and Extensions

A *category* is an Objective-C language feature that allows code to reach right into an existing class and inject additional methods. This is comparable to a Swift extension ([Chapter 4](#)), so I’ll start by reminding you how extensions are used, and then I’ll describe how Cocoa uses categories.



Objective-C categories have names, and you may see references to these names in the headers, the documentation, and so forth. However, the names are effectively meaningless, so don’t worry about them.

## How Swift Uses Extensions

In the Swift standard library header, many native object type declarations consist of an initial declaration followed by a series of extensions. After declaring the generic struct `Array<Element>`, the header proceeds to declare some dozen extensions on the `Array` struct. Some of these add protocol adoptions; all of them add declarations of properties or methods.

These extensions are not, for the most part, functionally significant. The header could have declared the `Array` struct with all of those properties and methods within the body of a single declaration. Instead, it breaks things up into multiple extensions as a way of clumping related functionality together, organizing this object type’s members so as to make them easier for human readers to understand.

In the Swift Core Graphics header, on the other hand, extensions *are* functionally significant — and just about everything *is* an extension — because Swift is adapting types that are already defined elsewhere. It adapts Swift numeric types for use with Core Graphics and `CGFloat`, and it adapts C structs such as `CGPoint` and `CGRect` for use as Swift object types.

## How You Use Extensions

For the sake of object-oriented encapsulation, you will often want to write a function that you inject, as a method, into an existing object type. To do so, you’ll write an extension. Subclassing merely to add a method or two is heavy-handed — and besides, it often wouldn’t help you do what you need to do.

Suppose you wanted to add a method to Cocoa’s `UIView` class. You could subclass `UIView` and declare your method, but then it would be present only in your `UIView` subclass and in subclasses of that subclass. It would *not* be present in `UIButton`, `UILabel`, and all the other built-in `UIView` subclasses, because they are subclasses of

UIView, not of *your* subclass. An extension solves the problem beautifully: you inject your method into UIView, and it is inherited by all built-in UIView subclasses as well.

For more fine-grained injection of functionality, you can use protocol extensions. Suppose I want UIButton and UIBarButtonItem — which is not a UIView, but does have button-like behavior — to share a certain method. I can declare a protocol with a method, implement that method in a protocol extension, and then use extensions to make UIButton and UIBarButtonItem adopt that protocol and acquire that method:

```
protocol ButtonLike {
    func behaveInButtonLikeWay()
}
extension ButtonLike {
    func behaveInButtonLikeWay() {
        // ...
    }
}
extension UIButton : ButtonLike {}
extension UIBarButtonItem : ButtonLike {}
```

## How Cocoa Uses Categories

Cocoa uses categories as an organizational tool much as Swift uses extensions. The declaration of a class will often be divided by functionality into multiple categories; these can even appear in separate header files.

A good example is NSString. NSString is defined as part of the Foundation framework, and its basic methods are declared in *NSString.h*. Here we find that NSString itself, aside from its initializers, has just two members, `length` and `character(at:)`, because these are regarded as the minimum functionality that a string needs in order to be a string.

Additional NSString methods — those that create a string, deal with a string's encoding, split a string, search in a string, and so on — are clumped into categories. These are shown in the Swift translation of the header as extensions. After the declaration for the NSString class itself, we find this in the Swift translation of the header:

```
extension NSString {
    func substring(from: Int) -> String
    func substring(to: Int) -> String
    // ...
}
```

That is actually Swift's translation of this Objective-C code:

```
@interface NSString (NSStringExtensionMethods)
- (NSString *)substringFromIndex:(NSUInteger)from;
- (NSString *)substringToIndex:(NSUInteger)to;
// ...
@end
```

That notation — the keyword `@interface`, followed by a class name, followed by another name in parentheses — is an Objective-C category.

Moreover, although the declarations for some of Cocoa’s `NSString` categories appear in this same file, *NSString.h*, many of them appear elsewhere:

- A string may serve as a file pathname, so we also find a category on `NSString` in *NSPathUtilities.h*, where methods and properties such as `pathComponents` are declared for splitting a pathname string into its constituents and the like.
- In *NSURL.h*, which is devoted primarily to declaring the `NSURL` class (and its categories), there is also another `NSString` category, declaring methods for dealing with percent encoding in a URL string, such as `addingPercentEncoding(withAllowedCharacters:)`.
- Off in a completely different framework (UIKit), *NSStringDrawing.h* adds two further `NSString` categories, with methods like `draw(at:withAttributes:)` having to do with drawing a string in a graphics context.

This organization means that the `NSString` methods are not gathered in a single header file. In general, fortunately, this won’t matter to you as a programmer, because an `NSString` is an `NSString`, no matter how it acquires its methods.

## Protocols

Objective-C has protocols, and these are generally comparable to and compatible with Swift protocols (see [Chapter 4](#)). Since classes are the only Objective-C object type, all Objective-C protocols are seen by Swift as class protocols. Conversely, Swift protocols marked as `@objc` are implicitly class protocols and can be seen by Objective-C. Cocoa makes extensive use of protocols.

A case in point is how Cocoa objects are copied. Some objects can be copied; some can’t. This has nothing to do with an object’s class heritage. Yet we would like a uniform method to which any object that *can* be copied will respond. So Cocoa defines a protocol named `NSCopying`, which declares just one required method, `copyWithZone:.` Here’s how *NSObject.h* declares the `NSCopying` protocol:

```
@protocol NSCopying
- (id)copyWithZone:(nullable NSZone *)zone;
@end
```

That’s translated into Swift:



```
protocol NSCopying {
    func copy(with zone: NSZone? = nil) -> Any
}
```

The NSCopying protocol declaration in *NSObject.h*, however, is not a statement that NSObject *itself* conforms to NSCopying. Indeed, NSObject does *not* conform to NSCopying! This doesn't compile:

```
let obj = NSObject().copy(with:nil) // compile error
```

But this does compile, because NSString *does* conform to NSCopying:

```
let s = ("hello" as NSString).copy(with: nil)
```

Far and away the most pervasive use of protocols in Cocoa is in connection with the delegation pattern. I'll discuss this pattern in detail in [Chapter 12](#), but you can readily see an example in our handy Empty Window project: the AppDelegate class provided by the project template is declared like this:

```
class AppDelegate: UIResponder, UIApplicationDelegate { // ...
```

AppDelegate's chief purpose on earth is to serve as the shared application's delegate. The shared application object is a UIApplication, and UIApplication's delegate property is declared like this (I'll explain the unsafe modifier in [Chapter 13](#)):

```
unowned(unsafe) var delegate: UIApplicationDelegate?
```

The UIApplicationDelegate type is a protocol. UIApplication is saying: "I don't care what class my delegate belongs to, but whatever it is, it should conform to the UIApplicationDelegate protocol." Such conformance constitutes a promise that the delegate will implement instance methods declared by the protocol, such as application(\_:didFinishLaunchingWithOptions:). The AppDelegate class officially announces its role by explicitly adopting the UIApplicationDelegate protocol.

A Cocoa protocol has its own documentation page. When the UIApplication class documentation tells you that the delegate property is typed as UIApplicationDelegate, it's implicitly telling you that if you want to know what messages the application's delegate might receive, you need to look in the UIApplicationDelegate protocol documentation. application(\_:didFinishLaunchingWithOptions:) isn't mentioned anywhere in the UIApplication class documentation page; it's in the UIApplicationDelegate protocol documentation page.

## Optional Members

Objective-C protocols, and Swift protocols marked as @objc, can have optional members (see ["Optional Protocol Members" on page 200](#)). The UIApplicationDelegate protocol method application(\_:didFinishLaunchingWithOptions:) is a case in point; it's optional. But how, in practice, is an optional member feasible? We know that if a message is sent to an object and the object can't handle that message, an

exception is raised and your app will likely crash. How does Objective-C prevent that from happening?

The answer is that Objective-C is both dynamic and introspective. Objective-C can ask an object whether it can deal with a message without actually sending it that message. The key method here is NSObject’s `responds(to:)` method (Objective-C `respondsToSelector:`), which takes a selector parameter (see [Chapter 2](#)) and returns a `Bool`. Thus it is possible to send a message to an object *conditionally* — that is, only if it would be safe to do so.

Demonstrating `responds(to:)` in Swift is generally a little tricky, because Swift, with its strict type checking, doesn’t want to let us send an object a message to which it might not respond. In this artificial example, I start by defining, at top level, a class that derives from NSObject, because otherwise we can’t send `responds(to:)` to it, along with an `@objc` protocol to declare the message that I want to send conditionally:

```
class MyClass : NSObject {  
}  
@objc protocol Dummy {  
    func woohoo()  
}
```

Now I can say this:

```
let mc = MyClass()  
if mc.responds(to: #selector(Dummy.woohoo)) {  
    (mc as AnyObject).woohoo()  
}
```

Note the cast of `mc` to `AnyObject`. This causes Swift to abandon its strict type checking (see [“Suppressing type checking” on page 230](#)); we can now send this object any message that Swift knows about, provided this object is susceptible to Objective-C introspection — that’s why I marked my protocol declaration as `@objc` to start with. As you know, Swift provides a shorthand for sending a message conditionally: append a question mark to the name of the message. I could have written this:

```
let mc = MyClass()  
(mc as AnyObject).woohoo?()
```

Behind the scenes, those two approaches are exactly the same; the latter is syntactic sugar for the former. In response to the question mark, Swift is calling `responds(to:)` for us, and will refrain from sending `woohoo` to this object if it *doesn’t* respond to this selector.

That explains how optional protocol members work. It is no coincidence that Swift treats optional protocol members like `AnyObject` members. Here’s the example I gave in [Chapter 4](#):

```
@objc protocol Flier {
    @objc optional var song : String {get}
    @objc optional func sing()
}
```

When you call `sing?()` on an object typed as `Flier`, `responds(to:)` is called behind the scenes to determine whether this call is safe. That is also why optional protocol members work only on `@objc` protocols and classes derived from `NSObject`: Swift is relying here on a purely Objective-C feature.

You wouldn't want to send a message optionally, or call `responds(to:)` explicitly, before sending just any old message, because it isn't generally necessary except with optional methods, and it slows things down a little. But Cocoa does in fact call `responds(to:)` on your objects as a matter of course. To see that this is true, implement `responds(to:)` on the `AppDelegate` class in our Empty Window project and instrument it with logging:

```
override func responds(to aSelector: Selector) -> Bool {
    print(aSelector)
    return super.responds(to:aSelector)
}
```

The output on my machine, as the Empty Window app launches, includes the following:

```
application:handleOpenURL:
application:openURL:sourceApplication:annotation:
application:openURL:options:
applicationDidReceiveMemoryWarning:
applicationWillTerminate:
applicationSignificantTimeChange:
application:willChangeStatusBarOrientation:duration:
application:didChangeStatusBarOrientation:
application:willChangeStatusBarFrame:
application:didChangeStatusBarFrame:
application:deviceAccelerated:
application:deviceChangedOrientation:
applicationDidBecomeActive:
applicationWillResignActive:
applicationDidEnterBackground:
applicationWillEnterForeground:
applicationWillSuspend:
application:didResumeWithOptions:
application:shouldSaveApplicationState:
application:shouldSaveSecureApplicationState:
application:supportedInterfaceOrientationsForWindow:
application:defaultWhitePointAdaptivityStyleForWindow:
application:configurationForConnectingSceneSession:options:
application:didDiscardSceneSessions:
```

```
application:performFetchWithCompletionHandler:  
application:didReceiveRemoteNotification:fetchCompletionHandler:  
application:willFinishLaunchingWithOptions:  
application:didFinishLaunchingWithOptions:
```

That's Cocoa, checking to see which optional UIApplicationDelegate protocol methods are actually implemented by our AppDelegate instance. Cocoa checks all the optional protocol methods once, when it first meets the object in question, and presumably stores the results; the app is slowed a tiny bit by this one-time initial bombardment of responds(to:) calls, but now Cocoa knows all the answers and won't have to perform any of these same checks on the same object later. The entire pattern of a delegate with optional delegate members depends upon this technique.

## Informal Protocols

You may occasionally see, online or in the Cocoa documentation, a reference to an *informal protocol*. An informal protocol isn't really a protocol at all; it's just an Objective-C trick for providing the compiler with a knowledge of a method name so that it will allow a message to be sent without complaining.

There are two complementary ways to implement an informal protocol. One is to define a category on NSObject; this makes any object eligible to receive the messages listed in the category. The other is to define a protocol to which no class formally conforms; instead, messages listed in the protocol are sent only to objects typed as id (AnyObject), suppressing any objections from the compiler.

These techniques were widespread in Cocoa before Objective-C protocols could declare methods as optional; now they are largely unnecessary, and are also mildly dangerous. Nowadays, very few informal protocols remain, but they do exist. NSCoder (discussed later in this chapter) is an informal protocol; you may see the term NSCoder in the documentation and elsewhere, but there isn't actually any such type — it's a category on NSObject.

## Some Foundation Classes

The Foundation classes of Cocoa provide fundamental data types and utilities that will form the basis of your communication with Cocoa. In this section, I'll survey those that you'll probably want to be aware of initially. For more information, start with Apple's list of the Foundation classes in the Foundation framework documentation page.

In many situations, you can use Foundation classes implicitly by way of Swift classes. That's because of Swift's ability to *bridge* between its own classes and those of Foundation. There are two kinds of bridging to be distinguished here:

### *Native Swift types*

Certain purely native Swift types are bridged to Objective-C types for purposes of interoperability. For instance, `String` and `Array` are native Swift types, with an independent existence. `String` is bridged to `NSString` ([Chapter 3](#)), and `Array` is bridged to `NSArray` ([Chapter 4](#)), so a `String` and an `NSString` can be cast to one another, and an `Array` and an `NSArray` can be cast to one another. But in fact you'll rarely need to cast, because wherever the Objective-C API expects you to pass an `NSString` or an `NSArray`, these will be typed in the Swift translation of that API as a `String` or an `Array`. And when you use `String` or `Array` in the presence of Foundation, many `NSString` and `NSArray` properties and methods spring to life.

### *Foundation overlay types*

The Swift Foundation overlay puts a native Swift interface in front of many Foundation types. The Swift interface is distinguished by dropping the “NS” prefix that marks Foundation class names. These are not native Swift types; they are façades for Objective-C types, meaning that you cannot use them except in the presence of Cocoa's Foundation framework. For instance, Objective-C `NSData` is accessed through Swift `Data`, and Objective-C `NSDate` is accessed through Swift `Date` — though you can still use `NSData` and `NSDate` directly if you really want to. The Swift and Objective-C types are bridged to one another, and the API shows the Swift type, so casting and passing both work as you would expect. The Swift types provide many conveniences that the Objective-C types do not: they may declare adoption of appropriate Swift protocols such as `Equatable`, `Hashable`, and `Comparable`, and, in some cases, they may be value types (structs) where the Objective-C types are reference types (classes).

## **NSRange**

`NSRange` is a C struct (see the [Appendix](#)). Its components are integers, `location` and `length`. An `NSRange` whose `location` is 1 starts at the second element of something (because element counting is always zero-based), and if its `length` is 2 it designates this element and the next.

A Swift `Range` and a Cocoa `NSRange` are constructed very differently from one another. A Swift `Range` is defined by two endpoints. A Cocoa `NSRange` is defined by a starting point and a length. Nevertheless, Swift (in the Foundation overlay) helps you work with an `NSRange`:

- `NSRange` is endowed with `Range`-like members such as `lowerBound`, `upperBound`, and `contains(_:)`.
- You can coerce a Swift `Range` whose `Bound` type (the type of its endpoints) is `Int` (or any other integer type) to an `NSRange`.

- You can coerce from an NSRange to a Swift Range — resulting in an Optional wrapping a Range, for reasons I’ll explain in a moment.

For example:

```
// Range to NSRange
let r = 2..<4
let nsr = NSRange(r) // (2,2), an NSRange
// NSRange to Range
let nsr2 = NSRange(location: 2, length: 2)
let r2 = Range(nsr2) // Optional wrapping Range 2..<4
```

But what about strings? A Swift String’s range Bound type is *not* Int; it is String.Index. Meanwhile, on the Cocoa side, an NSString still uses an NSRange whose components are integers. Not only is there a type mismatch, there’s also a value mismatch, because a String is indexed on its characters, meaning its graphemes, but an NSString is indexed on its Unicode codepoints (“[The String–NSString Element Mismatch](#)” on page 101).

Sometimes, Swift will solve the problem by crossing the bridge for you in both directions; here’s an example I’ve already used:

```
let s = "hello"
let range = s.range(of:"ell") // Optional wrapping Range 1..<4
```

The range(of:) method in that code is actually a Cocoa method. Swift has cast the String s to an NSString for us, called a Foundation method that returns an NSRange, and coerced the NSRange to a Swift Range (wrapped in an Optional), adjusting its value as needed, entirely behind the scenes.

On other occasions, you will want to perform that coercion explicitly. For this purpose, Range has an initializer init(\_:in:), taking an NSRange and the String to which the resulting range is to apply:

```
let range = NSRange(location: 1, length: 3)
let r = Range(range, in:"hello") // Optional wrapping 1..<4 of String.Index
```

And NSRange has the converse initializer init(\_:in:), taking a Range of String.Index and the String to which it applies:

```
let s = "hello"
let range = NSRange(s.range(of:"ell")!, in: s) // (1,3), an NSRange
```

Sometimes, however, you may actively *want* to operate in the Cocoa Foundation world, *without* bridging back to Swift. You can do that by casting:

```
let s = "Hello"
let range = (s as NSString).range(of: "ell") // NSRange
let mas = NSMutableAttributedString(string:s)
mas.addAttribute([.foregroundColor:UIColor.red], range: range)
```

In that code, we cast a `String` to an `NSString` so as to be able to call `NSString`'s `range(of:)` and get an `NSRange`, because that is what `NSMutableAttributedString`'s `addAttributes(_:range:)` wants as its second parameter. It would be wasteful and time-consuming to call `range(of:)` on a Swift `String`, which crosses into the Foundation world, gets the range, and brings it back to the Swift world, only to convert it back to an `NSRange` *again*.

(New in iOS 15, however, you won't have to write code like that, because the Swift Foundation overlay provides a native `AttributedString` type. I'll demonstrate later.)

## NSNotFound

`NSNotFound` is a constant integer indicating that some requested element was not found. The true numeric value of `NSNotFound` is of no concern; you always compare against `NSNotFound` itself to learn whether a result is meaningful. If you ask for the index of a certain object in an `NSArray` and the object isn't present, the result is `NSNotFound`:

```
let arr = ["hey"] as NSArray
let ix = arr.index(of:"ho")
if ix == NSNotFound {
    print("it wasn't found")
}
```

Why does Cocoa resort to an integer value with a special meaning in this way? Because it has to. The result could not be `0` to indicate the absence of the object, because `0` would indicate the first element of the array. Nor could it be `-1`, because an `NSArray` index value is always positive. Nor could it be `nil`, because Objective-C can't return `nil` when an integer is expected (and even if it could, it would be seen as another way of saying `0`). Contrast Swift, whose `Array` `firstIndex(of:)` method returns an `Int` wrapped in an `Optional`, precisely so that it *can* return `nil` to indicate that the target object wasn't found.

If a search returns an `NSRange` and the thing sought is not present, the `location` component of the result will be `NSNotFound`. This means that, when you turn an `NSRange` into a Swift `Range`, the `NSRange`'s `location` might be `NSNotFound`, and Swift needs to be able to express that as a `nil` `Range`. That's why the initializers for coercing an `NSRange` to a `Range` are failable. It is also why, when you call `NSString`'s `range(of:)` method on a Swift `String`, the result is an `Optional`:

```
let s = "hello"
let r = s.range(of:"ha") // nil; an Optional wrapping a Swift Range
```

## NSString and Friends

NSString is the Cocoa object version of a string. NSString and Swift String are bridged to one another, and you will often move between them without thinking, passing a Swift String to Cocoa, calling Cocoa NSString methods on a Swift String, and so forth:

```
let s = "hello"
let s2 = s.capitalized
```

In that code, `s` is a Swift String and `s2` is a Swift String, but the `capitalized` property actually belongs to Cocoa. In the course of that code, a Swift String has been bridged to NSString and passed to Cocoa, which has processed it to get the capitalized string; the capitalized string is an NSString, but it has been bridged back to a Swift String. In all likelihood, you are not conscious of the bridging; `capitalized` feels like a native String property, but it isn't — as you can readily prove by trying to use it in an environment where Foundation is not imported.

In some cases, Swift may fail to cross the bridge implicitly for you, and you will need to cast explicitly. If `s` is a Swift string, you can't call `appendingPathExtension` on it directly:

```
let s = "MyFile"
let s2 = s.appendingPathExtension("txt") // compile error
```

You have to cast explicitly to NSString:

```
let s2 = (s as NSString).appendingPathExtension("txt")
```

Similarly, to use NSString's `substring(to:)`, you must cast the String to an NSString beforehand:

```
let s2 = (s as NSString).substring(to:4)
```

In this situation, however, we can stay entirely within the Swift world by calling `prefix`, which is a native Swift method, not a Foundation method; delightfully, it takes an `Int`, not a `String.Index`:

```
let s2 = s.prefix(4)
```

But remember, those two calls are not equivalent: they can give different answers, because, as I said a moment ago, String and NSString have fundamentally different notions of what constitutes an element of a string.

Another important difference between a Swift String and a Cocoa NSString is that an NSString is immutable. This means that, with NSString, you can do things such as obtain a new string based on the first — as `capitalized` and `substring(to:)` do — but you can't change the string *in place*. To do that, you need another class, a subclass of NSString, `NSMutableString`. Swift String isn't bridged to `NSMutableString`, so you can't get from String to `NSMutableString` merely by casting. To obtain an



NSMutableString, you'll have to make one. The simplest way to do that is with NSMutableString's initializer `init(string:)`, which expects an NSString — meaning that you can pass a Swift String. Coming back the other way, you can cast all the way from NSMutableString to a Swift String in one move, because an NSMutableString is an NSString:

```
let s = "hello"
let ms = NSMutableString(string:s)
ms.deleteCharacters(in:NSMakeRange(location: ms.length-1, length:1))
let s2 = (ms as String) + "ion" // now s2 is a Swift String, "hellion"
```

As I said in [Chapter 3](#), native Swift String methods are thin on the ground. All the real string-processing power lives over on the Cocoa side of the bridge. So you're going to be crossing that bridge a lot! And this will not be only for the power of the NSString and NSMutableString classes. Many other useful classes are associated with them. Suppose you want to search a string for some substring; all the best ways come from Cocoa:

- An NSString can be searched using various `range` methods, with numerous options such as ignoring diacriticals, ignoring case, and searching backward.
- Perhaps you don't know exactly what you're looking for: you need to describe it structurally. A Scanner (Objective-C NSScanner) lets you walk through a string looking for pieces that fit certain criteria; for example, with Scanner (and also CharacterSet, Objective-C NSCharacterSet) you can skip past everything in a string that precedes a number and then extract the number.
- By specifying the `.regularExpression` search option, you can search using a regular expression. Regular expressions are also supported as a separate class, NSRegularExpression, which in turn uses NSTextCheckingResult to describe match results.
- More sophisticated automated textual analysis is supported by some additional classes, such as NSDataDetector, an NSRegularExpression subclass that efficiently finds certain types of string expression such as a URL or a phone number.

In this example, our goal is to replace all occurrences of the word “hell” with the word “heaven.” We don't want to replace mere occurrences of the *substring* “hell” — the word “hello” should be left intact. Clearly our search needs some intelligence as to what constitutes a word boundary. That sounds like a job for a regular expression. Swift doesn't have regular expressions, so the work has to be done by Cocoa:

```
var s = "hello world, go to hell"
let r = try! NSRegularExpression(
    pattern: #"\\bhell\\b"#,
    options: .caseInsensitive)
s = r.stringByReplacingMatches(
```

```

        in: s,
        range: NSRange(s.startIndex..., in:s),
        withTemplate: "heaven")
// s is "hello world, go to heaven"

```

NSString also has convenience utilities for working with a file path string, and is often used in conjunction with URL (Objective-C NSURL), which is another Foundation type worth looking into, along with its companion types, URLComponents (Objective-C NSURLComponents) and URLQueryItem (Objective-C NSURLQueryItem). In addition, NSString — like some other classes discussed in this section — provides methods for writing out to a file’s contents or reading in a file’s contents; the file can be specified either as a string file path or as a URL.

An NSString carries no font and size information. Interface objects that display strings (such as UILabel) have a font property that is a UIFont; but this determines the *single* font and size in which the string will display. If you want styled text — where different runs of text have different style attributes (size, font, color, and so forth) — you need to use NSAttributedString, along with its supporting classes NSMutableAttributedString, NSParagraphStyle, and NSMutableParagraphStyle. These allow you to style text and paragraphs easily in sophisticated ways. The built-in interface objects that display text can display an attributed string.

New in iOS 15, however, the Foundation overlay provides a native Swift AttributedString type. So you might be able to avoid direct use of NSAttributedString and its friends. Here’s an example I used earlier:

```

let s = "Hello"
let range = (s as NSString).range(of: "ell") // NSRange
let mas = NSMutableAttributedString(string:s)
mas.addAttributes([.foregroundColor:UIColor.red], range: range)

```

In iOS 15, you can say the same thing this way:

```

let s = "Hello"
var attrib = AttributedString(s)
if let range = attrib.range(of: "ell") {
    attrib[range].uiKit.foregroundColor = .red
}

```

Swift AttributedString is not bridged to NSAttributedString, so in order to use this attributed string in the interface, you have to coerce:

```

self.label.attributedText = NSAttributedString(attrib)

```

String drawing in a graphics context can be performed with methods provided through the NSStringDrawing category on NSString and on NSAttributedString.

## NSDate and Friends

A `Date` (Objective-C `NSDate`) is a date and time, represented internally as a number of seconds since some reference date. Calling `Date`'s initializer `init()` — that is, saying `Date()` — gives you a `Date` object for the current date and time; new in iOS 15, you can say `Date.now` instead, which has the virtue of clarity.

Many date operations will also involve the use of `DateComponents` (Objective-C `NSDateComponents`); conversions between `Date` and `DateComponents` require use of a `Calendar` (Objective-C `NSCalendar`). Here's an example of constructing a date based on its calendrical values:

```
let greg = Calendar(identifier:.gregorian)
let comp = DateComponents(calendar: greg,
    year: 2021, month: 8, day: 10, hour: 15)
let d = comp.date // Optional wrapping Date
```

Similarly, `DateComponents` provides the correct way to do date arithmetic. Here's how to add one month to a given date:

```
let d = Date() // or whatever
let comp = DateComponents(month:1)
let greg = Calendar(identifier:.gregorian)
let d2 = greg.date(byAdding: comp, to:d) // Optional wrapping Date
```

Because a `Date` is essentially a wrapper for a `TimeInterval` (a `Double`), Swift can overload the arithmetic operators so that you can do arithmetic directly on a `Date`:

```
let d = Date()
let d2 = d + 4 // 4 seconds later
```

You can express the range between two dates as a `DateInterval` (Objective-C `NSDateInterval`). `DateIntervals` can be compared, intersected, and checked for containment:

```
let greg = Calendar(identifier:.gregorian)
let d1 = DateComponents(calendar: greg,
    year: 2021, month: 1, day: 1, hour: 0).date!
let d2 = DateComponents(calendar: greg,
    year: 2021, month: 8, day: 10, hour: 15).date!
let di = DateInterval(start: d1, end: d2)
if di.contains(Date()) { // are we currently between those two dates?
```

You will also likely be concerned with dates represented as strings. If you don't take explicit charge of a date's string representation, it is represented by a string whose format may surprise you. If you simply `print` a `Date`, you are shown the date in the GMT timezone, which can be confusing if that isn't where you live. A simple solution when you're just logging to the console is to call `description(with:)`, whose parameter is a `Locale` (Objective-C `NSLocale`) comprising the user's current time zone, language, region format, and calendar settings:

```
print(d)
// 2021-08-10 22:00:00 +0000
print(d.description(with:Locale.current))
// Monday, August 10, 2021 at 3:00:00 PM Pacific Daylight Time
```

For full control over date strings, especially when presenting them to the user, you need to *format* the string. In the past, this required a separate formatter object, a `DateFormatter` (Objective-C `NSDateFormatter`); it takes a format string describing how the date string is laid out:

```
let df = DateFormatter()
df.dateFormat = "M/d/y"
let s = df.string(from: Date())
// 7/6/2021
```

The `dateFormat` here is a Unicode date format string. For the notation that it uses, see Appendix F of *Unicode Technical Report 35*.

New in iOS 15, however, Swift provides a formatted method on `Date`, allowing you to convert to a string directly. The preceding code becomes a one-liner:

```
let s = Date.now.formatted(date:.numeric, time:.omitted)
// 7/6/2021
```

If you want more control over which date components are rendered in the output, there's a different approach:

```
let s = Date.now.formatted(.dateTime.day().month())
// Jul 6
```

Note the use of chaining, reminiscent of SwiftUI modifiers; `.dateTime` is a `Date.FormatStyle`, and its `day` and `month` methods also return a `Date.FormatStyle`, so they can be applied to one another in any order.

The precise output from those examples depends on the user's local conventions as expressed in the current `Locale`. It's purely contingent, for instance, whether the month comes first; I'm an American, but in a British date, the day comes first. To take firmer control of the format, you can use a *verbatim* format style; even then you don't need a Unicode date format string, because Swift uses custom string interpolation instead ([Chapter 5](#)):

```
let s = Date.now.formatted(Date.VerbatimFormatStyle(
    format: ""
    \ (month: .defaultDigits)/\ (day: .defaultDigits)/\ (year: .defaultDigits)
    """,
    locale: .autoupdatingCurrent,
    timeZone: .autoupdatingCurrent,
    calendar: .autoupdatingCurrent))
// 7/6/2021
```

That produces month, then day, then year, separated by slashes, regardless of the user's `Locale`.



The `.autoupdatingCurrent` locale has the advantage of being “live” in the app’s interface; if the user changes the device’s Locale while the app is running, any strings based on the `.autoupdatingCurrent` locale already being displayed in the interface will change to match, without having to be regenerated by running the same code again.

In general, however, you *will* probably want a user-facing date string to use a Locale-based format, because it’s what the user expects and understands. For instance:

```
let s = Date.now.formatted(date:.long, time:.complete)
```

The output depends on a combination of region format and language, which are two separate settings:

- On my device, the result might be “July 9, 2021, 12:34:25 PM PDT.”
- If I change my device’s *region* to France, it might be “9 July 2021 at 12:34:25 GMT-7.”
- If I also change my device’s *language* to French, and if my app is localized for French ([Chapter 10](#)), it might be “9 juillet 2021 à 12:34:25 UTC-7.”

You can also translate in the opposite direction, parsing a date string into a `Date`. Again, the old way is to use a `DateFormatter`. The iOS 15 way is to use a parse strategy. This, too, can be a `Date.FormatStyle`, or you can construct a `Date.ParseStrategy` object; again, this uses string interpolation rather than a Unicode date format string:

```
let s = "7/14/2021"
let d = try?(Date(s, strategy: Date.ParseStrategy(
    format: ""
    \ (month: .defaultDigits) / \ (day: .defaultDigits) / \ (year: .defaultDigits)
    "",
    timeZone: .autoupdatingCurrent,
    isLenient: false)))
```

That works: we get the right `Date`. If the initial string were “14/7/2021”, we’d get `nil` instead, because 14 can’t represent a month. Another possibility is to set `isLenient` to `true` (the default), but be careful: this can be *so* lenient as to turn the string into an unrelated `Date` rather than rejecting it.

If you’re curious about what Unicode format string a `Date.ParseStrategy` represents, you can find out by constructing the strategy as an independent object and asking for its format:

```
let formatString : Date.FormatString = ""
    \ (month: .defaultDigits) / \ (day: .defaultDigits) / \ (year: .defaultDigits)
    ""
let strategy = Date.ParseStrategy(format: formatString, timeZone: .current)
print(strategy.format)
```

## NSNumber

An `NSNumber` is an object that wraps a numeric value. The wrapped value can be any standard Objective-C numeric type (including `BOOL`, the Objective-C equivalent of Swift `Bool`). In Swift, everything is an object — a number is a `Struct` instance — so it comes as a surprise to Swift users that `NSNumber` is needed. But an ordinary number in Objective-C is a scalar, not an object, so it cannot be used where an object is expected; and an object cannot be used where a number is expected. Thus, `NSNumber` solves an important problem for Objective-C, converting a number into an object and back again.

Swift does its best to shield you from having to deal directly with `NSNumber`. It bridges Swift numeric types to Objective-C in two different ways:

### *As a scalar*

If Objective-C expects an ordinary number, a Swift number is bridged to an ordinary number (a scalar):

```
UIView.animate(withDuration: 1,
               animations: whatToAnimate, completion: whatToDoLater)
```

Objective-C `animateWithDuration:animations:completion:` takes a C double as its first parameter. The Swift numeric object that you supply as the first argument to `animate(withDuration:animations:completion:)` becomes a C double.

### *As an NSNumber*

If Objective-C expects an object, a Swift numeric type is bridged to an `NSNumber` (including `Bool`, because `NSNumber` can wrap an Objective-C `BOOL`):

```
UserDefaults.standard.set(1, forKey:"Score")
```

Objective-C `setObject:forKey:` takes an Objective-C object as its first parameter. The Swift numeric object that you supply as the first argument to `set(_:forKey:)` becomes an `NSNumber`.

Naturally, if you need to cross the bridge explicitly, you can. You can cast a Swift number to an `NSNumber`:

```
let n = 1 as NSNumber
```

Coming back from Objective-C to Swift, an `NSNumber` (or an `Any` that is actually an `NSNumber`) can be unwrapped by casting it down to a numeric type — provided the wrapped numeric value matches the type. To illustrate, I'll fetch the `NSNumber` that I created in `UserDefaults` by bridging a moment ago:

```

let n = UserDefaults.standard.value(forKey:"Score")
// n is an Optional<Any> containing an NSNumber
let i = n as! Int // legal
let d = n as! Double // legal

```

An NSNumber object is just a wrapper and no more. It can't be used directly for numeric calculations; it isn't a number. It *wraps* a number. One way or another, if you want a number, you have to extract it from the NSNumber.

An NSNumber subclass, NSDecimalNumber, on the other hand, *can* be used in calculations, thanks to a bunch of arithmetic methods:

```

let dec1 = 4.0 as NSDecimalNumber
let dec2 = 5.0 as NSDecimalNumber
let sum = dec1.adding(dec2) // 9.0

```

Underlying NSDecimalNumber is the Decimal struct (Objective-C NSDecimal); it is an NSDecimalNumber's decimalValue. In Objective-C, NSDecimal comes with C functions that are faster than NSDecimalNumber methods. In Swift, things are even better, because the arithmetic operators are overloaded to allow you to do Decimal arithmetic; you are likely to prefer working with Decimal rather than NSDecimalNumber:

```

let dec1 = Decimal(4.0)
let dec2 = Decimal(5.0)
let sum = dec1 + dec2

```

Why does Decimal exist? Well, a computer thinks in binary, and native numeric types are stored in a base-2 representation. When there are digits after the decimal point, the results of an arithmetic operation may not appear quite as you would expect:

```

let d1 = 0.2222
let d2 = 0.2221
let diff = d1 - d2 // 0.00010000000000000167

```

(The reasons for that kind of result are explained in a classic exposition entitled *What Every Computer Scientist Should Know About Floating-Point Arithmetic*.)

Decimal, on the other hand, represents base-10 numbers, and its operations are base-10 operations:

```

let dec1 = Decimal(d1) // 0.2222
let dec2 = Decimal(d2) // 0.2221
let decDiff = dec1 - dec2 // 0.0001
let diff = NSDecimalNumber(decimal: decDiff).doubleValue // 0.0001

```

But of course Decimal operations are much slower than normal arithmetic operations! So you'll use them only when you have to.

Numbers are like dates; if you need to show one to the user, that's a string, and you'll probably want to format it. Just as a date string is formatted by a DateFormatter

(NSDateFormatter), a number string is formatted by a NumberFormatter (NSNumberFormatter). The number might have to be cast to an NSNumber:

```
let formatter = NumberFormatter()
formatter.maximumFractionDigits = 2
let s = formatter.string(from: Double.pi as NSNumber) // 3.14
```

New in iOS 15, a number, like a Date, has a `formatted` method that you can call directly:

```
let s = Double.pi.formatted(.number.precision(.fractionLength(2))) // 3.14
```

There's a lot of power here; you can present a number as currency, as a percentage, using scientific notation, with grouping (as in US "1,000"), with rounding, and more.

## NSNumber

NSNumber is NSNumber's superclass. It is used for wrapping nonnumeric C values, such as C structs, where an object is expected. The problem being solved here is parallel to the problem solved by NSNumber: a Swift struct is an object, but a C struct is not, so a struct cannot be used in Objective-C where an object is expected, and vice versa.

Convenience methods provided through the `NSNumberUIGeometryExtensions` category on NSNumber allow easy wrapping and unwrapping of such common structs as CGPoint, CGSize, CGRect, CGAffineTransform, UIEdgeInsets, and UIOffset:

```
let pt = self.oldButtonCenter // a CGPoint
let val = NSNumber(cgPoint:pt)
```

Additional categories allow easy wrapping and unwrapping of NSRange, CATransform3D, CMTIME, CMTIME\_MAPPING, CMTIME\_RANGE, MKCoordinate, and MKCoordinateSpan (and you are unlikely to need to store any other kind of C value in an NSNumber, but if you do need to, you can).

But you will rarely need to deal with NSNumber explicitly, because Swift will wrap any of those common structs in an NSNumber for you as it crosses the bridge from Swift to Objective-C. Here's an example from my own real-life code:

```
let pt = CGPoint(
    x: screenbounds.midX + r * cos(rads),
    y: screenbounds.midY + r * sin(rads)
)
// apply an animation of ourselves to that point
let anim = CABasicAnimation(keyPath:"position")
anim.fromValue = self.position
anim.toValue = pt
```



In that code, `self.position` and `pt` are both `CGPoint`s. The `CABasicAnimation` properties `fromValue` and `toValue` need to be Objective-C objects (that is, class instances) so that Cocoa can obey them to perform the animation. It is therefore necessary to wrap `self.position` and `pt` as `NSValue` objects. But *you* don't have to do that; Swift wraps those `CGPoint`s as `NSValue` objects for you, Cocoa is able to interpret and obey them, and the animation works correctly.

The same thing is true of an array of common structs. Again, animation is a case in point. If you assign an array of `CGPoint` to a `CAKeyframeAnimation`'s `values` property, the animation will work properly, without your having to map the `CGPoint`s to `NSValues` first. That's because Swift maps them for you as the array crosses the bridge.

## NSData

Data (Objective-C `NSData`) is a general sequence of bytes (`UInt8`); basically, it's just a buffer, a chunk of memory. In Objective-C, `NSData` is immutable; the mutable version is its subclass `NSMutableData`. In Swift, however, where Data is a bridged value type imposed in front of `NSData`, a Data object is mutable if it was declared with `var`, just like any other value type. Although you can work with `NSData` and `NSMutableData` if you want to (by casting to cross the bridge), you are much more likely to prefer Data.

In practice, Data tends to arise in two main ways:

### *When downloading from the internet*

`NSURLSession` (Objective-C `NSURLSession`) supplies whatever it retrieves from the internet as Data. Transforming it from there into (let's say) a string, specifying the correct encoding, would then be up to you.

### *When serializing an object*

A typical use case is that you're storing an object as a file or in user preferences (`UserDefaults`). You can't store a `UIColor` value directly into user preferences. So if the user has made a color choice and you need to save it, you transform the `UIColor` into a Data object (using `NSKeyedArchiver`) and save that:

```
let ud = UserDefaults.standard
let c = UIColor.blue
let cdata = try! NSKeyedArchiver.archivedData(
    withRootObject: c, requiringSecureCoding: true)
ud.set(cdata, forKey: "myColor")
```

Because a Data object represents a byte sequence, Swift makes it a Collection (and therefore a Sequence), causing Swift features such as enumeration with `for...in`, subscripting, and `append(_:)` to spring to life.

But there's an oddity to watch out for: the Data subsequence type is Data. For example, when you subscript an array with a range, you get a slice with that range:

```
let arr : [UInt8] = [1,2,3,4]
let slice = arr[1...2]
print(slice.indices) // 1..  
3
print(type(of:slice)) // ArraySlice<UInt8>
```

In that code, `slice` isn't an Array; it's an ArraySlice, which serves to warn you that its first index might not be 0. But when you do the same thing with a Data, you get another Data:

```
let d = Data(arr)
let d2 = d[1...2]
print(d2.indices) // 1..  
3
print(type(of:d2)) // Data
```

So you can end up with a sort of deficient Data object without realizing it; if you were to say `d2[0]`, you'd crash.

## NSMeasurement and Friends

The Measurement type (Objective-C NSMeasurement) embodies the notion of a measurement by some unit (Unit, Objective-C NSUnit). A unit may be along some dimension that can be expressed in different units convertible to one another; by reducing values in different units of the same dimension to a base unit, a Measurement permits you to perform arithmetic operations and conversions.

The dimensions, which are all subclasses of the (abstract) Dimension class (Objective-C NSDimension, an NSUnit subclass), have names like UnitAngle and UnitLength (Objective-C NSUnitAngle, NSUnitLength), and have class properties vending an instance corresponding to a particular unit type; UnitAngle has class properties `degrees` and `radians` and others, UnitLength has class properties `miles` and `kilometers`, and so on.

To illustrate, I'll add 5 miles to 6 kilometers:

```
let m1 = Measurement(value:5, unit: UnitLength.miles)
let m2 = Measurement(value:6, unit: UnitLength.kilometers)
let total = m1 + m2
```

The answer, `total`, is 14046.7 meters under the hood, because meters are the base unit of length. But it can be converted to any length unit:

```
let totalFeet = total.converted(to: .feet).value // 46084.9737532808
```

If your goal is to output a measurement as a user-facing string, you can use a MeasurementFormatter (Objective-C NSMeasurementFormatter). Its behavior is locale-dependent by default, expressing the value and the units as the user would expect:

```
let mf = MeasurementFormatter()
let s = mf.string(from:total) // "8.728 mi"
```

My code says nothing about miles, but the `MeasurementFormatter` outputs "8.728 mi" because my device is set to United States (region) and English (language). If my device is set to France (region) and French (language), the very same code outputs "14,047 km" — using the French decimal point notation and the French preferred unit of distance measurement.

New in iOS 15, a measurement, like a date or a number, has a `formatted` method. Here's the modern way to write that code:

```
let s = total.formatted(.measurement(
    width: .abbreviated,
    numberFormatStyle: .number.precision(.fractionLength(1...3))))
```

## Equality, Hashability, and Comparison

In Swift, the equality and comparison operators can be overridden for an object type that adopts `Equatable` and `Comparable` (“Operators” on page 310). But Objective-C operators are applicable only to scalars. Objective-C therefore performs comparison of object instances in a special way, and it can be useful to know about this when working with Cocoa classes.

To permit determination of whether two objects are “equal” — whatever that may mean for this object type — an Objective-C class must implement `isEqual(_:)`, which is inherited from `NSObject`. Swift will help out by treating `NSObject` as `Equatable` and by permitting the use of the `==` operator, implicitly converting it to an `isEqual(_:)` call. Thus, if a class derived from `NSObject` implements `isEqual(_:)`, ordinary Swift comparison will work. If an `NSObject` subclass *doesn't* implement `isEqual(_:)`, it inherits `NSObject`'s implementation, which compares the two objects for identity (like Swift's `===` operator).

These two `Dog` objects can be compared with the `==` operator, even though `Dog` does not adopt `Equatable`, because they derive from `NSObject`. `Dog` doesn't implement `isEqual(_:)`, so `==` defaults to using `NSObject`'s identity comparison:

```
class Dog : NSObject {
    var name : String
    var license : Int
    init(name:String, license:Int) {
        self.name = name
        self.license = license
    }
}
let d1 = Dog(name:"Fido", license:1)
let d2 = Dog(name:"Fido", license:1)
let ok = d1 == d2 // false
```

If we wanted two Dogs with the same name and license to be considered equal, we'd need to implement `isEqual(_:)`, like this:

```
class Dog : NSObject {
    var name : String
    var license : Int
    init(name:String, license:Int) {
        self.name = name
        self.license = license
    }
    override func isEqual(_ object: Any?) -> Bool {
        if let otherdog = object as? Dog {
            return (otherdog.name == self.name &&
                    otherdog.license == self.license)
        }
        return false
    }
}

let d1 = Dog(name:"Fido", license:1)
let d2 = Dog(name:"Fido", license:1)
let ok = d1 == d2 // true
```

At this point, you might be saying (thinking of “[Synthesized Protocol Implementations](#)” on page 323): “But wait, why don’t you just declare Dog to adopt Equatable and get autosynthesis of equatability based on its properties?” But you can’t do that. Autosynthesis of Equatable conformance doesn’t work for classes, and in any case Dog is *already* Equatable by virtue of being an NSObject subclass. Besides, Equatable is about how to implement `==`, whereas what we need to implement here is `isEqual:`.

Foundation types implement `isEqual(_:)` in a sensible way, so Swift equatability works as you would expect. NSNumber implements `isEqual(_:)` by comparing the underlying numbers; thus, you can use NSNumber where a Swift Equatable is expected, and, because a Swift number will be cast automatically to an NSNumber if needed, you can even compare an NSNumber to a Swift number:

```
let n1 = 1 as NSNumber
let n2 = 2 as NSNumber
let n3 = 3 as NSNumber
let ok = n2 == 2 // true
let ix = [n1,n2,n3].firstIndex(of:2) // Optional wrapping 1
```

By the same token, for an NSObject subclass to work properly where hashability is required — as a dictionary key or a set member, for instance — it must conform to the NSObject notion of hashability, namely an implementation of `isEqual(_:)` plus a corresponding override of the NSObject hash property, such that two equal objects should have equal hash values. If we wanted our Dog from the previous code to be usable in a Set, we’d need to override hash; that would be tricky to implement on our own, but fortunately the Hasher struct makes it easy:

```

class Dog : NSObject {
    var name : String
    var license : Int
    init(name:String, license:Int) {
        self.name = name
        self.license = license
    }
    override func isEqual(_ object: Any?) -> Bool {
        if let otherdog = object as? Dog {
            return (otherdog.name == self.name &&
                    otherdog.license == self.license)
        }
        return false
    }
    override var hash: Int {
        var h = Hasher()
        h.combine(self.name)
        h.combine(self.license)
        return h.finalize()
    }
}
var set = Set<Dog>()
set.insert(Dog(name:"Fido", license:1))
set.insert(Dog(name:"Fido", license:1))
print(set.count) // 1

```

Objective-C Foundation types come with a built-in hash implementation, and the Swift overlay types are all both Equatable and Hashable as well.

In Objective-C it is also up to individual classes to supply ordered comparison methods. The standard method is `compare(_:)`, which returns one of three cases of `ComparisonResult` (Objective-C `NSComparisonResult`):

`.orderedAscending`

The receiver is less than the argument.

`.orderedSame`

The receiver is equal to the argument.

`.orderedDescending`

The receiver is greater than the argument.

Swift comparison operators (< and so forth) do *not* magically call `compare(_:)` for you. You can't compare two `NSNumber` values directly:

```

let n1 = 1 as NSNumber
let n2 = 2 as NSNumber
let ok = n1 < n2 // compile error

```

You will typically fall back on calling `compare(_:)` yourself:

```
let n1 = 1 as NSNumber
let n2 = 2 as NSNumber
let ok = n1.compare(n2) == .orderedAscending // true
```

On the other hand, a Swift Foundation overlay type *can* adopt Comparable, and in that case comparison operators *do* work. You can't use the < operator to compare two NSDate values, but you can use it to compare two Date values.

## NSArray and NSMutableArray

NSArray is Objective-C's array object type. It is fundamentally similar to Swift Array, and they are bridged to one another; but NSArray elements must be objects (classes and class instances), and they don't have to be of a single type. For a full discussion of how to bridge back and forth between Swift Array and Objective-C NSArray, implicitly and by casting, see [“Swift Array and Objective-C NSArray” on page 249](#).

An NSArray's length is its count, and an element can be obtained by index number using `object(at:)`. The index of the first element, as with a Swift Array, is zero, so the index of the last element is count minus one.

Instead of calling `object(at:)`, you can use subscripting with an NSArray. This is not because NSArray is bridged to Swift Array, but because NSArray implements an Objective-C method, `objectAtIndexedSubscript:`, which is the Objective-C equivalent of a Swift subscript getter. In fact, when you examine the NSArray header file translated into Swift, that method is shown as a subscript declaration!

You can seek an object within an array with `index(of:)` or `indexOfObjectIdentical(to:)`; the former's idea of equality is to call `isEqual(_:)`, whereas the latter uses object identity (like Swift's `===`). If the object is not found in the array, the result is `NSNotFound`.

Like an Objective-C NSString, an NSArray is immutable. This doesn't mean you can't mutate any of the objects it contains; it means that once the NSArray is formed you can't remove an object from it, insert an object into it, or replace an object at a given index. To do those things while staying in the Objective-C world, you can derive a new array consisting of the original array plus or minus some objects, or use NSArray's subclass, NSMutableArray.

Swift Array is not bridged to NSMutableArray; if you want an NSMutableArray, you must create it. The simplest way is with the NSMutableArray initializers, `init()` or `init(array:)`. Once you have an NSMutableArray, you can call methods such as `insert(_:at:)` and `replaceObject(at:with:)`. You can also assign into an NSMutableArray using subscripting. Again, this is because NSMutableArray implements a special Objective-C method, `setObject:atIndexedSubscript:`, and Swift recognizes this as equivalent to a subscript setter.

Coming back the other way, you can cast an NSMutableArray down to a Swift array:

```
let marr = NSMutableArray()
marr.add(1) // an NSNumber
marr.add(2) // an NSNumber
let arr = marr as NSArray as! [Int]
```

Cocoa provides ways to sort an array, as well as to search or filter an array by passing a function. You might prefer to perform those kinds of operation in the Swift Array world, but it can be useful to know how to do them the Cocoa way. Here's an example of filtering:

```
let pep = ["Manny", "Moe", "Jack"] as NSArray
let ems = pep.objects(
    at: pep.indexesOfObjects { obj, idx, stop -> Bool in
        return (obj as! NSString).range(
            of: "m", options:.caseInsensitive
        ).location == 0
    }
) // ["Manny", "Moe"]
```

One of the best ways to sort an NSArray is with an NSSortDescriptor. It can sort on a property of the array's elements, and with multiple sort descriptors you can *subsort* the array, thus solving a problem that can be a hard nut to crack with Swift alone (see [Chapter 4](#)).

It can be worthwhile round-tripping to and from the Foundation NSArray world, just to take advantage of NSSortDescriptor. New in iOS 15, there's a Swift Foundation overlay type, SortDescriptor, that makes this easier.

I'll demonstrate. Your array element type needs to be introspectable by Objective-C on the relevant properties, so it has to be derived from NSObject and those properties must be marked @objc; here's a Person object meeting those requirements:

```
@objcMembers
class Person : NSObject {
    let firstName : String
    let lastName : String
    internal init(firstName: String, lastName: String) {
        self.firstName = firstName
        self.lastName = lastName
    }
    override var description : String {
        self.firstName + " " + self.lastName
    }
}
```

And here's an array of Persons:

```
let people : [Person] = [
    Person(firstName: "Harpo", lastName: "Marx"),
    Person(firstName: "Moe", lastName: "Pep"),
    Person(firstName: "Groucho", lastName: "Marx"),
    Person(firstName: "Manny", lastName: "Pep")
]
```

Our goal is to sort on the last names of these Persons, but where the last name is the same for both, we should sort on the first name. Using the Swift SortDescriptor overlay, we can specify the properties using Swift key paths and we can call a native Sequence `sorted(using:)` method, blissfully unaware of the fact that Foundation and Objective-C are doing all the work:

```
let sort1 = SortDescriptor(\Person.lastName)
let sort2 = SortDescriptor(\Person.firstName)
let result = people.sorted(using: [sort1, sort2])
// [Groucho Marx, Harpo Marx, Manny Pep, Moe Pep]
```

It happens that the same problem can be solved by Swift tuple sorting; but a sort descriptor can readily handle cases that a tuple can't. For instance, we can just as easily ask to sort the first names in reverse order:

```
let sort1 = SortDescriptor(\Person.lastName)
let sort2 = SortDescriptor(\Person.firstName, order: .reverse)
let result = people.sorted(using: [sort1, sort2])
// [Harpo Marx, Groucho Marx, Moe Pep, Manny Pep]
```

## NSDictionary and NSMutableDictionary

NSDictionary is Objective-C's dictionary object type. It is fundamentally similar to Swift Dictionary, and they are bridged to one another. But NSDictionary keys and values must be objects (classes and class instances), and they don't have to be of a single type; the keys must conform to NSCopying and must be hashable. See [“Swift Dictionary and Objective-C NSDictionary” on page 257](#) for a full discussion of how to bridge back and forth between Swift Dictionary and Objective-C NSDictionary, including casting.

An NSDictionary is immutable; its mutable subclass is NSMutableDictionary. Swift Dictionary is not bridged to NSMutableDictionary; you can most easily make an NSMutableDictionary with an initializer, `init()` or `init(dictionary:)`, and you can cast an NSMutableDictionary down to a Swift Dictionary type.

The keys of an NSDictionary are distinct (using `isEqual(_:)` for comparison). If you add a key-value pair to an NSMutableDictionary, then if that key is not already present, the pair is simply added, but if the key is already present, then the corresponding value is replaced. This is parallel to the behavior of Swift Dictionary.

The fundamental use of an NSDictionary is to request an entry's value by key (using `object(forKey:)`); if no such key exists, the result is `nil`. In Objective-C, `nil` is not



an object and cannot be a value in an `NSDictionary`, so the meaning of this response is unambiguous. Swift handles this by treating the result of `object(forKey:)` as an `Optional` wrapping an `Any`.

Subscripting is possible on an `NSDictionary` or an `NSMutableDictionary`, for similar reasons to an `NSArray` or an `NSMutableArray`. `NSDictionary` implements `objectForKeyedSubscript:`, and Swift understands this as equivalent to a subscript getter. In addition, `NSMutableDictionary` implements `setObject:forKeyedSubscript:`, and Swift understands this as equivalent to a subscript setter.

Like a Swift Dictionary, an `NSDictionary` is unordered. You can get from an `NSDictionary` a list of keys (`allKeys`), a list of values (`allValues`), or a list of keys sorted by value. You can also walk through the key–value pairs, and you can even filter an `NSDictionary` by a test against its values.

## NSSet and Friends

An `NSSet` is an unordered collection of distinct objects. Swift `Set` is bridged to `NSSet`, and the Swift Foundation overlay even allows you to initialize an `NSSet` from a Swift array literal. But `NSSet` elements must be objects (classes and class instances), and they don't have to be of a single type. For details, see [“Swift Set and Objective-C NSSet” on page 263](#).

“Distinct” for an `NSSet` means that no two objects in a set can return `true` when they are compared using `isEqual(_:)`. Learning whether an object is present in a set is much more efficient than seeking it in an array (because a set's elements are hashable), and you can ask whether one set is a subset of, or intersects, another set. You can walk through (`enumerate`) a set with the `for...in` construct, though the order is of course undefined. You can filter a set, as you can an `NSArray`. Indeed, much of what you can do with a set is parallel to what you can do with an array, except that you can't do anything with a set that involves the notion of ordering.

To transcend that restriction, there's also an *ordered set* (`NSOrderedSet`). (Recall that the Swift Collections package has an ordered set as well an ordered dictionary.) `NSOrderedSet` is very like an array, and the methods for working with it are similar to the methods for working with an array — you can even fetch an element by subscripting (because it implements `objectAtIndexedSubscript:`). But an ordered set's elements must be distinct. As with an `NSSet`, learning whether an object is present in an ordered set is much more efficient than for an array, and you can readily take the union, intersection, or difference with another set.

An `NSSet` is immutable. You can derive one `NSSet` from another by adding or removing elements, or you can use its subclass, `NSMutableSet`. Similarly, `NSOrderedSet` has its mutable counterpart, `NSMutableOrderedSet` (which you can insert into by subscripting, because it implements `setObject:atIndexedSubscript:`). There is no

penalty for adding to a set an object that the set already contains; nothing is added (and so the distinctness rule is enforced), but there's no error.

`NSCountedSet`, a subclass of `NSMutableSet`, is a mutable unordered collection of objects that are *not* necessarily distinct (this concept is often referred to as a *bag*). It is implemented as a set plus a count of how many times each element has been added.

`NSMutableSet`, `NSCountedSet`, `NSOrderedSet`, and `NSMutableOrderedSet` are easily formed from a set or an array using an initializer. Coming back the other way, you can cast an `NSMutableSet` or `NSCountedSet` down to a Swift `Set`.

## NSIndexSet

`IndexSet` (Objective-C `NSIndexSet`) represents a collection of unique whole numbers; its purpose is to express element numbers of an ordered collection, such as an array. For instance, to retrieve multiple elements simultaneously from an `NSArray`, you specify the desired indexes as an `IndexSet`. It is also used with other things that are array-like; for example, you pass an `IndexSet` to a `UITableView` to indicate what sections to insert or delete.

`NSIndexSet` is immutable; it has a mutable subclass, `NSMutableIndexSet`. But `IndexSet` is a value type, so it is mutable if the declaration uses `var`. And, as with other Swift types imposed in front of Foundation types, `IndexSet` gets to do all sorts of convenient Swift magic. Comparison and arithmetic operators work directly with `IndexSet` values. Even more important, an `IndexSet` acts like a `Set`: it adopts the `SetAlgebra` protocol, and methods like `contains(_:)` and `intersection(_:)` spring to life. You probably won't need `NSMutableIndexSet` at all.

To take a specific example, let's say you want to speak of the elements at indexes 1, 2, 3, 4, 8, 9, and 10 of an array. `IndexSet` embodies this notion using some compact implementation that can be readily queried. The actual implementation is opaque, but you can imagine that this `IndexSet` might consist of two `Ranges`, `1...4` and `8...10`, and `IndexSet`'s methods actually invite you to think of it as a `Set` of `Ranges`:

```
let arr = ["zero", "one", "two", "three", "four", "five",
           "six", "seven", "eight", "nine", "ten"]
var ixS = IndexSet()
ixS.insert(integersIn: 1...4)
ixS.insert(integersIn: 8...10)
let arr2 = (arr as NSArray).objects(at:ixS)
// ["one", "two", "three", "four", "eight", "nine", "ten"]
```

To walk through (enumerate) the index values specified by an `IndexSet`, you can use `for...in`; alternatively, you can walk through an `IndexSet`'s indexes or ranges by calling various `enumerate` methods that let you pass a function returning a `Bool`.



A Swift Array cannot access elements by way of `IndexSet`; `IndexSet` is ultimately a façade for `NSIndexSet`, and applies only to `NSArray`. As of this writing, though, there's a Swift Evolution proposal for adding a true native Swift type, `RangeSet`, that will allow subscripting into a native Swift collection. You can try it out by way of the Standard Library Preview package, <https://github.com/apple/swift-standard-library-preview>.

## NSNull

The `NSNull` class does nothing but supply a pointer to a singleton object, `NSNull()`. This singleton object is used to stand for `nil` in situations where an actual Objective-C object is required and `nil` is not permitted. You can't use `nil` as the value of an element of an Objective-C collection (such as `NSArray`, `NSDictionary`, or `NSSet`), so you'd use `NSNull()` instead.

`NSNull()` makes it possible for a Swift Array of Optional to be handed to Objective-C. The Swift Array might contain `nil`, which is illegal in Objective-C. But Swift will bridge the Array of Optional for you, as it crosses into Objective-C, by substituting `NSNull()` for any `nil` elements. And, coming back the other way, Swift will perform the inverse operation when you cast an `NSArray` down to an Array of Optional, substituting `nil` for any `NSNull()` elements.

You can test an object for equality against `NSNull()` using the ordinary equality operator (`==`), because it falls back on `NSObject`'s `isEqual(_:)`, which is identity comparison. This is a singleton instance, and therefore identity comparison works.

## Immutable and Mutable

Cocoa Foundation has a pattern of class pairs where the superclass is immutable and the subclass is mutable; I've given many examples already, such as `NSString` and `NSMutableString`, or `NSArray` and `NSMutableArray`. This is similar to the Swift distinction between a constant (`let`) and a true variable (`var`). An `NSArray` being immutable means that you can't append or insert into this array, or replace or delete an element of this array; but if its elements are reference types — and of course, for an `NSArray`, they *are* reference types — you can mutate an element in place. That's just like the behavior of a Swift Array referred to with `let`.

The reason why Cocoa needs these immutable/mutable pairs is to prevent unauthorized mutation. An `NSString` object, say, is an ordinary class instance — a reference type. If `NSString` were mutable, an `NSString` property of a class could be mutated by some other object, behind this class's back. To prevent that from happening, a class will work internally and temporarily with a mutable instance, but then store and vend to other classes an immutable instance, protecting the value from being changed by anyone else. Swift doesn't face the same issue, because its fundamental built-in object

types such as `String`, `Array`, and `Dictionary` are structs, and therefore are value types, which cannot be mutated in place; they can be changed only by being replaced, and that is something that can be guarded against, or detected through a setter observer. `NSString` isn't a value *type*, but as far as mutability is concerned, it displays value *semantics* (“[Value Types and Reference Types](#)” on page 157).

The documentation may not make it completely obvious that the mutable classes obey and, if appropriate, override the methods of their immutable superclasses. Dozens of `NSMutableArray` methods are not listed on `NSMutableArray`'s class documentation page, because they are inherited from `NSArray`. And when such methods are inherited by the mutable subclass, they may be overridden to fit the mutable subclass. `NSArray`'s `init(array:)` generates an immutable array, but `NSMutableArray`'s `init(array:)` — which isn't even listed on the `NSMutableArray` documentation page, because it is inherited from `NSArray` — generates a mutable array.

That fact also answers the question of how to make an immutable array mutable, and vice versa. This single method, `init(array:)`, can transform an array between immutable and mutable in either direction. You can also use `copy` (produces an immutable copy) and `mutableCopy` (produces a mutable copy), both inherited from `NSObject`; but these are not as convenient because they yield an `Any` which must then be cast.



These immutable/mutable class pairs are all implemented as *class clusters*, which means that Cocoa uses a secret class, different from the documented class you work with. You may discover this by peeking under the hood; an `NSString`, for instance, might be characterized as an `NSTaggedPointerString` or an `NSCFString`. You should not spend any time wondering about this secret class. It's a mere implementation detail, and is subject to change without notice; you should never have looked at it in the first place.

## Property Lists

A *property list* is a string (XML) representation of data. The Foundation classes `NSString`, `NSData`, `NSArray`, and `NSDictionary` are the only Cocoa classes that can be expressed directly in a property list. Moreover, an `NSArray` or `NSDictionary` can be expressed in a property list only if its elements are instances of those classes, along with `NSDate` and `NSNumber`. Those are the *property list types*.

(That is why, as I mentioned earlier, you must convert a `UIColor` into a `Data` object in order to store it in user defaults; the user defaults storage is a property list, and `UIColor` is not a property list type. But `Data` *is* a property list type, because it is bridged to `NSData`.)

The primary use of a property list is as a way of *serializing* a value — saving it to disk in a form from which it can be reconstructed. `NSArray` and `NSDictionary` provide

write methods that generate property list files; conversely, they also provide initializers that create an NSArray object or an NSDictionary object based on the property list contents of a given file. (The NSString and NSData write methods just write the data out as a file directly, not as a property list.)

Here I'll create an array of strings and write it out to disk as a property list file:

```
let arr = ["Manny", "Moe", "Jack"]
let fm = FileManager.default
let temp = fm.temporaryDirectory
let f = temp.appendingPathComponent("pep.plist")
try! (arr as NSArray).write(to: f)
```

The result is a file that looks like this:

```
<?xml version="1.0" encoding="UTF-8"?>
<!DOCTYPE plist PUBLIC "-//Apple//DTD PLIST 1.0//EN"
    "http://www.apple.com/DTDs/PropertyList-1.0.dtd">
<plist version="1.0">
<array>
    <string>Manny</string>
    <string>Moe</string>
    <string>Jack</string>
</array>
</plist>
```

To reconstruct the array from that file later on, you'd construct a reference to the file and call the NSArray initializer `init(contentsOf:)` with that reference. When you reconstruct an NSArray or NSDictionary object from a property list file in this way, the collections, string objects, and data objects in the collection are all immutable. If you want them to be mutable, or if you want to convert an instance of one of the other property list classes to a property list, you'll use the `PropertyListSerialization` class (Objective-C `NSPropertyListSerialization`; see the *Property List Programming Guide* in the documentation archive).

## Codable

Property lists are a Cocoa Objective-C construct, useful for serializing objects. But in Swift you can serialize an object without crossing the bridge into the Objective-C world, provided it adopts the Codable protocol. In effect, every native Swift type and every Foundation overlay type *does* adopt the Codable protocol! This means, among other things, that enums and structs can easily be serialized.

There are three main use cases, involving three pairs of classes to serialize the object and extract it again later; what you're encoding to and decoding from is a Data object:

### *Property lists*

Use `PropertyListEncoder` and `PropertyListDecoder`.

## JSON

Use `JSONEncoder` and `JSONDecoder`.

## NSCoder

Use `NSKeyedArchiver` and `NSKeyedUnarchiver`.

To illustrate, let's rewrite the previous example, serializing an array of strings to a property list, without casting it to an `NSArray`. This works because both Swift `Array` and Swift `String` adopt `Codable`; indeed, thanks to conditional conformance ([Chapter 4](#)), an `Array` is `Codable` only just in case its element type is `Codable`:

```
let arr = ["Manny", "Moe", "Jack"]
let fm = FileManager.default
let temp = fm.temporaryDirectory
let f = temp.appendingPathComponent("pep.plist")
let penc = PropertyListEncoder()
penc.outputFormat = .xml
let d = try! penc.encode(arr)
try! d.write(to: f)
```

The resulting file looks like this:

```
<?xml version="1.0" encoding="UTF-8"?>
<!DOCTYPE plist PUBLIC "-//Apple//DTD PLIST 1.0//EN"
    "http://www.apple.com/DTDs/PropertyList-1.0.dtd">
<plist version="1.0">
<array>
    <string>Manny</string>
    <string>Moe</string>
    <string>Jack</string>
</array>
</plist>
```

That example doesn't do anything that we couldn't have done with `NSArray`. But now consider, for instance, an index set. You can't write an `NSIndexSet` directly into a property list using Objective-C, because `NSIndexSet` is not a property list type. But the Swift Foundation overlay type, `IndexSet`, is `Codable`:

```
let penc = PropertyListEncoder()
penc.outputFormat = .xml
let d = try! penc.encode(IndexSet([1,2,3]))
```

And here's the result:

```
<?xml version="1.0" encoding="UTF-8"?>
<!DOCTYPE plist PUBLIC "-//Apple//DTD PLIST 1.0//EN"
    "http://www.apple.com/DTDs/PropertyList-1.0.dtd">
<plist version="1.0">
<dict>
    <key>indexes</key>
    <array>
        <dict>
            <key>length</key>
```

```

        <integer>3</integer>
        <key>location</key>
        <integer>1</integer>
    </dict>
</array>
</dict>
</plist>

```

Notice how cleverly Swift has encoded this object. You can't put an `IndexSet` into a property list — but this property list doesn't contain any `IndexSet`! It is composed entirely of legal property list types, namely a dictionary containing an array of dictionaries whose values are numbers. And Swift can extract the encoded object from the property list:

```

let ix = try! PropertyListDecoder().decode(IndexSet.self, from: d)
// [1,2,3]

```

Your own custom types can adopt `Codable` and make themselves encodable in the same way. In fact, in the simplest case, adopting `Codable` is *all* you have to do! If the type's properties are themselves `Codable`, the right thing will happen automatically. The `Codable` protocol has two required methods, but we don't have to implement them because default implementations are synthesized (see “[Synthesized Protocol Implementations](#)” on page 323) — though we *could* implement them if we wanted to customize the details of encoding and decoding.

Here's a simple `Person` struct:

```

struct Person : Codable {
    let firstName : String
    let lastName : String
}

```

`Person` adopts `Codable`, so with no further effort we can turn a `Person` into a property list:

```

let p = Person(firstName: "Matt", lastName: "Neuburg")
let penc = PropertyListEncoder()
penc.outputFormat = .xml
let d = try! penc.encode(p)

```

Here's our encoded `Person`:

```

<?xml version="1.0" encoding="UTF-8"?>
<!DOCTYPE plist PUBLIC "-//Apple//DTD PLIST 1.0//EN"
    "http://www.apple.com/DTDs/PropertyList-1.0.dtd">
<plist version="1.0">
<dict>
    <key>firstName</key>
    <string>Matt</string>

```

```

        <key>lastName</key>
        <string>Neuburg</string>
    </dict>
</plist>

```

Observe that this would work just as well for, say, an array of `Person`, or a dictionary with `Person` values, or any `Codable` struct with a `Person` property.

`UserDefaults` storage is a property list, so an object that isn't a property list type must be archived to a `Data` object in order to store it in `UserDefaults`. A `PropertyListEncoder` creates a `Data` object, so we can use it to store a `Person` object in `UserDefaults`:

```

let ud = UserDefaults.standard
let p = Person(firstName: "Matt", lastName: "Neuburg")
let pdata = try! PropertyListEncoder().encode(p)
ud.set(pdata, forKey: "person")

```

Encoding as JSON is similar to encoding as a property list:

```

let p = Person(firstName: "Matt", lastName: "Neuburg")
let jenc = JSONEncoder()
jenc.outputFormatting = .prettyPrinted
let d = try! jenc.encode(p)
print(String(data:d, encoding:.utf8!))
/*
{
  "firstName" : "Matt",
  "lastName" : "Neuburg"
}
*/

```

The final use case is encoding or decoding through an `NSCoder`. There are various situations where Cocoa lends you an `NSCoder` object and invites you to put some data into it or pull some data out of it. The `NSCoder` in question will be either an `NSKeyedArchiver`, when you're encoding, or an `NSKeyedUnarchiver`, when you're decoding. These subclasses, respectively, provide methods `encodeEncodable(_:forKey:)`, which takes a `Codable` object, and `decodeDecodable(_:forKey:)`, which produces a `Codable` object. Thus, your `Codable` adopters can pass into and out of an archive by way of `NSCoder`.

As I mentioned earlier, your `Codable` adopter can take more control of the encoding and decoding process. You can map between your object's property names and the encoded key names by adding a `CodingKeys` enum, and you can provide an explicit implementation of the `encode(to:)` and `init(from:)` methods instead of letting them be synthesized for you. For more information, consult the help document "Encoding and Decoding Custom Types."



# Accessors, Properties, and Key–Value Coding

An Objective-C instance variable is structurally similar to a Swift instance property: it's a variable that accompanies each instance of a class, with a lifetime and value associated with that particular instance. An Objective-C instance variable, however, is usually private, in the sense that instances of other classes can't see it (and Swift can't see it). If an instance variable is to be made public, an Objective-C class will typically implement *accessor methods*: a getter method and (if this instance variable is to be publicly writable) a setter method. This is such a common thing to do that there are naming conventions:

## *The getter method*

A getter should have the same name as the instance variable (without an initial underscore if the instance variable has one). If the instance variable is named `myVar` (or `_myVar`), the getter method should be named `myVar`.

## *The setter method*

A setter method's name should start with `set`, followed by a capitalized version of the instance variable's name (without an initial underscore if the instance variable has one). The setter should take one parameter — the new value to be assigned to the instance variable. If the instance variable is named `myVar` (or `_myVar`), the setter should be named `setMyVar:`.

This pattern — a getter method, possibly accompanied by an appropriately named setter method — is itself so common that the Objective-C language provides a shorthand: a class can declare a *property*, using the keyword `@property` and a name. Here's a line from the `UIView` class declaration in Objective-C (ignore the material in the parentheses):

```
@property(n nonatomic) CGRect frame;
```

This declaration constitutes a promise that there is a getter accessor method `frame` returning a `CGRect`, along with a setter accessor method `setFrame:` that takes a `CGRect` parameter.

When Objective-C formally declares a `@property` in this way, *Swift sees it as a Swift property*. `UIView`'s `frame` property declaration is translated directly into a Swift declaration of an instance property `frame` of type `CGRect`:

```
var frame: CGRect
```

An Objective-C property name, however, is mere syntactic sugar; Objective-C objects do not really “have” properties. When you apparently set a `UIView`'s `frame` property, you are actually calling its `setFrame:` setter method, and when you apparently get a `UIView`'s `frame` property, you are actually calling its `frame` getter method. In Objective-C, use of the property is optional; Objective-C code can, and often does,

call the `setFrame:` and `frame` methods *directly*. But you can't do that in Swift! If an Objective-C class has a formal `@property` declaration, *the accessor methods are hidden from Swift*.

An Objective-C property declaration can include the word `readonly` in the parentheses. This indicates that there is a getter but no setter:

```
@property(n nonatomic, readonly, strong) CALayer *layer;
```

(Ignore the other material in the parentheses.) Swift will reflect this restriction with `{get}` after the declaration, as if this were a computed read-only property; the compiler will not permit you to assign to such a property:

```
var layer: CALayer { get }
```

Although Objective-C accessor methods may literally be ways of accessing an invisible instance variable, they don't have to be. When you set a `UIView`'s `frame` property and the `setFrame:` accessor method is called, you have no way of knowing what that method is really doing: it might be setting an instance variable called `frame` or `_frame`, but who knows? In this sense, accessors and properties are a façade, hiding the underlying implementation. This is similar to how, within Swift, you can set a variable without knowing or caring whether it is a stored variable or a computed variable (and, if it is a computed variable, without knowing what its getter and setter functions really do).

## Swift Accessors

Just as Objective-C properties are actually a shorthand for accessor methods, so Objective-C treats Swift properties as a shorthand for accessor methods — even though no such methods are formally present. If you, in Swift, declare that a class has a property `prop`, Objective-C can call a `prop` method to get its value or a `setProp:` method to set its value, *even though you have not implemented such methods*. Those calls are routed to your property through *implicit* accessor methods.

In Swift, you should *not* write *explicit* accessor methods for a property; the compiler will stop you if you attempt to do so. If you need to implement an accessor method explicitly and formally, use a computed property. Here I'll add to my `UIViewController` subclass a computed color property with a getter and a setter:

```
class ViewController: UIViewController {
    @objc var color : UIColor {
        get {
            print("someone called the getter")
            return .red
        }
        set {
```

```

        print("someone called the setter")
    }
}

```

Objective-C code can now call explicitly the implicit `setColor:` and `color` accessor methods — and when it does, the computed property's setter and getter methods are in fact called:

```

ViewController* vc = [ViewController new];
[vc setColor:[UIColor redColor]]; // "someone called the setter"
UIColor* c = [vc color]; // "someone called the getter"

```

This proves that, in Objective-C's mind, you *have* provided `setColor:` and `color` accessor methods.

You can even *change* the Objective-C names of accessor methods! To do so, follow the `@objc` attribute with the Objective-C name in parentheses. You can add it to a computed property's setter and getter methods, or you can add it to a property itself:

```
@objc(hue) var color : UIColor?
```

Objective-C code can now call `hue` and `setHue:` accessor methods directly.

If, in speaking to Objective-C, you need to pass a selector for an accessor method, precede the contents of the `#selector` expression with `getter:` or `setter:`. For example, `#selector(setter:color)` is `"setHue:"` if we have modified our `color` property's Objective-C name with `@objc(hue)` (or `"setColor:"` if we have not).

If all you want to do is add functionality to the setter, use a setter observer. To add functionality to the Objective-C `setFrame:` method in your `UIView` subclass, you can override the frame property and write a `didSet` observer:

```

class MyView: UIView {
    override var frame : CGRect {
        didSet {
            print("the frame setter was called: \(super.frame)")
        }
    }
}

```

## Key–Value Coding

Cocoa can dynamically call an accessor method, or access an instance variable, based on a string name specified at runtime, through a mechanism called *key–value coding* (KVC). The string name is the *key*; what is passed or returned is the *value*. The basis for key–value coding is the `NSKeyValueCoding` protocol, an informal protocol; it is actually a category injected into `NSObject`. A Swift class, to be susceptible to key–value coding, must therefore be derived from `NSObject`.

The fundamental Cocoa key-value coding methods are `setValue(_:forKey:)` and `value(forKey:)`. When one of these methods is called on an object, the object is introspected. In simplified terms, first the appropriate accessor method is sought; if it doesn't exist, the instance variable is accessed directly. The value can be an Objective-C object of any type, so its Objective-C type is `id`; therefore it is typed in Swift as `Any`. Whatever you pass into `setValue(_:forKey:)` will cross the bridge from Swift to Objective-C. Coming back the other way, when calling `value(forKey:)`, you'll receive an `Optional` wrapping an `Any`; you'll want to cast this down safely to its expected type.

A class is *key-value coding compliant* (or *KVC compliant*) on a given key if it provides the accessor methods, or possesses the instance variable, required for access through that key. An attempt to access a key for which a class is *not* key-value coding compliant will likely cause a crash at runtime. It is useful to be familiar with the message you'll get when such a crash occurs, so let's cause it deliberately:

```
let obj = NSObject()
obj.setValue("hello", forKey:"keyName") // crash
```

The console says: "This class is not key value coding-compliant for the key keyName." The last word in that error message is the key string that caused the trouble.

What would it take for that method call *not* to crash? The class of the object to which it is sent would need to have a `setKeyName:` setter method, or a `keyName` or `_keyName` instance variable. In Swift, as I demonstrated in the previous section, an instance property implies the existence of accessor methods. So we can use Cocoa key-value coding on an instance of any `NSObject` subclass that has a declared property, provided the key string is the string name of that property. Let's try it! Here is such a class:

```
class Dog : NSObject {
    @objc var name : String = ""
}
```

And here's our test:

```
let d = Dog()
d.setValue("Fido", forKey:"name") // no crash!
print(d.name) // "Fido" - it worked!
```

## How Outlets Work

Key-value coding lies at the heart of how outlet connections work ([Chapter 8](#)). Suppose that you have a class `Dog` with an `@IBOutlet` property `person` typed as `Person`, and you've drawn a "person" outlet from a `Dog` object in the nib to a `Person` object in the nib. The name of that outlet, "person", is just a string. When the nib loads, the outlet name "person" is translated *through key-value coding* to the accessor method

name `setPerson:`, and your `Dog` instance's `setPerson:` implicit accessor method is called with the `Person` instance as its parameter, setting the value of your `Dog` instance's `person` property to the `Person` instance (Figure 8-6).

If something goes wrong with the match between the outlet name in the nib and the name of the property in the class, then at runtime, when the nib loads, Cocoa's attempt to use key-value coding to set a value in your object based on the name of the outlet will fail, and your app will crash — with an error message complaining (you guessed it) that the class is not key-value coding compliant for the key. (The key here is the outlet name.) A likely way for this to happen is that you formed the outlet correctly but then later changed the name of (or deleted) the property in the class; see “Misconfigured Outlets” on page 455.

## Cocoa Key Paths

A Cocoa *key path* allows you to chain keys in a single expression. If an object is key-value coding compliant for a certain key, and if the value of that key is itself an object that is key-value coding compliant for another key, you can chain those keys by calling `value(forKeyPath:)` and `setValue(_:forKeyPath:)`.

A key path string looks like a succession of key names joined using dot-notation. `valueForKeyPath("key1.key2")` effectively calls `value(forKey:)` on the message receiver, with "key1" as the key, and then takes the object returned from that call and calls `value(forKey:)` on that object, with "key2" as the key.

To illustrate, here are two classes that form a chain of properties — a `DogOwner` that has a `dog` property which is a `Dog` that has a `name` property:

```
class Dog : NSObject {
    @objc var name : String = ""
}
class DogOwner : NSObject {
    @objc var dog : Dog?
}
```

Now let's configure an actual chain:

```
let owner = DogOwner()
let dog = Dog()
dog.name = "Fido"
owner.dog = dog
```

Now we can use key-value coding with a key path to work our way down the chain:

```
if let name = owner.value(forKeyPath:"dog.name") as? String {
```

We retrieve the value as an `Optional` wrapping an `Any` which is actually a string, and we cast down safely to retrieve the real value, "Fido".

## Uses of Key–Value Coding

Cocoa key–value coding allows you, in effect, to decide at runtime, based on a string, what accessor to call. In the simplest case, you’re using a string to access a dynamically specified property. That’s useful in Objective-C code; but such unfettered introspective dynamism is contrary to the spirit of Swift, and in translating my own Objective-C code into Swift I have generally found myself accomplishing the same ends by other means.

Nevertheless, key–value coding remains useful in programming iOS, especially because a number of built-in Cocoa classes permit you to use it in special ways:

- If you send `value(forKey:)` to an `NSArray`, it sends `value(forKey:)` to each of its elements and returns a new array consisting of the results, an elegant shorthand. `NSSet` behaves similarly.
- `NSDictionary` implements `value(forKey:)` as an alternative to `object(forKey:)` (useful particularly if you have an `NSArray` of dictionaries). Similarly, `NSMutableDictionary` treats `setValue(_:forKey:)` as a synonym for `set(_:forKey:)`, except that the first parameter can be `nil`, in which case `removeObject(forKey:)` is called.
- `NSSortDescriptor` sorts an `NSArray` by sending `value(forKey:)` to each of its elements. This makes it easy to sort an array of dictionaries on the value of a particular dictionary key, or an array of objects on the value of a particular property.
- `NSManagedObject`, used in conjunction with Core Data, is guaranteed to be key–value coding compliant for attributes you’ve configured in the entity model. It’s common to access those attributes with `value(forKey:)` and `setValue(_:forKey:)`.
- `CALayer` and `CAAnimation` permit you to use key–value coding to define and retrieve the values for *arbitrary* keys, as if they were a kind of dictionary; they are, in effect, key–value coding compliant for *every key*. This is extremely helpful for attaching extra information to an instance of one of these classes.

Also, many Cocoa APIs use key–value coding indirectly: you supply a key string, and Cocoa applies it for you. For example, a `CABasicAnimation` must be initialized with a `keyPath` string parameter:

```
let anim = CABasicAnimation(keyPath:"transform")
```

What you’re really doing here is telling the animation that you’re going to want to animate a `CALayer`’s `transform` property. Similarly, the AV Foundation framework, used in conjunction with videos, takes string keys to specify properties whose value you’re going to be interested in:

```
let url = Bundle.main.url(forResource:"ElMirage", withExtension:"mp4")!
let asset = AVURLAsset(url:url)
asset.loadValuesAsynchronously(forKeys:["tracks"]) {
```

That works because an AVURLAsset has a tracks property.

## KeyPath Notation

Using key–value coding can be dangerous, because you risk using a key for which the target object is not key–value coding compliant. But Swift can often provide some measure of safety. Instead of forming the key string yourself, you ask the Swift compiler to form it for you. To do so, use `#keyPath` notation.

`#keyPath` notation is similar to `#selector` syntax ([Chapter 2](#)): you’re asking the Swift compiler to form the key string for you, and it will refuse if it can’t confirm that the key in question is legal. We crashed by saying this:

```
let obj = NSObject()
obj.setValue("hello", forKey:"keyName") // crash
```

But if we had used `#keyPath` notation, our code wouldn’t have crashed — because it wouldn’t even have compiled:

```
let obj = NSObject()
obj.setValue("howdy", forKey: #keyPath(NSObject.keyName)) // compile error
```

Now return to our Dog with a name property:

```
class Dog : NSObject {
    @objc var name : String = ""
}
```

This compiles, because Swift *knows* that Dog has a name property:

```
let d = Dog()
d.setValue("Fido", forKey:#keyPath(Dog.name))
```

But that code will *not* compile if Dog is not an NSObject subclass, or if its name property is not exposed to Objective-C. Thus the Swift compiler can often help to save us from ourselves. Some of my earlier examples can be rewritten more safely using `#keyPath` notation, and in real life, this is how I would write them:

```
let anim = CABasicAnimation(keyPath: #keyPath(CALayer.transform))
```

And:

```
let url = Bundle.main.url(forResource:"ElMirage", withExtension:"mp4")!
let asset = AVURLAsset(url:url)
let tracks = #keyPath(AVURLAsset.tracks)
asset.loadValuesAsynchronously(forKeys:[tracks]) {
```

But the compiler can't *always* save us from ourselves. There are situations where you can't form a string indirectly using `#keyPath` notation, and you'll just have to hand Cocoa a string that you form yourself. For example (`self` is a `CALayer`):

```
self.rotationLayer.setValue(.pi/4.0, forKeyPath:"transform.rotation.y")
```

You can't rewrite that using `#keyPath(CALayer.transform.rotation.y)`, because the compiler won't let you form that key path. The problem is that the compiler is unaware of any `rotation` property of a `CALayer transform` — because there is no such property. That sort of key path works by a special dispensation within Cocoa: `CATransform3D` (the type of a `CALayer`'s transform) is key-value coding compliant for a repertoire of keys and key paths that don't correspond to any actual properties, and Swift has no way of knowing that.

You may be wondering how all of this relates to Swift's own key path mechanism ([Chapter 5](#)). If a `Dog` has a `name` property, you can say:

```
let d = Dog()
d[keyPath:\.name] = "Rover"
```

That is a completely different mechanism! You'll surely prefer to use the Swift mechanism where possible. It provides complete safety, along with type information; a Swift `KeyPath` object is strongly typed, because it is a generic, specified to the type of the corresponding property. But that won't help you when you're talking to Cocoa. Objective-C key-value coding uses string keys, and a Swift `KeyPath` object cannot be magically transformed into a string key.

(But it apparently can be transformed into a string key *somehow*, because that is exactly what `NSSortDescriptor` does in the `SortDescriptor` example I gave earlier.)



Cocoa key-value coding is a powerful technology with many ramifications beyond what I've described here; see Apple's *Key-Value Coding Programming Guide* in the documentation archive for full information.

## The Secret Life of NSObject

Every Objective-C class inherits from `NSObject`, which is constructed in a rather elaborate way:

- It defines some native class methods and instance methods having mostly to do with the basics of instantiation and of method sending and resolution.
- It adopts the `NSObject` protocol. This protocol declares instance methods having mostly to do with memory management, the relationship between an instance and its class, and introspection. Because all the `NSObject` protocol methods are required, the `NSObject` class implements them all. In Swift, the `NSObject` protocol is called `NSObjectProtocol`, to avoid name clash.



- It implements convenience methods related to the NSCopying, NSMutableCopying, and NSCoder protocols, without formally adopting those protocols. NSObject intentionally doesn't adopt these protocols because this would cause all other classes to adopt them, which would be wrong. But thanks to this architecture, if a class *does* adopt one of these protocols, you can call the corresponding convenience method. For instance, NSObject implements the copy instance method, so you can call copy on any instance, but you'll crash unless the instance's class also adopts the NSCopying protocol and implements copy(with:).
- A large number of methods are injected into NSObject by more than two dozen categories on NSObject, scattered among various header files. For example, awakeFromNib (see [Chapter 8](#)) comes from the UINibLoadingAdditions category on NSObject, declared in *UINibLoading.h*.
- A class object is an object. Therefore all Objective-C classes, which are objects of type Class, inherit from NSObject. Therefore, *any instance method of NSObject can be called on a class object as a class method!* For example, responds(to:) is defined as an instance method by the NSObject protocol, but it can (therefore) be treated also as a class method and sent to a class object.

Taken as a whole, the NSObject methods may be roughly classified as follows:

#### *Creation, destruction, and memory management*

Methods for creating an instance, such as alloc and copy, along with methods for learning when something is happening in the lifetime of an object, such as initialize and dealloc, plus methods that manage memory.

#### *Class relationships*

Methods for learning an object's class and inheritance, such as superclass, isKindOfClass:, and isMember(of:).

#### *Object introspection and comparison*

Methods for asking what would happen if an object were sent a certain message, such as responds(to:), for representing an object as a string (description), and for comparing objects (isEqual(\_:)).

#### *Message response*

Methods for meddling with what *does* happen when an object is sent a certain message, such as doesNotRecognizeSelector(\_:). If you're curious, see the *Objective-C Runtime Programming Guide* in the documentation archive.

#### *Message sending*

Methods for sending a message dynamically. For example, perform(\_:) takes a selector as parameter, and sending it to an object tells that object to perform that selector. This might seem identical to just sending that message to that object,

but what if you don't know what message to send until runtime? Moreover, variants on `perform` allow you to send a message on a specified thread, or to send a message after a certain amount of time has passed (`perform(_:with:afterDelay:)` and similar).

---

# Cocoa Events

All of your app's executable code lies in its functions. The impetus for a function being called must come from somewhere. One of your functions may call another, but who will call the first function in the first place? How, ultimately, will *any* of your code *ever* run?

After your app has completely finished launching, *none* of your code runs. `UIApplicationMain` (see “[How an App Gets Going](#)” on page 431) just sits and loops — the *event loop* — waiting for something to happen. In general, the user needs to *do* something, such as touching the screen, or switching away from your app. When something does happen, the runtime detects it and informs your app, and Cocoa can call your code.

But Cocoa can call your code only if your code is there to be called. Your code is like a panel of buttons, ready for Cocoa to press one. If something happens that Cocoa feels your code needs to know about and respond to, it presses the right button — if the right button is there. Cocoa wants to send your code a message, but your code must have ears to hear.

The art of Cocoa programming lies in knowing *what* messages Cocoa would like to send your app. You organize your code, right from the start, with those messages in mind. Cocoa makes certain promises about how and when it will dispatch messages to your code. These are Cocoa's *events*. Your job is to know what those events are and how they will arrive; armed with that knowledge, you can arrange for your code to respond to them.

## Reasons for Events

Broadly speaking, the reasons you might receive an event may be divided informally into four categories. These categories are not official; I made them up. Often it isn't

completely clear which of these categories an event fits into. But they are still generally useful for visualizing how and why Cocoa interacts with your code:

#### *User events*

The user does something interactive, and an event is triggered directly. Obvious examples are events that you get when the user taps or swipes the screen, or types a key on the keyboard.

#### *Lifetime events*

These are events notifying you of the arrival of a stage in the life of the app, such as the fact that the app is starting up or is about to go into the background, or of a component of the app, such as the fact that a UIViewController’s view has just loaded or is about to be removed from the screen.

#### *Functional events*

Cocoa is about to do something by calling its own code, and is willing to let you subclass and override that code so as to modify its behavior. I would put into this category UIView’s `draw(_:)` (your chance to have a view draw itself), with which we experimented in [Chapter 11](#).

#### *Query events*

Cocoa turns to you to ask a question; its behavior will depend upon your answer. The way data appears in a table (a UITableView) is that Cocoa asks you how many rows the table should have, and then, for each row, asks you for the corresponding cell.

## Subclassing

A built-in Cocoa class may define methods that Cocoa itself will call if you override them in a subclass, so that your custom behavior, and not (merely) the default behavior, will take place. As I explained in [Chapter 11](#), this is not a commonly used architecture in Cocoa, but for many classes it’s there if you need it, and for certain classes it is downright essential. UIView and UIViewController are the best examples.

UIView’s `draw(_:)` is what I call a functional event. By default it does nothing, but by overriding it in a UIView subclass, you dictate how a view draws itself. You don’t know exactly when this method will be called, and you don’t care; when it is, you draw, and this guarantees that the view will always appear the way you want it to.

UIViewController is a class meant for subclassing, and is probably the only Cocoa class that you will *regularly* subclass. Of the methods listed in the UIViewController class documentation, just about all are methods you might have reason to override. If you create a UIViewController subclass in Xcode, you’ll see that the template already includes some method overrides to get you started. `viewDidLoad` is called to let you know that your view controller has obtained its main view (its `view`), so that you can

perform initializations; it's an obvious example of a lifetime event. And `UIViewController` has many other lifetime events that you can and will override in order to get fine control over what happens when.

Not only methods but also properties may be overridden in order to get an event. A case in point is `UIViewController`'s `supportedInterfaceOrientations`. You'll override this property as a computed variable in order to receive what I call a query event. Whenever Cocoa wants to know what orientations your view can appear in, it fetches the value of this property; your getter is a function that is called at that moment, and its job is to return a bitmask ("**Option sets**" on page 261) providing the answer to that question. You trust Cocoa to trigger this call at the appropriate moments, so that if the user rotates the device, your app's interface will or won't be rotated to compensate, depending on what value you return.

When you're looking for events that you can receive through subclassing, be sure to look upward through the inheritance hierarchy. If you're wondering how to get an event when your custom `UILabel` subclass is embedded into another view, you won't find the answer in the `UILabel` class documentation; a `UILabel` receives the appropriate event by virtue of being a `UIView`. In the `UIView` class documentation, you'll learn that you can override `didMoveToSuperview` to be informed when this happens.

By the same token, look upward through adopted protocols as well. If you're wondering how to get an event when your view controller's view is about to undergo app rotation, you won't find out by looking in the `UIViewController` class documentation; a `UIViewController` receives the appropriate event by virtue of adopting the `UINavigationController` protocol. In the `UINavigationController` protocol documentation, you'll learn that you can override `viewWillTransition(to:with:)`.

## Notifications

Cocoa provides your app with a single `NotificationCenter` instance (Objective-C `NSNotificationCenter`), available as `NotificationCenter.default`. This instance, the *notification center*, is the basis of a mechanism for sending and receiving messages called *notifications*. A notification is a `Notification` instance (Objective-C `NSNotification`).

Think of a notification as having a topic and a sender. The topic is some subject matter that might be of interest to others; the sender is some object that others might be interested in hearing from. The notification center functions as a kind of broker for message transmission:

1. A potential recipient of messages can *register* with the notification center, saying: "Hey, if any messages on this topic or from this sender arrive, please pass them on to me."

2. A sender does in fact hand the notification center a message to send out; this is called *posting* a notification.
3. When the notification center receives a posting on a certain topic or from a certain sender, it looks through its list of registered recipients and passes along the message to any recipients that match.

More than one recipient can register for messages with the same topic or sender. The notification mechanism is well described as a dispatching or broadcasting mechanism. It lets the poster send a message without knowing or caring whether there are recipients or, if there are, who or how many they may be. And it lets the recipient arrange to receive the message without being in direct contact with the sender (possibly without even knowing who the sender is).

Who can post a notification? Anyone who cares to! There are two main posters of notifications to consider — Cocoa and you:

#### *Cocoa*

Cocoa posts notifications through the notification center, and your code can register to receive them. Notifications are a way for your code to receive events from Cocoa. You'll find a separate Notifications section in the documentation for a class that provides them.

#### *You*

You can post notifications yourself as a way of communicating with your own code. This relieves your app's architecture from the formal responsibility of somehow hooking up instances just so a message can pass from one to the other (which can sometimes be quite tricky or onerous, as I'll discuss in [Chapter 14](#)). When objects are conceptually "distant" from one another, notifications can be a fairly lightweight way of permitting one to message the other.

A Notification instance has three pieces of information associated with it, which can be retrieved through properties:

#### `name`

The *topic* of the notification. It's a string, but it has been wrapped up in a `Notification.Name`, a struct adopting `RawRepresentable` with a `String rawValue`. Built-in Cocoa notification names are vended as `static/class Notification.Name` properties, either of `Notification.Name` itself or of the class that sends them.

#### `object`

An instance associated with the notification; typically, the *sender* who posted it.

#### `userInfo`

An Optional dictionary; if not `nil`, it contains additional information associated with the notification. What information it will contain, and under what keys, depends on the particular notification; you have to consult the documentation.

When you post a notification yourself, you can put anything you like into the `userInfo` for the notification's recipient(s) to retrieve. Do *not* misuse a notification's object as a way of passing along a value. That's what the `userInfo` is for.

## Receiving a Notification

To register to receive notifications, you send one of two messages to the notification center.

### Selector-based registration

One way to register for notifications is to call the notification center's `addObserver(_:selector:name:object:)`. The parameters are:

**observer:**

The first parameter is the instance to which the notification is to be sent. This will typically be `self`; it would be quite unusual for one instance to register a different instance as the receiver of a notification.

**selector:**

The message to be sent to the observer instance when the notification occurs. The designated method should take one parameter, which will be the Notification instance. The selector must specify correctly a method that is exposed to Objective-C; Swift's `#selector` syntax will help you with that (see [Chapter 2](#)).

**name:**

The name (topic) of the notification you'd like to receive. If this is `nil`, you're asking to receive *all* notifications associated with the object designated in the `object:` parameter.

**object:**

The object (sender) of the notification you're interested in. If this is `nil`, you're asking to receive *all* notifications with the name designated in the `name:` parameter. (If both the `name:` and `object:` parameters are `nil`, you're asking to receive all notifications!)

Here's a real-life example. There is a music player belonging to the `MPMusicPlayerController` class; this class promises to post a notification whenever the music player starts playing a different song. (To find this out, I look under Notifications in the `MPMusicPlayerController` class documentation; the notification in question is called `MPMusicPlayerControllerNowPlayingItemDidChange`.) In my app, I want to receive that notification and change my interface accordingly.

Here's how I register myself to receive the desired playback notification:

```
NotificationCenter.default.addObserver(self,
    selector: #selector(nowPlayingItemChanged),
    name: .MPMusicPlayerControllerNowPlayingItemDidChange,
    object: nil)
```

As a result, whenever an `.MPMusicPlayerControllerNowPlayingItemDidChange` notification is posted, my `nowPlayingItemChanged` method will be called. Note that this method must be marked `@objc` so that Objective-C can see it (the Swift compiler will help out by ensuring this when you use `#selector` syntax):

```
@objc func nowPlayingItemChanged (_ n:Notification) {
    self.updateNowPlayingItem()
    // ... and so on ...
}
```

## Function-based registration

Heavy use of `addObserver(_:selector:name:object:)` means that your code ends up peppered with methods that exist solely in order to be called by the notification center. There is nothing about these methods that tells you what they are for — you may want to use explicit comments to remind yourself — and the methods are separate from the registration call, which can make your code rather confusing.

One way to solve that problem is to use the *other* way of registering to receive a notification, `addObserver(forName:object:queue:using:)`. The parameters are:

**name:**

**object:**

Just like `addObserver(_:selector:name:object:)`.

**queue:**

This is the `OperationQueue` on which your `using:` function will be called. It will usually be `nil`. (Explaining what a non-`nil` queue would mean is outside the scope of this book.)

**using:**

Instead of providing an observer and a selector, you provide as the `using:` parameter a *function*, typically an anonymous function, consisting of the actual code to be executed when the notification arrives. This function should take one parameter — the `Notification` itself. This is an escaping closure, so if it refers to `self` you will be careful not to form a retain cycle.

This method also *returns a value*, which is in fact the observer that has been registered with the notification center. I'll talk more about that in a moment.

The outcome is that your registration for a notification and your response when the notification arrives are encapsulated in a single call:



```
let ob = NotificationCenter.default.addObserver(
    forName: .MPMusicPlayerControllerNowPlayingItemDidChange,
    object: nil, queue: nil) { [unowned self] _ in
        self.updateNowPlayingItem()
        // ... and so on ...
    }
}
```

That can be a much cleaner way of dealing with notifications. Unfortunately, using `addObserver(forName:...)` correctly is a little more complicated than that, because you still need to unregister the observer, as I'll discuss in the next section.

## Unregistering

To unregister an object as a recipient of notifications, call the notification center's `removeObserver(_:)` method. Alternatively, you can unregister an object for just a specific set of notifications with `removeObserver(_:name:object:)`. The object passed as the first argument is the object that is no longer to receive notifications. What object that is depends on how you registered it in the first place:

*You called* `addObserver(_:selector:name:object:)`

You *supplied* an observer originally, as the first argument; that is the observer you will now unregister. This will typically be `self`.

*You called* `addObserver(forName:object:queue:using:)`

The call *returned* an observer token object typed as an `NSObjectProtocol` (its real class and nature are undocumented); that is the observer you will now unregister.

In the old days, if you failed to unregister an object as a notification recipient and that object went out of existence, your app would crash the next time the notification was sent — because the runtime was trying to send a message to an object that was now missing in action. But in iOS 9, Apple introduced a safety check. Nowadays, if the notification center tries to send a message to a nonexistent object, there is no crash, and the notification center helpfully unregisters the object for you.

What you need to do as you go out of existence depends, once again, on how you registered in the first place:

*You called* `addObserver(_:selector:name:object:)`

You probably don't need to unregister the object passed as the first argument. If that object goes out of existence, and if the notification is posted subsequently, there won't be any crash.

*You called* `addObserver(forName:object:queue:using:)`

You *do* need to unregister the observer, because otherwise the notification center *keeps it alive* and can continue to send notifications to it (which means that the attached function will continue to be called).

So the question now boils down to how you're going to unregister the observer returned by a call to `addObserver(forName:object:queue:using:)`. If you only need to receive a notification *once*, you can unregister from within the anonymous function that runs when the notification is received (because the observer is in scope within the anonymous function). Otherwise, you'll have to keep a separate persistent reference to the observer object so that you can unregister it later.

What's a good way to do that? Let's assume you're going to be calling `addObserver(forName:object:queue:using:)` many times from within the same class. Then you're going to end up receiving many observer tokens, and you'll need to preserve a reference to all of them. One obvious approach is to store the observers in an instance property that is a mutable collection. My favored approach is a `Set` property:

```
var observers = Set<NSObject>()
```

So now, each time I register for a notification by calling `addObserver(forName:object:queue:using:)`, I capture the result and add it to the set:

```
let ob = NotificationCenter.default.addObserver(
    forName: .MPMusicPlayerControllerNowPlayingItemDidChange,
    object: nil, queue: nil) { [unowned self] _ in
        self.updateNowPlayingItem()
        // ... and so on ...
    }
self.observers.insert(ob as! NSObject)
```

When it's time to unregister all observers, I enumerate the set and empty it:

```
for ob in self.observers {
    NotificationCenter.default.removeObserver(ob)
}
self.observers.removeAll()
```



It is *crucial* that you unregister all observer tokens by calling `removeObserver`, for reasons that I'll explain in [Chapter 13](#).

## Subscribing to a Notification

In recent versions of iOS, the notification registration process has been wrapped in an arguably cleaner and more modern architecture. The idea is that the notification center is regarded as publishing a stream of occasional notifications. You then *subscribe* to that stream. Instead of unregistering with the notification center, you cancel the subscription itself.

### Combine framework

The Combine framework was introduced in iOS 13. It is a “reactive” framework: there is a publisher that vends a stream of occasional values, and a subscriber that

receives those values. The publisher and the subscriber, together with any operators that process a value as it passes between the publisher and the subscriber, form a pipeline. You store the pipeline so that it persists; when you no longer need it, you cancel it or release it.

I'll say more about the Combine framework in [Chapter 14](#), plus I've written a complete online tutorial about it (<https://www.apeth.com/UnderstandingCombine>). Here, I'll just show the syntax, without further comment.

You'll need to `import Combine`. Your view controller (or other persistent object) will need an instance property to store the pipeline:

```
var pipeline : AnyCancellable?
```

To subscribe to a notification stream, you call the notification center's `publisher(for:)` method to get the publisher. From there, you construct the pipeline and store it so that it lives long enough to receive values:

```
self.pipeline = NotificationCenter.default.publisher(  
    for: .MPMusicPlayerControllerNowPlayingItemDidChange)  
    .sink { [unowned self] _ in  
        self.updateNowPlayingItem()  
        // ... and so on ...  
    }
```

To unregister explicitly, send the `cancel()` message to `self.pipeline`, or set it to `nil`, which releases it and causes it to cancel itself. But there may be no need to do that. The pipeline instance property will be released when its owner (`self`) goes out of existence; that, in turn, will cancel the pipeline, effectively unregistering automatically.

## Structured concurrency

Structured concurrency is new in Swift 5.5 ([Chapter 6](#)). To accompany this innovation, new in iOS 15, the notification center can vend its notifications as an asynchronous sequence.

To subscribe to the sequence, you call the notification center instance method `notifications(named:)`. That returns the asynchronous sequence. In a task, you can now loop through that sequence with an asynchronous `for` loop (or use any asynchronous sequence method). If you want to cancel the task later, you'll need to keep a reference to the task; I'll use an instance property:

```
var task : Task<(), Never>?
```

To subscribe to the sequence, I create the task and store it in that instance property:

```

let stream = NotificationCenter.default.notifications(
    named: .MPMusicPlayerControllerNowPlayingItemDidChange)
let task = Task {
    for await _ in stream {
        self.updateNowPlayingItem()
        // ... and so on ...
    }
}
self.task = task

```

To unregister, I cancel the task:

```
self.task?.cancel()
```

The cancellation of the task stops the stream, and the asynchronous for loop terminates; at this point we could set `self.task` to `nil`.

## Posting a Notification

Notifications can be a way of communicating between your own objects. You post a notification yourself (in one object) and receive it yourself (in another object). This is probably not a good way to compensate for a failure to devise proper lines of communication between objects, but it can be appropriate when the objects are conceptually distant or independent from one another, or when you need the flexibility of broadcasting to multiple recipients.

To post a notification, send `post(name:object:userInfo:)` to the notification center. For the `name:`, you'll have to coerce a string into a `Notification.Name`. There are two main places to do this:

### *In the name: argument*

You perform the coercion directly in the method call; for example, you might say `Notification.Name("someName")`. That's simple but error-prone: you'll need to perform the same coercion twice (to post the notification and to register to receive it), and the repeated string literal is an invitation to make a typing mistake and have things mysteriously go wrong.

### *As a globally available constant*

You define a namespaced constant beforehand, and use it both when posting the notification and when registering for it. This approach localizes the coercion in a single place; it's a little more work than the first approach, but it's more correct and you should use it.

For example, one of my apps is a simple card game. The game needs to know when a card is tapped. But a card knows nothing about the game; when it is tapped, it simply emits a virtual shriek by posting a notification. I've defined my notification name by extending my `Card` class:

```
extension Card {
    static let tappedNotification = Notification.Name("cardTapped")
}
```

When a card is tapped, it responds like this:

```
NotificationCenter.default.post(name: Self.tappedNotification, object: self)
```

The game object has registered for `Card.tappedNotification`, so it hears about this and retrieves the notification's object; now it knows what card was tapped and can proceed appropriately.



The notification center has no API for introspecting it in code, but you can introspect it while paused in the debugger; enter `po NotificationCenter.default` to see a list of registered notifications, with the name, object, recipient, and options for each. The object and recipient are listed as memory addresses, but you can learn more from such an address by entering `expr -l objc -O --` followed by the address.

## Timer

A Timer (Objective-C `NSTimer`) is not a notification, but it behaves quite similarly. It gives off a signal (*fires*) after the lapse of a certain time interval. Thus you can arrange to get an event when a certain time has elapsed. The timing is not perfectly accurate, nor is it intended to be, but it's good enough for most purposes.

A timer that is actively watching the clock is said to be *scheduled*. A timer may fire once, or it may be a *repeating* timer. To stop a timer, it must be *invalidated*. A timer that is set to fire once is invalidated automatically after it fires; a repeating timer repeats until *you* invalidate it by sending it the `invalidate` message. An invalidated timer should be regarded as dead: you cannot revive it or use it for anything further, and you should probably not send any messages to it.

For example, one of my apps is a game with a score; I want to penalize the user by diminishing the score for every ten seconds that elapses after each move without the user making a further move. So I create and schedule a repeating timer whose time interval is ten seconds. Whenever the timer fires, I diminish the score. Whenever the user moves, I invalidate the existing timer and start over with a new repeating timer.

The traditional way to create a timer is with a class factory method that returns a Timer object and also schedules the timer, so that it begins watching the clock immediately. There are two of them:

```
scheduledTimer(timeInterval:target:selector:userInfo:repeats:)
```

The `target:` and `selector:` determine what message will be sent to what object when the timer fires; the method in question should take one parameter, which

will be a reference to the timer. The `userInfo:` is just like the `userInfo:` of a notification.

`scheduledTimer(withTimeInterval:repeats:block:)`

The `block:` parameter is a function (usually an anonymous function) that you want called when the timer fires; the function should take one parameter, which will be a reference to the timer.

A repeating Timer is often assigned to an instance property, retaining the reference to it so that you can invalidate the timer later on. But do *not* call `scheduledTimer(timeInterval:target:selector:userInfo:repeats:)` directly as the initializer in your declaration of a Timer instance property, like this:

```
class ViewController : UIViewController {
    // bad idea!
    var timer = Timer.scheduledTimer(timeInterval: 1, target: self,
                                     selector: #selector(timerFired), userInfo: nil, repeats: true)
```

If the target is `self`, that won't work, because `self` doesn't exist yet at the time you're initializing the instance property. (In my opinion, Swift should warn you about this, and I regard its failure to do so as a bug.) Use deferred initialization instead ("**Deferred initialization of properties**" on page 130):

```
class ViewController: UIViewController {
    var timer : Timer!
    override func viewDidLoad() {
        super.viewDidLoad()
        self.timer = Timer.scheduledTimer(timeInterval: 1, target: self,
                                           selector: #selector(timerFired), userInfo: nil, repeats: true)
    }
}
```

In modern Swift, you might prefer to receive the signals from a repeating timer through a subscription. As with notifications, there are two ways:

### *Combine framework*

To obtain a Combine publisher that behaves as a repeating timer, call the Timer static method `publish(every:on:in:)`. This returns a publisher on which you can build your pipeline; the publisher emits Date objects at regular intervals.

Note that this publisher is a `ConnectablePublisher`, meaning that it doesn't start publishing until you tell it to connect. Alternatively, you can attach the `.autoconnect()` operator to it, to make it start publishing immediately.

In this example, we start the timer from a view controller's `viewDidLoad`:

```

var pipeline : AnyCancellable?
override func viewDidLoad() {
    super.viewDidLoad()
    self.pipeline = Timer.publish(every: 1, on: .main, in: .default)
        .autoconnect()
        .sink { print("timer fired at", $0) }
}

```

To stop the timer, send `cancel()` to the pipeline, or release it by setting `self.pipeline` to `nil`. This happens automatically when the view controller goes out of existence.

### *Structured concurrency*

A `Timer` has no method that produces an asynchronous sequence. But new in iOS 15, every Combine publisher has a `values` property that is an `AsyncStream`. So start with the `Timer` publisher I just described and fetch its `values`; that is the asynchronous sequence, and now you can loop through it. This is essentially the example I gave in [Chapter 6](#):

```

var task : Task<(), Never>?
override func viewDidLoad() {
    super.viewDidLoad()
    let timerpub = Timer.publish(every: 1, on: .main, in: .default)
        .autoconnect()
    self.task = Task {
        for await value in timerpub.values {
            print("timer fired at", value)
        }
    }
}

```

To stop the timer, send the `cancel()` message to `self.task`. At that point, you might also set `self.task` to `nil`.



Timers have some memory management implications that I'll be discussing in [Chapter 13](#).

## Delegation

*Delegation* is an object-oriented design pattern, a relationship between two objects in which a primary object's behavior is customized or assisted by a secondary object. The secondary object is the primary object's *delegate*. No subclassing is involved, and indeed the primary object is agnostic about the delegate's class.

The class of the primary object can be Cocoa's class or your class. As with notifications, you'll want to understand Cocoa's delegation pattern because it's an important

way of getting events from Cocoa; plus, you might want to implement the pattern yourself as a useful way of communicating between your own objects.

## Cocoa Delegation

As implemented by Cocoa, here's how delegation works:

1. A built-in Cocoa class has an instance property, usually called `delegate` (it will certainly have `delegate` in its name).
2. The Cocoa class promises that at certain moments it will turn to its delegate for instructions by sending it a certain message.
3. One of those moments arrives! If the Cocoa instance finds that its delegate is not `nil`, and that its delegate is prepared to receive that message, the Cocoa instance sends the message to the delegate.

Delegation is one of Cocoa's main uses of protocols ([Chapter 11](#)). In the old days, delegate methods were listed in the Cocoa class's documentation, and their names were made known to the compiler through an informal protocol (a category on `NSObject`). Nowadays, a class's delegate methods are usually listed in a genuine protocol with its own documentation. There are over 70 Cocoa delegate protocols; that shows how heavily Cocoa relies on delegation. Most delegate methods are optional, but in a few cases you'll discover some that are required.

To take advantage of Cocoa delegation, you'll have one of *your* classes adopt a Cocoa delegate protocol, and you'll set some Cocoa object's `delegate` (typed as that protocol) to an instance of your class. You might form the connection in code; alternatively, you might do it in a nib by connecting an object's `delegate` outlet to an appropriate object within the nib. Now *you* are the delegate, and you get to help determine the Cocoa object's behavior.

Your delegate class will probably do other things besides serving as this instance's delegate. Indeed, one of the nice things about delegation is that it leaves you free to slot delegate code into your class architecture however you like; the delegate type is a protocol, so the actual delegate can be an instance of *any* class.

Here's a typical example. I want to ensure that my app's root view controller, a `UINavigationController`, should appear only in portrait orientation when this view controller is in charge. But `UINavigationController` isn't my class; my class is a *different* view controller, a `UIViewController` subclass, which acts as the `UINavigationController`'s child. How can the child tell the parent how to rotate?

Delegation to the rescue! `UINavigationController` has a `delegate` property, typed as `UINavigationControllerDelegate` (a protocol). It promises to send this delegate the `navigationControllerSupportedInterfaceOrientations(_:)` message when it needs to know how to rotate. So my view controller, very early in its lifetime, sets



itself as the UINavigationController’s delegate. It also implements the navigationControllerSupportedInterfaceOrientations( \_: ) method. Presto, the problem is solved:

```
class ViewController : UIViewController, UINavigationControllerDelegate {
    override func viewDidLoad() {
        super.viewDidLoad()
        self.navigationController?.delegate = self
    }
    func navigationControllerSupportedInterfaceOrientations(
        _ nav: UINavigationController) -> UIInterfaceOrientationMask {
        return .portrait
    }
}
```

When you’re searching the documentation for how you can be notified of a certain event, be sure to consult the corresponding delegate protocol, if there is one. Suppose you’d like to know when the user taps in a UITextField to start editing it. You won’t find anything relevant in the UITextField class documentation; what you’re after is textFieldDidBeginEditing( \_: ) in the UITextFieldDelegate protocol.



You might be tempted to try to *inject* a method into a class that adopts a Cocoa delegate protocol by extending the protocol and implementing the delegate method *in the protocol extension*. That isn’t going to work, because Objective-C can’t *see* Swift protocol extensions (see the [Appendix](#))! You can call such a method from Swift, but Cocoa is *never* going to call it, because it doesn’t know that the method implementation exists.

## Implementing Delegation

The Cocoa protocol-and-delegate pattern is very useful, and you’ll probably want to adopt it in your own code. Setting up the pattern takes some practice, and can be a little time-consuming. But it’s a clean solution to the problem of apportioning knowledge and responsibilities among your objects. I’ll demonstrate with an example from one of my apps.

The app declares a view controller, a UIViewController subclass called ColorPickerController; its view contains three sliders that the user can move to choose a color. Some other view controller will create and present the ColorPickerController instance, displaying its view. When the user taps Done or Cancel, the view should be dismissed and the ColorPickerController instance can go out of existence; but first, I need to send a message from the ColorPickerController instance *back to the view controller that presented it*, reporting what color the user chose.

Here’s the declaration for the message that I want the ColorPickerController to send before it goes out of existence:

```
func colorPicker(_ picker:ColorPickerController,
                didSetColorNamed theName:String?,
                to theColor:UIColor?)
```

The question is: where and how should this method be declared?

Now, it happens that in my app I know the class of the instance that will in fact present the `ColorPickerController`: it is a `SettingsController`. So I could simply declare this method in `SettingsController` and stop. But that would mean that the `ColorPickerController`, in order to send this message to the `SettingsController`, must *know* that the instance that presented it *is* a `SettingsController`. That's wrong. Surely it is a mere *contingent* fact that the instance being sent this message is a `SettingsController`; it should be open to *any* class to present and dismiss a `ColorPickerController`.

Therefore we want `ColorPickerController` *itself* to declare the method that *it itself* is going to call; and we want it to send that message blindly to some receiver, without regard to the class of that receiver. That's what a protocol is for!

The solution, then, is for `ColorPickerController` to define a protocol, with this method as part of that protocol, and for the class that presents a `ColorPickerController` to conform to that protocol. `ColorPickerController` will also need an appropriately typed `delegate` instance property; this provides the channel of communication, and tells the compiler that sending this message is legal:

```
protocol ColorPickerDelegate : AnyObject {
    func colorPicker(_ picker:ColorPickerController,
                    didSetColorNamed theName:String?,
                    to theColor:UIColor?)
}
class ColorPickerController : UIViewController {
    weak var delegate: ColorPickerDelegate?
    // ...
}
```

(For the weak attribute and the `AnyObject` designation, see [Chapter 5](#).) When my `SettingsController` instance creates and configures and presents a `ColorPickerController` instance, it also sets itself as that `ColorPickerController`'s `delegate` — which it can do, because it adopts the protocol:

```
extension SettingsController : ColorPickerDelegate {
    func showColorPicker() {
        let colorName = // ...
        let c = // ...
        let cpc = ColorPickerController(colorName:colorName, color:c)
        cpc.delegate = self // *
        self.present(cpc, animated: true)
    }
    func colorPicker(_ picker:ColorPickerController,
                    didSetColorNamed theName:String?,
```

```

        to theColor:UIColor?) {
            // ...
        }
    }
}

```

When the user picks a color, the `ColorPickerController` *knows* to whom it should send `colorPicker(_:didSetColorNamed:to:)` — namely, its delegate! And the compiler allows this, because the delegate has adopted the `ColorPickerDelegate` protocol:

```

@IBAction func dismissColorPicker(_ sender : Any?) { // user tapped Done
    let c : UIColor? = self.color
    self.delegate?.colorPicker(self, didSetColorNamed: self.colorName, to: c)
}

```

## Data Sources

A *data source* is like a delegate, except that its methods supply the data for another object to display. The chief Cocoa classes with data sources are `UITableView`, `UICollectionView`, `UIPickerView`, and `UIPageViewController`. In each case, the data source must formally adopt a data source protocol with required methods.

It comes as a surprise to some beginners that a data source is necessary at all. Why isn't a table's data just a property of the table? The reason is that such an architecture would violate generality. A view displays data; the structure and management of that data is a separate matter, and is up to the data source. The only requirement is that the data source must be able to supply information quickly, because it will be asked for it in real time when the data needs displaying.

Another surprise is that the data source is different from the delegate. But this again is only for generality; it's an option, not a requirement. There is no reason why the data source and the delegate should not be the same object, and most of the time they probably will be.

In this example from one of my apps, I implement a `UIPickerView` that allows the user to configure a game by saying how many stages it should consist of (“1 Stage,” “2 Stages,” and so on). The first two methods are `UIPickerView` data source methods; the third method is a `UIPickerView` delegate method. It takes all three methods to supply the picker view's content:

```

extension NewGameController: UIPickerViewDataSource, UIPickerViewDelegate {
    func numberOfComponents(in pickerView: UIPickerView) -> Int {
        return 1
    }
    func pickerView(_ pickerView: UIPickerView,
        numberOfRowsInComponent component: Int) -> Int {
        return 9
    }
    func pickerView(_ pickerView: UIPickerView,

```

```

        titleForRow row: Int, forComponent component: Int) -> String? {
            return "\(row+1) Stage" + ( row > 0 ? "s" : "")
        }
    }
}

```

## Actions

An *action* is a message emitted by an instance of a UIControl subclass (a *control*) reporting a significant user event taking place in that control. The UIControl subclasses are all simple interface objects that the user can interact with directly, such as a button (UIButton) or a segmented control (UISegmentedControl).

The significant user events (*control events*) are listed under UIControl.Event in the Constants section of the UIControl class documentation. Different controls implement different control events: a segmented control's Value Changed event signifies that the user has tapped a segment, but a button's Touch Up Inside event signifies that the user has tapped the button. Of itself, a control event has no external effect; the control responds visually (a tapped button looks tapped), but it doesn't automatically share the information that the event has taken place. If you want to know when a control event takes place, so that you can respond to it in your code, *you* must arrange for that control event to trigger an *action message*.

Here's how it works. A control maintains an internal dispatch table: for each control event, there can be any number of target-action pairs, in each of which the *action* is a selector designating the name of a method, and the *target* is an object on which that method is to be called. When a control event occurs, the control consults its dispatch table, finds all the target-action pairs associated with that control event, and sends each action message to the corresponding target (Figure 12-1).

There are two ways to manipulate a control's action dispatch table:

### Action connection

You can configure an action connection in a nib. I described in [Chapter 8](#) how to do this, but I didn't completely explain the underlying mechanism. Now all is revealed: an action connection formed in the nib editor is a visual way of configuring a control's action dispatch table.

### Code

Your code can directly configure the control's action dispatch table. The key method here is the UIControl instance method `addTarget(_:action:for:)`, where the `target:` is an object, the `action:` is a selector, and the `for:` parameter is a UIControl.Event bitmask ("[Option sets](#)" on page 261).

Recall the example of a control and its action from [Chapter 8](#). We have a button-Pressed(\_:) method:




Figure 12-1. The target-action architecture

```
@IBAction func buttonPressed(_ sender: Any) {
    let alert = UIAlertController(
        title: "Howdy!", message: "You tapped me!", preferredStyle: .alert)
    alert.addAction(
        UIAlertAction(title: "OK", style: .cancel))
    self.present(alert, animated: true)
}
```

That sort of method is an *action handler*. Its purpose is to be called when the user taps a certain button in the interface. In [Chapter 8](#), we arranged for that to happen by setting up an action connection in the nib: we connected the button's Touch Up Inside event to the ViewController `buttonPressed(_:)` method. In reality, we were forming a target-action pair and adding that target-action pair to the button's dispatch table for the Touch Up Inside control event.

Instead of making that arrangement in the nib, we could have done the same thing in code. Suppose we had *never* drawn that action connection. And suppose that, instead, we have an outlet connection from the view controller to the button, called

`self.button`. Then the view controller, after the nib loads, can configure the button's dispatch table like this:

```
self.button.addTarget(self,
    action: #selector(buttonPressed),
    for: .touchUpInside)
```

The signature for the action handler method can be in any of three forms:

- The fullest form takes two parameters:
  - The control.
  - The `UIEvent` that generated the control event. This will rarely be needed. (I'll talk more about `UIEvents` in the next section.)
- A shorter form, the one most commonly used, omits the second parameter. `buttonPressed(_:)` is an example; it takes one parameter. When `buttonPressed(_:)` is called through an action message emanating from the button, its parameter will be a reference to the button.
- There is a still shorter form that omits both parameters.

Curiously, none of the action method parameters provide any way to learn *which* control event triggered the sending of this action message! To distinguish a Touch Up Inside control event from a Touch Up Outside control event, their corresponding target–action pairs must specify two different action handlers; if you dispatch them to the same action handler, that handler cannot discover which control event occurred.

Starting in iOS 14, a `UIControl`'s target and action can be expressed by attaching to the `UIControl` itself a `UIAction` instance encapsulating the action as a function — probably an anonymous function. The parameter to the action function is the `UIAction`; its sender property is the `UIControl`. In this way, there is no explicit target and no separate action method; the action method is effectively sent to and handled by the `UIControl` itself. This is a very nice notation, but behind the scenes it is still the target–action architecture.

In this example, `self` is the view controller and `myButton` is an outlet to a button in the interface:

```
let action = UIAction { [unowned self] _ in
    let alert = UIAlertController(
        title: "Howdy!", message: "You tapped me!", preferredStyle: .alert)
    alert.addAction(
        UIAlertAction(title: "OK", style: .cancel))
    self.present(alert, animated: true)
}
self.myButton.addAction(action, for: .touchUpInside)
```



A control event can have multiple target–action pairs. You might configure it this way intentionally, but it is also possible to do so accidentally. Unintentionally giving a control event a target–action pair without removing its *existing* target–action pair is an easy mistake to make, and can cause some very mysterious behavior. If you form an action connection in the nib *and* configure the dispatch table in code, a tap on the button will cause the action handler method to be called *twice*, and you will be completely mystified for several hours. (Ask me how I know *that*.)

## The Responder Chain

Whenever the user does something with a finger (sets it down on the screen, moves it, raises it from the screen), a touch object (UITouch) is used to represent that finger. UIEvents are the lowest-level objects charged with communication of touch objects to your app; a UIEvent is basically a timestamp (a Double) along with a collection (Set) of touch objects. As I said in the previous section, you can receive a UIEvent along with a control event, but you will rarely need to do so.

A *responder* is an object that knows how to receive UIEvents directly. It is an instance of UIResponder or a UIResponder subclass. If you examine the Cocoa class hierarchy, you'll find that just about any class that has anything to do with display on the screen is a responder. A UIView is a responder. A UIWindow is a responder. A UIViewController is a responder. Even a UIApplication is a responder. Even the app delegate is a responder!

A UIResponder has four low-level methods for receiving touch-related UIEvents:

- touchesBegan(\_:with:)
- touchesMoved(\_:with:)
- touchesEnded(\_:with:)
- touchesCancelled(\_:with:)

These methods — the *touch methods* — are called to notify a responder that a touch event has occurred: the user has placed, moved, or lifted a finger from the screen. No matter how your code ultimately hears about a user-related touch event — indeed, even if your code *never* hears about a touch event directly — the touch was initially communicated to a responder through one of the touch methods.

The mechanism for this communication starts by deciding which responder the user touched. The UIView methods hitTest(\_:with:) and point(inside:with:) are called until the correct view (the *hit-test view*) is located. Then UIApplication's sendEvent(\_:with:) method is called, which calls UIWindow's sendEvent(\_:with:), which now wants to call the correct touch method in some responder.

So now the runtime starts looking for a responder that *implements* the correct touch method, so that the touch event can be reported by calling it. That responder need not be the hit-test view! The hit-test view is just the starting place for the search. The search depends upon the fact that your app’s responders participate in a *responder chain*, which essentially links them up through the view hierarchy.

The responder chain, from bottom to top, looks roughly like this:

1. The UIView that we start with (here, the hit-test view).
2. If this UIView is a UIViewController’s view, the UIViewController.
3. The UIView’s superview.
4. Go back to step 2 and repeat! Keep repeating until we reach...
5. The UIWindow.
6. The UIWindowScene.
7. The UIApplication.
8. The UIApplication’s delegate.

The next responder up the responder chain is a responder’s *next responder*, which is obtained from a responder through its `next` property (which returns an Optional wrapping a `UIResponder`). Thus the responder chain can be walked upward from any responder to the top of the chain. To help you explore the responder chain, here’s how to configure a button with an action method that walks the chain and logs the identity of each responder:

```
let action = UIAction { action in
    if var resp = action.sender as? UIResponder {
        while let r = resp.next {
            print(r); resp = r
        }
    }
}
self.myButton.addAction(action, for: .touchUpInside)
```

## Nil-Targeted Actions

A *nil-targeted* action is a UIControl target–action pair in which the target is `nil`. There is no designated target object, so the following rule is used: starting with the hit-test view (the view with which the user is interacting), Cocoa walks up the responder chain looking for an object that can respond to the action message:

- If a responder is found that handles this message, that method is called on that responder, and that’s the end.



- If we get all the way to the top of the responder chain without finding a responder to handle this message, nothing happens; the message goes unhandled, with no penalty.

Here's a UIButton subclass that configures itself to call a nil-targeted action when tapped:

```
override func awakeFromNib() {
    super.awakeFromNib()
    class Dummy {
        @objc func buttonPressed(_:Any) {}
    }
    self.addTarget(nil, // nil-targeted
        action: #selector(Dummy.buttonPressed),
        for: .touchUpInside)
}
```

That's a nil-targeted action. So what happens when the user taps the button? First, Cocoa looks in the UIButton itself to see whether it responds to `buttonPressed`. If not, it looks in the UIView that is its superview. And so on, up the responder chain. If a responder is found that implements the `buttonPressed` method, that method is called.



The declaration for your action handler method (such as `buttonPressed`) must be marked `@objc` (or `@IBAction`). Otherwise, Cocoa won't be able to find it as it walks up the responder chain.

It's obvious how to construct a nil-targeted action in code: you set up a target-action pair where the target is `nil`, as in the preceding example. But how do you construct a nil-targeted action in a nib? The answer is: you form a connection to the First Responder proxy object. That's what the First Responder proxy object is for! The First Responder isn't a real object with a known class, so before you can connect an action to it, you have to define the action message within the First Responder proxy object, like this:

1. In the nib editor, select the First Responder proxy and switch to the Attributes inspector.
2. You'll see a table (probably empty) of user-defined nil-targeted First Responder actions. Click the Plus button and give the new action a name. This name is an Objective-C selector, and it must end with a colon, indicating a method that takes one parameter (see the [Appendix](#)).
3. Now you can Control-drag from a control, such as a UIButton, to the First Responder proxy to specify a nil-targeted action with the name you specified.

# Key–Value Observing

Key–value observing, or *KVO*, is rather like a target–action mechanism that works between *any* two objects. One object (the observer) registers directly with another object (the observed) so as to be notified *when a value in the observed object changes*. The observed object doesn’t actually have to *do* anything; when the value in the observed object changes, the observer is *automatically* notified.

The process of using KVO may be broken down into stages:

## *Registration*

The observer — that is, the object that desires to hear about future changes in a value belonging to the observed object — must register with that observed object.

## *Change*

A change takes place in the value belonging to the observed object, and it must take place in a special way — a KVO compliant way. Typically, this means using a key–value coding compliant accessor to make the change. Setting a property passes through a key–value coding compliant accessor.

## *Notification*

The observer is automatically notified that the value in the observed object has changed.

## *Unregistration*

The observer eventually unregisters to prevent the arrival of further notifications about the observed value of the observed object.

As with notifications and delegation, you can use KVO with Cocoa objects or you can implement it as a form of communication between your own objects. When you use KVO with Cocoa:

- The observer will be *your* object; you will write the code that will respond when the observer is notified of the change for which it has registered.
- The observed object will be *Cocoa’s* object. Many Cocoa objects promise to behave in a KVO compliant way. Certain frameworks, such as the AVFoundation framework, don’t implement delegation or notifications very much; instead, they expect you to use KVO to hear about what they are doing. Thus, KVO can be an important form of Cocoa event.

When you use KVO with your own observed object, you have to configure that object to be KVO compliant for one or more values. I’ll explain later how to do that.

## Registration and Notification

There are two different ways to configure KVO registration and notification. The first way is the Cocoa way; it basically just translates the Objective-C API directly into Swift. The second way is provided by Swift; it uses the Cocoa way under the hood, but it shields you from some of the messy details.

I'll first describe the Cocoa way, just so that you understand the mess that the Swift way shields you from:

1. In the Cocoa way, you call `addObserver(_:forKeyPath:options:context:)` on the object whose property you want to observe, using a Cocoa key path ([Chapter 11](#)).
2. Subsequently, the observer's `observeValue(forKeyPath:of:change:context:)` is called for every change for which this observer has been registered.

There are two problems here. First, step 1 and step 2 happen in two different places; there's a disconnect between the two steps. And second, this observer might be observing more than one property, possibly in more than one observed object, so there can be many repetitions of step 1; but no matter how many times step 1 happens, *there is only one step 2*. There is just one single observer method, through which all observation calls must flow — which constitutes a nasty bottleneck. That's what the Swift way protects you from.

Here's how the Swift way works. You register by calling `observe(_:options:changeHandler:)` on the object whose property you want to observe, with these parameters:

**keyPath:**

The first parameter is a Swift key path ([Chapter 5](#)), not a Cocoa key path.

**options:**

An `NSKeyValueObservingOptions` bitmask (an option set) specifying such things as when you want to be notified (only when the observed value changes, or now as well) and what information you want included in the notification (the old value, the new value, or both).

**changeHandler:**

A function to be called as a way of sending the notification. It will typically be an anonymous function. It should take two parameters:

*The object*

This will be the observed object with which we are registered.

### *The change*

An `NSKeyValueObservedChange` object. Its properties give you information such as the old value and the new value if you requested them in the `options:` argument.

The call to `observe(_:options:changeHandler:)` also returns a value, an `NSKeyValueObservation` instance. *That* is the registered observer.

The Swift key-value observing API is a *language* feature, not an SDK feature. It puts a convenient mechanism in front of the Cocoa API, but it still *uses* the Cocoa API. When you call `observe(_:options:changeHandler:)`, Swift in turn calls `addObserver(_:forKeyPath:options:context:)` to register the observer with the observed object. And the `NSKeyValueObservation` object implements the bottleneck method `observeValue(forKeyPath:of:change:context:)` to receive notification messages, which it passes on to you.

## Unregistering

Unregistration is performed through a message to the observed object, namely `removeObserver(_:forKeyPath:context:)`. If the observer goes out of existence without unregistering, the observed object might later try to send a message to a non-existent observer, resulting in a crash. So the observer needs to maintain a reference to the observed object and, at the latest, must unregister itself when going out of existence.

That can be a daunting responsibility — and is yet another thing that the Swift API helps you with. The `NSKeyValueObservation` object returned from the call to `observe(_:options:changeHandler:)` maintains a reference to the observed object, so you don't have to; and it will unregister itself, by calling `removeObserver(_:forKeyPath:context:)` on the observed object, either if you send it the `invalidate` message or *automatically* when it itself is about to go out of existence.

Your job is to capture the `NSKeyValueObservation` object and maintain it, probably in an instance property of the observer. That's all, because this means it will go out of existence, at the latest, when the observer does — and at that moment will unregister itself in good order. But you *must* capture and maintain that object somehow! If you don't, it will go out of existence and unregister itself *immediately* — before a notification is ever sent — and you'll never get any notifications in the first place.

Another problem is what happens if *the observed object* goes out of existence when observers are still registered on it. There are two cases:

### *In iOS 10 and before*

Your app will crash immediately. To prevent that, if the observed object is about to go out of existence while the observer continues to exist, you must unregister

the `NSKeyValueObservation` object explicitly, yourself, by sending it the `invalidate` message.

*In iOS 11 and later*

There are no bad consequences. There is no crash, and the `NSKeyValueObservation` object sends itself the `invalidate` message.

## Key–Value Observing Example

To demonstrate KVO, I'll declare classes to play both roles, the observer and the observed.

First, the observed. My `Observed` class has a `value` instance property that we want other objects to be able to observe:

```
class Observed : NSObject { ❶
    @objc dynamic var value : Bool = false ❷
}
```

- ❶ The observed object's class must derive from `NSObject`; otherwise, you won't be able to call `observe(_:options:changeHandler:)` on it. That's because the mechanism for being observed is a feature of `NSObject`.
- ❷ The property to be observed must be declared `@objc` in order to expose it to Objective-C — and it must also be declared `dynamic`. That's because KVO works by *swizzling* the accessor methods; Cocoa needs to be able to reach right in and change this object's code, and it can't do that unless the property is `dynamic`.

The `Observer` class contains code that registers with an `Observed` to hear about changes in its `value` property:

```
class Observer {
    var obs = Set<NSKeyValueObservation>() ❶
    func register(with observed:Observed) {
        let opts : NSKeyValueObservingOptions = [.old, .new]
        let ob = observed.observe(\.value, options:opts) { obj, change in ❷
            if let oldValue = change.oldValue {
                print("old value was \(oldValue)")
            }
            if let newValue = change.newValue {
                print("new value is \(newValue)")
            }
        }
        self.obs.insert(ob) ❸
    }
}
```

- ❶ Observer has an instance property for maintaining `NSKeyValueObservation` objects. As with Notification observer tokens (discussed earlier in this chapter), I like to use a `Set` for this purpose.
- ❷ Observer (in its `register(with:)` method) will register with an `Observed` instance by calling `observe(_:options:changeHandler:)`, using a Swift key path to specify the value property. I've illustrated the use of `NSKeyValueObservingOptions` by asking for both the old and new values of the observed property when a notification arrives. That information will arrive into the notification function inside an `NSKeyValueObservedChange` object.
- ❸ The call to `observe(_:options:changeHandler:)` returns an `NSKeyValueObservation` object. It is *crucial* to ensure the continued existence of this object; otherwise, it will go out of existence and unregister itself before the notification can ever arrive. Therefore, I immediately store it in the `Set` instance property that was declared for this purpose.

Presume now that we have a persistent `Observer` instance, `observer`, and that its `register(with:)` has been called with argument `observed`, an `Observed` instance that is also persistent:

```
observer.register(with: observed)
```

So much for registration!

Now let's talk about change and notification. Somehow, someone sets `observed`'s value property to `true`. That changes it in a KVO compliant way. So, at that moment, the notification is sent and the anonymous function is called! The following appears in the console:

```
old value was false
new value is true
```

Finally, let's talk about unregistering. As long as we are running in iOS 11 or later, there is nothing to talk about! It doesn't matter whether `observed` or `observer` goes out of existence first; everything happens automatically and in good order:

- If `observed` goes out of existence first, there is no crash and there will be no further notifications.
- When `observer` goes out of existence, the `obs` property is destroyed, and so the `NSKeyValueObservation` object is destroyed — and at that moment, if `observed` still exists, the `NSKeyValueObservation` object unregisters itself (and if `observed` no longer exists, nothing bad happens).

In general your real-life use of KVO in programming iOS will likely be as simple as that. Cocoa key-value observing, however, is a deep and complex mechanism;

consult Apple’s *Key-Value Observing Programming Guide* in the documentation archive for full information.

## Swamped by Events

Cocoa has the potential to send *lots* of events, telling you what the user has done, informing you of each stage in the lifetime of your app and its objects, asking for your input on how to proceed. To receive the events that you need to hear about, your code is peppered with *entry points* — methods that you have written with just the right name and in just the right class so that they can be called as Cocoa events. In fact, it is easy to imagine that in many cases your code for a class will consist almost entirely of entry points.

Arranging all those entry points is one of your primary challenges as a Cocoa programmer. You know what you want to do, but you don’t get to “just do it.” You have to divide up your app’s functionality and allocate it in accordance with when and how Cocoa is going to call into your code. You know the events that Cocoa is going to want to send you, and you need to be prepared to receive them. Before you’ve written a single line of your own code, the skeleton structure of a class is likely to have been largely mapped out for you.

Suppose that your iPhone app presents an interface consisting of a table view. You’ll probably subclass `UITableViewController` (a built-in `UIViewController` subclass); an instance of that subclass will own and control the table view, and you’ll probably use it as the table view’s data source and delegate as well. In this single class, then, you’re likely to want to implement *at a minimum* the following methods:

`init(coder:) or init(nibName:bundle:)`

`UIViewController` lifetime method, where you perform instance initializations.

`viewDidLoad`

`UIViewController` lifetime method, where you perform view-related initializations and deferred initializations.

`viewDidAppear`

`UIViewController` lifetime method, where you set up states that need to apply only while your view is onscreen. If you’re going to register for a notification or set up a timer, this is a likely place to do it.

`viewDidDisappear`

`UIViewController` lifetime method, where you reverse what you did in `viewDidAppear`. This would be a likely place to unregister for a notification or invalidate a repeating timer that you set up in `viewDidAppear`.

`supportedInterfaceOrientations`

UIViewController query method, where you specify what device orientations are allowed for this view controller's main view.

`numberOfSections(in:)`

`tableView(_:numberOfRowsInSection:)`

`tableView(_:cellForRowAt:)`

UITableView data source query methods, where you specify the contents of the table.

`tableView(_:didSelectRowAt:)`

UITableView delegate user action method, where you respond when the user taps a row of the table.

`deinit`

Swift class instance lifetime method, where you perform end-of-life cleanup.

Suppose, further, that you do in fact use `viewDidAppear` to register for a notification and to set up a timer, using the target-selector architecture; then you must also implement the methods specified by those selectors.

We already have, then, about a dozen methods whose presence is effectively boilerplate. These are not *your* methods; *you* are never going to call them. They are *Cocoa's* methods, which you have placed here so that each can be called at the appropriate moment in the life story of your app.

A Cocoa program consists of numerous disconnected entry points, each with its own meaning, each called at its own set moment. The logic of such a program is far from obvious; a Cocoa program, even *your* program, even while you're writing it, is hard to read and hard to understand. To figure out what our hypothetical class does, you have to know *already* such things as when `viewDidAppear` is called and how it is typically used; otherwise, you don't know what this method is for. Moreover, because of your code's object-oriented structure, multiple methods in this class (and perhaps others) will be managing the same instance properties; your program's logic is divided between methods and even across different classes.

Your challenges are compounded by surprises involving the *order* of events. Beginners (and even experienced programmers) are often mystified when their program doesn't work as expected, because they have wrong expectations about *when* an entry point will be called, or what the state of an instance will be when it *is* called. To make matters worse, the order of events isn't even reliable; my apps often break when I upgrade them from one iOS version to the next, because the new version of iOS is sending certain events in a different order from the old version.

How will you find your way through the swamp of events that a Cocoa program consists of? There's no easy solution, but here's some simple advice:



### Write comments

Comment every method, quite heavily if need be, saying what that method does and under what circumstances you expect it to be called — especially if it is an entry point, where it is Cocoa itself that will do the calling.

### Debug

Instrument your code heavily during development with caveman debugging (see [Chapter 10](#)). As you test your code, keep an eye on the console output and check whether the messages make sense. You may be surprised at what you discover. If things don't work as expected, add breakpoints and run the app again so you can see the order of execution and watch the variables and properties as they change.

Perhaps the most common kind of mistake in writing a Cocoa app is not that there's a bug in your code itself, but that you've put the code *in the wrong place*. Your code isn't running, or it's running at the wrong time, or the pieces are running in the wrong order. I see questions about this sort of thing all the time on the various online user forums (these are all actual examples that appeared over the course of just two days):

- *There's a delay between the time when my view appears and when my button takes on its correct title.*

That's because you put the code that sets the button's title in `viewDidAppear`. That's *too late*; your code needs to run earlier, perhaps in `viewWillAppear`.

- *My subviews are positioned in code and they're turning out all wrong.*

That's because you put the code that positions your subviews in `viewDidLoad`. That's *too early*; your code needs to run later, when your view's dimensions have been determined.

- *My view is rotating even though my view controller's `supportedInterfaceOrientations` says not to.*

That's because you implemented `supportedInterfaceOrientations` in the *wrong class*. Only the topmost view controller in the view controller hierarchy is consulted through this property.

- *I set up an action connection for `ValueChanged` on a text field, but my code isn't being called when the user edits.*

That's because you connected the *wrong control event*; a text field emits `EditingChanged`, not `ValueChanged`.

## Delayed Performance

Your code is executed in response to some event; but your code in turn may trigger a new event or chain of events. Sometimes this causes bad things to happen: there

might be a crash, or Cocoa might appear not to have done what you said to do. To solve this problem, perhaps you just need to step outside Cocoa’s own chain of events for a moment and wait for everything to settle down before proceeding.

The technique for doing this is called *delayed performance*. You tell Cocoa to do something, not right this moment, but in a little while, when things *have* settled down. Perhaps you need only a very short delay, just to let Cocoa finish doing something, such as laying out the interface. Technically, you’re allowing the current run loop to finish, completing and unwinding the entire current call stack, before proceeding further with your own code.

When you program Cocoa, you’re likely to be using delayed performance a lot more than you might expect. With experience, you’ll develop a kind of sixth sense for when delayed performance might be the solution to your difficulties.

Traditionally, the main way to get delayed performance has been by calling `DispatchQueue’s after(when:execute:)` method. It takes an asynchronous function stating what should happen after the specified time has passed. Here’s a utility function that encapsulates the call:

```
func delay(_ delay:Double, closure:@escaping () -> ()) {
    let when = DispatchTime.now() + delay
    DispatchQueue.main.asyncAfter(deadline: when, execute: closure)
}
```

In this example from one of my own apps, the user has tapped a row of a table, and my code responds by creating and showing a new view controller:

```
override func tableView(_ tableView: UITableView,
    didSelectRowAt indexPath: IndexPath) {
    let t = TracksViewController(
        mediaItemCollection: self.albums[indexPath.row])
    self.navigationController?.pushViewController(t, animated: true)
}
```

Unfortunately, the innocent-looking call to my `TracksViewController` initializer `init(mediaItemCollection:)` can take a moment to complete, so the app comes to a stop with the table row highlighted — very briefly, but just long enough to startle the user. To cover this delay with a sense of activity, I’ve rigged my `UITableViewCell` subclass to show a spinning activity indicator when it’s selected:

```
override func setSelected(_ selected: Bool, animated: Bool) {
    if selected {
        self.activityIndicator.startAnimating()
    } else {
        self.activityIndicator.stopAnimating()
    }
    super.setSelected(selected, animated: animated)
}
```

But there's a problem: the spinning activity indicator never appears and never spins. The reason is that the events are stumbling over one another here. `UITableViewCell`'s `setSelected(_:animated:)` isn't called until the `UITableView` delegate method `tableView(_:didSelectRowAt:)` has finished. But the delay we're trying to paper over is *during* `tableView(_:didSelectRowAt:)`; the whole problem is that it *doesn't* finish fast enough.

Delayed performance to the rescue! I'll rewrite `tableView(_:didSelectRowAt:)` so that it finishes immediately — triggering `setSelected(_:animated:)` immediately and causing the activity indicator to appear and spin — and I'll use delayed performance to call `init(mediaItemCollection:)` later on, when the interface has ironed itself out:

```
override func tableView(_ tableView: UITableView,
    didSelectRowAt indexPath: IndexPath) {
    delay(0.1) {
        let t = TracksViewController(
            mediaItemCollection: self.albums[indexPath.row])
        self.navigationController?.pushViewController(t, animated: true)
    }
}
```

New in Swift 5.5, you could use the `Task` `sleep` static method ([Chapter 6](#)) instead of `DispatchQueue`. If you are already in a task, you *should* use it; `DispatchQueues` do not interface well with structured concurrency. If you're not already in a task, you'll have to make one; but that's no worse than making an asynchronous function. Here's a rewrite using my extension of the `Task` static `sleep` method:

```
override func tableView(_ tableView: UITableView,
    didSelectRowAt indexPath: IndexPath) {
    Task {
        await Task.sleep(0.1)
        let t = TracksViewController(
            mediaItemCollection: self.albums[indexPath.row])
        self.navigationController?.pushViewController(t, animated: true)
    }
}
```

The task operation runs on the main thread, which is just what we want.



---

# Memory Management

Classes, both in Swift and in Objective-C, are *reference types* (see “[Value Types and Reference Types](#)” on page 157). Behind the scenes, Swift and Objective-C memory management for reference types works essentially the same way. Such memory management, as I pointed out in [Chapter 5](#), can be a tricky business.

Fortunately, Swift uses ARC (automatic reference counting), so you don’t have to manage the memory for every reference type object explicitly and individually, as was once necessary in Objective-C. Thanks to ARC, you are far less likely to make a memory management mistake, and more of your time is liberated to concentrate on what your app actually does instead of dealing with memory management concerns.

Still, even in Swift, and even with ARC, it is possible to make a memory management mistake, or to be caught unawares by Cocoa’s memory management behavior. A memory management mistake can lead to runaway excessive memory usage, crashes, or mysterious misbehavior of your app. Cocoa memory management can be surprising in individual cases, and can mislead you into making a memory management mistake; so you need to understand, and prepare for, what Cocoa is going to do.

## Principles of Cocoa Memory Management

The reason why reference type memory must be managed at all is that references to reference type objects are merely pointers to the actual object, and there can be multiple references (pointers) to the very same object. This means that every reference must deal carefully with that object, out of consideration for the needs of other possible references. At the very latest, the object *should* go out of existence when there are *no* pointers to it. But so long as there are *any* pointers to it, the object must *not* go out of existence.

To illustrate, imagine three objects, Manny, Moe, and Jack, where both Manny and Moe have references to Jack. Jack is the object whose memory we are concerned to manage:

*The object must not go out of existence too late*

If both Manny and Moe go out of existence, and if no other object has a reference to Jack, Jack should go out of existence too. An object without a pointer to it is useless; it is occupying memory, but no other object has, or can ever get, a reference to it. This is a *memory leak*.

*The object must not go out of existence too soon*

If both Manny and Moe have a pointer to Jack, and if Manny somehow causes Jack to go out of existence, poor old Moe is left with a pointer to nothing (or worse, to garbage). A pointer whose object has been destroyed behind the pointer's back is a *dangling pointer*. If Moe subsequently uses that dangling pointer to send a message to the object that he thinks is there, the app will crash.

To prevent both memory leakage and dangling pointers, there is a policy of manual memory management based on a number, maintained by every reference type object, called its *retain count*. The rule is that other objects can increment or decrement an object's retain count — and that's all they are allowed to do. As long as an object's retain count is positive, the object will persist. No object has the direct power to tell another object to be destroyed; rather, as soon as an object's retain count is decremented to zero, it is destroyed automatically.

By this policy, every object that needs Jack to persist should increment Jack's retain count, and should decrement it once again when it no longer needs Jack to persist. As long as all objects are well-behaved in accordance with this policy, the problem of manual memory management is effectively solved:

- There cannot be any dangling pointers, because any object that has a pointer to Jack has incremented Jack's retain count, ensuring that Jack persists.
- There cannot be any memory leaks, because any object that no longer needs Jack decrements Jack's retain count. If every object that doesn't need Jack any longer behaves this way, then when *no* object needs Jack any longer, Jack's retain count will reach zero and Jack will go out of existence.

## Rules of Cocoa Memory Management

An object is well-behaved with respect to memory management as long as it adheres to certain very simple, well-defined rules in conformity with the basic concepts of memory management. The underlying ethic is that *each* object that has a reference to a reference type object is responsible solely for *its own* memory management of that object, in accordance with these rules. If *all* objects that ever get a reference to this

reference type object behave correctly with respect to these rules, the object’s memory will be managed correctly and it will go out of existence exactly when it is no longer needed:

- If Manny or Moe *explicitly instantiates* Jack — by directly calling an initializer — then the initializer *increments* Jack’s retain count.
- If Manny or Moe *makes a copy* of Jack — by calling `copy` or `mutableCopy` or any other method with `copy` in its name — then the copy method *increments* the retain count of this new, duplicate Jack.
- If Manny or Moe *acquires* a reference to Jack (not through explicit instantiation or copying), and needs Jack to *persist* — long enough to work with Jack in code, or long enough to be the value of an instance property — then he himself *increments* Jack’s retain count. (This is called *retaining* Jack.)
- If and only if Manny or Moe has done any of those things — that is, if Manny or Moe has ever directly or indirectly caused Jack’s retain count to be incremented — then when he himself no longer needs his reference to Jack, before letting go of that reference, he *decrements* Jack’s retain count to balance exactly all previous increments that he himself has performed. (This is called *releasing* Jack.)

Having released Jack, Manny or Moe should then assume that Jack no longer exists, because if this causes Jack’s retain count to drop to zero, Jack *will* no longer exist. This is the *golden rule of memory management* — the rule that makes memory management work coherently and correctly.

A general way to understand the golden rule of memory management is in terms of *ownership*. If Manny has created, copied, or retained Jack — that is, if Manny has ever incremented Jack’s retain count — Manny has asserted ownership of Jack. Both Manny and Moe can own Jack at the same time, but each is responsible only for managing his own ownership of Jack correctly. It is the responsibility of an owner of Jack eventually to decrement Jack’s retain count — to release Jack, resigning ownership of Jack. The owner says: “Jack may or may not persist after this, but as for me, I’m done with Jack, and Jack can go out of existence as far as I’m concerned.” At the same time, a nonowner of Jack must *never* release Jack. As long as all objects behave this way with respect to Jack, Jack will not leak nor will any pointer to Jack be left dangling.

## What ARC Is and What It Does

Once upon a time, retaining and releasing an object was a matter of you, the programmer, literally sending `retain` and `release` messages to it. `NSObject` still implements `retain` and `release`, but under ARC (and in Swift) you can’t call them. That’s because ARC is calling them for you! That’s ARC’s job — to do for you what you would have had to do if memory management were still up to the programmer.

ARC is implemented as part of the compiler. The compiler is literally modifying your code by inserting `retain` and `release` calls behind the scenes. When you receive a reference type object by calling some method, ARC immediately retains it so that it will persist for as long as this same code continues to run; then ARC releases it when the code comes to an end. Similarly, when you create or copy a reference type object, ARC knows that its retain count has been incremented, and releases it when the code comes to an end.

ARC is conservative but reliable. In effect, ARC retains at every juncture that might have implications for memory management: it retains when an object is received as an argument, it retains when an object is assigned to a variable, and so forth. It may even insert temporary variables, behind the scenes, to enable it to refer sufficiently early to an object so that it can retain it. But of course it eventually also releases to match.

## How Cocoa Objects Manage Memory

Built-in Cocoa objects will take ownership of objects that you hand to them, by retaining them, if it makes sense for them to do so, and will of course then balance that retain with a release later. Indeed, this is so generally true that if a Cocoa object is *not* going to retain an object you hand it, there will be a note to that effect in the documentation.

A collection, such as an array or dictionary, is a particularly obvious case in point. An object can hardly be an element of a collection if that object can go out of existence at any time; so when you add an element to a collection, the collection asserts ownership of the object by retaining it. Thereafter, the collection acts as a well-behaved owner. If this is a mutable collection, then if an element is removed from it, the collection releases that element. If the collection object goes out of existence, it releases all its elements.

Prior to ARC, removing an object from a mutable collection constituted a potential trap. Consider the following Objective-C code:

```
id obj = myMutableArray[0]; // an NSMutableArray
[myMutableArray removeObjectAtIndex: 0]; // bad idea in non-ARC code!
// ... could crash here by referring to obj ...
```

As I just said, when you remove an object from a mutable collection, the collection releases it. So, without ARC, the second line of that code involves an implicit release of the object that used to be the first element of `myMutableArray`. If this reduces the object's retain count to zero, it will be destroyed. The pointer `obj` will then be a dangling pointer, and a crash may be in our future when we try to use it as if it were a real object.



With ARC, however, that sort of danger doesn't exist. Assigning a reference type object to a variable retains it — and we *did* assign this object to a variable, `obj`, *before* we removed it from the collection. Therefore, that code is perfectly safe, and so is its Swift equivalent:

```
let obj = myMutableArray[0] // retain
myMutableArray.removeObject(at:0) // release
// ... safe to refer to obj ...
```

The first line retains the object. The second line releases the object — but that release balances the retain that was placed on the object when the object was placed in the collection originally. So the object's retain count is still more than zero, and it continues to exist for the duration of this code.

## Autorelease Pool

When a method creates an instance and returns that instance, some memory management hanky-panky has to take place. Consider this simple code:

```
func makeImage() -> UIImage? {
    if let im = UIImage(named:"myImage") {
        return im
    }
    return nil
}
```

Think about the retain count of `im`, the `UIImage` we are returning. This retain count has been incremented by our call to the `UIImage` initializer `UIImage(named:)`. According to the golden rule of memory management, as we pass `im` out of our own control by returning it, we should decrement the retain count of `im`, balancing the increment and surrendering ownership. But when can we possibly do that? If we do it *before* the line `return im`, the retain count of `im` will be zero and it will vanish in a puff of smoke; we will be returning a dangling pointer. But we can't do it *after* the line `return im`, because when that line is executed, our code comes to an end.

Clearly, we need a way to vend this object without decrementing its retain count *now* — so that it stays in existence long enough for the caller to receive and work with it — while ensuring that at some future time we *will* decrement its retain count, so as to balance our `init(named:)` call and fulfill our own management of this object's memory. The solution is something midway between releasing the object and not releasing it — *autoreleasing* it.

Here's how autoreleasing works. Your code runs in the presence of something called an *autorelease pool*. When ARC autoreleases an object, that object is placed in the autorelease pool, and a number is incremented saying how many times this object has been placed in this autorelease pool. From time to time, when nothing else is going on, the autorelease pool is automatically *drained*. This means that the



Figure 13-1. Memory usage grows during a loop

autorelease pool releases each of its objects, the same number of times as that object was placed in this autorelease pool, and empties itself of all objects. If that causes an object's retain count to be zero, so be it; the object is destroyed in the usual way. So autoreleaseing an object is just like releasing it, but with a proviso, "later, not right this second."

In general, autoreleaseing and the autorelease pool are merely an implementation detail. You can't see them; they are just part of how ARC works. But sometimes, on very rare occasions, you might want to drain the autorelease pool yourself. Consider the following code (it's slightly artificial, but that's because demonstrating the need to drain the autorelease pool isn't easy):

```
func test() {
    let path = Bundle.main.path(forResource:"001", ofType: "png")!
    for j in 0 ..< 50 {
        for i in 0 ..< 100 {
            let im = UIImage(contentsOfFile: path)
        }
    }
}
```

That method does something that looks utterly innocuous; it loads an image. But it loads it repeatedly in a loop. As the loop runs, memory climbs constantly (Figure 13-1); by the time our method comes to an end, our app's memory usage has reached over 77MB. This is not because the images aren't being released each time through the loop; it's because a lot of *intermediate* objects — things you've never even heard of, such as `NSPathStore2` objects — are secondarily generated by our call to `init(contentsOfFile:)` and are *autoreleased*. As we keep looping, those objects are all sitting there, piling up in the autorelease pool by the tens of thousands, waiting for the pool to be drained. When our code finally comes to an end, the autorelease pool is drained, and our memory usage drops precipitately back down to almost nothing.

Granted, 77MB isn't exactly a massive amount of memory. But you may imagine that a more elaborate inner loop might generate more and larger autoreleased objects, and that our memory usage could potentially rise quite significantly. It would be nice to have a way to drain the autorelease pool *manually* now and then during the course of a loop with many iterations. Swift provides such a way — the global `autoreleasepool` function, which takes a single argument that you'll supply as an anonymous function using trailing closure syntax. Before the anonymous function is




Figure 13-2. Memory usage holds steady with an autorelease pool

called, a special temporary autorelease pool is created, and is used for all autoreleased objects thereafter. After the anonymous function exits, the temporary autorelease pool is drained and goes out of existence. Here's the same method with an `autoreleasepool` call wrapping the inner loop:

```
func test() {
    let path = Bundle.main.path(forResource:"001", ofType: "png")!
    for j in 0 ..< 50 {
        autoreleasepool {
            for i in 0 ..< 100 {
                let im = UIImage(contentsOfFile: path)
            }
        }
    }
}
```

The difference in memory usage is dramatic: memory holds roughly steady at about 4MB (Figure 13-2). Setting up and draining the temporary autorelease pool probably involves some overhead, so if possible you may want to divide your loop into an outer and an inner loop, as shown in the example, so that the autorelease pool is not set up and torn down on every iteration.

## Memory Management of Instance Properties

Before ARC, managing memory for instance properties (Objective-C instance variables, Chapter 11) was one of the trickiest parts of Cocoa programming. The correct behavior is to retain a reference type object when you assign it to a property, and then release it when either of these things happens:

- You assign a different value to the same property.
- The instance whose instance property this is goes out of existence.

Memory management for a property therefore had to be distributed in two places:

### *The setter method for the property*

The setter must release whatever object is currently the value of the property, and must retain whatever object is being assigned to that property. The exact details can be quite tricky (what if they are the same object?), and before ARC it was easy for programmers to get them wrong.

### *The owner’s dealloc method*

This is the Objective-C equivalent of `dealloc`. This method must be implemented to release every object being retained as the value of a property, or the object will leak when the owner goes out of existence.

Fortunately, ARC understands all that, and in Swift the memory of instance properties, like the memory of all variables, is managed correctly for you.

That fact also gives us a clue as to how to *release an object on demand* when you are holding it in an instance property. This is a valuable thing to be able to do, because an object may be using a lot of memory. You don’t want to put too great a strain on the device’s memory, so you want to release the object as soon as you’re done with it. Also, when your app goes into the background and is suspended, the Watchdog process will terminate it in the background if it is found to be using too much memory; so you might want to release this object when you are notified that the app is about to be backgrounded.

You can’t call `release` explicitly, so you need another way to do it, some way that is consonant with the design and behavior of ARC. The solution is to *assign something else* — something small — to this property. That causes the object that was previously the value of this property to be released. A commonly used approach is to type this property as an `Optional`. This means that `nil` can be assigned to it, purely as a way of replacing the object that is the instance property’s current value and releasing it.

## Retain Cycles and Weak References

As I explained in [Chapter 5](#), you can get yourself into a retain cycle where two reference type objects have references to one another: for example, each is the value of the other’s instance property. If such a situation is allowed to persist until no other objects have a reference to either of these objects, then neither can go out of existence, because each has a retain count greater than zero and neither will “go first” and release the other. Since these two objects, *ex hypothesi*, can no longer be referred to by any object except one another, this situation can now never be remedied — these objects are leaking.

The solution is to step in and modify how the memory is managed for one of these references. By default, a reference is a strong reference: assigning to it retains the assigned value. In Swift, you can declare a reference type variable as `weak` or as `unowned` to change the way its memory is managed:

`weak`

When a reference is `weak`, ARC does *not* retain the object assigned to it. This seems dangerous, because it means that the object might go out of existence behind our backs, leaving us with a dangling pointer and leading to a potential

crash later on. But ARC is very clever about this. A reference marked as *weak* *must* be a var reference to an Optional. ARC keeps track of all weak references and all objects assigned to them. When such an object's retain count drops to zero and the object is about to be destroyed, just before the object's `dealloc` is called, ARC sneaks in and assigns `nil` to all weak references to the object. Provided you handle the Optional coherently (by coping with the fact that it might suddenly be `nil`), nothing bad can happen.

#### unowned

An *unowned* reference is a different kettle of fish. When you mark a reference as *unowned*, you're telling ARC to take its hands off completely: it does no memory management at all when something is assigned to this reference. This really *is* dangerous — if the object referred to goes out of existence, you really *can* be left with a dangling pointer and you really *can* crash. That is why you must never use *unowned* unless you know that the object referred to will *not* go out of existence: *unowned* is safe, provided the object referred to will outlive the object that refers to it. So an *unowned* reference should point to an independent object, retained in some other way, without which the referrer cannot exist at all.

A weak reference is commonly used to connect an object to its delegate ([Chapter 12](#)):

```
class ColorPickerController : UIViewController {
    weak var delegate: ColorPickerDelegate?
    // ...
}
```

A delegate is an independent entity; there is usually no reason why an object needs to claim ownership of its delegate. Indeed, an object is usually its delegate's servant, not its owner, and ownership, if there is any, runs the other way; Object A might create *and retain* Object B, and make itself Object B's delegate:

```
let cpc = ColorPickerController(colorName:colorName, color:c)
cpc.delegate = self
self.present(cpc, animated: true) // retains cpc
```

There's no danger of a retain cycle in that code, because the `ColorPickerController`'s `delegate` property is weak. This view controller (`self`) is not somehow retaining itself.

Very rarely, you may encounter properties of built-in Cocoa classes that keep weak references as *non-ARC* weak references (because they are old and backward compatible, whereas ARC is new). Such properties are declared in Objective-C using the keyword `assign`. For instance, `NSCache`'s `delegate` property is declared like this:

```
@property (nullable, assign) id<NSCacheDelegate> delegate;
```

In Swift, that declaration is translated like this:

```
unowned(unsafe) var delegate: NSCacheDelegate?
```

```

libobjc.A.dylib`objc_msgSend:-
  0x10ed4a3c0 <+0>: testq %rdi, %rdi
  0x10ed4a3c3 <+3>: jle 0x10ed4a428 ; <+104>
  0x10ed4a3c5 <+5>: movq (%rdi), %r10
  0x10ed4a3c8 <+8>: movq %rsi, %r11
-> 0x10ed4a3cb <+11>: andl 0x18(%r10), %r11d Thread 1: EXC_BAD_ACCESS
  0x10ed4a3cf <+15>: shlq $0x4, %r11

```

Figure 13-3. A crash from messaging a dangling pointer

The Swift term `unowned` and the Objective-C term `assign` are synonyms; they tell you that there’s no ARC memory management here. The `unsafe` designation is a further warning inserted by Swift; unlike your own code, where you won’t use `unowned` unless it is safe, Cocoa’s `unowned` is potentially dangerous and you need to exercise caution.

A reference such as an `NSCache`’s `delegate` can end up as a dangling pointer, pointing at garbage, if the object to which that reference was pointing has gone out of existence. If anyone tries to send a message by way of such a reference, the app will then crash. (This is the `delegate`, so what usually happens is that Cocoa eventually tries to send it a `delegate` message.) The tell-tale sign of such a crash is that `EXC_BAD_ACCESS` is reported somewhere in `objc_msgSend` (Figure 13-3).

Figuring out the cause of a crash like that can be quite difficult, especially since the crash itself typically takes place long after the point where the real mistake occurred, namely that some object went out of existence while a reference to it continued to exist. You might not even know *what* object went out of existence. (This is the sort of situation in which you might need to “turn on zombies” in order to debug, as I’ll describe at the end of this chapter.)

Non-ARC weak references of this kind are few and far between in Cocoa nowadays; but they were once relatively common, so the earlier the iOS version on which you’re running, the more likely you are to encounter one. Fortunately, it’s easy to avoid a dangling pointer by making sure there is always something to point to. With an `NSCache`’s `delegate`, if the `delegate` object is about to go out of existence at a time when the `NSCache` instance still exists, we would assign `nil` (or some other object) to the `delegate` property, rendering it harmless.

## Unusual Memory Management Situations

This section discusses some situations that call for some special memory management handling on your part.

## Notification Observers

Recall the example I gave in [Chapter 12](#), where you register with the notification center by calling `addObserver(forName:object:queue:using:)`, like this:

```
let ob = NotificationCenter.default.addObserver(
    forName: .MPMusicPlayerControllerNowPlayingItemDidChange,
    object: nil, queue: nil) { [unowned self] _ in
        self.updateNowPlayingItem()
        // ... and so on ...
    }
self.observers.insert(ob as! NSObject)
```

As I said at the time, it is crucial that we eventually unregister the observer token returned from that call (`ob`). The reason has to do with some weird memory management behind the scenes; the observer token is *retained by the notification center* until you unregister it. (I regard this as something of a dirty trick on the notification center's part; I think I understand Apple's reasoning in designing things this way, but I also think they reasoned incorrectly.) If we fail to deregister the observer token before `self` goes out of existence, the observer token itself will still live on — and the function that we supplied when we obtained the observer token can be called *again* even though now `self` no longer exists. If we marked `self` as `unowned`, the app will crash at that moment with a dangling pointer; and we probably *did* mark `self` as `unowned`, because if we didn't, `self` (the view controller) will leak and its `deinit` will never be called. A complete solution looks something like this:

```
var observers = Set<NSObject>()
override func viewDidLoad() {
    super.viewDidLoad()
    let ob = NotificationCenter.default.addObserver(
        forName: .MPMusicPlayerControllerNowPlayingItemDidChange,
        object: nil, queue: nil) { [unowned self] _ in ❶
            self.updateNowPlayingItem()
            // ... and so on ...
        }
    self.observers.insert(ob as! NSObject)
}
deinit {
    for ob in self.observers {
        NotificationCenter.default.removeObserver(ob) ❷
    }
}
```

- ❶ If you omit `unowned self`, then `self` will leak (and `deinit` will never be called).
- ❷ If you omit `removeObserver`, then any observers will leak, and we can crash if the notification center later sends a notification to an observer with an `unowned` reference to a `self` that no longer exists.

If you subscribe to a notification stream as a Combine framework publisher or an asynchronous sequence, things are simpler:

#### *Combine framework*

If a Combine pipeline is stored as an instance property of `self`, then it will be released automatically when `deinit` is called on `self`. But if the pipeline involves an anonymous function that refers to `self`, that's a straightforward retain cycle that must be broken through the anonymous function's capture list (typically by saying `[unowned self]`); otherwise, `deinit` won't be called (and `self` will leak).

#### *Asynchronous sequence*

An asynchronous for loop in a Task won't cause a retain cycle, but if you don't cancel the Task, you won't cancel the for loop, and the loop will still be receiving notifications even after the surrounding `self` is gone. The solution is to cancel the Task in `deinit` at the latest; that will be possible because there's no retain cycle.

## KVO Observers

The `NSKeyValueObservation` observer object that you get when you call `observe(_:options:changeHandler:)` (Chapter 12) is quite similar to the observer token you get from the notification center. You maintain a reference to the observer object, because otherwise the notification message won't arrive. And you'll probably want to let the observer object just go out of existence when you yourself go out of existence, because it will then unregister itself automatically, which is exactly what you want.

If your notification function refers to `self`, that's potentially a retain cycle, because you are retaining an observer whose function is also retaining you. Therefore you *won't* go out of existence, so the observer won't go out of existence either and won't be automatically unregistered. The solution, once again, is to mark `self` as `unowned` in the notification function:

```
var obs = Set<NSKeyValueObservation>()
func registerWith(_ mc: MyClass1) {
    let opts : NSKeyValueObservingOptions = [.old, .new]
    let ob = mc.observe(\.value, options: opts) { [unowned self] obj, ch in
        print(self) // potential leak
    }
    self.obs.insert(ob)
}
```



## Timers

The class documentation for `Timer` ([Chapter 11](#)) says that “run loops maintain strong references to their timers”; it then says of `scheduledTimer(timeInterval:target:selector:userInfo:repeats:)` that “The timer maintains a strong reference to `target` until it (the timer) is invalidated.” This should set off alarm bells in your head: “Danger, Will Robinson, danger!” The documentation is warning you that as long as a repeating timer has not been invalidated, the target is being retained by the run loop; the only way to stop this is to send the `invalidate` message to the timer. (With a non-repeating timer, the problem arises less starkly, because the timer invalidates itself immediately after firing.)

Moreover, the `target:` argument is probably `self`. This means that you (`self`) are being retained, and cannot go out of existence until you invalidate the timer. But when will you do that? You can’t do it in your `deinit` implementation, because as long as the timer is repeating and has not been sent the `invalidate` message, `deinit` won’t be called! You therefore need to find another appropriate moment for sending `invalidate` to the timer, such as `viewDidDisappear`:

```
var timer : Timer!
override func viewWillAppear(_ animated: Bool) {
    super.viewWillAppear(animated)
    self.timer = Timer.scheduledTimer(timeInterval: 1, target: self,
        selector: #selector(fired), userInfo: nil, repeats: true)
    self.timer.tolerance = 0.1
}
@objc func fired(_ t:Timer) {
    print("timer fired")
}
override func viewDidDisappear(_ animated: Bool) {
    super.viewDidDisappear(animated)
    self.timer.invalidate()
}
```

A more flexible approach is to call instead the `scheduledTimer(withTimeInterval:repeats:block:)` class method. Now there is no retained `target:`. Of course, there is a retained function, so there’s a potential retain cycle. If the timer is a repeating timer, you are retaining it so that you can invalidate it later, but the timer is retaining the function, and if that function involves a reference to `self`, it will retain `self`, causing a retain cycle. But we know what to do about that! Mark `self` as `weak` or `unowned` in the function. Now you *can* invalidate the timer in `deinit`. This is similar to the two-part solution I described earlier for notification observer token objects:

```
var timer : Timer!
override func viewDidLoad() {
    super.viewDidLoad()
    self.timer = Timer.scheduledTimer(withTimeInterval: 1, repeats: true) {
```

```

        [unowned self] t in // *
            self.fired(t)
    }
}
func fired(_ t:Timer) {
    print("timer fired")
}
deinit {
    self.timer.invalidate() // *
}

```

## Other Unusual Situations

Other Cocoa objects with unusual memory management behavior will usually be called out clearly in the documentation. A `CAAnimation` object *retains its delegate*; this is exceptional and can cause serious trouble if you're not conscious of it (as usual, I speak from bitter experience). There are also situations where the documentation fails to warn of any special memory management considerations, but you can wind up with a retain cycle anyway. Discovering the problem can be tricky. Areas of Cocoa that have given me trouble include UIKit Dynamics (a `UIDynamicBehavior`'s action handler) and WebKit (a `WKWebKit`'s `WKScriptMessageHandler`).

Three Foundation collection classes — `NSPointerArray`, `NSHashTable`, and `NSMapTable` — are similar respectively to `NSMutableArray`, `NSMutableSet`, and `NSMutableDictionary`, except that (among other things) their memory management policy is up to you. An `NSHashTable` created with the `weakObjects` class method maintains ARC-weak references to its elements, meaning that they are replaced by `nil` if the retain count of the object to which they were pointing has dropped to zero. You may find uses for these classes as a way of avoiding retain cycles.

## Memory Management of CTypeRefs

A `CTypeRef` is a pure C analog to an Objective-C object. In Objective-C, `CTypeRef` types are distinguished by the suffix `Ref` at the end of their name; in Swift, this `Ref` suffix is dropped. For instance, a `CGContextRef` is a `CTypeRef`, and is known in Swift as a `CGContext`.

A `CTypeRef` is a pointer to an opaque C struct (see the [Appendix](#)), where “opaque” means that the struct has no directly accessible components. This struct acts as a pseudo-object; a `CTypeRef` is analogous to an object type. But it is *not* an object.

In Objective-C, the fact that a `CTypeRef` is not an object is particularly obvious, because the code that operates upon a `CTypeRef` is not object-oriented. A `CTypeRef` has no properties or methods, and you do not send any messages to it; you work with `CTypeRefs` entirely through global C functions. In Swift's Core Graphics overlay, however, those global C functions are hand-tweaked to *look* like methods; for

instance, the `CGContextDrawLinearGradient` C function is called, in Swift, by sending `drawLinearGradient(_:start:end:options:)` to a `CGContext` pseudo-object, just as if a `CGContext` were an object and `drawLinearGradient` were an instance method.

Here's some actual Swift code for drawing a gradient; `con` is a `CGContext`, `sp` is a `CGColorSpace`, and `grad` is a `CGGradient` (all of them being `CTypeRefs`):

```
let con = UIGraphicsGetCurrentContext()!
let locs : [CGFloat] = [ 0.0, 0.5, 1.0 ]
let colors : [CGFloat] = [
    0.8, 0.4, // starting color, transparent light gray
    0.1, 0.5, // intermediate color, darker less transparent gray
    0.8, 0.4, // ending color, transparent light gray
]
let sp = CGColorSpaceCreateDeviceGray()
let grad = CGGradient(colorSpace: sp,
    colorComponents: colors, locations: locs, count: 3)!
con.drawLinearGradient(grad,
    start: CGPoint(x:89,y:0), end: CGPoint(x:111,y:0), options:[])
```

Despite being only a pseudo-object, however, a `CTypeRef` *is a reference type*, and its memory must be managed in just the same way as that of a real object. Therefore, a `CTypeRef` pseudo-object has a retain count! And this retain count works exactly as for a true object, in accordance with the golden rule of memory management. A `CTypeRef` must be retained when it comes within the sphere of influence of an owner who wants it to persist, and it must be released when that owner no longer needs it.

In Objective-C, the golden rule, as applied to `CTypeRefs`, is that if you obtained a `CTypeRef` object through a function whose name contains the word `Create` or `Copy`, its retain count has been incremented. In addition, if you are worried about the object persisting, you'll retain it explicitly by calling the `CFRetain` function to increment its retain count.

Then, to balance your `Create`, `Copy`, or `CFRetain` call, you must eventually release the object. By default, you'll do that by calling the `CFRelease` function; some `CTypeRefs`, however, have their own dedicated object release functions — for `CGPath`, for instance, there's a dedicated `CGPathRelease` function. There's no ARC management of `CTypeRefs` in Objective-C, so you have to do all of this yourself, explicitly.

In Swift, however, you will *never* need to call `CFRetain`, or any form of `CFRelease`; indeed, you cannot. Swift will do it for you, behind the scenes, automatically.

Think of `CTypeRefs` as living in two worlds: the `CTypeRef` world of pure C, and the memory-managed object-oriented world of Swift. When you obtain a `CTypeRef` pseudo-object, it *crosses the bridge* from the `CTypeRef` world into the Swift world. From that moment on, until you are done with it, it needs memory management.

Swift is aware of this, and for the most part, Swift itself will use the golden rule and will apply correct memory management.

For this reason, the code I showed earlier for drawing a gradient is in fact memory-management complete. In Objective-C, we would have to release `sp` and `grad`, because they arrived into our world through `Create` calls; if we failed to do this, they would leak. In Swift, however, there is no need, because Swift will do it for us. (See the [Appendix](#) for more about how objects move between the `CTypeRef` world and the memory-managed object world.)

Working with `CTypeRefs` in Swift, then, is much easier than in Objective-C. In Swift, you can treat `CTypeRef` pseudo-objects as actual objects! You can assign a `CTypeRef` to a property in Swift, or pass it as an argument to a Swift function, and its memory will be managed correctly; in Objective-C, those are tricky things to do.

It is still possible, though, to receive a `CTypeRef` through some API that lacks memory management information. Such a value will come forcibly to your attention, because it will arrive into Swift, *not* as a `CTypeRef`, but as an `Unmanaged` generic wrapping the actual `CTypeRef`. That situation alerts you to the fact that Swift does not know how to proceed with the memory management of this pseudo-object.

You will be unable to use a `CTypeRef` obtained in this way until you extract it from its `Unmanaged` wrapper by calling the `Unmanaged` object's `takeRetainedValue` or `takeUnretainedValue` method. You will call whichever method tells Swift how to manage the memory for this object correctly. For a `CTypeRef` with an incremented retain count (usually acquired through a function with `Create` or `Copy` in its name), call `takeRetainedValue`; otherwise, call `takeUnretainedValue`.

## Property Memory Management Policies

In Objective-C, a `@property` declaration (see [Chapter 11](#)) includes a statement of the memory management policy implemented by the corresponding setter accessor method. It is useful to be aware of this and to know how such policy statements are translated into Swift.

Earlier I said that a `UIViewController` retains its view (its main view). How do I know this? Because the `@property` declaration tells me so:

```
@property(null_resettable, nonatomic, strong) UIView *view;
```

The term `strong` means that the setter retains the incoming `UIView` object. The Swift translation of this declaration doesn't add any attribute to the variable:

```
var view: UIView!
```

The default in Swift is that a variable referring to a reference object type *is* a strong reference. This means that it retains the object. You can safely conclude from this declaration that a `UIViewController` retains its view.

The possible memory management policies for a Cocoa property are:

**strong**, **retain** (*no Swift equivalent term*)

The default. The two terms are pure synonyms; **retain** is the term inherited from pre-ARC days. Assignment to this property releases the existing value (if any) and retains the incoming value.

**copy** (*Swift @NSCopying*)

The same as **strong** or **retain**, except that the setter copies the incoming value by sending `copy` to it; the incoming value must be an object of a type that adopts `NSCopying`, to ensure that this is possible. The copy, which has an increased retain count already, becomes the new value.

**weak** (*Swift weak*)

An ARC-weak reference. The incoming object value is not retained, but if it goes out of existence behind our back, ARC will magically substitute `nil` as the value of this property, which *must* be typed as an `Optional` declared with `var`.

**assign** (*Swift unowned(unsafe)*)

No memory management. This policy is inherited from pre-ARC days, and is inherently unsafe (hence the additional `unsafe` warning in the Swift translation of the name): if the object referred to goes out of existence, this reference will become a dangling pointer and can cause a crash if you subsequently try to use it.

The copy policy is used by Cocoa particularly when an immutable class has a mutable subclass (such as `NSString` and `NSMutableString`, or `NSArray` and `NSMutableArray`; see [Chapter 11](#)). The idea is to deal with the danger of the setter's caller passing an object of the mutable subclass. This is possible because, in accordance with the substitution principle of polymorphism ([Chapter 4](#)), wherever an instance of a class is expected, an instance of its subclass can be used instead. It would be bad if this were to happen, because now the caller might keep a reference to the incoming value and, since it is in fact mutable, could later mutate it behind our back. To prevent this, the setter calls `copy` on the incoming object; this creates a new instance, separate from the object provided — and belonging to the immutable class.

In Swift, this problem is unlikely to arise with strings and arrays, because on the Swift side these are value types (structs) and are effectively copied when assigned, passed as an argument, or received as a return value. Cocoa's `NSString` and `NSArray` property declarations, when translated into Swift as `String` and `Array` property declarations, don't show any special marking corresponding to Objective-C `copy`. But Cocoa types

that are *not* bridged to Swift value types *do* show a marking: `@NSCopying`. The declaration of the `attributedString` property of a `UILabel` appears like this in Swift:

```
@NSCopying var attributedText: NSAttributedString?
```

`NSAttributedString` has a mutable subclass, `NSMutableAttributedString`. You’ve probably configured this attributed string as an `NSMutableAttributedString`, and now you’re assigning it as a `UILabel`’s `attributedString`. The `UILabel` doesn’t want you keeping a reference to this mutable string and mutating it in place, since that would change the value of the property without passing through the setter. It copies the incoming value to ensure that what it has is a separate immutable `NSAttributedString`.

You’ll want to do the same thing in your own code, and you can. Simply mark your property with the `@NSCopying` attribute; Swift will enforce the copy policy and will take care of the actual copying for you whenever this property is assigned to:

```
class StringDrawer {
    @NSCopying var attributedString : NSAttributedString!
    // ...
}
```

If, as is sometimes the case, your own class wants the internal ability to mutate the value of this property while preventing a mutable value from arriving from outside, put a private computed property façade in front of it whose getter transforms it to the corresponding mutable type:

```
class StringDrawer {
    @NSCopying var attributedString : NSAttributedString!
    private var mutableAttributedString : NSMutableAttributedString! {
        get {
            if self.attributedString == nil {return nil}
            return NSMutableAttributedString(
                attributedString:self.attributedString)
        }
        set {
            self.attributedString = newValue
        }
    }
    // ...
}
```

`@NSCopying` can be used *only* for instance properties of classes, not of structs or enums — and only in the presence of Foundation, because that is where the `NSCopying` protocol is defined, which the type of a variable marked as `@NSCopying` must adopt.

# Debugging Memory Management Mistakes

Though far less likely to occur under ARC (and Swift), memory management mistakes *can* still occur, especially because a programmer is apt to assume that they can't. Experience suggests that you should use every tool at your disposal to ferret out possible mistakes. Here are some of those tools (and see [Chapter 10](#)):

- The memory gauge in the Debug navigator charts memory usage whenever your app runs, allowing you to observe possible memory leakage or other unwarranted heavy memory use. Note that memory management in the Simulator is not necessarily indicative of reality! Always observe the memory gauge with the app running on a device before making a judgment.
- Instruments (Product → Profile) has excellent tools for discerning leaks and tracking memory management of individual objects (Leaks, Allocations).
- Good old caveman debugging can help confirm that your objects are behaving as you want them to. Implement `deinit` with a `print` call. If it isn't called, your object is not going out of existence. This technique can reveal problems that even Instruments will not directly expose.
- Memory graphing ("[Memory Debugging](#)" on [page 544](#)) will draw you a picture of the ownership relations between your objects; circular references are usually easy to spot. In conjunction with Malloc Stack Logging, you can trace object ownership through the actual retain calls.
- Dangling pointers are particularly difficult to track down, but they can often be located by "turning on zombies." This is easy in Instruments with the Zombies template (on a device). Alternatively, edit the Run action in your scheme, switch to the Diagnostics tab, and check Enable Zombie Objects. The result is that an object that goes out of existence is replaced by a "zombie" that will report to the console if a message is sent to it ("message sent to deallocated instance"). Moreover, the zombie knows what *kind* of object it replaces, so you can learn *what* got deallocated. Be sure to turn zombies back off when you've finished tracking down your dangling pointers. Don't use zombies with the Leaks instrument: zombies *are* leaks.
- The Address Sanitizer (also in the scheme's Run action's Diagnostics tab) lets you debug even more subtle forms of memory misuse. Here we're doing a Very Bad Thing, writing directly into memory that doesn't belong to us:

```
let b = UnsafeMutablePointer<CGFloat>.allocate(capacity:3)
b.initializeFrom([0.1, 0.2, 0.3])
b[4] = 0.4
```

That code probably won't crash; it corrupts memory silently, which is even worse. But if we run our app under Address Sanitizer, it detects the problem and reports a heap buffer overflow.





---

# Communication Between Objects

As soon as an app grows to more than a few objects, puzzling questions can arise about how to send a message or communicate data between one object and another. It may require some planning to construct your code so that all the pieces fit together and information can be shared as needed at the right moment. This chapter presents some organizational considerations that will help you arrange for coherent communication between objects.

## Visibility Through an Instance Property

One object's ability to communicate with another often comes down to one object being able to *see* another. If the object Manny needs to be able to find the object Jack repeatedly and reliably over the long term so as to be able to send Jack messages, Manny will presumably need a way of seeing Jack in the first place.

One obvious solution is an instance property of Manny whose value *is* Jack. An instance property is appropriate particularly when Manny and Jack share certain responsibilities or supplement one another's functionality. Here are some commonly occurring cases where one object needs to have an instance property pointing at another:

- The application object and its delegate
- A table view and its data source
- A view controller and the view that it controls

Manny may have an instance property pointing to Jack, but this does not necessarily imply that Manny needs to assert *ownership* of Jack as a matter of memory management policy (see [Chapter 13](#)). Here are some common situations in which one object has a property pointing to another object, but does not retain that object:

- An object does not typically retain its delegate or its data source.
- An object that implements the target-action pattern, such as a UIControl, does not retain its target.

By using a weak reference and typing the property as an Optional, and then treating the Optional coherently and safely, Manny can keep a reference to Jack without owning Jack (while coping with the possibility that his supposed reference to Jack will turn out to be `nil`). On the other hand, sometimes ownership is appropriate and crucial. A view controller is useless without a view to control, and its view truly belongs to the view controller and to no one else; once a view controller has a view, it will retain it, releasing it only when it itself goes out of existence.

Objects can perform two-way communication without both of them holding references to one another. It may be sufficient for *one* of them to have a reference to the other — because the former, as part of a message to the latter, can include a reference to himself. Manny might send a message to Jack where one of the parameters is a reference to Manny; this might merely constitute a form of identification, or an invitation to Jack to send a message back to Manny if Jack needs further information while doing whatever this method does. Manny makes himself, as it were, momentarily visible to Jack; Jack should not wantonly retain Manny (especially since there's an obvious risk of a retain cycle). Again, this is a common pattern:

- The first parameter of a target-action message is a reference to the control that sent the message. For example, if `buttonPressed(_:)` is an action handler method called by the user tapping a button, the parameter is the button.
- The first parameter of a delegate message is usually a reference to the object whose delegate this is. For example, the parameter of `textFieldShouldBeginEditing(_:)` is the text field.

## Visibility by Instantiation

Every instance comes from somewhere and at someone's behest: some object sent a message commanding this instance to come into existence in the first place. The commanding object therefore has a reference to the new instance at the moment of instantiation. When Manny creates Jack, Manny has a reference to Jack.

That simple fact can serve as the starting point for establishing future communication. If Manny creates Jack and knows that he (Manny) will need a reference to Jack later on, Manny can keep the reference that he obtained by creating Jack in the first place.

Or it might be the other way around: Manny creates Jack and knows that Jack will need a reference to Manny later on, so Manny can supply that reference immediately after creating Jack, and Jack will then keep it.

Delegation is a case in point; Manny may create Jack and immediately make himself Jack's delegate. This example is from [Chapter 12](#):

```
let cpc = ColorPickerController(colorName:colorName, color:c)
cpc.delegate = self
```

When Manny creates Jack, it might not be a reference to Manny himself that Jack needs, but to something that Manny knows or has. You will presumably endow Jack with a method or property so that Manny can hand over that information. In fact, if Jack simply cannot live without the information, it might be reasonable to endow Jack with an initializer that *requires* this information as part of the very act of creation.

This example, again from [Chapter 12](#), comes from a table view controller. The user has tapped a row of the table. In response, we create a secondary table view controller, a `TracksViewController` instance; we hand it the data it will need, and display the secondary table view:

```
override func tableView(_ tableView: UITableView,
    didSelectRowAt indexPath: IndexPath) {
    delay(0.1) {
        let t = TracksViewController(
            mediaItemCollection: self.albums[indexPath.row])
        self.navigationController?.pushViewController(t, animated: true)
    }
}
```

In that code, I instantiate the `TracksViewController` by calling its initializer, `init(mediaItemCollection:)`, which requires me to hand over the media item collection that the view controller will need as the basis of its table view. And where did this initializer come from? I made it up! I have deliberately devised `TracksViewController` to have a designated initializer `init(mediaItemCollection:)`, making it virtually obligatory for a `TracksViewController` to have access, from the moment it comes into existence, to the data it needs.

When a segue in a storyboard is triggered, there are two view controllers that may need to meet — the view controllers at the two ends of the segue, the source view controller and the destination view controller. This is parallel to the situation where one view controller creates another view controller and presents it, but there's an important difference: with a triggered segue, the source view controller *doesn't* directly create the destination view controller, so how will it get an early reference to the destination view controller?

When a segue is triggered, the segue itself instantiates the destination view controller, and has a reference to it. The runtime immediately turns to the source view controller and hands it a reference to the segue, by calling the source view controller's `prepare(for:sender:)` method. Now the source view controller has the segue, which means it has a reference to the newly instantiated destination view controller. This is

the source view controller's chance to make itself the destination view controller's delegate, or hand it any needed information, and so forth.

In iOS 13 and later, there's an even better way. The segue *doesn't* necessarily instantiate the destination view controller. Instead, the source view controller can implement a *segue action method* that is called when the segue is triggered, where it *can* instantiate the destination view controller directly.

Whether a view controller creates another view controller instance directly or is brought together with the destination view controller by the `prepare(for:sender:)` event, the first view controller, for one brief shining moment, has a reference to the second view controller. Therefore it takes advantage of that moment to hand the second view controller instance the information it needs. There will be no better moment to do this. Knowing the moment, and taking care not to miss it, is part of the art of data communication.

## Getting a Reference

Sometimes another object *already* exists somewhere out there, but you don't have direct access to it. That kind of situation can be a particular source of frustration.

Let's say you're a view controller and there's some other view controller you need to talk to. But you didn't instantiate the other view controller, and you are not the source view controller for the segue that instantiated the other view controller. You may know a lot about this other view controller — you know what its class is, and you can probably see its view sitting there in the interface when you run the app — but you cannot get hold of it in code.

Here's what *not* to do in that situation: You know the class of the view controller you're looking for, so you *make* an instance of that class. That won't do you any good! The instance you want to talk to is a particular instance that *already* exists. There's no point making *another* instance. If you lose your car in a parking lot, the solution is not to build another car of the same model; the solution is to find *your* car.

For example, in a real-life iOS app, you will have a root view controller, which will be an instance of some type of `UIViewController`. Let's say it's an instance of the `ViewController` class. Once your app is up and running, this instance already exists. Now suppose we are in some other view controller, and we want to talk to the `ViewController` instance that is serving as the root view controller of the app. It would be counterproductive to try to speak to that view controller by *instantiating* the `ViewController` class:

```
let theVC = ViewController() // legal but pointless
```

All that does is to make a *second, different* instance of the `ViewController` class, and your messages to that instance will be wasted, as it is not the same instance of

ViewController that you wanted to talk to. The instance you want to talk to already exists; what you want is to *get a reference* to that *already existing* instance. But how? Here are some considerations that will help you.

## Visibility by Relationship

It is not the *class* of an already existing object that will get you a reference to that object, but rather the *relationship* between you and that object. Objects may acquire the ability to see one another automatically by virtue of their position in a containing structure. Before worrying about how to supply one object with a reference to another, consider whether there may *already* be a chain of references leading from one to the other.

A subview can see its superview, through its `superview` property. A superview can see all its subviews, through its `subviews` property, and can pick out a specific subview through that subview's `tag` property, by calling the `viewWithTag(_:)` method. A subview in a window can see its window, through its `window` property. Working your way up or down the view hierarchy by means of these properties, it may be possible to obtain the desired reference.

A view controller can see its view through its `view` property, and from there can work its way down to subviews to which it may not have an outlet. What about going in the other direction? A responder ([Chapter 12](#)) can see the next object up the responder chain, through the `next` property — which also means, because of the structure of the responder chain, that a view controller's main view, or any of its subviews, can see the view controller.

View controllers are themselves part of a hierarchy and therefore can see one another. If a view controller is currently presenting a view through a second view controller, the latter is the former's `presentedViewController`, and the former is the latter's `presentingViewController`. If a view controller is the child of a `UINavigationController`, the latter is its `navigationController`. A `UINavigationController`'s visible view is controlled by its `visibleViewController`. And so forth.

## Global Visibility

Some objects are globally visible — that is, they are visible to all other objects. Object types themselves are an important example. You can *always* refer to a type, just by saying its name.

Classes sometimes have class methods or properties that vend singleton instances. Some of these singletons, in turn, have properties pointing to other objects, making those other objects likewise globally visible. You can think of such objects as globally *reachable*.

For example, any object can see the singleton `UIApplication` instance as `UIApplication.shared`. So any object can also see the app delegate, because that is the application's delegate property. Public properties of the app delegate are therefore globally reachable.

By the same sort of reasoning, we can solve the problem I posed earlier of getting a reference to the app's root view controller. We start with the globally visible shared application instance:

```
let app = UIApplication.shared
```

The application has at least one window scene:

```
let scene = app.connectedScenes.first as? UIWindowScene
```

From there we can get the window:

```
let wind = scene?.windows.first
```

That window owns the root view controller, and will hand us a reference to it through its `rootViewController` property:

```
let root = wind?.rootViewController
```

And voilà — a reference to our app's root view controller. To obtain the reference to this persistent instance, we have created, in effect, a chain leading from the known to the unknown, from a globally available class to the particular desired instance. And from there, as I said earlier, we can navigate the view controller hierarchy and the view hierarchy.

You can make your own objects globally visible by attaching them to a globally visible object. The globally visible object might be a type; as I pointed out in [Chapter 4](#), a Swift struct or enum with static members is a reasonable way of providing globally available namespaced constants ("[Constant Namespaces](#)" on page 156). Or it might be an instance that's globally reachable. For example, I've already said that a public property of the app delegate is globally reachable by virtue of the app delegate being globally visible (by virtue of the shared application being globally visible). Well, you are free to create such a property.

Another globally visible object is the shared defaults object obtained as `UserDefaults.standard`. This object is the gateway to storage and retrieval of user defaults, which is similar to a dictionary (a collection of values named by keys). The user defaults are automatically saved when your application quits and are automatically available when your application is launched again later, so they are one of the ways in which your app maintains information between launches. But, being globally visible, they are also a conduit for communicating values within your app.

In one of my apps there's a preference setting I call `Default.hazyStripy`. This determines whether a certain visible interface object (a card in a game) is drawn with a

hazy fill or a stripy fill. This is a setting that the user can change, so there is a preferences interface allowing the user to make this change. When the user displays this preferences interface, I examine the `Default.hazyStripy` setting in the user defaults to configure the preferences interface to reflect it in a segmented control (called `self.hazyStripy`):

```
func setHazyStripy () {
    let hs = UserDefaults.standard
        .object(forKey:Default.hazyStripy) as! Int
    self.hazyStripy.selectedSegmentIndex = hs
}
```

Conversely, if the user interacts with the preferences interface, tapping the hazy-Stripy segmented control to change its setting, I respond by changing the actual `Default.hazyStripy` setting in the user defaults:

```
@IBAction func hazyStripyChange(_ sender: Any) {
    let hs = self.hazyStripy.selectedSegmentIndex
    UserDefaults.standard.set(hs, forKey: Default.hazyStripy)
}
```

But here's the really interesting part. The preferences interface is not the only object that uses the `Default.hazyStripy` setting in the user defaults; the drawing code that actually draws the hazy-or-stripy-filled card also uses it, so as to know how the card should draw itself! When the user leaves the preferences interface and the card game reappears, the cards are redrawn — consulting the `Default.hazyStripy` setting in `UserDefaults` in order to do so:

```
override func draw(_ rect: CGRect) {
    let hazy : Bool = UserDefaults.standard
        .integer(forKey:Default.hazyStripy) == HazyStripy.hazy.rawValue
    CardPainter.shared.drawCard(self.card, hazy:hazy)
}
```

There is no need for the card object and the view controller object that manages the preferences interface to be able to see one another, because they can both see this common object, the `Default.hazyStripy` user default. `UserDefaults` becomes, in effect, a global conduit for communicating information from one part of my app to another.

## Notifications and Key–Value Observing

Notifications ([Chapter 12](#)) can be a way to communicate between objects that are conceptually distant from one another without bothering to provide *any* way for one to see the other. All they really need to have in common is a knowledge of the name of the notification. Every object can see the notification center — it is a globally visible object — so every object can arrange to post or receive a notification.

Using a notification in this way may seem lazy, an evasion of your responsibility to architect your objects sensibly. But sometimes one object doesn't need to know, and indeed shouldn't know, what object (or objects) it is sending a message to.

Recall the example I gave in [Chapter 12](#). In a simple card game app, the game needs to know when a card is tapped. A card, when it is tapped, knowing nothing about the game, simply emits a virtual shriek by posting a notification; the game object has registered for this notification and takes over from there:

```
NotificationCenter.default.post(name: Self.tappedNotification, object: self)
```

Here's another example, taking advantage of the fact that notifications are a broadcast mechanism. In one of my apps, the app delegate may detect a need to tear down the interface and build it back up again from scratch. If this is to happen without causing memory leaks (and all sorts of other havoc), every view controller that is currently running a repeating Timer needs to invalidate that timer ([Chapter 13](#)). Rather than my having to work out what view controllers those might be, and endowing every view controller with a method that can be called, I simply have the app delegate shout "Everybody stop timers!" by posting a notification. All my view controllers that run timers have registered for this notification, and they know what to do when they receive it.

By the same token, Cocoa itself provides notification versions of many delegate and action messages. The app delegate has a lifetime event method for being told when the app goes into the background, but other objects might need to know this too; those objects can register for the corresponding notification.

Similarly, key-value observing can be used to keep two conceptually distant objects synchronized with one another: a property of one object changes, and the other object hears about the change. As I said in [Chapter 12](#), entire areas of Cocoa routinely expect you to use KVO when you want to be notified of a change in an object property. You can configure the same sort of thing with your own objects.

## The Combine Framework

There is some commonality between mechanisms such as the notification center and key-value observing. In both cases, you register with some other object to receive a certain message whenever that other object cares to send it. Basically, you're opening and configuring a pipeline of communication, and leaving it in place until you no longer need it. Looked at in that way, notifications and key-value observing seem closely related to one another. In fact, the target-action mechanism of reporting control events seems related as well. And so does a Timer.

The Combine framework, introduced in Swift 5.1 and iOS 13, offers to unify these and other similar architectures under a single head. I have mentioned the Combine framework in earlier chapters; now I'll describe it a bit more deeply.



At its heart, Combine depends upon an abstract notion of publish-and-subscribe, and reifies that abstraction with two protocols, Publisher and Subscriber:

#### *Publisher*

A publisher promises to provide a certain kind of a value, perhaps repeatedly, at some time in the future.

#### *Subscriber*

A Subscriber registers itself with (subscribes to) a Publisher to receive its value whenever that value may come along.

When a Subscriber subscribes to a Publisher, here's what happens:

1. The Publisher responds by handing the Subscriber a Subscription (yet another protocol).
2. The Subscriber can then use the Subscription to ask the Publisher for a value.
3. The Publisher can respond by sending, whenever it cares to, a value to the Subscriber. It can do this as many times as it likes.
4. The entire connection can be cancelled when the Subscriber no longer wishes to receive values.

That's a rather elaborate-sounding dance, but in most cases you won't experience it that way. You won't experience the dance at all! Instead, you'll just hook up a built-in subscriber directly to a built-in publisher and all the right things will happen.

To illustrate, I'll start with a trivial example. One of the simplest forms of publisher is a Subject. Every time you call `send(_ : )` on a Subject, handing it a value, it sends that value to its subscribers. There are just two kinds of Subject:

#### *PassthroughSubject*

Produces the value sent to it with `send`.

#### *CurrentValueSubject*

Like a *PassthroughSubject*, except that it also has a value at the outset, and produces it to any new subscriber.

Let's make a Subject:

```
let pass = PassthroughSubject<String, Never>()
pass.send("howdy")
```

That compiles and runs, but we don't know that anything happened because we have no subscriber. There are just two built-in independent subscribers, and each can be created with a convenience method `sent` to a publisher; the method subscribes the subscriber to the publisher and returns it:

`sink`

Takes a function to be called whenever a value is received. The function takes a single parameter, namely the value.

`assign`

Takes a Swift key path and an object. Whenever a value is received, assigns that value to the property of that object designated by the key path.

So here's a complete publish-and-subscribe example:

```
let pass = PassthroughSubject<String, Never>()
let sink = pass.sink {
    print($0)
}
pass.send("howdy") // howdy
```

That works, in the sense that "howdy" appears in the console; but it still isn't a very realistic example. In real life, we're never going to make a publisher, subscribe to it, and make it publish, all within the immediate local scope of a single series of commands. In a realistic scenario:

- The publisher belongs to, and is vended by, one object.
- The subscriber is created and attached to the publisher by a different object.
- If the publisher publishes at all, that will happen at some unknown future time. Therefore the subscriber needs to *persist* long enough to wait for the publisher to publish.

To simulate that, let's store our publisher and subscriber in instance properties, and let's make the publisher publish only after a delay:

```
let pass = PassthroughSubject<String, Never>()
var storage = Set<AnyCancellable>()
override func viewDidLoad() {
    super.viewDidLoad()
    let sink = self.pass.sink {
        print($0)
    }
    sink.store(in: &self.storage)
    delay(1) {
        self.pass.send("howdy") // howdy
    }
}
```

In that code, the Subject publisher persists long enough for us to make it publish one second later, because it is assigned to an instance property. And the `sink` subscriber is *also* assigned to an instance property; in particular, it is added to a Set of `AnyCancellable`, using the `store(in:)` method. The result is that when we come along one second later and tell the Subject publisher to publish, the `sink` subscriber still exists, inside the storage Set, and receives the published value and prints it.

To help you take advantage of the Combine framework in your Cocoa code, a number of Foundation and Cocoa types vend Combine publishers, such as:

- The notification center
- A KVO compliant property
- A computed property declared with the `@Published` property wrapper
- The Timer class
- A `URLSession` (for obtaining a value via the network)

Besides publishers and subscribers, there are also *operators*. An operator is a publisher that is somewhat like a subscriber, in that it can be attached to another publisher. The real power of the Combine framework lies in the operators. By *chaining* operators, you construct a *pipeline* that passes along only the information you're really interested in; the logic of analyzing, filtering, and transforming that information is pushed up into the pipeline itself.

To illustrate, I'll use the notification center as my source of data. Let's go back to my example of a Card view that emits a virtual shriek when it is tapped by posting a notification:

```
static let tapped = Notification.Name("tapped")
@objc func tapped() {
    NotificationCenter.default.post(name: Self.tapped, object: self)
}
```

Now let's say, for purposes of the example, that what the game is interested in when it receives one of these notifications is the string value of the `name` property of the Card that posted the notification. Getting that information is a two-stage process. First, we have to register to receive notifications at all:

```
NotificationCenter.default.addObserver(self,
    selector: #selector(cardTapped), name: Card.tapped, object: nil)
```

Then, when we receive a notification, we have to look to see that its object really is a Card, and if it is, fetch its `name` property and do something with it:

```
@objc func cardTapped(_ n:Notification) {
    if let card = n.object as? Card {
        let name = card.name
        print(name) // or something
    }
}
```

Now let's do the same thing using the Combine framework. We obtain a publisher from the notification center by calling its `publisher` method. But we don't stop there. We don't want to receive a notification in the first place if the object isn't a Card, so we use the `compactMap` operator to cast it safely to Card — and if it isn't a Card, the

pipeline just stops as if nothing had happened. And we only want the Card’s name, so we use the map operator to get it. Here’s the result:

```
let cardTappedCardNamePublisher =  
    NotificationCenter.default.publisher(for: Card.tapped)  
        .compactMap {$0.object as? Card}  
        .map {$0.name}
```

Let’s say that cardTappedCardNamePublisher is an instance property of our view controller. Then what we now have in this instance property is a publisher that publishes the string name of a Card if that Card posts the tapped notification, and otherwise does nothing. Do you see what I mean when I say that the logic is pushed up into the pipeline?

Finally, let’s arrange to receive that string, by subscribing to the publisher:

```
let sink = self.cardTappedCardNamePublisher.sink {  
    print($0)  
}  
sink.store(in: &self.storage)
```

(In real life, of course, the sink function would probably do something useful with the card name each time it receives it.)

Here’s another example. You may have noticed that I didn’t list controls (UIControl) among the built-in publishers. This means we can’t automatically replace the control target–action mechanism using the Combine framework. However, with just a little modification, we can turn a control into a publisher. I’ll demonstrate with a switch control (UISwitch). It has an isOn property, which is changed when the user toggles the switch on or off.

The target–action way to learn that the user has toggled the switch is through the switch’s .valueChanged control event. Let’s write a UISwitch subclass where we instead vend a publisher and funnel the isOn value through it:

```
class MySwitch : UISwitch {  
    @Published var isOnPublisher = false  
    required init?(coder: NSCoder) {  
        super.init(coder:coder)  
        self.isOnPublisher = self.isOn  
        let action = UIAction {[unowned self] _ in  
            self.isOnPublisher = self.isOn  
        }  
        self.addAction(action, for: .valueChanged)  
    }  
}
```

That code illustrates the @Published property wrapper. This creates a publisher behind the scenes, and vends it through the property wrapper’s dollar-sign projectedValue (“[Property Wrappers](#)” on page 332). With our subclass, the way to

be kept informed about changes to the switch's `isOn` property is to subscribe to its publisher, namely `$isOnPublisher`.

So let's subscribe to it! Suppose we are the view controller that ultimately owns this switch. And suppose we have an outlet to the switch:

```
@IBOutlet var mySwitch : MySwitch!
```

Then we, the view controller, can subscribe to that publisher:

```
let sink = self.mySwitch.$isOnPublisher.sink {
    print($0)
}
sink.store(in: &self.storage)
```

But wait — doesn't that look awfully familiar? Yes, it does; it looks like what we did a moment ago with notifications from the notification center. And that's the point. Using Combine, we've effectively reduced the notification center mechanism and the control target-action mechanism to the *same mechanism*.

Even more of the power of the Combine framework emerges when we build complex pipelines. To illustrate, let's combine (sorry about that) the notification center pipeline and the switch pipeline. Imagine that our interface consists of Cards along with a switch. When the switch is on, the cards are interactive: the user can tap one, and we hear about it. When the switch is off, the user's taps do nothing.

To implement this, we can put the notification center publisher and the switch publisher together into a single pipeline. The Combine publisher that does that is `CombineLatest`:

```
lazy var combination =
    Publishers.CombineLatest(
        self.cardTappedCardNamePublisher,
        self.mySwitch.$isOnPublisher
    )
```

What we now have is a publisher that channels the pipelines from our other two publishers into one. It remembers every value that last arrived from either source, and when it gets a new value, it emits a tuple consisting of both values. In our case, that's a `(String, Bool)`.

However, that's not what we actually want to have coming down the pipeline at us. We still want just the string name of the tapped card. So we'll use the `map` operator to extract it:

```
lazy var combination =
    Publishers.CombineLatest(
        self.cardTappedCardNamePublisher,
        self.mySwitch.$isOnPublisher
    )
    .map { $0.0 }
```

Now we're getting just the string name, but we're getting *too many* string names; the switch isn't having any effect. The pipeline is emitting values in response to user taps even when the switch is off! The whole idea of combining these two publishers was to *eliminate* any output when the switch is off. So we'll interpose the filter operator to block any tuples whose Bool is false:

```
lazy var combination =
  Publishers.CombineLatest(
    self.cardTappedCardNamePublisher,
    self.mySwitch.$isOnPublisher
  )
  .filter { $0.1 }
  .map { $0.0 }
```

This is looking much better. If the user taps while the switch is on, we get the card name. If the user taps while the switch is off, nothing happens. But there's still one little problem. The CombineLatest publisher publishes if it gets a value from *either* of its source publishers. That means we don't just get a value when the user taps a Card; we also get a value when the user toggles the switch. We don't want that value to come out the end of the pipeline; we just want to use it to allow or prevent the arrival of the Card name.

What we want to do here is compare *two* values: the new tuple coming down the pipeline, and the *previous* tuple that came down the pipeline most recently. If the difference between the new tuple and the old tuple is merely that the Bool changed, we don't want to emit a value from the pipeline. The way to obtain both the current value and the previous value is with the scan operator. I'll use that operator to pass both the old switch value and the new switch value down the pipeline. Then, in the filter operator, I'll block any value unless *both* the old switch value *and* the new switch value are true:

```
lazy var combination =
  Publishers.CombineLatest(
    self.cardTappedCardNamePublisher,
    self.mySwitch.$isOnPublisher
  )
  .scan((" ",true,true)) { ($1.0, $0.2, $1.1) }
  .filter { $0.1 && $0.2 }
  .map { $0.0 }
```

Our goal is now accomplished. If the user taps a Card while the switch is on, the pipeline produces its name. If the user taps a Card while the switch is off, or toggles the switch, nothing happens.

These examples have only scratched the surface of what the Combine framework can do; but they demonstrate its spirit. And the potential benefits are profound.

In [Chapter 12](#) I complained that the event-driven nature of the Cocoa framework means that you're bombarded with events through different entry points at different

times, so that state has to be maintained in shared instance properties, and understanding the implications of any single entry point method call can be difficult. The Combine framework offers the potential of funneling events into pipelines whose logic can be manipulated internally, so that what comes out is just the information you need when you need it.

For a full discussion of the Combine framework, see my online tutorial book about it (<https://www.apeth.com/UnderstandingCombine>).

## Alternative Architectures

In real life, one way to improve communication between objects in an app of any significant size and complexity is to construct the internal architecture of the app appropriately. My goal in this section is not to recommend a particular architecture, but rather to make you aware of some of the possibilities and how they can ease the pain of communicating between objects in your app.

### Model–View–Controller

The naïve standard architecture implied by Cocoa’s classes is called *Model–View–Controller* (MVC). In this terminology, *model* is the data; *view* is what the user sees and interacts with; and *controller* is the code that mediates between them, deciding what data to display to the user and how, and responding to the user’s actions by modifying the data.

The name *view controller* implies that a `UIViewController` is a controller. Each scene of the app corresponds to one view controller, and the view controllers do all the work of moving data around the app. If one view controller pushes or presents another, it hands the needed data “forward” to that view controller. When a pushed or presented view controller goes out of existence, it hands the needed data “back” to the view controller that pushed or presented it.

Simple MVC, on its own, has some unfortunate consequences. As soon as an app consists of more than one or two view controllers, or if there is a need to access data that cannot easily be handed back and forth in this way, we get into the sort of difficulties that I’ve been describing in this chapter. Moreover, this architecture has a tendency to lead to very large view controller classes, which can make the code hard to read — because functionality is hard to find and trace and understand — and hard to maintain. It can also make the code hard to test.

### Router and Data Space

The fact is that view controllers exist; we’re stuck with them (unless you opt to drop UIKit-based architecture entirely and go with SwiftUI, as I’ll describe in the next section). One key step toward making view controllers tractable is to get the business of

navigation from one view controller to another out of the hands of the view controllers themselves. The idea here is that no view controller should know about the existence of any other view controller. Such knowledge arguably constitutes a leakage of responsibility. Instead, we need some centralized governing mechanism to which we can turn and ask to go to a different scene, whatever that may turn out to mean. This mechanism is sometimes called the *router*; some architectures refer to it as the *coordinator*, or *flow coordinator*. (For a basic example, take a look at [URLNavigator](#) on GitHub.)

Using a router means you're almost certainly going to have to abandon storyboard segues. That may be disappointing, but such is the price that must be paid for separation of responsibilities. The whole idea is that all navigation must be performed by way of the central router mechanism; an automatically triggered segue would go behind the router's back. (Indeed, a further complication arises because UIKit wants to perform "back" navigation automatically. Both a navigation controller's Back button and dismissal of a presented view controller threaten to take place without consulting our code at all; you might have to take definite steps to make sure that that doesn't happen.)

When a view controller doesn't know anything about other view controllers, it doesn't know what data the next view controller needs. The router therefore also has the responsibility for communicating any needed data to the next view controller. We can imagine the router turning to the first view controller and asking it for the data and passing it along to the next view controller.

At that point we may start to wonder why a view controller is maintaining any real data in the first place. Why isn't there just *the data* belonging to the app as a whole? The idea here is that perhaps we could put the data in some centralized global location, where anyone can access it. I call this centralized location the *data space*. The Combine framework is a great way to organize access to the data space. The data space can use Combine pipelines to vend an automatic messaging mechanism. If something changes the data, all subscribers hear about it instantly, and the state of the app remains synchronized everywhere.

## Model–View–Presenter

A further key insight is that, in the Model–View–Controller division of responsibilities, a view controller should perhaps be considered View, not Controller. (Your eyes will be opened to this notion if you watch a wonderful [YouTube video](#) by Dave DeLong.) On that basis, all the logic for deciding what to show the user and how to respond to user actions can be moved out of the view controller into another class, which we may call the Presenter. The Presenter knows nothing of the details of the visible interface, and the view controller knows nothing of the Model. The Presenter



is the one that knows about and talks to the Model; the view controller controls and observes the user interface.

The Presenter and the view controller communicate with one another solely in terms of *intent*. For example, let's say the data represents a bank account. The Presenter might consult the Model and then say to the view controller: "Here is a number. Display it to the user, as being the user's current balance." The Presenter knows nothing of *how* the view controller will do that. The view controller, meanwhile, is responsible for making that number visible to the user, and no more. The view controller knows that the interface has a UILabel for this purpose, and it formats the number and displays it in the label. It knows nothing of where the number came from; what it knows is what the number is *for*, with regard to communicating with the user.

Going the other way, when the user does something, such as tapping a button, the view controller will interpret that button in terms of intent as well. It will say to the Presenter: "Here is what the user wants to do." (For example, "The user wants to make a withdrawal of \$10.") The Presenter is then responsible for the action logic of deciding how to proceed, which might involve consulting or changing the Model, and then might involve telling the view controller what to display next.

This approach has many advantages. The view controller is pared down to the status of an intermediary; it musters the visible interface and communicates with the Presenter, and that's *all* it does. So view controllers are smaller and simpler. It is now far easier for you to find your code, because it will be readily evident what are view controller concerns and what are Presenter concerns. Moreover, the Presenter is testable: given a certain intent as input, does it respond correctly as output? Your unit tests can ask questions like that, without involving the interface.

Another indication of the separation of concerns here is that, when used in conjunction with a router, the Presenter usually doesn't have to import UIKit. It knows nothing of views or view controllers! It embodies the pure logic of a scene's behavior without reference to anything extraneous.

A consequence of this reorganization is that the app architecture as a whole has now become more elaborate. Every scene consists of a little cluster of instances. In addition to the view controller, there is a corresponding Presenter. Every time the router creates and configures a new view controller, it must also create the corresponding Presenter and hook the two together correctly. The need for this assembly step is part of the price that must be paid for the resulting organizational purity and testability of our code.

## Protocols and Reactive Programming

In my discussion of Model–View–Presenter, I have avoided specifying the exact mechanism by which the View (meaning the view controller) and the corresponding

Presenter will communicate with one another. The most obvious approach is that each of them has methods that the other is allowed to call. To make this contract explicit, as well as to facilitate testing, it's probably a good idea to express these public interfaces as protocols — one stating what the view controller is allowed to say to the Presenter, and another stating what the Presenter is allowed to say to the view controller.

It might also be nice to make this communication more automatic. For instance, we could put a setter observer on some property of the view controller, so that when a user action changes that property, the change is relayed directly to the Presenter. Similarly, a change in some property of the Presenter could be relayed directly to the view controller.

One can then imagine going even further and replacing the property observers with a “reactive” mechanism. Before iOS 13, this mechanism typically comes from some third-party library; nowadays, we can use the Combine framework. If we make the same sort of connection between the Presenter and the data, we end up with a kind of automatic data flow throughout the app. Ideally, the interface should depend directly on the data, and the Presenter's adjustments to the data should depend directly on the user's actions, with the view controller acting as a sort of automatic conduit.

## SwiftUI

The SwiftUI framework is a wholesale alternative to Cocoa. It operates on a programming paradigm that's completely different from Cocoa's, and offers the promise of writing iOS apps in a totally different way — not to mention that the same code might be reusable on Apple TV, Apple Watch, and desktop Macs. SwiftUI as a whole is outside the scope of this book; it needs a book of its own. The subject here is how objects see and communicate with one another.

To illustrate how SwiftUI deals with communication, let's start with the prototypical “Hello World” app:

```
struct ContentView : View {  
    var body: some View {  
        Text("Hello World")  
    }  
}
```

That code puts the text “Hello World” in the middle of the screen. But how? It doesn't seem to contain any runnable code. Well, actually it does: `body` is a computed property, and the curly braces that surround `Text("Hello World")` are its getter (with `return` omitted). The interface is constructed in code and returned. But that's not quite accurate; it isn't the *interface* that's returned — it's a *description* of the interface.

In SwiftUI, there is no storyboard; there are no nibs; there are no outlets. There is no UIViewController; there isn't even a UIView. Text is a mere struct, and View is just a protocol. A SwiftUI View is extremely lightweight, and is barely persistent. There are no entry points other than the body property getter, which is merely the answer to an occasional question, "What should this view look like at this moment?"

The most pervasive object-oriented pattern in SwiftUI is that one View instantiates another View. Our simple "Hello World" app consists entirely of our ContentView instantiating a Text object in its body getter. This is the same pattern of visibility by instantiation that I discussed at the start of this chapter: when Manny creates Jack, Manny has a reference to Jack and can hand Jack any information that Jack needs in order to do his job. We do not have to get a reference to something in order to customize its appearance; we customize its appearance as part of its initialization. There is no need for the ContentView to get a reference to the Text in order to tell it what its visible content ("Hello World") should be; the ContentView creates the Text *with* that content.

## Result Builders and Modifiers

SwiftUI's syntax for constructing interfaces is declarative and functional rather than imperative and sequential. To illustrate, I'll add a button to the interface. Initially, I'll declare the button without giving it any functionality:

```
struct ContentView : View {
    var body: some View {
        HStack {
            Text("Hello World")
            Spacer()
            Button("Tap Me") {
                // does nothing
            }
        }.frame(width: 200)
    }
}
```

The Text object returned by the body getter has been replaced by an HStack, which lines up views horizontally. Inside the HStack's curly braces are three objects in series: a Text, a Spacer, and a Button. That seems impossible syntactically. What's happening? The curly braces after HStack are the body of an anonymous function, supplied using trailing closure syntax as a parameter to HStack's initializer. That initializer is allowed to "list" three objects because it is fed to a ViewBuilder, which is a result builder (["Result Builders" on page 341](#)); the ViewBuilder wraps up those objects in a TupleView, and that is what is returned from the anonymous function.

The frame method being called on the HStack determines the width of the HStack on the screen. What's interesting about it is that it *is* a method. Instead of getting a reference to the HStack object and setting a property *of* that object, we apply a method

directly *to* that object. This sort of method is called a *modifier*, and it returns in effect the very same instance to which it was sent. The modified instance is of a more complex type, but this complexity is hidden from us by type erasure and ultimately by the body reverse generic return type `some View` (see “Reverse Generics” on page 339).

Because the return type of a modifier is the same object to which the modifier was applied, modifiers can be chained, just like operators in the Combine framework. The effect is that we describe the object in more and more detail. If we wanted our text-and-button `HStack` to have a yellow background with 20-pixel margins, we could write:

```
HStack {
    Text("Hello World")
    Spacer()
    Button("Tap Me") {
        // does nothing
    }
}.frame(width: 200)
.padding(20)
.background(Color.yellow)
```

## State Properties

At this point, you may be saying: “Fine, I see how visibility by instantiation is sufficient when all you want to do is create the app’s *initial* interface; you configure a view’s initial appearance in its initializer. But what about when the interface needs to *change* over the course of the app’s lifetime?” Amazingly, the answer is the same: SwiftUI *still* handles everything through a view’s initializer. But how can that be?

To demonstrate, let’s give our button some functionality. In particular, the user should be able to tap the button to toggle the text between “Hello World” and “Goodbye World.” Here’s how to do that:

```
struct ContentView : View {
    @State var isHello = true ❶
    var greeting : String {
        self.isHello ? "Hello" : "Goodbye" ❷
    }
    var body: some View {
        HStack {
            Text(self.greeting + " World")
            Spacer()
            Button("Tap Me") {
                self.isHello.toggle() ❸
            }
        }.frame(width: 200)
        .padding(20)
        .background(Color.yellow)
    }
}
```

- ❶ We have declared an `isHello` instance property on which the interface depends — in this case, whether the text should read “Hello World” or “Goodbye World.” Crucially, this instance property is declared with the `@State` property wrapper. This means that if the value of `isHello` changes, whatever depends upon it will be recalculated. So in our code, whenever `isHello` changes, *the body getter will be called again*.
- ❷ For simplicity and clarity, we also declare a computed instance property `greeting` that translates the `Bool` of the `@State` property `isHello` into a corresponding string.
- ❸ The button’s action — what it should do when tapped — is supplied as an anonymous function, using trailing closure syntax, as part of its initializer. That action changes the value of the `@State` property `isHello`. When the `@State` property `isHello` changes in response to the tapping of the button, the body getter is called *again* — and the `Text` content is freshly calculated and takes on its new value. The new result is returned and displayed, and so we have achieved what we set out to accomplish: tapping the button changes the text displayed on the screen.

Notice what did *not* happen in that example:

- The button did not use a target–action architecture: there is no separate target to send a message to, and there is no separate action function. Instead, the action function is part of the button.
- The action function did not talk to the `Text` to change what it displays; it talked only to the `@State` property.
- The `@State` property has no setter observer that talks to the `Text`. Instead, the change in the `@State` property effectively flows “downhill” to the body of the `View`, *automatically*.

In that code, there are no event handlers, no events, and no action handlers. And there are no references from one object to another! There is no problem of communicating data from one object to another, because objects don’t try to communicate with one another. There is just a `View` and its state at any given moment.

Moreover, view state in SwiftUI can be maintained *only* through `@State` properties. A `View` stored property can’t be settable; a view is a struct and isn’t mutable. A `@State` property, on the other hand, is a computed property backed by a property wrapper whose underlying `State` struct *is* mutable. In this way, SwiftUI forces you to clarify the locus of state throughout your app.

Another important lesson of our code is that `View` objects are ephemeral. A `View`’s body getter can be called at any time; it generates some `Views`, like our `Text`, that

describe the interface and are then thrown away. You never know how often a View's body may be called; you never know how often a View struct like our ContentView will be created anew. And you don't need to know! All that matters is that you can instantly describe the interface based on the state.

## Bindings

Some views have even tighter coupling with a `@State`. To illustrate, I'll replace the Button in our example with a Toggle:

```
struct ContentView : View {
    @State var isHello = true
    var greeting : String {
        self.isHello ? "Hello" : "Goodbye"
    }
    var body: some View {
        VStack {
            Text(self.greeting + " World")
            Spacer()
            Toggle("Friendly", isOn: $isHello) // *
        }.frame(width: 150, height: 100)
        .padding(20)
        .background(Color.yellow)
    }
}
```

A Toggle is drawn as a labeled UISwitch. When the user changes the switch, the Text changes in the interface. But how?

A Toggle takes a Binding in its initializer. The State property wrapper vends a Binding property as its dollar-sign `projectedValue`. Our `@State` property is `isHello`, so its binding is `$isHello`. We handed that binding to the Toggle when we initialized it. When the user changes the UISwitch value, that binding's value is toggled. That change takes place in the `@State` property, and so, once again, the Text changes accordingly.

That is somewhat similar to what we did in the earlier discussion of the Combine framework, where we modified a UISwitch to vend a Publisher of its own `isOn` value — except that in SwiftUI, the communication between the `@State` property and the Toggle is two-way and automatic by way of the binding. Our Toggle has no action function, and doesn't need one, because it is tightly integrated with a Bool property through a binding.

## Passing Data Downhill

In a real app, there are multiple “scenes” that share data with one another. These may not be scenes in the storyboard sense, but they are still screens of interface. In a Cocoa app, these scenes are handled by view controllers — and so we end up with the

problems of visibility, getting a reference, and passing data forward and back between view controllers that I've been discussing throughout this chapter. How does SwiftUI handle this situation?

In SwiftUI, each scene is a View. So we are going to have, in addition to our ContentView, another View with which ContentView is somehow to share its data. How is that going to work?

In the first place, the second View must come into existence. That can happen only in one way — some other view must create it. In our example, that can only be the ContentView. Okay, so how would you pass data from the ContentView that does the creating to the new View that is created? In exactly the same way that we've been doing it up to now! You give the second View type a property, and you set that property as part of its initialization.

That is legal, even though a View is an immutable struct whose stored properties cannot be set, because we are *not* mutating the struct; we are *initializing* it. It is also easy, because a View is just a struct. Typically, you won't even bother to write an initializer for your custom View; the implicit memberwise initializer will be sufficient.

In this example, we present modally a secondary view, an instance of a Greeting struct that we ourselves have defined:

```
struct ContentView : View {
    @State var isHello = true
    var greeting : String {
        self.isHello ? "Hello" : "Goodbye"
    }
    @State var showSheet = false
    var body: some View {
        VStack {
            Button("Show Message") {
                self.showSheet.toggle()
            }.sheet(isPresented: $showSheet) { [greeting] in
                Greeting(greeting: greeting) // *
            }
            Spacer()
            Toggle("Friendly", isOn: $isHello)
        }.frame(width: 150, height: 100)
        .padding(20)
        .background(Color.yellow)
    }
}

struct Greeting : View {
    let greeting : String
    var body: some View {
        Text(greeting + " World")
    }
}
```

The sheet modifier is the SwiftUI equivalent of a Cocoa presented view controller. It describes a view that we intend to present modally. Whether it is actively presenting that view modally depends upon a binding to a Bool, which we have supplied by adding a `@State` property called `showSheet`. The Button toggles `showSheet` to true, and the binding `$showSheet` toggles to true in response, and causes the view to be presented.

The view we want to present is a wrapper for a Text that will display the “Hello World” or “Goodbye World” greeting; we have named that wrapper view `Greeting`, and we instantiate it in an anonymous function that we supply as the last parameter to the sheet modifier, using trailing closure syntax. When we instantiate `Greeting`, we must also *configure* the `Greeting` instance we are creating. We do that through the `Greeting` initializer. The `Greeting` struct belongs to us, so we’re free to give it a `greeting` property, and Swift synthesizes the memberwise initializer with a `greeting:` parameter. All we have to do is set that property as we create the `Greeting`. Once again, the data flows “downhill.”

(The `[greeting]` capture list is a trick to get the `greeting` value inside the anonymous function to update automatically from the `greeting` instance property when there has been a change in the `@State` instance property `isHello` on which it depends.)

## Passing Data Uphill

What about when the data needs to flow “uphill” out of the secondary view back to the view that presented it? This is the sort of problem that you’d solve in Cocoa programming using the protocol-and-delegate pattern (“[Implementing Delegation](#)” on [page 633](#)). In SwiftUI, you simply “lend” the secondary view the binding from a `@State` property.

Suppose our `Greeting` view is to contain a text field (SwiftUI `TextField`) in which is to be entered the user’s name, and that this information is to be communicated back to our `ContentView`. Then `ContentView` would contain another `@State` property:

```
@State var name = ""
```

And `Greeting` would contain a `@Binding` property:

```
@Binding var username : String
```

When `ContentView` initializes `Greeting`, the memberwise initializer now has a `username:` parameter that takes a string `Binding`; we hand it the binding from the `@State` property:



```

Button("Show Message") {
    self.showSheet.toggle()
}.sheet(isPresented: $showSheet) { [greeting] in
    Greeting(greeting: greeting,
             username: self.$name)
}

```

And Greeting’s TextField is initialized with that binding:

```

TextField("Your Name", text:$username)
    .frame(width:200)
    .textFieldStyle(RoundedBorderTextFieldStyle())

```

Whatever the user types in this text field in the Greeting view flows “uphill” through the username binding, which is the @State property name binding, and changes the value of the @State property name back in the ContentView. And now the data flows “downhill” once more: the ContentView body getter will be called again, and all views that depend upon this @State property will change to match.

Once again, what’s most significant in that example is what we *didn’t* do. We didn’t get a reference from the Greeting back to the ContentView. The Greeting didn’t call any method of the ContentView. It didn’t set a property of the ContentView. It set its *own* property, username. In SwiftUI, communication between objects is communication of data, and takes place through bindings. They are like little pipelines from one object to another — and the object at one end (our Greeting) doesn’t have to know anything about what’s at the other end.

## Custom State Objects

You can construct your own state object by writing a custom class that conforms to the ObservableObject protocol. For example, your app’s data might reside in, or be accessed through, an ObservableObject. To use it, you can assign an instance of your class into a @StateObject property. Then you can access its properties directly. Any properties of an ObservableObject that are marked with the @Published attribute will behave like @State properties: when a @Published property changes, your body getter that references it is called again, and you can access an associated binding through the dollar-sign projectedValue of the underlying StateObject property wrapper struct.

To illustrate, suppose we want the name entered into the text field by the user to persist between launches. We can implement that functionality using an ObservableObject. To get started, I’ll write a simple NameSaver class with a username property:

```

class NameSaver : ObservableObject {
    @Published var username: String = ""
    // ...
}

```

An `ObservableObject` has an `objectWillChange` property that is a `Publisher`; in fact, it is a `Subject`, as I described in the earlier discussion of the Combine framework. The `objectWillChange` property is synthesized automatically, so we don't have to declare it (though we can if we want to). Being a `Subject`, it notifies its subscribers whenever its `send` method is called. A `@Published` property of an `ObservableObject` automatically calls that `send` method. It is also itself a `Publisher` — or rather, its dollar-sign `projectedValue` is a `Publisher`. So if our Views refer to a `NameSaver` instance in a `@StateObject` property, they will automatically be updated when the `NameSaver`'s `username` changes. Our `NameSaver` will be the ultimate “source of truth” for the `username`.

In our `ContentView`, there is no longer a `@State String` property called `name`; it is replaced by a `@StateObject NameSaver` property called `nameSaver`, which is the new “source of truth”:

```
@StateObject var nameSaver = NameSaver()
```

When we need to access the value of the `NameSaver username` property, we do so directly:

```
Text(self.nameSaver.username.isEmpty ? "" :  
      greeting + ", " + self.nameSaver.username)
```

When we need a binding to the `NameSaver username` property, we pass through the binding from `nameSaver`, namely `$nameSaver`:

```
Button("Show Message") {  
    self.showSheet.toggle()  
}.sheet(isPresented: $showSheet) { [greeting] in  
    Greeting(greeting: greeting,  
             username: self.$nameSaver.username)  
}
```

The app now works exactly as it did before. But if that was all we wanted, why did we create `NameSaver` in the first place? We did it so that we can give `NameSaver` further functionality — namely, to save the `username` to disk. Let's add that functionality to `NameSaver` now.

The idea here is to back the `username` property with a file on disk. When a `NameSaver` is initialized, I'll have it read the `username` value from disk. And when the `username` value changes, I want it to be written to disk. To ensure that, I'll construct a Combine pipeline that subscribes to the `username` publisher and responds to changes by saving the new value.

Here's a slightly simplified version of the resulting NameSaver class:

```
var storage = Set<AnyCancellable>()
var fileURL : URL? { /* return URL of text file on disk */ }
init() {
    self.username = self.read() ?? ""
    self.$username
        .sink { [unowned self] in self.save($0) }
        .store(in: &self.storage)
}
func read() -> String? {
    if let url = self.fileURL {
        return try? String(contentsOf: url, encoding: .utf8)
    }
    return nil
}
func save(_ newName: String) {
    if let url = self.fileURL {
        try? newName.write(to: url, atomically: true, encoding: .utf8)
    }
}
```

Presto! The username that the user types in the TextField is now saved to disk and persists between launches.

Those examples should suffice to demonstrate the nature, spirit, and fundamental principles of SwiftUI.



---

# C, Objective-C, and Swift

The APIs for Cocoa and its associated frameworks are written in Objective-C or its underlying base language, C. Messages that you send to Cocoa using Swift are being translated for you into Objective-C. Objects that you send and receive back and forth across the Swift/Objective-C bridge are Objective-C objects. Some objects that you send from Swift to Objective-C are even being translated for you into other object types, or into nonobject types.

This appendix summarizes the relevant linguistic features of C and Objective-C, and describes how Swift interfaces with those features. I do not explain here how to write Objective-C! For example, I'll talk about Objective-C methods and method declarations, because you need to know how to call an Objective-C method from Swift; but I'm not going to explain how to call an Objective-C method using Objective-C.

## The C Language

C provides the linguistic underpinnings of Objective-C. Objective-C is a superset of C; everything that is true of C is true also of Objective-C. It is possible, and often necessary, to write long stretches of Objective-C code that are, in effect, pure C. Some of the Cocoa APIs are written in C. Therefore, in order to know about Objective-C, it is necessary to know about C.

The C language was evolved during the early 1970s at Bell Labs in conjunction with the creation of Unix. The reference manual, *The C Language* by Brian Kernighan and Dennis M. Ritchie, was published in 1978, and remains one of the best computer books ever written.

C statements, including declarations, must end in a semicolon. Variables must be declared before use. A variable declaration consists of a data type name followed by the variable name, optionally followed by assignment of an initial value:

```
int i;  
double d = 3.14159;
```

The C `typedef` statement starts with an existing type name and defines a new synonym for it:

```
typedef double NSTimeInterval;
```

## C Data Types

C is not an object-oriented language; its data types are not objects (they are *scalars*). The basic built-in C data types are all numeric: `char` (one byte), `int` (four bytes), `float` and `double` (floating-point numbers), and varieties such as `short` (short integer), `long` (long integer), `unsigned short`, and so on. Objective-C adds `NSInteger`, `NSUInteger` (unsigned), and `CGFloat`. The C `bool` type is actually a numeric, with zero representing false; Objective-C adds `BOOL`, which is also a numeric. Even the C native text type (string) is actually a null-terminated array of `char`.

Swift supplies numeric types that interface directly with C numeric types, even though Swift's types are objects and C's types are not. Swift type aliases provide names that correspond to the C type names: a Swift `CBool` (`Bool`) is a C `bool`, a Swift `CChar` (`Int8`) is a C `char`, a Swift `CInt` (`Int32`) is a C `int`, a Swift `CFloat` (`Float`) is a C `float`, and so on. Swift `Int` interchanges with `NSInteger`; Swift `UInt` interchanges with `NSUInteger`. `CGFloat` is adopted as a Swift type name. Swift `ObjCBool` represents Objective-C `BOOL`, but it is not a `Bool`; to derive the `Bool`, take its `boolValue`. (You can, however, assign a Swift `Bool` *literal* where an `ObjCBool` is expected, because `ObjCBool` adopts `ExpressibleByBooleanLiteral`.)

A major difference between C and Swift is that C (and therefore Objective-C) implicitly coerces when variables with different numeric types are assigned, passed, compared to, or combined with one another; Swift doesn't, so you must coerce explicitly to make types match, as I described in [Chapter 3](#).

## C Enums

A C enum is numeric; values are some sort of integer, and can be implicit (starting from 0) or explicit. Enums arrive in various forms into Swift, depending on how they are declared.

### Old-fashioned C enum

This is the simplest and oldest form:

```
enum State {  
    kDead,  
    kAlive  
};  
typedef enum State State;
```

(The `typedef` in the last line merely allows C programs to use the term `State` as the name of this type instead of the more verbose `enum State`.) In C, the enumerator names `kDead` and `kAlive` are not “cases” of anything; they are not namespaced. They are constants, and as they are not explicitly initialized, they represent 0 and 1 respectively. An enum declaration can specify the integer type further; this one doesn’t, so the values are typed in Swift as `UInt32`.

This old-fashioned sort of C enum arrives as a Swift struct adopting the `RawRepresentable` protocol, and its enumerands (here, `kDead` and `kAlive`) arrive into Swift as synonyms for instances of the `State` struct with an appropriate `rawValue` (here, 0 and 1 respectively). The result is that you can use the enumerator names as a medium of interchange wherever a `State` enum arrives from or is expected by C. If a C function `setState` takes a `State` enum parameter, you can call it from Swift with one of the `State` enumerator names:

```
setState(kDead)
```

Observe that there are no namespaces in this story! The enumerands are bare names, not members of the `State` struct; you say `kDead`, not `State.kDead`. If you are curious about what integer is represented by the name `kDead`, you have to take its `rawValue`. You can also create an arbitrary `State` value by calling its `init(rawValue:)` initializer — there is no check to see whether this value is one of the defined constants. But you aren’t expected to do either of those things.

## NS\_ENUM

Starting back in Xcode 4.4, a C enum notation was introduced that uses the `NS_ENUM` macro:

```
typedef NS_ENUM(NSInteger, UIStatusBarAnimation) {
    UIStatusBarAnimationNone,
    UIStatusBarAnimationFade,
    UIStatusBarAnimationSlide,
};
```

That notation both specifies the integer type and associates a type name with this enum as a whole. Swift imports an enum declared this way *as a Swift enum* with the name and raw value type intact; the enumerator names become namespaced case names, with the common prefix subtracted:

```
enum UIStatusBarAnimation : Int {
    case none
    case fade
    case slide
}
```

Going the other way, a Swift enum with an `Int` raw value type can be exposed to Objective-C using the `@objc` attribute:

```
@objc enum Star : Int {
    case blue
    case white
    case yellow
    case red
}
```

Objective-C sees that as an enum with type `NSInteger` and enumerand names `StarBlue`, `StarWhite`, and so on. That is the *only* kind of Swift enum that Objective-C can see.

In the special case where the `NS_ENUM` type name ends in `Error`, it arrives from Objective-C into Swift as a struct conforming to `Error`. Here’s the start of an enum declaration from the Core Location framework:

```
typedef NS_ENUM(NSInteger, CLError) {
    kCLLocationUnknown = 0,
    kCLErrorDenied,
    kCLErrorNetwork,
    // ...
};
```

The result is that when Objective-C throws an `NSError` whose domain is `kCLErrorDomain` and whose code is `kCLLocationUnknown`, Swift can catch it by saying `catch CLError.locationUnknown`.

A knotty problem arises when you write a Swift switch statement that exhausts a C enum tag’s cases. What if, in a future release, the C code is changed to add a case to this enum? If that happens, and if your “exhaustive” switch receives an unknown case, you’ll crash. But Swift is ready with a solution:

- When you compile your code, you’ll be warned by the compiler that this enum “may have additional unknown values.” To remove the warning, you add a `default` case. Normally, the compiler would warn you that your default case will never be executed, because your switch is exhaustive; but in this situation, your switch might *not* be exhaustive some day, so that warning doesn’t appear.
- In addition, you mark the default case with the `@unknown` attribute. This tells the compiler that you *think* your switch is exhaustive (without the default), and you’d like to be warned if it isn’t. If your switch isn’t exhaustive, you’ll get the warning now; if some day a new case is added to the enum, you’ll get the warning then, and you can silence it by adding the new case to your switch.

Let’s demonstrate. Here’s a C enum:

```
typedef NS_ENUM(NSInteger, TestEnum) {
    TestEnumOne
    TestEnumTwo
};
```



This arrives into Swift as an enum called `TestEnum`. Here's an exhaustive switch over a `TestEnum`:

```
switch test { // test is a TestEnum
case .one : break
case .two : break
} // compiler warns
```

We get a warning from the compiler. Our switch looks exhaustive, but in the future it might not be. So we add an `@unknown default` case, and the warning goes away:

```
switch test { // test is a TestEnum
case .one : break
case .two : break
@unknown default: break
}
```

Suppose the C enum later acquires another case (case `.three`). No problem! Our Swift switch is crash-proof, because there's a `default` case. Even better, when we compile against the updated C code, our Swift switch will now get another warning, telling us that the switch is no longer exhaustive.

If the Objective-C code is our own, and if we're sure that the C enum will never acquire a new case, we can mark it with `NS_CLOSED_ENUM` instead of `NS_ENUM`; this will cause Swift to treat `TestEnum` like an ordinary Swift enum.



Some enums in the Swift standard library and Foundation overlays are marked as open to future additional cases in the same way as `NS_ENUM`.

## NS\_OPTIONS

Another variant of C enum notation, using the `NS_OPTIONS` macro, is suitable for bitmasks:

```
typedef NS_OPTIONS(NSUInteger, UIViewAutoresizing) {
    UIViewAutoresizingNone           = 0,
    UIViewAutoresizingFlexibleLeftMargin = 1 << 0,
    UIViewAutoresizingFlexibleWidth   = 1 << 1,
    UIViewAutoresizingFlexibleRightMargin = 1 << 2,
    UIViewAutoresizingFlexibleTopMargin  = 1 << 3,
    UIViewAutoresizingFlexibleHeight    = 1 << 4,
    UIViewAutoresizingFlexibleBottomMargin = 1 << 5
};
```

An enum declared like that arrives into Swift as a struct adopting the `OptionSet` protocol. The `OptionSet` protocol adopts the `RawRepresentable` protocol, so this is a struct with a `rawValue` instance property holding the underlying integer. The C enum case names are represented by static properties, each of whose values is an instance of this struct; the names of these static properties are imported with the common prefix

subtracted. In Swift, this struct is namespaced by nesting it into the `UIView` class as `UIView.AutoresizingMask`:

```
struct AutoresizingMask : OptionSet {
    init(rawValue: UInt)
    static var flexibleLeftMargin: UIView.AutoresizingMask { get }
    static var flexibleWidth: UIView.AutoresizingMask { get }
    static var flexibleRightMargin: UIView.AutoresizingMask { get }
    static var flexibleTopMargin: UIView.AutoresizingMask { get }
    static var flexibleHeight: UIView.AutoresizingMask { get }
    static var flexibleBottomMargin: UIView.AutoresizingMask { get }
}
```

When you say something like `UIView.AutoresizingMask.flexibleLeftMargin`, it *looks* as if you are initializing a case of a Swift enum, but in fact this is an instance of the `UIView.AutoresizingMask` struct, whose `rawValue` property has been set to the value declared by the original C enum — which, for `.flexibleLeftMargin`, is `1<<0`. Because a static property of this struct is an instance of the same struct, you can, as I explained in [“Inference of Type Name with Static/Class Members” on page 145](#), omit the struct name when supplying a static property name where the struct is expected:

```
self.view.autoresizingMask = .flexibleWidth
```

Because this is an `OptionSet` struct, you can represent and manipulate the bitmask as if it were a `Set`:

```
self.view.autoresizingMask = [.flexibleWidth, .flexibleHeight]
```



In Objective-C, where an `NS_OPTIONS` enum is expected, you pass `0` to indicate that no options are provided. In Swift, where a corresponding struct is expected, you pass `[]` (an empty set) or omit the `options:` parameter entirely. Some `NS_OPTIONS` enums have an explicit option that *means* `0`; Swift sometimes won't bother to import its name, because passing `[]` means the same thing. To set a `UIView.AutoresizingMask` value to `UIViewAutoresizingNone` in Swift, set it to `[]` (not `.none`).

## Global string constants

The names of many Objective-C global string constants (referred to jokingly by Apple as *stringly typed*) are namespaced by importing them into Swift as static struct properties. This is accomplished by means of the `NS_STRING_ENUM` and `NS_EXTENSIBLE_STRING_ENUM` Objective-C macros. For example, the names of the `NSAttributedString` attribute keys used to be simple global string constants (type `NSString*`):

```
NSString* const NSFontAttributeName;
NSString* const NSParagraphStyleAttributeName;
NSString* const NSForegroundColorAttributeName;
// ... and so on ...
```

This meant that they were global string constants in Swift as well. Now, however, they are typed as `NSAttributedStringKey` values:

```
NSAttributedStringKey const NSFontAttributeName;
NSAttributedStringKey const NSParagraphStyleAttributeName;
NSAttributedStringKey const NSForegroundColorAttributeName;
// ... and so on ...
```

`NSAttributedStringKey`, in Objective-C, is just a synonym for `NSString`, but it is marked with the `NS_EXTENSIBLE_STRING_ENUM` macro:

```
typedef NSString * NSAttributedStringKey NS_EXTENSIBLE_STRING_ENUM;
```

The result is that these names are imported into Swift as namespaced static properties of an `NSAttributedString.Key` struct with names like `.name`, `.paragraphStyle`, and so on.

## C Structs

A C struct is a compound type whose elements can be accessed by name using dot-notation after a reference to the struct:

```
struct CGPoint {
    CGFloat x;
    CGFloat y;
};
typedef struct CGPoint CGPoint;
```

After that declaration, it becomes possible to talk like this in C:

```
CGPoint p;
p.x = 100;
p.y = 200;
```

A C struct arrives wholesale into Swift as a Swift struct, which is thereupon endowed with Swift struct features. `CGPoint` in Swift has `CGFloat` instance properties `x` and `y`, but it also magically acquires the implicit memberwise initializer! In addition, a zeroing initializer with no parameters is injected; saying `CGPoint()` makes a `CGPoint` whose `x` and `y` are both 0. Extensions can supply additional features, and the Swift CoreGraphics header adds a few to `CGPoint`:

```
extension CGPoint {
    static var zero: CGPoint { get }
    init(x: Int, y: Int)
    init(x: Double, y: Double)
}
```

As you can see, a Swift `CGPoint` has additional initializers accepting `Int` or `Double` arguments, along with another way of making a zero `CGPoint`, `CGPoint.zero`. `CGSize` is treated similarly. `CGRRect` is particularly well endowed with added methods and properties in Swift.

The fact that a Swift struct is an object, while a C struct is not, does not pose any problems of communication. You can assign or pass a Swift `CGPoint` where a C `CGPoint` is expected, because `CGPoint` came from C in the first place. The fact that Swift has endowed `CGPoint` with object methods and properties doesn't matter; C doesn't see them. All C cares about are the `x` and `y` elements of this `CGPoint`, which are communicated from Swift to C without difficulty.

## C Pointers

A C pointer is an integer designating the location in memory (the *address*) where the real data resides. Allocating and disposing of that memory is a separate matter. The declaration for a pointer to a data type is written with an asterisk after the data type name; a space can appear on either or both sides of the asterisk. These are equivalent declarations of a pointer-to-int:

```
int *intPtr1;
int* intPtr2;
int * intPtr3;
```

The type name itself is `int*` (or, with a space, `int *`). Objective-C, for reasons that I'll explain later, uses C pointers heavily, so you're going to be seeing that asterisk a lot if you look at any Objective-C.

A C pointer arrives into Swift as an `UnsafePointer` or, if writable, an `UnsafeMutablePointer`; this is a generic, and is specified to the actual type of data pointed to. (A pointer is “unsafe” because Swift isn't managing the memory for, and can't even guarantee the integrity of, what is pointed to.)

To illustrate, here's an Objective-C `UIColor` method declaration; I haven't discussed this syntax yet, but just concentrate on the types in parentheses:

```
- (BOOL) getRed: (CGFloat *) red
    green: (CGFloat *) green
    blue: (CGFloat *) blue
    alpha: (CGFloat *) alpha;
```

`CGFloat` is a basic numeric type. The type `CGFloat *` states (despite the space) that these parameters are all `CGFloat*` — that is, pointer-to-`CGFloat`.

The Swift translation of that declaration looks, in effect, like this:

```
func getRed(_ red: UnsafeMutablePointer<CGFloat>,
    green: UnsafeMutablePointer<CGFloat>,
    blue: UnsafeMutablePointer<CGFloat>,
    alpha: UnsafeMutablePointer<CGFloat>) -> Bool
```

`UnsafeMutablePointer` in this context is used like a Swift `inout` parameter: you declare and initialize a `var` of the appropriate type beforehand, and then pass its

address as argument by way of the & prefix operator. When you pass the address of a reference in this way, you are in fact creating and passing a pointer:

```
var r : CGFloat = 0
var g : CGFloat = 0
var b : CGFloat = 0
var a : CGFloat = 0
c.getRed(&r, green: &g, blue: &b, alpha: &a)
```

It's fine to take the address of a variable reference and hand it to a C function that returns immediately, as we are doing here; but do not *persist* such an address yourself. If `r` is a `CGFloat`, saying `let rPtr = &r` would be a really bad idea; the compiler will warn, and in future this warning is slated to be promoted to an error. If you need to do that sort of thing, call some form of `withUnsafePointer`, which takes an anonymous function within which the pointer is valid.

In C, to access the memory pointed to by a pointer, you use an asterisk before the pointer's name: `*intPtr` is “the thing pointed to by the pointer `intPtr`.” In Swift, you use the pointer's `pointee` property. In this example, we receive a `stop` parameter typed originally as a `BOOL*`, a pointer-to-`BOOL`; in Swift, it's an `UnsafeMutablePointer<ObjCBool>`. To set the `BOOL` at the far end of this pointer, we set the pointer's `pointee`:

```
// mas is an NSMutableAttributedString, r is an NSRange, f is a UIFont
mas.enumerateAttribute(.font, in: r) { value, r, stop in
    if let value = value as? UIFont, value == f {
        // ...
        stop.pointee = true
    }
}
```

The most general type of C pointer is pointer-to-void (`void*`), also known as the *generic pointer*. The term `void` here means that no type is specified; it is legal in C to use a generic pointer wherever a specific type of pointer is expected, and vice versa. In effect, pointer-to-void casts away type checking as to what's at the far end of the pointer. This will appear in Swift as a “raw” pointer, either `UnsafeRawPointer` or `UnsafeMutableRawPointer`.

Raw pointers are even more unsafe than normal pointers; not only the lifetime and extent of the memory pointed to, but also the *type* of what's in that memory, is now your responsibility. As far as the pointer is concerned, what the memory contains is just bytes. You can cast a typed unsafe pointer to a raw unsafe pointer, but not the other way. Instead, starting with a raw pointer, you can load an object from an address within the memory, or you can *bind* the memory to derive a typed pointer to the same memory:

```

// buff is a CImageBuffer
if let baseAddress = CVPixelBufferGetBaseAddress(buff) {
    // baseAddress is an UnsafeMutableRawPointer
    let addrptr = baseAddress.assumingMemoryBound(to: UInt8.self) // *
    // addrptr is an UnsafeMutablePointer<UInt8>
    // ...
}

```

## C Arrays

A C array contains a fixed number of elements of a single data type. Under the hood, it is a contiguous block of memory sized to accommodate this number of elements of this data type. For this reason, the name of an array in C is the name of a pointer to the first element of the array. If `arr` has been declared as an array of `int`, the term `arr` can be used wherever a value of type `int*` (a pointer-to-`int`) is expected. The C language will indicate an array type either by appending square brackets to a reference or as a pointer.

For example, the C function `CGContextStrokeLineSegments` is declared like this:

```

void CGContextStrokeLineSegments(CGContextRef c,
    const CGPoint points[],
    size_t count
);

```

The square brackets in the second line tell you that the second parameter is a C array of `CGPoint`s.

A C array carries no information about how many elements it contains, so to pass this C array to this function, you must also *tell* the function how many elements the array contains; that's what the third parameter in that declaration is for.

A C array of `CGPoint` is a pointer to a `CGPoint`, so that function's declaration is translated into Swift like this:

```

func __strokeLineSegments(
    between points: UnsafePointer<CGPoint>?,
    count: Int)

```

Now, you're not really expected to call that function. The `CGContext` Swift overlay provides a pure Swift version, `strokeLineSegments`, which takes a Swift array of `CGPoint` with no need to provide a count; and the original `CGContextStrokeLineSegments` has been marked `NS_REFINED_FOR_SWIFT` to generate the two underscores and hide it from you. But let's say you wanted to call `__strokeLineSegments` anyway. How would you do it?

To call `__strokeLineSegments` and pass it a C array of `CGPoint`s, it would appear that you need to *make* a C array of `CGPoint`s. A C array is not, by any stretch of the imagination, a Swift array; so how on earth will you do this?

Surprise! You don't have to. Even though a Swift array is not a C array, you can pass a pointer to a Swift array here. In this example, you don't even need to pass a pointer; you can pass a reference to a Swift array *itself*. And since this is not a mutable pointer, you can declare the array with `let`; indeed, you can even pass a Swift array literal! No matter which approach you choose, Swift will convert to a C array for you as the argument crosses the bridge from Swift to C:

```
let c = UIGraphicsGetCurrentContext()!
let arr = [
    CGPoint(x:0,y:0),
    CGPoint(x:50,y:50),
    CGPoint(x:50,y:50),
    CGPoint(x:0,y:100),
]
c.__strokeLineSegments(between: arr, count: arr.count)
```

However, you *can* form a C array if you really want to. This is where the “Unsafe” in an unsafe pointer really comes into play: you must explicitly manage the memory yourself, and getting it right is entirely up to you.

First, you set aside the block of memory by declaring an `UnsafeMutablePointer` of the desired type and calling the class method `allocate(capacity:)` with the desired number of elements. Then you populate (technically, *initialize*) that memory. You will also be responsible for undoing all of that later; you deinitialize the memory and deallocate it. The best way to ensure that is to configure the block of memory and then immediately complete the memory management in a defer block:

```
let ptr = UnsafeMutablePointer<CGPoint>.allocate(capacity:4)
ptr.initialize(repeating: .zero, count: 4)
defer {
    ptr.deinitialize(count:4)
    ptr.deallocate()
}
```

Once the memory management is configured, you can manipulate the element values. In this instance, we want to write real `CGPoint` values into the memory block. You could do this by manipulating the `pointee`, but you can also use subscripting, which might be a lot more convenient. Be careful to stay within the block of memory you have configured! There's no range checking, and writing outside memory you own can mysteriously wreck your program later:

```
ptr[0] = CGPoint(x:0,y:0)
ptr[1] = CGPoint(x:50,y:50)
ptr[2] = CGPoint(x:50,y:50)
ptr[3] = CGPoint(x:0,y:100)
```

Finally, since the `UnsafeMutablePointer` *is* a pointer, you pass *it*, not a pointer to it, as argument:

```
let c = UIGraphicsGetCurrentContext()!
c.__strokeLineSegments(between: ptr, count: 4)
```

The same convenient subscripting is available when you receive a C array. In this example, `col` is a `UIColor`; `comp` is typed as an `UnsafePointer` to `CGFloat`. That is really a C array of `CGFloat`, and so you can access its elements by subscripting:

```
if let comp = col.cgColor.__unsafeComponents,
    let sp = col.cgColor.colorSpace,
    sp.model == .rgb {
    let red = comp[0]
    let green = comp[1]
    let blue = comp[2]
    let alpha = comp[3]
    // ...
}
```

## C Strings

The native C string type is not a distinct type; it is a null-terminated array of `char`. Therefore it may be typed in Swift as `[Int8]` or `[CChar]`, because `CChar` is `Int8`, or as `UnsafePointer<Int8>` or `UnsafePointer<CChar>`, because a C array is a pointer to the first element of the array. These representations are effectively interchangeable.

A C string can't be formed as a literal in Swift, but you can pass a Swift String where a C string is expected; in this example, `takeCString` is a C function that takes a C string:

```
let s = "hello"
takeCString("hello") // fine
takeCString(s) // fine too
```

If you have to, you can form a real C string in Swift. The Swift Foundation overlay provides the `cString(using:)` method:

```
let arrayOfCChar : [CChar]? = s.cString(using: .utf8)
takeCString(arrayOfCChar!)
```

Swift String provides the `utf8CString` property, a `ContiguousArray<CChar>`; you can turn that into a pointer by calling its `withUnsafeBufferPointer` method:

```
let contiguousArrayOfCChar : ContiguousArray<CChar> = s.utf8CString
contiguousArrayOfCChar.withUnsafeBufferPointer { ptr -> Void in
    takeCString(ptr.baseAddress!)
}
```

More simply, you can call the `String.withCString` method:

```
s.withCString { ptr -> Void in
    takeCString(ptr)
}
```



In the other direction, a UTF-8 C string can be rendered into a Swift String by way of a Swift String initializer such as `init(cString:)` or `init?(validatingUTF8:)`. To specify some other encoding, call the static method `decodeCString(_:as:)`. In this example, `returnCString` is a C function that returns a C string:

```
let result : UnsafePointer<Int8> = returnCString()
let resultString : String = String(cString: result)
```

## C Functions

A C function declaration starts with the return type (which might be `void`, meaning no returned value), followed by the function name, followed by a parameter list — parentheses containing comma-separated pairs consisting of the type followed by the parameter name. The parameter names are purely internal. C functions are global, and Swift can call them directly.

Here's the C declaration for an Audio Services function:

```
OSStatus AudioServicesCreateSystemSoundID(
    CFURLRef inFileURL,
    SystemSoundID* outSystemSoundID)
```

An `OSStatus` is basically an `Int32`. A `CFURLRef` is a `CTypeRef` (“[Memory Management of CTypeRefs](#)” on page 666) and is called `CFURL` in Swift. A `SystemSoundID` is a `UInt32`, and the `*` makes this a C pointer, as we already know. The whole thing translates directly into Swift:

```
func AudioServicesCreateSystemSoundID(
    _ inFileURL: CFURL,
    _ outSystemSoundID: UnsafeMutablePointer<SystemSoundID>) -> OSStatus
```

`CFURL` is interchangeable with `NSURL` and Swift URL, for reasons that I'll explain later; so here we are, calling this C function in Swift (while ignoring the returned value):

```
let sndurl = Bundle.main.url(forResource: "test", withExtension: "aif")!
var snd : SystemSoundID = 0
AudioServicesCreateSystemSoundID(sndurl as CFURL, &snd)
```

## Struct functions

Most of the commonly used C global functions in Cocoa operate on a struct; they have the name of that struct as the first element of their name, and have that struct itself as their first parameter. In Swift, where structs are objects, these functions are often transformed into methods on the struct.

For example, in Objective-C, the way to construct a `CCGRect` from scratch is with the `CCGRectMake` function, and the way to divide a `CCGRect` is with the `CCGRectDivide` function:

```
CGRect rect = CGRectMake(10,10,100,100);
CGRect arrow;
CGRect body;
CGRectDivide(rect, &arrow, &body, arrowHeight, CGRectMinYEdge);
```

In Swift, `CGRectMake` is overshadowed by the `CGRect` struct initializer `init(x:y:width:height:)`, and `CGRectDivide` is overshadowed by the `CGRect` `divided` method:

```
let rect = CGRect(x: 10, y: 10, width: 100, height: 100)
let (arrow, body) = rect.divided(atDistance: arrowHeight, from: .minYEdge)
```

## Pointer-to-function

In C, a function has a type based on its signature, and the name of a function is a reference to the function, and so it is possible to pass a function — sometimes termed a *pointer-to-function* — by using the function’s name where a function of that type is expected.

Here’s the declaration for a C function from the Audio Toolbox framework:

```
OSStatus AudioServicesAddSystemSoundCompletion(SystemSoundID inSystemSoundID,
    CFRunLoopRef __nullable inRunLoop,
    CFStringRef __nullable inRunLoopMode,
    AudioServicesSystemSoundCompletionProc inCompletionRoutine,
    void * __nullable inClientData)
```

(I’ll explain the term `__nullable` later.) What’s an `AudioServicesSystemSoundCompletionProc`? Here’s how it’s declared:

```
typedef void (*AudioServicesSystemSoundCompletionProc)(
    SystemSoundID ssID,
    void* __nullable clientData);
```

In the first line, the asterisk and name in parentheses means that this is the name of a pointer-to-function. A `SystemSoundID` is a `UInt32`. So this declaration means that an `AudioServicesSystemSoundCompletionProc` is a pointer to a function taking two parameters (typed `UInt32` and pointer-to-void) and returning no result.

Amazingly, you can pass a Swift function where a C pointer-to-function is expected! As always when passing a function, you can define the function separately and pass its name, or you can form the function inline as an anonymous function. If you’re going to define the function separately, it cannot be a method. A function defined at the top level of a file is fine; so is a function defined locally within a function.

So here’s my `AudioServicesSystemSoundCompletionProc`, declared at the top level of a file:

```
func soundFinished(_ snd:UInt32, _ c:UnsafeMutableRawPointer?) {
    AudioServicesRemoveSystemSoundCompletion(snd)
    AudioServicesDisposeSystemSoundID(snd)
}
```

And here's my code for playing a sound file as a system sound, including a call to `AudioServicesAddSystemSoundCompletion`:

```
let sndurl = Bundle.main.url(forResource: "test", withExtension: "aif")!
var snd : SystemSoundID = 0
AudioServicesCreateSystemSoundID(sndurl as CFURL, &snd)
AudioServicesAddSystemSoundCompletion(snd, nil, nil, soundFinished, nil)
AudioServicesPlaySystemSound(snd)
```

## Objective-C

Objective-C is built on top of C. It adds some syntax and features, but it continues at the same time to use C syntax and data types, and remains C under the hood.

The Objective-C language was created by Brad Cox and Tom Love in the early 1980s to furnish C with the object-oriented capabilities of Smalltalk. Its adoption by NeXT, under the leadership of Steve Jobs, drove the evolution toward the mature form of the language during the late 1980s, spearheaded by Steve Naroff. In 1997, when Jobs had returned to Apple and Apple acquired NeXT, Objective-C became the language of Mac OS X Cocoa. Cocoa Touch, created for the iPhone a decade later, still uses Objective-C; that's why your use of Swift in programming iOS through Cocoa depends upon Swift's interoperability with Objective-C.

Unlike Swift, Objective-C has no namespaces. For this reason, different frameworks distinguish their contents by starting the names of types, functions, and constants with distinct prefixes. The “CG” in “CGFloat” stands for Core Graphics, because it is declared in the Core Graphics framework. The “NS” in “NSString” stands for NeXT-Step, the framework that later became Cocoa.

## Objective-C Objects and C Pointers

All the data types and syntax of C are part of Objective-C. But Objective-C is object-oriented, so it needs a way of adding objects to C. It does this by taking advantage of C pointers. C pointers accommodate having anything at all at the far end of the pointer; management of whatever is pointed to is a separate matter, and that's just what Objective-C takes care of. Objective-C object types are expressed using C pointer syntax.

Here's the Objective-C declaration for the `addSubview:` method:

```
- (void)addSubview:(UIView *)view;
```

I haven't discussed Objective-C method declaration syntax yet, but focus on the type declaration for the view parameter, in parentheses: it is `UIView*`. This appears to mean "a pointer to a `UIView`." It does mean that — and it doesn't. What's at the far end of the pointer is certainly a `UIView` instance. But *all* Objective-C object references are pointers. The fact that this is a pointer is merely a consequence of the fact that it's an object.

The Swift translation of this method declaration doesn't appear to involve any pointers:

```
func addSubview(_ view: UIView)
```

What you pass as argument when calling `addSubview(_:)` from Swift is a `UIView` instance — which is exactly what Objective-C expects. The asterisk used in Objective-C to express the fact that this is an object is obviously not present in Swift. There is, of course, a sense in which you *are* passing a pointer when you pass a Swift class instance — because classes are reference types! A class instance is actually seen the same way by both Swift and Objective-C; the difference is that Swift doesn't use pointer *notation*.

Objective-C's `id` type is a general pointer to an object — the object equivalent of C pointer-to-void. Any object type can be assigned or cast to or from an `id`. Because `id` is itself a pointer, a reference declared as `id` doesn't use an asterisk; it is rare (though not impossible) to encounter an `id*`.

## Objective-C Objects and Swift Objects

Objective-C objects are classes and instances of classes. They arrive into Swift more or less intact. You won't have any trouble subclassing Objective-C classes or working with instances of Objective-C classes. (For how Swift sees Objective-C properties and accessors, see [Chapter 11](#).)

Going the other way, when Objective-C expects an object, it expects a class or an instance of a class, and Swift can provide it. But what Objective-C means by a class, in general, is a subclass of `NSObject`. Every other kind of object known to Swift has to be bridged or boxed in order to survive the journey into Objective-C's world. Moreover, many features of Swift are meaningless to Objective-C, and those features are invisible to Objective-C. Objective-C can't see any of the following:

- Swift enums, except for an `@objc` enum with an `Int` raw value
- Swift structs, except for structs that come ultimately from C or that are bridged to Objective-C classes
- Swift classes not derived from `NSObject`
- Swift protocols not marked `@objc`

- Protocol extensions
- Generics
- Tuples
- Nested types

Nothing in that list can be directly exposed to Objective-C — and, by implication, nothing that *involves* anything in that list can be exposed to Objective-C. Suppose we have a class `MyClass` not derived from `NSObject`. Then if your `UIViewController` subclass has a property typed as `MyClass`, that property cannot be exposed to Objective-C; and if your `UIViewController` subclass has a method that receives or returns a value typed as `MyClass`, that method cannot be exposed to Objective-C.

Nevertheless, you are perfectly free to use such properties and methods, even in a class (such as a `UIViewController` subclass) that *is* exposed to Objective-C. Objective-C simply won't be able to see those aspects of the class that would be meaningless to it.

## Exposure of Swift to Objective-C

With a few exceptions, even if Objective-C *can* theoretically see a thing, it *won't* see it unless you explicitly expose it to Objective-C. You do that with the `@objc` attribute.

Let's talk first about the exceptions. These are things in your Swift code that Objective-C will be able to see automatically, *without* an explicit `@objc` attribute:

- A class derived from `NSObject`. Such a class will be declared in Swift either as subclassing `NSObject` itself or as subclassing some `NSObject` subclass, typically a class defined by Cocoa (such as `UIViewController`).
- Within such a class, an override of a method defined in Objective-C (such as `UIViewController`'s `viewDidLoad`) or defined in Swift but marked `@objc`.
- Within such a class, an implementation of a member of a protocol adopted by the class, if the protocol is defined in Objective-C (such as `NSCoding`'s `init(coder:)`) or defined in Swift but marked `@objc`.
- Within such a class, an instance property marked `@IBOutlet` or `@IBInspectable` or `@Managed`, or a method marked `@IBAction` (see [Chapter 8](#)).

Otherwise, to expose to Objective-C a property, method, or protocol, mark it with `@objc`. The compiler will stop you if you try to expose to Objective-C something that it is unable to see (such as a property whose type Objective-C cannot see or cannot understand). A protocol marked as `@objc` automatically becomes a class protocol.

A useful trick, if you have several methods that you need to expose explicitly to Objective-C, is to clump them into an extension that is itself marked `@objc`; there is then no need to mark those methods individually with `@objc`. If most or all of a

class's members are to be exposed to Objective-C, you can mark the class `@objc-Members`; again, there is then no need to mark those members individually with `@objc`. Conversely, if a class member would be exposed to Objective-C and you want to prevent this, you can mark it `@nonobjc`.

There are two additional uses of `@objc`:

#### *Expose a member of a nonObjective-C class*

Even if a class is not exposed to Objective-C, it can be useful to mark a member of that class with `@objc` so that your Swift code can take advantage of Objective-C language features with regard to that member. A Timer using the target-action pattern ([Chapter 12](#)) can have a method of a nonObjective-C class as its action, but only if that method is marked `@objc`, because the method is specified with a selector ([Chapter 2](#)) and selectors are an Objective-C feature.

#### *Change the Objective-C name of something*

When you mark something with `@objc`, you can add parentheses containing the name by which you want Objective-C to see this thing. You are free to do this even for a class or a class member that Objective-C can see already. An example appeared in [Chapter 11](#) when I changed the name by which Objective-C sees a property accessor. When using this feature, you bypass Swift's behind-the-scenes *name mangling* designed to prevent clashes with any existing Objective-C names, so you must take responsibility for avoiding such a clash yourself.



Class members marked `@objc`, `@IBAction`, and `@IBOutlet` can be marked `private` to speed up compilation and to hide them from your class's public API within this module. However, as I mentioned in [Chapter 5](#), you shouldn't do that with an implementation of an optional member of an adopted Objective-C protocol, as this will hide the method from Cocoa and it will never be called.

## Bridged Types and Boxed Types

Swift will convert certain native nonclass types to their Objective-C class equivalents for you. The following native Swift structs are bridged to Objective-C class types:

- String to NSString
- Numbers (and Bool) to NSNumber
- Array to NSArray
- Dictionary to NSDictionary
- Set to NSSet

Bridging has two immediate practical consequences for your code:

### *Parameter passing*

You can pass an instance of the Swift struct where the Objective-C class is expected. In fact, in general you'll rarely even encounter the Objective-C class, because the Swift rendering of the API will display it as the Swift struct: if an Objective-C method takes an `NSString`, you'll see it in Swift as taking a `String`, and so on.

### *Casting*

You can cast between the Swift struct and the Objective-C class. When casting from Swift to Objective-C, this is not a downcast, so the bare `as` operator is all you need. But casting from Objective-C to Swift, except for `NSString` to `String`, involves adding type information — `NSNumber` wraps some specific numeric type, and the collection types contain elements of some specific type — so you might need to cast down with `as!` or `as?` in order to specify that type.

Also, certain common Objective-C structs that can easily be wrapped by `NSValue` in Objective-C are bridged to `NSValue` in Swift. The common structs are `CGPoint`, `CGSize`, `CGRect`, `CGAffineTransform`, `UIEdgeInsets`, `UIOffset`, `NSRange`, `CATransform3D`, `CMTIME`, `CMTIME_MAPPING`, `CMTIME_RANGE`, `MKCoordinate`, and `MKCoordinateSpan`.

In addition, various Cocoa Foundation classes are overlaid by Swift types whose names are the same but without the “NS” prefix. Often, extra functionality is injected to make the type behave in a more Swift-like way; and, where appropriate, the Swift type may be a struct, allowing you to take advantage of Swift value type semantics. `NSMutableData`, for instance, becomes `otiose`, because `Data`, the overlay for Objective-C `NSData`, is a struct with mutating methods and can be declared with `let` or `var`. And `Date`, the overlay for Objective-C `NSDate`, adopts `Equatable` and `Comparable`, so that an `NSDate` method like `earlierDate:` can be replaced by the `min` function.

The Swift overlay types are all bridged to their Foundation counterparts. The Swift rendering of an Objective-C API will show you the Swift overlay type rather than the Objective-C type: a Cocoa method that takes or returns an `NSDate` in Objective-C will take or return a `Date` in Swift, and so on. If necessary, you can cast between bridged types; for example, you can turn a `Date` into an `NSDate` with `as`.

(The exception that proves the rule is `AttributedString`, new in Swift 5.5; see [Chapter 11](#). It is injected into Foundation, but it is not an overlay type, and it isn't bridged to `NSAttributedString`. `NSAttributedString` appears in Swift as `NSAttributedString`, and to use an `AttributedString` where an `NSAttributedString` is expected, you have to coerce, not cast.)

Objective-C `id` is rendered as `Any` in Swift. This means that wherever an Objective-C API accepts an `id` parameter, that parameter is typed in Swift as `Any` and can be

passed any Swift value whatever. If that value is of a bridged type, *the bridge is crossed automatically*, just as if you had cast explicitly with `as`. A `String` becomes an `NSString`, an `Array` becomes an `NSArray`, a number is wrapped in an `NSNumber`, a `CGPoint` or other common struct is wrapped in an `NSValue`, a `Data` becomes an `NSData`, and so forth.

The same rule applies when you pass a Swift collection to Objective-C, with regard to the collection's elements. If an element is of a bridged type, *the bridge is crossed automatically*. The typical case in point is when you pass a Swift array to Objective-C: an array of `Int` becomes an `NSArray` of `NSNumber`s; an array of `CGPoint` becomes an `NSArray` of `NSValues`; for an array with an `Optional` element type, any `nil` elements become `NSNull` instances (Chapter 11).

What happens when an object tries to cross the bridge from Swift to Objective-C, but that instance is *not* of a bridged type? (Such an object might be an enum, a struct of a nonbridged type, or a class that doesn't derive from `NSObject`.) On the one hand, Objective-C can't do anything with this object. On the other hand, the object needs to be allowed to cross the bridge somehow, especially because you, on the Swift side, might ask for the object back again later, and it needs to be returned to you intact.

To illustrate, suppose `Person` is a struct with a `firstName` and a `lastName` property. Then you might need to be able to do something like this:

```
// lay is a CALayer
let p = Person(firstName: "Matt", lastName: "Neuburg")
lay.setValue(p, forKey: "person")
// ... time passes ...
if let p2 = lay.value(forKey: "person") as? Person {
    print(p2.firstName, p2.lastName) // Matt Neuburg
}
```

Amazingly, this works. How? The answer, in a nutshell, is that Swift *boxes* this object into something that Objective-C can see *as* an object, even though Objective-C can't *do* anything with that object other than store and retrieve it. How Swift does this is irrelevant; it's an implementation detail, and none of your business. It happens that in this case the `Person` object is wrapped up in a `_SwiftValue`, but that name is unimportant; what's important is that it is an Objective-C object, wrapping the value we provided. In this way, Objective-C is able to store the object for us, in its box, and hand it back to us intact upon request. Like Pandora, Objective-C will cope perfectly well as long as it doesn't look in the box!

## Objective-C Methods

In Objective-C, method parameters can (and nearly always do) have external names, and the name of a method as a whole is not distinct from the external names of the parameters: the parameter names are *part* of the method name, with a colon



appearing where each parameter would need to go. Here's a typical Objective-C method declaration from Cocoa's NSString class:

```
- (NSString *)stringByReplacingOccurrencesOfString:(NSString *)target
                        withString:(NSString *)replacement
```

The Objective-C name of that method is:

```
stringByReplacingOccurrencesOfString:withString:
```

A declaration for an Objective-C method has three parts:

- Either + or -, meaning that the method is a class method or an instance method, respectively.
- The data type of the return value, in parentheses. It might be void, meaning no returned value.
- The name of the method, split after each colon so as to make room for the parameters. Following each colon is the data type of the parameter, in parentheses, followed by a placeholder (internal) name for the parameter.

## Renamification

When Swift calls an Objective-C method, there's an obvious mismatch between the rules and conventions of the two languages:

### *Swift method names*

A Swift method is a function; the base name of the function is followed by parentheses, and if the function's parameters have external names (labels), they appear inside the parentheses, like this: `swiftFunction(parameter:)`.

### *Objective-C method names*

An Objective-C method name involves *no* parentheses and has *no* separate base name. If the method takes parameters, the parameter names, each followed by a colon, constitute the name of the method; the first thing in the name is just the name of the first parameter, like this: `objcMethodWithParameter:`. (If it takes no parameters, its name is just its name with no colon.)

To cope with this mismatch, Swift renders the Objective-C method's name more Swift-like by a process called *renamification*, which is performed by a component called the *Clang importer*, mediating between the two languages. The renamification rules are rather elaborate, but you don't need to know the details; you can get a general sense of how they behave from an example. Here's how the renamification rules transform the Objective-C `stringByReplacingOccurrencesOfString:withString:` method name into a Swift function name:

1. Swift prunes *redundant initial type names*. We're starting with a string, and it's obvious from the return type that a string is returned, so there's no point saying

string at the start. We are left with `byReplacingOccurrencesOfString:with-String:`.

2. Swift prunes *initial by*. That's a common Cocoa locution, but Swift finds it merely verbose. Now we're down to `replacingOccurrencesOfString:with-String:`.
3. Swift prunes *redundant final type names*. It's obvious that the parameters are strings, so there's no point saying `string` at the end of the parameter names. That leaves `replacingOccurrencesOf:with:`.
4. Finally, Swift decides *where to split* the first parameter name into the Swift base name and the external first parameter name. Here, Swift sees that the first parameter name now ends with a known preposition, `of`, so it splits before that preposition.

Here's the resulting renamification of that method:

```
func replacingOccurrences(of target:String, with replacement:String)
```

And here's an actual example of calling it:

```
let s = "hello"
let s2 = s.replacingOccurrences(of: "ell", with:"ipp")
// s2 is now "hippo"
```

If the Objective-C method being renamified belongs to you, you can intervene manually and *tell* Swift how to renamify this method, by appending `NS_SWIFT_NAME(...)` to the declaration (before the semicolon), where what's inside the parentheses is a Swift function reference. Here's an example:

```
- (void) triumphOverThing: (Thing*) otherThing NS_SWIFT_NAME(triumph(over:));
```

The Clang importer would normally renamify that in Swift as:

```
func triumphOverThing(_ otherThing: Thing)
```

Presumably that's because the importer doesn't understand `over` as a preposition. But by intervening manually, we've told it to use this instead:

```
func triumph(over otherThing: Thing)
```

## Internal parameter names

When you *call* an Objective-C method from Swift, Objective-C's internal names for the parameters don't matter; you don't use them, and you don't need to know or care what they are. The internal names do *appear* in the Swift declaration of the method, and they might even help you understand what the method does; but they are not involved in the call. This is the Objective-C declaration of a method:

```
- (NSString *)stringByReplacingOccurrencesOfString:(NSString *)target
    withString:(NSString *)replacement
```

And this is the Swift translation of that declaration:

```
func replacingOccurrences(of target:String, with replacement:String)
```

But at the call site, the terms `target` and `replacement` don't appear:

```
let s2 = s.replacingOccurrences(of: "ell", with: "ipp")
```

When you *override* an Objective-C method in Swift, code completion will suggest internal names corresponding to the Objective-C internal names, but you are free to change them. Here's the Objective-C declaration of the `UIViewController prepareForSegue:sender:` instance method:

```
- (void)prepareForSegue:(UIStoryboardSegue *)segue sender:(nullable id)sender;
```

When you override that method in your `UIViewController` subclass, the suggested template, in accordance with the renamification rules, looks like this:

```
override func prepare(for segue: UIStoryboardSegue, sender: Any?) {  
    // ...  
}
```

But the internal names are local variable names for your use inside the function body, and Objective-C doesn't care about them; so you can change them. This is a valid (but weird) override of `prepareForSegue:sender:` in Swift:

```
override func prepare(for war: UIStoryboardSegue, sender bow: Any?) {  
    // ...  
}
```

## Reverse renamification

Now let's talk about what happens going the other way: How does Objective-C see methods declared in Swift? The simplest case is when the first parameter has no external name. Here's a Swift method intended as the action method of a button in the interface:

```
@IBAction func doButton(_ sender: Any?) {  
    // ...  
}
```

That method is seen by Objective-C as `doButton:`. That is the canonical form for an action method with one parameter, and for that reason I like to declare my action methods along those lines.

If a Swift method's first parameter does have an external name, then as seen by Objective-C that external name is appended to the Swift base name following an inserted preposition `with`. Here's a Swift method:

```
func makeHash(ingredients stuff:[String]) {  
    // ...  
}
```

That method is seen by Objective-C as `makeHashWithIngredients:`.

But if the external name of the first parameter is a preposition, then it is appended directly to the Swift base name. Here's another Swift method:

```
func makeHash(of stuff:[String]) {  
    // ...  
}
```

That method is seen by Objective-C as `makeHashOf:`.

## Overloading

Objective-C does not permit overloading of methods. Two ViewController instance methods called `myMethod:` returning no result, one taking a `CGFloat` parameter and one taking an `NSString` parameter, would be illegal in Objective-C.

In Swift, however, overloading is legal. You are perfectly free to have two methods of the same class, both called `myMethod(_:)`, one taking a `CGFloat` and the other taking a string. But it would be illegal to expose both of those methods to Objective-C! If methods are overloads of one another in Swift, you can't expose more than one of them to Objective-C.

## Variadics

Objective-C has its own version of a variadic parameter. The `NSArray` instance method `arrayWithObjects:` is declared like this:

```
+ (id)arrayWithObjects:(id)firstObj, ... ;
```

Unlike Swift, such methods in Objective-C must somehow be told explicitly how many arguments are being supplied. Many such methods, including `arrayWithObjects:`, use a `nil` terminator; that is, the caller supplies `nil` after the last argument, and the callee knows when it has reached the last argument because it encounters `nil`. A call to `arrayWithObjects:` in Objective-C would look something like this:

```
NSArray* pep = [NSArray arrayWithObjects: manny, moe, jack, nil];
```

Objective-C cannot call (or see) a Swift method that takes a variadic parameter. Swift, however, *can* call an Objective-C method that takes a variadic parameter, provided it is marked `NS_REQUIRES_NIL_TERMINATION`. And in fact, `arrayWithObjects:` is marked in this way, so you can say `NSArray(objects:1, 2, 3)` and Swift will supply the missing `nil` terminator.

## Initializers and factories

Objective-C initializer methods are instance methods; actual instantiation is performed using the `NSObject` class method `alloc`, for which Swift has no equivalent (and doesn't need one), and the initializer message is sent to the instance that results.

Here's how you create a `UIColor` instance by supplying red, green, blue, and alpha values in Objective-C:

```
UIColor* col = [[UIColor alloc] initWithRed:0.5 green:0.6 blue:0.7 alpha:1];
```

The name of that initializer, in Objective-C, is `initWithRed:green:blue:alpha:`. It's declared like this:

```
- (UIColor *)initWithRed:(CGFloat)red green:(CGFloat)green  
    blue:(CGFloat)blue alpha:(CGFloat)alpha;
```

In short, an initializer method, to all outward appearances, is just an instance method like any other in Objective-C.

Swift, nevertheless, is able to detect that an Objective-C initializer *is* an initializer, because the name is special — it starts with `init`! Therefore, Swift is able to translate an Objective-C initializer into a Swift initializer. The word `init` is stripped from the start of the method name, and the preposition `with`, if it appears, is stripped as well. What's left is the external name of the first parameter.

So Swift translates the initializer `initWithRed:green:blue:alpha:` from Objective-C into the Swift initializer `init(red:green:blue:alpha:)`, which is declared like this:

```
init(red: CGFloat, green: CGFloat, blue: CGFloat, alpha: CGFloat)
```

And you'd call it like this:

```
let col = UIColor(red: 0.5, green: 0.6, blue: 0.7, alpha: 1.0)
```

The same principle operates in reverse: a Swift initializer `init(value:)` is visible to and callable by Objective-C under the name `initWithValue:`.



If you're in charge of the Objective-C header being imported into Swift, be sure to mark your designated initializers as `NS_DESIGNATED_INITIALIZER` so that Swift can distinguish them. To block an initializer explicitly from being imported into Swift, mark it `NS_UNAVAILABLE`.

There is a second way to create an instance in Objective-C. Very commonly, a class will supply a class method that is a *factory* for instances. For example, the `UIColor` class has a class factory method `colorWithRed:green:blue:alpha:`, declared as follows:

```
+ (UIColor*) colorWithRed: (CGFloat) red green: (CGFloat) green  
    blue: (CGFloat) blue alpha: (CGFloat) alpha;
```

Swift detects a factory method of this kind by some pattern-matching rules — a class method that returns an instance of the class, and whose name begins with the name of the class, stripped of its prefix — and translates it *as an initializer*, stripping the class name (and the `with`) from the start of the first parameter name. If the resulting initializer exists already, as it does in this example, then Swift treats the factory

method as superfluous and suppresses it completely! The Objective-C class method `colorWithRed:green:blue:alpha:` isn't callable from Swift, because it would be identical to `init(red:green:blue:alpha:)` which already exists.

## Error pointers

There's a specialized pattern in Objective-C where a method returning a `BOOL` or an object takes an `NSErrorPointer` parameter — that is, an `NSError**`, the Objective-C equivalent of an `inout Error`. The idea is that if there's an exception, the method returns `false` or `nil` respectively, and sets the `NSError` parameter by indirection. This is Objective-C's way of solving the problem that it can return only one value (there are no tuples).

For example, `NSString` has an initializer declared in Objective-C like this:

```
- (instancetype)initWithContentsOfFile:(NSString *)path
                                encoding:(NSStringEncoding)enc
                                error:(NSError **)error;
```

And here is some Objective-C code that calls that initializer:

```
NSError* err;
NSString* s = [[NSString alloc] initWithContentsOfFile:f
                                encoding:NSUTF8StringEncoding
                                error:&err];

if (s == nil) {
    NSLog(@"%@", err);
}
```

As you can see, the whole procedure really is a lot like using a Swift `inout` parameter. An `NSError` variable is prepared beforehand, and its address is passed to the initializer as the `error:` argument. After the call, we test the initializer's result for `nil` explicitly, to see whether the initialization succeeded; if it didn't, we can examine the `NSError` variable to see what the error was. This is an annoyingly elaborate but necessary dance in Objective-C (and is all too easy to get wrong).

In Swift, an Objective-C method that takes an `NSError**` and returns a `BOOL` or a nullable object is automatically recast to take advantage of the error mechanism. The `error:` parameter is stripped from the Swift translation of the declaration, and is replaced by a `throws` marker:

```
init(contentsOfFile path: String, encoding enc: String.Encoding) throws
```

If there are no other parameters besides the `NSError**` and the parameter name ends with `Error:`, those words are stripped to form the base name of the Swift method, which takes no parameters. If the Objective-C method returns a `BOOL`, Swift portrays it as returning no result, as the presence or absence of an error is dispositive.

If you call a throws method that belongs to Objective-C and the Objective-C method returns `false` or `nil`, Swift sees that as a throw and throws the error that the Objective-C method returned by indirection. If the Objective-C method gets the pattern wrong and returns `nil` or `false` but forgets to set the `NSError`, Swift just makes up an error (`_GenericObjCError.nilError`) and throws it anyway.

The same method bridging works also in reverse. A Swift throws method that is exposed to Objective-C is seen as taking an `NSError**` parameter. If the method returns a value, Objective-C sees that value as nullable, and the value will be `nil` if the method actually throws an error; if it doesn't return a value, Objective-C sees it as returning a `BOOL`, which will be `false` if the method actually throws an error.

## Async methods

A Swift async method ([Chapter 6](#)) that could be made visible to Objective-C if it weren't async can be made visible to Objective-C even though it *is* async. It is automatically treated and renamed as a method taking a completion handler.

Here's a typical async method declaration in Swift:

```
@objc func asyncFunc() async -> Data
```

That declaration is renamed into Objective-C like this:

```
- (void)asyncFuncWithCompletionHandler:(void (^)(NSData *))completionHandler;
```

Our async method returns a `Data`, so in Objective-C the completion handler block takes an `NSData` parameter. If our async method were also marked `throws`, then the completion handler would take *two* parameters, an `NSData` and an `NSError`.

## Selectors

A Cocoa Objective-C method will sometimes expect as parameter the name of a method that Cocoa is to call later. Such a name is called a *selector*. For example, the Objective-C `UIControl addTarget:action:forControlEvents:` method can be called as a way of telling a button in the interface, “From now on, whenever you are tapped, send this message to this object.” The object is the `target:` parameter. The message, the `action:` parameter, is a selector. The target object *implements* this method; Cocoa will *call* this method on the target object.

You may imagine that, if this were a Swift method, you'd be passing a function here. But a selector is not the same as a function. It's just a name. Objective-C, unlike Swift, is so dynamic that it is able at runtime to construct and send an arbitrary message to an arbitrary object based on the name alone. Still, a selector is not exactly a string, either; it's a separate object type, designated in Objective-C declarations as `SEL` and in Swift declarations as `Selector`.

You can create a Selector by calling the Selector initializer, which takes a string. In the following examples, `b` is a UIButton:

```
b.addTarget(self, action: Selector("doNewGame:"), for: .touchUpInside)
```

As a shorthand, you can even pass a string literal where a Selector is expected, even though a Selector is not a string:

```
b.addTarget(self, action: "doNewGame:", for: .touchUpInside)
```

But don't do either of those things! Forming a literal selector string by hand is an invitation to form the string incorrectly, resulting in a selector that at best will fail to work and at worst will cause your app to crash. Swift solves this problem by providing `#selector` syntax (described in [Chapter 2](#)):

```
b.addTarget(self, action: #selector(doNewGame), for: .touchUpInside)
```

The use of `#selector` syntax has numerous advantages. In addition to translating the method name to a selector for you, the compiler can check for the existence of the method in question, and can stop you from telling Objective-C to use a selector to call a method that isn't exposed to Objective-C (which would cause a crash at runtime).

Indeed, `#selector` syntax means that you will probably *never* need to form a selector from a string! Nevertheless, you can do so if you really want to; basically, you have to reverse renamify the method by hand:

1. The string starts with everything that precedes the left parenthesis in the method name (the base name).
2. If the method takes *no parameters*, stop. That's the end of the string.
3. If the method's first parameter has an external parameter name, append `With` and a capitalized version of that name, unless it is a preposition, in which case append a capitalized version of it directly.
4. Add a colon.
5. If the method takes exactly *one parameter*, stop. That's the end of the string.
6. If the method takes more than one parameter, add the external names of all remaining parameters, with a colon after each external parameter name.

Observe that this means that if the method takes any parameters, its Objective-C name string will end with a colon. Capitalization counts, and the name should contain no spaces or other punctuation except for the colons.

To illustrate, here are some Swift method declarations, with their Objective-C name strings given in a comment:



```

func sayHello() -> String          // "sayHello"
func say(_ s:String)              // "say:"
func say(string s:String)         // "sayWithString:"
func say(of s:String)             // "sayOf:"
func say(_ s:String, times n:Int) // "say:times:"

```

## CTypeRefs

A CTypeRef is a pointer to an opaque struct that acts as a pseudo-object. (I talked about CTypeRef pseudo-objects and their memory management in [Chapter 13](#).) CTypeRef functions are global C functions. Swift can call C functions, and before Swift 3 introduced renaming, CTypeRef code looked almost as if Swift were C:

```

// before Swift 3:
let con = UIGraphicsGetCurrentContext()!
let sp = CGColorSpaceCreateDeviceGray() ❶
// ... colors and locs are arrays of CGFloat ...
let grad = CGGradientCreateWithColorComponents(sp, colors, locs, 3) ❷
CGContextDrawLinearGradient ( ❸
    con, grad, CGPointMake(89,0), CGPointMake(111,0), [])

```

Notice that the “subject” of each function call appears at the start of the name:

- ❶ `CGColorSpaceCreateDeviceGray` creates a `CGColorSpace` pseudo-object.
- ❷ `CGGradientCreateWithColorComponents` creates a `CGGradient` pseudo-object; the first parameter is the `CGColorSpace` pseudo-object.
- ❸ `CGContextDrawLinearGradient` draws a gradient in a `CGContext` pseudo-object; the first parameter is the `CGContext` pseudo-object, and the second parameter is the `CGGradient` pseudo-object.

Nowadays, as part of renaming, many commonly used CTypeRef functions, especially in the Core Graphics framework, are recast as if the “subject” CTypeRef objects were genuine class instances, with the functions themselves as initializers and instance methods. Those lines are recast in Swift like this (thanks to the mighty power of `NS_SWIFT_NAME`):

```

let con = UIGraphicsGetCurrentContext()!
let sp = CGColorSpaceCreateDeviceGray() ❶
// ... colors and locs are arrays of CGFloat ...
let grad = CGGradient(colorSpace: sp, ❷
    colorComponents: colors, locations: locs, count: 3)
con.drawLinearGradient(grad, ❸
    start: CGPoint(x:89,y:0), end: CGPoint(x:111,y:0), options:[])

```

In that code:

- ❶ `CGColorSpaceCreateDeviceGray` is unchanged.

- ❷ `CGGradientCreateWithColorComponents` is turned into a `CGGradient` pseudo-object initializer, with external parameter names.
- ❸ `CGContextDrawLinearGradient` is turned into an instance property of a `CGContext` pseudo-object, with external parameter names.

Many `CTypeRefs` are *toll-free bridged* to corresponding Objective-C object types. `CFString` and `NSString`, `CFNumber` and `NSNumber`, `CFArray` and `NSArray`, `CFDictionary` and `NSDictionary` are all toll-free bridged (and there are many others). Such pairs are interchangeable by casting. This is much easier in Swift than in Objective-C. In Objective-C, ARC memory management doesn't apply to `CTypeRefs`; therefore you must perform a *bridging cast*, to tell Objective-C how to manage this object's memory as it crosses between the memory-managed world of Objective-C objects and the unmanaged world of C and `CTypeRefs`. But in Swift, `CTypeRefs` *are* memory-managed, and so there is no need for a bridging cast; you can just cast, plain and simple.

In this code from one of my apps, I'm using the ImageIO framework. This framework has a C API (which has not been renamed) and uses `CTypeRefs`. `CGImageSourceCopyPropertiesAtIndex` returns a `CFDictionary` whose keys are `CFStrings`. The easiest way to obtain a value from a dictionary is by subscripting, but you can't do that with a `CFDictionary`, because it isn't an object — so I cast it to a Swift dictionary. The key `kCGImagePropertyPixelWidth` is a `CFString`, and yet when I try to use it directly in a subscript, Swift allows me to do so, because Swift injects `AnyHashable` conformance into `CFString`:

```
let d = CGImageSourceCopyPropertiesAtIndex(src, 0, nil) as! [AnyHashable:Any]
let width = d[kCGImagePropertyPixelWidth] as! CGFloat
```

Similarly, in this code, I form a dictionary `d` using `CFString` keys — and then, by casting, I can pass it to the `CGImageSourceCreateThumbnailAtIndex` function where a `CFDictionary` is expected:

```
let d : [AnyHashable:Any] = [
    kCGImageSourceShouldAllowFloat : true,
    kCGImageSourceCreateThumbnailWithTransform : true,
    kCGImageSourceCreateThumbnailFromImageAlways : true,
    kCGImageSourceThumbnailMaxPixelSize : w
]
let imref = CGImageSourceCreateThumbnailAtIndex(src, 0, d as CFDictionary)!
```

A `CTypeRef` is a pointer (to a pseudo-object), so it is interchangeable with C pointer-to-void. This can result in a perplexing situation in Swift. If a C API casts a `CTypeRef` as a pointer-to-void, Swift will see it as an `UnsafeRawPointer`. How can you cast between this and the actual `CTypeRef`? You cannot use the memory binding technique that I used earlier to turn an `UnsafeRawPointer` into an `UnsafePointer`

generic, because the `CTypeRef` does not lie at the far end of the pointer; it is the pointer.

We might simply call the global `unsafeBitCast` function, but that's dangerous (as the name suggests), because it gives the resulting `CTypeRef` no memory management. The correct approach is to pass through an `Unmanaged` generic to apply memory management; its `fromOpaque` static method takes an `UnsafeRawPointer`, and its `toOpaque` instance method yields an `UnsafeMutableRawPointer`. (I owe this technique to Martin R.; see <http://stackoverflow.com/a/33310021/1187415>.)

To illustrate, I'll repeat the earlier example where I called `CGImageSourceCopyPropertiesAtIndex`, but this time I won't cast to a Swift dictionary; I'll work with the result as a `CFDictionary` to extract the value of its `kCGImagePropertyPixelWidth` key. To do so, I'll call `CFDictionaryGetValue`, which takes an `UnsafeRawPointer` parameter and returns an `UnsafeRawPointer` result. To form the parameter, I'll cast a `CFString` to an `UnsafeMutableRawPointer`; to work with the result, I'll cast an `UnsafeRawPointer` to a `CFNumber`. No one of sound mind would ever write this code, but it does work:

```
let result = CGImageSourceCopyPropertiesAtIndex(src, 0, nil!)
let key = kCGImagePropertyPixelWidth // CFString
let p1 = Unmanaged.passUnretained(key).toOpaque() // UnsafeMutableRawPointer
let p2 = CFDictionaryGetValue(result, p1) // UnsafeRawPointer
let n = Unmanaged<CFNumber>.fromOpaque(p2!).takeUnretainedValue() // CFNumber
var width : CGFloat = 0
CFNumberGetValue(n, .cgFloatType, &width) // width is now 640.0
```

## Blocks

A *block* is a C language feature introduced by Apple starting in iOS 4. It is very like a C function, but it behaves as a closure and can be passed around as a reference type. A block, in fact, is parallel to a Swift function, and the two are interchangeable: you can pass a Swift function where a block is expected, and when a block is handed to you by Cocoa it appears as a function.

In C and Objective-C, a block declaration is signified by the caret character (^), which appears where an asterisk would appear in a C pointer-to-function declaration. The `NSArray` instance method `sortedArrayUsingComparator:` takes an `NSComparator` parameter, which is defined through a typedef like this:

```
typedef NSComparisonResult (^NSComparator)(id obj1, id obj2);
```

That says: “An `NSComparator` is a block taking two `id` parameters and returning an `NSComparisonResult`.” In Swift, therefore, that typedef is translated as the function signature `(Any, Any) -> ComparisonResult`. It is then trivial to supply a function of the required type as argument when you call `sortedArray(comparator:)` in Swift:

```

let arr = ["Mannyz", "Moey", "Jackx"]
let arr2 = (arr as NSArray).sortedArray { s1, s2 in
    let c1 = String((s1 as! String).last!)
    let c2 = String((s2 as! String).last!)
    return c1.compare(c2)
} // [Jackx, Moey, Mannyz]

```

In many cases, there won't be a `typedef`, and the type of the block will appear directly in a method declaration. Here's the Objective-C declaration for a `UIView` class method that takes two block parameters:

```

+ (void)animateWithDuration:(NSTimeInterval)duration
    animations:(void (^)(void))animations
    completion:(void (^ __nullable)(BOOL finished))completion;

```

In that declaration, `animations:` is a block taking no parameters (`void`) and returning no value, and `completion:` is a block taking one `BOOL` parameter and returning no value. Here's the Swift translation:

```

class func animate(withDuration duration: TimeInterval,
    animations: @escaping () -> Void,
    completion: ((Bool) -> Void)? = nil)

```

Those are methods that you would *call*, passing a function as argument where a block parameter is expected (and see [Chapter 2](#) for an example of actually doing so). Here's a method that you would *implement*, where a function is passed *to you*. This is the Objective-C declaration:

```

- (void)webView:(WKWebView *)webView
    decidePolicyForNavigationAction:(WKNavigationAction *)navigationAction
    decisionHandler:(void (^)(WKNavigationActionPolicy))decisionHandler;

```

You implement this method, and it is called when the user taps a link in a web view, so that you can decide how to respond. The third parameter is a block that takes one parameter — a `WKNavigationActionPolicy`, which is an enum — and returns no value. The block is passed to you as a Swift function, and you respond by *calling* the function to report your decision:

```

func webView(_ webView: WKWebView,
    decidePolicyFor navigationAction: WKNavigationAction,
    decisionHandler: @escaping (WKNavigationActionPolicy) -> Void) {
    // ...
    decisionHandler(.allow)
}

```

A C function is not a block, but you can also use a Swift function where a C function is expected, as I demonstrated earlier. Going in the other direction, to declare a type as a C pointer-to-function, mark the type as `@convention(c)`. Here are two Swift method declarations:

```

func blockTaker(_ f:() -> ()) {}
func functionTaker(_ f:@convention(c)() -> ()) {}

```

Objective-C sees the first as taking a block, and the second as taking a pointer-to-function.



An Objective-C method whose last parameter is called `withCompletionHandler:` and is a block returning `void` is seen by Swift as an `async` method. But it is also seen as a method taking a completion handler function, in case you want to call it that way.

## API Markup

In the early days of Swift, its static strict typing was a poor match for Objective-C's dynamic loose typing, and this made the Swift versions of Objective-C methods ugly and unpleasant:

### *Too many Optionals*

In Objective-C, any object instance reference can be `nil`. But in Swift, only an `Optional` can be `nil`. The default solution was to use implicitly unwrapped `Optionals` as the medium of object interchange between Objective-C and Swift. But this was ugly, and a blunt instrument, especially because most objects arriving from Objective-C were never *in fact* going to be `nil`.

### *Too many umbrella collections*

In Objective-C, a collection type such as `NSArray` can contain elements of multiple object types, and the collection itself is agnostic as to what types of elements it contains. But a Swift collection type can contain elements of just one type, and is itself typed according to that element type. The default solution was for every collection to arrive from Objective-C typed as having `AnyObject` elements; it then had to be cast down explicitly on the Swift side. This was infuriating. You would ask for a view's subviews and get back an `Array` of `AnyObject`, which then had to be cast down to an `Array` of `UIView` — when nothing could be more obvious than that a view's subviews would in fact all be `UIView` objects.

These problems were subsequently solved by modifying the Objective-C language to permit *markup* of declarations in such a way as to communicate to Swift a more specific knowledge of what to expect.

## Nullability

An Objective-C object type can be marked as `nullable` or `nonnull`, to specify, respectively, that it might or will never be `nil`. In the same way, C pointer types can be marked `__nullable` or `__nonnull`. Using these markers generally obviates the need for implicitly unwrapped `Optionals` as a medium of interchange; every type can be either a normal type or a simple `Optional`, and if it's an `Optional`, there's a good reason for it. Implicitly unwrapped `Optionals` are a rare sight in the Cocoa APIs nowadays.

If you're writing an Objective-C header file and you don't mark up any of it as to nullability, you'll return to the bad old days: Swift will see your types as implicitly unwrapped Optionals. Here's an Objective-C method declaration:

```
- (NSString*) badMethod: (NSString*) s;
```

In the absence of markup, Swift sees that as:

```
func badMethod(_ s: String!) -> String!
```

Clearly our Objective-C needs some markup! As soon as your header file contains any markup, the Objective-C compiler will complain until it is *completely* marked up. As a shortcut, you can mark an entire stretch of your header file with a default nonnull setting, so that only the exceptional nullable types will need explicit markup, like this:

```
NS_ASSUME_NONNULL_BEGIN
- (NSString*) badMethod: (NSString*) s;
- (nullable NSString*) goodMethod: (NSString*) s;
NS_ASSUME_NONNULL_END
```

Swift sees that with no implicitly unwrapped Optionals:

```
func badMethod(_ s: String) -> String
func goodMethod(_ s: String) -> String?
```

You can use the Clang analyzer (Product → Analyze) to help audit the correctness of your nullability markup, but in the end it's your responsibility to tell the truth. If you still want a type to appear as an implicitly unwrapped Optional (perhaps because you're just not sure what the truth is), mark it `null_unspecified`.

## Lightweight generics

To mark an Objective-C collection type as containing a certain type of element, the element type can appear in angle brackets (< >) between the name of the collection type and the asterisk. Here's an Objective-C method that returns an array of strings:

```
- (NSArray<NSString*>*) pepBoys;
```

Swift sees the return type of that method as `[String]`, and there will be no need to cast it down.

In the declaration of an actual Objective-C collection type, a placeholder name stands for the type in angle brackets. The declaration for `NSArray` starts like this:

```
@interface NSArray<ObjectType>
- (NSArray<ObjectType> *)arrayByAddingObject:(ObjectType)anObject;
// ...
```

The first line says that we're going to use `ObjectType` as the placeholder name for the element type. The second line says that the `arrayByAddingObject:` method takes an object of the element type and returns an array of the element type. If a particular

array is declared as `NSArray<NSString*>*`, the `ObjectType` placeholder would be resolved to `NSString*`. Apple refers to this sort of markup as a *lightweight generic*, and you can readily see why.

In Swift, classes marked up as lightweight generics are imported into Swift as actual generics even if they are not bridged collection types. Suppose I declare my own Objective-C class, parallel to `NSArray`:

```
@interface Thing<ObjectType> : NSObject
- (void) giveMeAThing:(nonnull ObjectType)anObject;
@end
```

The `Thing` class arrives into Swift declared as a generic:

```
class Thing<ObjectType> : NSObject where ObjectType : AnyObject {
```

`Thing` has to be instantiated by resolving the generic somehow. Often, it will be resolved explicitly:

```
let t = Thing<NSString>()
t.giveMeAThing("howdy") // an Int would be illegal here
```

## Bilingual Targets

It is legal for a target to be a *bilingual target* — one that contains both Swift files and Objective-C files. A bilingual target can be useful for various reasons:

- You might want to take advantage of Objective-C language features.
- You might want to incorporate third-party code written in Objective-C.
- You might want to incorporate your own existing code written in Objective-C.
- Your app itself may have been written in Objective-C originally, and now you want to migrate part of it (or all of it, in stages) into Swift.

The key question is how, within a single target, Swift and Objective-C hear about one another's code in the first place.

Objective-C, unlike Swift, has a visibility problem already: Objective-C files cannot automatically see one another. Instead, each Objective-C file that needs to see another Objective-C file must be instructed explicitly to see that file, usually with an `#import` directive.

In order to prevent unwanted exposure of private information, an Objective-C class declaration is conventionally spread over *two* files: a header file (*.h*) containing the `@interface` section, and a code file (*.m*) containing the `@implementation` section.

Also conventionally, only *.h* files are ever imported with `#import`. If declarations of class members, constants, and so forth are to be public, they are placed in a *.h* file.

Visibility of Swift and Objective-C to one another depends upon those conventions: it works through *.h* files. There are two directions of visibility, and they operate separately through two special Objective-C header files:

#### *How Swift sees Objective-C*

When you add a Swift file to an Objective-C target, or an Objective-C file to a Swift target, Xcode offers to create a *bridging header*. This is a *.h* file *in the project*. Its default name is derived from the target name — such as *MyCoolApp-Bridging-Header.h* — but the name is arbitrary and can be changed, provided you change the target's Objective-C Bridging Header build setting to match. (Similarly, if you decline the bridging header and you decide later that you want one, create a *.h* file manually and point to it in the target's Objective-C Bridging Header build setting.) An Objective-C *.h* file will then be visible to Swift if you `#import` it in this bridging header.

#### *How Objective-C sees Swift*

When you build your target, the appropriate top-level declarations of *all* your Swift files are *automatically* translated into Objective-C and are used to construct a *generated interface header* within the *Intermediates* build folder for this target, deep inside your *DerivedData* folder. For a target called *MyCoolApp*, the generated interface header is called *MyCoolApp-Swift.h*. The name may involve some transformation; a space in the target name is translated into an underscore. You can examine or change the header name with the target's Objective-C Generated Interface Header Name build setting. The generated interface header is how your Swift code is exposed to Objective-C in general (even in a single-language Swift project); your own Objective-C files will be able to see your Swift declarations if you `#import` the generated interface header into each Objective-C file that needs to see them.

To sum up:

- The *bridging header* is visible in your Project navigator; you write an `#import` statement here to make your Objective-C declarations visible to Swift.
- The *generated interface header* is squirreled away in the *DerivedData* folder; you `#import` it to make your Swift declarations visible to your Objective-C code.

Here's an actual example. Let's say that I've added to my Swift target, called *MyCoolApp*, a *Thing* class written in Objective-C. It is distributed over two files, *Thing.h* and *Thing.m*. Then:

- For Swift code to see the *Thing* class, I need to `#import "Thing.h"` in the *bridging* header (*MyCoolApp-Bridging-Header.h*).
- For *Thing* class code to see my Swift declarations, I need to `#import "MyCoolApp-Swift.h"` (the generated bridging header) at the top of *Thing.m*.



That's how Objective-C and Swift are *able* to see one another; but *what* do Objective-C and Swift see when they see one another? Xcode makes it easy to find out, using the code editor's Related Items menu (Control-1). It contains a Generated Interface hierarchical menu:

- In an Objective-C header file (such as *Thing.h*), the Generated Interface menu lists the Swift interface. Choose it to see how these Objective-C declarations are translated into Swift.
- In a Swift file, the Generated Interface menu lists the Objective-C generated interface header. Choose it to see how your target's Swift declarations are translated into Objective-C.

Before Swift existed, all my iOS apps were written in Objective-C. When Swift came along, I translated those apps into Swift. I quickly developed a step-by-step procedure for doing that; here it is:

1. Pick a *.m* file to be translated into Swift. Objective-C cannot subclass a Swift class, so if you have defined both a class and its subclass in Objective-C, start with the subclass. (Leave the app delegate class for last.)
2. Remove that *.m* file from the target. To do so, select the *.m* file and use the File inspector.
3. In every Objective-C file that `#imports` the corresponding *.h* file, remove that `#import` statement and import in its place the generated interface header (if you aren't importing it in this file already).
4. If you were importing the corresponding *.h* file in the bridging header, remove the `#import` statement.
5. Create the *.swift* file for this class. Make sure it is added to the target.
6. In the *.swift* file, declare the class and provide stub declarations for all members that were being made public in the *.h* file. If this class needs to adopt Cocoa protocols, adopt them; you may have to provide stub declarations of required protocol methods as well. If this file needs to refer to any other classes that your target still declares in Objective-C, import their *.h* files in the bridging header.
7. The project should now compile! It doesn't work, of course, because you have not written any real code in the *.swift* file. But who cares about that? Time for a beer!
8. Now fill out the code in the *.swift* file. My technique is to translate more or less line-by-line from the original Objective-C code at first, even though the outcome is not particularly idiomatic or Swiftly.
9. When the code for this *.m* file is completely translated into Swift, build and run and test. If the runtime complains (probably accompanied by crashing) that it can't find this class, find all references to it in the nib editor and reenter the

class's name in the Identity inspector (and press Tab to set the change). Save and try again.

10. On to the next *.m* file! Repeat all of the above steps.
11. When all of the other files have been translated, translate the app delegate class. At this point, if there are no Objective-C files left in the target, you can delete the *main.m* file (replacing it with a `@main` attribute in the app delegate class declaration) and the *.pch* (precompiled header) file.

Your app should now run, and is rewritten in pure Swift (or is, at least, as pure as you intend to make it). Now go back and think about the code, making it more Swifty and idiomatic. You may well find that things that were clumsy or tricky in Objective-C can be made much neater and clearer in Swift.

You can also do a *partial* conversion of an Objective-C class by *extending* it in Swift. That can be useful as a stage along the path to total conversion, or you might quite reasonably write only one or two methods of an Objective-C class in Swift, just because Swift makes it so much easier to say or understand certain kinds of thing. However, Swift cannot see the Objective-C class's members unless they are made public, so methods and properties that you were previously keeping private in the Objective-C class's *.m* file may have to be declared in its *.h* file.

## A

- aborting, 302
- access control (see privacy)
- access, exclusive, 322
- accessibility, 531, 533
- accessors, Objective-C, 609
- Accounts preferences, 498, 538
- actions, 461, 636
  - Combine framework, 684
  - connections, 461
  - handler, 637
  - misconfiguring, 465
  - nil-targeted, 640
  - selector, 638
  - target, 636
- actors, 371
  - (see also concurrency)
- Ad Hoc distribution, 554, 558
- address operator, 37, 709
- Address Sanitizer, 671
- adopt a protocol, 194
- Algorithms package, 238, 243
- allCases, 147
- Allocations instrument, 546
- allSatisfy, 244
- ampersand (see address operator)
- anonymous functions, 44
  - abbreviated syntax, 46
  - capture list, 60, 319
  - define-and-call, 50
  - inline, 45
  - parameter list and return type, 44
  - retain cycles, 318
  - throws, 294
  - trailing closures, 48
- Any, 227
- AnyClass, 232
- AnyHashable, 257
- AnyObject, 229-231
  - object identity, 231
  - suppressing type checking, 230
- API, xvi
  - public, 306
  - tweaking, 122, 133, 733
- app
  - bundle, 418
  - delegate, 432
  - launch process, 429
  - name, 435, 563, 565
    - localizing, 549
  - registering, 542
  - signing, 538
  - target, 411
  - version number, 564
  - without main storyboard, 433
- App Store Connect, 554, 559, 565
- App Store distribution, 555, 565
- append, 99, 240
- Apple ID, 537
- ARC, 653
  - (see also memory management)
- archive
  - app, 555
  - documentation, 472
  - object, 593, 608
- arguments, 27
  - passed on launch, 494
- arithmetic operators, 92

- Array, 232
- arrays, 232-250
  - bridging, 249, 593, 598, 720
  - C arrays, 710
  - casting, 234
  - chunking, 242, 244
  - concatenating, 240
  - declaration, 233
  - enumerating, 244, 285
  - equality, 235
  - flattening, 241, 246
  - indexing, 236
  - initializers, 233
  - literal, 233
  - mutating, 236
  - nested, 237
  - Optional, 234, 247
  - partitioning, 243
  - properties and methods, 238
  - randomizing, 243
  - reversing, 242
  - searching, 239
  - sorting, 242
    - cosorting, 265
    - subsorting, 599
  - subscripting, 236
  - testing all elements, 244
  - testing element type, 235
  - transforming, 245
  - trimming, 245
  - uniquing, 259
- ArraySlice, 236
- arrow operator, 26
- as, 183, 197, 276
- assert, 303
- assertion, 525
- asset catalog, 419, 423, 560
- assignment, 7
  - compound, 94
  - conditional, 281
  - multiple, 109
- assistant, 407
- associated type, 208
  - chains, 215
- associated value, 145, 277, 283, 286
- async let, 362
- async/await, 354
- asynchronous, 347
  - for loops, 365

- sequences, 368
- testing, 526
- AsyncStream, 369
- AttributedString, 586
- Attributes inspector, 405, 444
- attributes, custom, 81
- auditing, 122, 133, 733
- authors, 497
- autoclosure, 303
- automatic signing, 539
- automatic variables, 73
- autorelease, 657
- availability, 474
- available, 491
- awakeFromNib, 467

## B

- background code, 343
- backslash, 96, 327
- backward compatibility, 491
- bag, 602
- balancing delimiters, 499
- base class, 162
- base name, 31
- Behaviors preferences, 399
- beta testing, 559
- bilingual target, 735
- binary numbers, 88
- Binding, 694
- binding, conditional, 271, 283, 304
- Bitbucket, 498
- bitmasks, 261, 705
- bitwise operators, 93, 261
  - (see also option sets)
- blocking, 345
- blocks
  - C, 44, 731
  - flow control, 270
- body of a function, 26
- bookmarking a line of code, 508
- Bool, 85
- BOOL, 590
- Boolean operators, 87
- boxing, 720
- branching, 270-282
  - conditional binding, 271
  - conditional evaluation, 280
  - if, 270
  - if case, 280

- short-circuiting, 289
- switch, 273
- break, 289
- Breakpoint navigator, 403, 518
- breakpoints, 517
  - creating and configuring, 517
  - kinds, 518
  - levels, 519
  - managing, 518
  - pausing at, 520
  - resuming from, 523
- bridged types, 580, 718
  - Any and id, 228, 720
  - AnyObject and id, 229
  - Array and NSArray, 249, 598, 720
  - array elements, 249, 593, 720
  - casting, 186
  - CTypeRefs, 730
  - Dictionary and NSDictionary, 257
  - Error and NSError, 298
  - Foundation, 581, 719
  - number and NSNumber, 590
  - Set and NSSet, 602
  - String and NSString, 101, 584
  - struct and NSValue, 592, 719
- bridging header, 736
- build, 4, 397
  - configurations, 414
  - phases, 411
  - settings, 413
    - Info.plist, 421
- bundle
  - app, 418
  - display name, 435, 549
  - framework, 425
  - identifier, 396
  - test, 527

## C

C, 701-715  
 (see also Objective-C)

- arrays, 710
- blocks, 731
- data types, 702
- enums, 702
- functions, 713
- numeric types, 90
- pointer-to-function, 714, 733
- pointer-to-void, 709
- pointers, 708
- strings, 712
- structs, 592, 707
- Calendar, 587
- call stack, 288, 403, 520
- callAsFunction, 329
- calling a function, 8, 27
- canvas, 439, 442
- Capabilities pane, 541
- capitalization, 8
- capture list, 60, 319
- captured variable references, 51
  - preserving, 58
  - setting, 57
- case
  - enum, 142
  - switch statement, 273
- CaseIterable, 147
- casting, 182-187
  - safely, 184, 276
- categories, 574
- caveman debugging, 512
- certificate, 538
  - cloud-based, 556
  - development, 539
  - distribution, 556
  - exporting, 557
  - obtaining manually, 541
- CTypeRefs, 729
  - memory management, 667
- CGFloat, 92
- chains
  - associated type, 215
  - Optional, 117
- change bars, 498
- Character, 102
- character sequence, 102
- characters vs. codepoints, 102
- characters, escaped, 96
- chunks, 242, 244
- class
  - changing in nib, 444
  - clusters, 604
  - documentation page, 473
  - members, 16
  - methods, 137
    - NSObject, 617
    - vs. static methods, 177
  - properties, 72, 134

- vs. static properties, 178
- protocols, 199
- classes, 156-178
  - (see also object types)
  - class methods, 177
  - class properties, 178
  - deinitializers, 176
  - documentation, 473
  - generic, subclassing, 213
  - hierarchy, 163
  - inheritance, 163
  - initializers, 168
    - inheritance, 171
  - instances, 157
    - multiple references, 160
    - mutating, 39, 158
  - methods, overriding, 165
    - extensions, 221
    - preventing, 167, 308
  - omitting type name, 146
  - polymorphism, 178
  - properties, overriding, 176
  - reference types, 157
  - static methods, 177
  - static properties, 178
  - subclass and superclass, 162
  - subclassing, preventing, 164, 308
  - subscripts, overriding, 167
  - test, 525
  - umbrella type, 227, 232
  - vs. structs, 156
- cleaning, 536
- closures, 51-61
  - (see also anonymous functions)
  - capture list, 60, 319
  - captured variable references, 51
    - preserving, 58
    - setting, 57
  - escaping, 59, 159
  - returned from function, 54
- cloud-based certificate, 556
- Cocoa, 571
  - actions, 636
  - categories, 574
  - data sources, 635
  - delegation, 631
  - events, 619
  - Foundation classes, 580
  - key-value coding, 611
  - key-value observing, 642
  - memory management, 653
  - notifications, 622
  - protocols, 576
  - responder chain, 639
  - subclassing, 571, 620
- Codable, 605
- code
  - actions, 505
  - background, 343
  - bookmarking, 508
  - change bars, 498
  - completion, 501
  - coverage, 530
  - editing, 499
  - folding, 499
  - font, 498
  - indentation, 500
  - location, 8, 619, 649
  - navigating, 506
  - refactoring, 503
  - searching, 509
  - selecting, 500
  - signing (see signing an app)
  - snippets, 503
  - strings, localizing, 549
- Code Review editor, 497
- codepoints, Unicode, 100
  - vs. characters, 102
- coercion, 89
  - numeric, 89, 702
  - Range and NSRange, 582
  - String and Int, 100
- collections
  - Foundation, 602-604
  - memory management, 656, 666
  - Swift, 232-263
- Collections package, 241, 263
- colon
  - adopting protocol, 194
  - argument label, 31
  - enum raw value type, 143
  - generic type constraint, 210
  - key-value, 251
  - label, 289
  - parameter name, 26
  - superclass, 164
  - ternary operator, 281
  - variable type, 74

- column breakpoint, 517
- column breakpoints, 517
- Combine framework, 680-687
  - notifications, 627
  - timers, 630
- comma
  - arguments, 27
  - array literal, 233
  - condition list, 272
  - dictionary literal, 251
  - generic constraints, 218
  - generic placeholders, 209
  - parameters, 26
  - protocol, 194, 196
  - switch case, 279
  - tuples, 108
  - variadics, 34
- comments, 4
  - documentation, 477
  - MARK, 499, 507
- communication, 673
  - bindings, 694
  - Combine framework, 680, 697
  - getting a reference, 676
  - key-value observing, 680
  - notifications, 679
  - SwiftUI, 690
  - visibility
    - by instantiation, 674
    - by relationship, 677
    - global, 677
    - through instance property, 673
- compactMap, 247
- Comparable, 211
  - synthesizing, 326
- compare, 597
- comparison operators, 95
- ComparisonResult, 597
- compatibility, backward, 491
- compilation, 4
  - conditional, 488
- compile error, 4
  - (see also errors, compiler)
- Compile Sources build phase, 412
- compiler, 4
- completion
  - code, 501
  - handler, 341, 347
    - (see also concurrency)
- compliant, key-value coding, 612
- Components preferences, 418
- composition of protocols, 198
- compound assignment operators, 94
- computed
  - properties, 79
  - property wrappers, 81, 332
  - variable initialization, 77
  - variables, 78
- concatenating
  - arrays, 240
  - strings, 99
- concurrency, 343-392
  - actors, 371
    - global, 389
    - isolated, 388
    - isolation, 371
    - main, 373
    - nonisolated, 388
    - reentrancy, 386
    - serialization, 372
  - async contexts, 355
  - async let, 362
  - async/await, 354
  - asynchronous, 347
    - for loops, 365
    - sequences, 368
  - background threads, 345, 371
  - blocking, 345
    - pausing without, 355
  - completion handler, 347
    - Objective-C, 727
    - returning a value, 349
    - throwing an error, 351
    - wrapping in async, 357, 504
  - context switching, 374
  - continuation, 360
  - delayed performance, 651
  - main thread, 344, 373
  - notifications, 627
  - sendable, 390
  - shared data, 346
  - sleeping, 378
  - syntax, 353
  - task groups, 363
  - tasks, 356
    - cancelling, 380
    - creating, 357
  - type-over, 499

- current task, 378
  - detached, 376
  - priority, 377
  - subtasks, 361
  - subtasks, cancelling, 383
  - threads, 344
  - timers, 631
  - yielding, 379
  - condition list, 272
  - conditional
    - assignment, 281
    - binding, 271, 283, 304
    - compilation, 488
    - conformance, 227
    - evaluation, 280
    - initialization, 75
  - conditions, 86, 269
  - configurations, 414
  - conform to a protocol, 194
  - connections, 448
    - action, 461
    - between nibs, 465
    - creating, 452, 457, 462
    - deleting, 457
    - outlet, 449, 612
  - Connections inspector, 405, 455, 457
  - console, 403, 512
    - debugger, 522
  - Console application, 514
  - constants, 7, 73, 156
    - global string, 706
  - constraints, type, 210
    - extensions, 225
    - multiple, 217
  - contains, 103, 107, 239
  - continue, 289
  - control events, 461, 636
  - control flow (see flow control)
  - convenience initializers, 168
  - convention(c), 732
  - coordinator, 688
  - Copy Bundle Resources build phase, 412
  - copying instances, 160
  - cosorting, 265
  - count, 100, 238, 258
  - covariant, 181, 214
  - coverage, code, 530
  - crash
    - could not cast value, 183
    - deallocated object, 662
    - key-value coding compliant, 455, 612
    - not enough bits, 92
    - simultaneous accesses, 322
    - unexpectedly found nil, 116, 456
    - unrecognized selector, 67, 465
    - view outlet was not set, 457
  - creating
    - action connection, 462
    - enum, 142
    - instance, 15, 35, 127
    - outlet, 457
  - curly braces, 4, 26, 44, 78, 82, 96, 125, 127, 140, 176, 197, 220, 270
  - currying, 62
  - custom attributes, 81
  - CustomNSError, 298
  - CustomReflectable, 310
  - CustomStringConvertible, 196
  - cycle through a sequence, 284
- ## D
- dance, weak-strong, 319
  - dangling pointers, 654
  - data
    - sources, 635
    - tips, 521
  - Data, 593
  - Date, 587
  - DateComponents, 587
  - DateFormatter, 588
  - DateInterval, 587
  - dates, 587
    - formatted, 588
    - from string, 589
  - debug bar, 403
  - Debug navigator, 402, 520, 544
  - Debug pane, 403, 520
  - debugger, Xcode, 516
  - debugging, 512-524
    - memory management, 545, 671
  - Decimal, 591
  - decimal point, 89
  - declaration
    - arrays, 233
    - dictionaries, 251
    - enums, 142
    - extensions, 220
    - functions, 25



- generics, 208
- jumping to, 482
- object types, 125
- operators, 311
- protocols, 197
- sets, 259
- variables, 73
- decoding and encoding, 605
- default, 274
  - unknown, 704
- defer, 300
- deferred initialization, 122, 131
- define-and-call, 50
- deinit, 176
  - not called, 314, 663
- delayed performance, 650
- delegate, 631
  - memory management, 661
- delegating initializers, 132
- delegation (see delegate)
- deleting an outlet, 457
- delimiters, balancing, 499
- dependencies, 487
- deployment target, 490
- Deque, 241
- description, 196
- designated initializers, 168, 171
- destinations, 417
- developer member center, 539
- development
  - certificate, 539
  - provisioning profile, 541
- Development Assets build setting, 490
- device
  - registering, 540, 542
  - running on, 537
  - type, 493
- Devices and Simulators window, 543
- dictionaries, 251-258
  - casting, 255
  - creating, 252
  - declaration, 251
  - enumerating, 255
  - equality, 255
  - keys, 256
    - hashable, 251
  - literals, 251
  - merging, 257
  - mutating, 253
  - ordered, 266
  - properties, 255
  - subscripting, 253
  - testing type, 255
  - transformations, 256
  - unordered, 255
  - values, 256
- Dictionary, 251
- didSet, 82
- dispatch
  - dynamic, 182
  - table, 636
- display name, 435, 549
- distributing your app, 554
- distribution
  - Ad Hoc, 558
  - App Store, 565
  - certificate, 556
  - provisioning profile, 557
  - TestFlight, 559
- do, 299
- do...catch, 291
- DocC, 479
- dock, 440
- document
  - outline, 440
  - tabs, 407
- documentation, 471-485
  - archive, 472
  - class, 473
  - comments, 477
  - delegate, 633
  - frameworks and packages, 479
  - immutable vs. mutable classes, 604
  - protocols, 577
  - searching, 472
  - window, 471
- dollar sign, 334, 694
- doom, pyramid of, 272, 304
- dot-notation, 5, 14
  - function references, 66
  - key paths, 613
  - Optionals, 117
  - tuples, 109
- Double, 88
- downcasting (see casting)
- drawing
  - text, 586
  - view, 572

- drop, 245
- dropFirst and dropLast, 104, 241
- dump, 310, 513
- dynamic
  - dispatch, 182
  - members, 330
  - properties, 645

## E

- early exit, 288
- editing
  - code, 498
  - project, 411
  - storyboard, 438
  - target, 411
  - xib file, 441
- editor, 405
  - nib, 438
  - panes, 406
- Empty Window example project, 395, 442, 572
- encoding and decoding, 605
- endIndex, 105, 239
- entitlements, 538, 541
- entry point
  - code, 430, 647
  - storyboard, 441
- enumerate a sequence, 284
- enumerated, 109, 244, 285
- enums, 142-153
  - (see also object types)
  - associated value, 145, 277, 283, 286, 324
  - C enums, 702
  - cases, 142
    - enumerating, 147
  - Comparable, 326
  - declaration, 142
  - equality, 143, 147, 324
  - indirect, 162
  - initializers, 148
  - initializing, 142
  - methods, 150
  - omitting type name, 142
  - properties, 149
  - raw value, 143
  - static properties, 156
  - subscripts, 152
- environment
  - overrides (debug bar), 511
  - variables, 494

- equal sign, 7
- equality
  - Objective-C, 595
  - operators, 95
  - Swift, 323
- Equatable, 147, 227, 239, 251
  - synthesizing, 323
- Error, 290
- ErrorPointer, 726
- errors, 290-298
  - catching, 291
  - Objective-C, 726
  - throwing, 291
- errors, compiler
  - ambiguous, 33
  - cannot assign to an immutable capture, 61
  - cannot find self in scope, 136
  - cannot invoke index, 239
  - cannot use instance member, 135
  - custom, 402
  - escaping closure captures mutating self, 159
  - expected declaration, 8
  - expressions are not allowed, 8
  - heterogeneous collection, 233
  - initializer requirement, 203
  - initializing from a metatype value, 191
  - overlapping accesses, 322
  - protocol can only be used, 212
  - reference to generic type, 213
  - required initializer must be provided, 203
  - return from initializer, 129
  - self used, 131
  - unable to infer return type, 46
  - use of unresolved identifier self, 135
  - value must be unwrapped, 113
- escaped characters, 96
- escaping, 59, 159
- evaluation, conditional, 280
- event-based programming, 647
- events, 461, 619
- exception breakpoint, 518
- exclamation mark, 113, 114, 119, 183, 202
- exclusive access, 322
- exit, early, 288
- explicit
  - specialization, 212
  - variable type, 74
- exporting
  - certificates, 557

- from an archive, 555
- ExpressibleByLiteral, 204
- extend (see extensions)
- extensions, 220, 574
  - (see also categories)
  - declaring, 220
  - generics, 225
    - type constraints, 225
  - object types, 221
  - overrides, 221
  - protocols, 222, 575
  - restrictions on, 220
  - structs, 222
- external parameter names, 30
  - initializers, 127
  - methods, 721
  - subscripts, 139

## F

- factory
  - functions, 56
  - methods, 189
  - Objective-C class method, 726
- failable initializers, 133, 172
- fallthrough, 279, 289
- false, 85
- fatal (see crash)
- fatalError, 302
- File inspector, 405
- file templates, 424
- fileprivate, 306
- File's Owner, 451
- filter, 245, 256
- final, 164, 167
- Find navigator, 401, 509
- finding, 509
  - (see also searching)
- first, 103, 238
- First Responder proxy object, 641
- firstIndex, 103, 239
- Fix-it, 505
- flag, 86
- flatMap, 120, 246
- flavors (of object type), 6
- Float, 91
- flow control, 269-305
  - branching, 270
    - (see also branching)
  - jumping, 288
    - (see also jumping)
  - looping, 282
    - (see also looping)
- folder-linked group, 410
  - renaming, 435
- folders in an Xcode project, 409, 422
- folding, code, 499
- font, 586
- for, 284
- for await, 365
- for case, 286
- for...in, 284
  - asynchronous, 365
- forced unwrap operator, 113
- forEach, 244
- format string, 513
- formatting
  - dates, 588
  - measurements, 595
  - numbers, 592
- Foundation framework, 14, 580
- frameworks, 14, 424
  - creating, 425
  - documenting, 479
  - linking, 424
  - testing, 531
- function in function, 40
- functional events, 620
- functions, 8, 25-69
  - anonymous, 44
    - (see also anonymous functions)
  - async, 355
  - base name, 31
  - body, 26
  - C blocks, 731
  - C functions, 713
  - calling, 8, 27
  - capture list, 60
  - closures, 51
  - curried, 62
  - declaration, 8, 25
  - define-and-call, 50
  - dynamic, 330
  - generic, 209
  - global, 9, 15
    - C, overshadowed, 713
    - class method instead, 221
  - instances as, 329
  - local, 40

- mathematical, 94
- overloading, 32
- parameters, 25
  - default values, 33
  - external names, 30
  - ignored, 35
  - internal names, 27
  - modifiable, 36
  - property wrapper, 335
  - variadic, 34
- recursion, 40
- reference, 63
- result, 25
  - ignoring, 28
- result builders, 341
- rethrows, 297
- return type, 26
- returned from function, 54
- signature, 30
- throws, 293
  - calling, 295
- trailing closures, 48
- type, 41
- values, 41
- where clauses, 226

## G

- garbage collection, 314
- gauges, 403, 543
- generated interface, 405
  - header, 736
- generic pointer, 709
- generics, 205-220
  - associated type chains, 215
  - classes, subclassing, 213
  - declaration, 208
  - extensions, 225
  - functions, 209
  - object types, 209
  - polymorphism, 214
  - protocols, 208
    - adopting conditionally, 227
    - constraining associated type, 218
  - resolution, 206
    - explicit, 212
  - reverse, 339
  - specialization, 206
    - explicit, 212
  - type constraints, 210

- extensions, 225
  - multiple, 217
- type, telling compiler, 211
- where clauses, 217
  - extensions, 225
  - methods, 226
- getter, 78
  - async, 354
  - Objective-C, 609, 611
  - throwing, 294
- Git, 496
- GitHub, 498
- GitLab, 498
- global
  - constants, 156
  - functions, 9, 15
    - C, overshadowed, 713
    - class method instead, 221
  - variables, 9, 71
    - initialization, 84
- globally visible instances, 678
- golden rule of memory management, 655
- groups, 399, 410
  - blue, 423
  - folder-linked, 410
  - renaming, 435
- guard, 303
- guard case, 305
- guard let, 304

## H

- hand-tweaking the APIs, 122, 133, 733
- handlers, 44
  - (see also functions)
- hash, 596
- hash character, 97
- hashability
  - Objective-C, 596
  - Swift, 325
- Hashable, 251, 258
  - synthesizing, 325
- Hasher, 325, 596
- hashValue, 251, 325
- hasPrefix, 99
- hasSuffix, 99
- header files, 483
  - bridging, 736
  - Core Graphics, 574
  - generated interface, 736

- jumping to, 483
  - Objective-C, 735
  - Swift, 15, 483
- heads-up display, 453
- hexadecimal number, 88
- hierarchy
  - class, 163
  - view, 440
- History inspector, 405, 497
- HUD, 453

## I

- IBAction, 462
- IBInspectable, 468
- IBOutlet, 453
- icons, 419, 560
- id, 227, 716
- identifiers and reserved words, 22
- Identity inspector, 405, 444
- identity operator, 231
- identity, developer, 538
- if, 270
- if case, 280
- if let, 271
- immutable Objective-C classes, 603
- implicit initializer, 127, 153, 168
- implicitly unwrapped Optional, 114
- import statement, 9, 425
- in, 44
- index
  - array, 236
  - enumerate with, 109, 244, 285
  - string, 105, 107
- indexed, 244
- IndexSet, 602
- indices, 239, 285
- indirect, 162
- inferred variable type, 74
  - learning, 91
- Info.plist, 420, 563
  - editing, 420
  - settings dependent on device type, 493
- informal protocols, 580
- inheritance, 163
- init, 127
  - with self, 132
  - with super, 171
  - with type reference, 189
- init(coder:), 204
- initialization
  - properties, 129, 134
    - deferred, 122, 131
    - lazy, 135
    - self, 135
  - variables, 6, 73
    - computed, 77
    - conditional, 75
    - lazy, 83
    - Optionals, 115
- initializers, 35, 127
  - class, 168
  - communication through, 675
  - convenience, 168
  - delegating, 132
  - designated, 168
  - enum, 148
  - failable, 133, 172
  - implicit, 127
    - class, 168
    - enum, 142
    - struct, 153
  - inheritance, 170
  - Objective-C, 725
  - overriding, 171
  - property wrapper, 333
  - recursive, 132
  - required, 175, 189, 203
  - struct, 153
  - throwing, 297
- inout, 37
- input, 25
- insert, 106, 240
- Inspector pane, 404
- instance
  - methods, 16, 137
  - properties, 16, 72, 134
  - variables, Objective-C, 609
- instances, 15-20, 676
  - as functions, 329
  - communication between, 673
    - (see also communication)
  - copying, 160
  - creation, 16, 35, 127, 676
  - getting a reference, 676
  - globally visible, 678
  - initial, 431
  - lifetime, 676
  - literals instead, 204

- multiple references, 160
- mutating, 39, 158
- nib-based, 444
  - additional configuration, 466
- relationships between, 677
- state, 19
- type, 179
  - learning, 187
  - telling compiler, 182
  - testing, 184
- instantiation, 15, 35, 127, 676
  - nib-based, 438
  - visibility by, 674
- instruction pointer, 520
- Instruments, 543, 671
- Int, 88
- interface
  - tests, 524
  - thread, 344
- Interface Builder, 438
- internal
  - identity principle, 178
  - parameter names, 27
  - privacy, 305
- internationalization (see localization)
- internet as documentation, 484
- interpolation, string, 98, 196
  - custom, 337
- interval operators, 106
- introspection, 309, 578, 612
- iOS Deployment Target build setting, 490
- is, 184, 197
- isEmpty, 99, 238, 258
- isEqual, 595
- isolated, 388
- Issue navigator, 401
- issues, live, 506
- iteration, 269
- iTunes Connect (see App Store Connect)

## J

- joined, 99, 241
- JSON, 608
- jump bar, 405, 507
  - Debug pane, 520
  - documentation, 473
  - menu, sections, 507
  - nib editor, 442
  - Related Items menu, 405

- jumping, 288-305
  - aborting, 302
  - break, 289
  - continue, 289
  - fallthrough, 289
  - guard, 303
  - label, 289
  - return, 288
  - throw, 290

## K

- Key Bindings preferences, 398
- key paths
  - Cocoa, 613
  - Swift, 326
- keyboard shortcuts in Xcode, 398
- keys (dictionary), 251
- KeyValuePairs, 255
- key-value coding, 611
- key-value observing, 642
  - Published instead, 685
  - retain cycles, 664
- key-value pairs, 251
- KVC, 611
- KVO, 642

## L

- labels
  - flow control, 289
  - function call, 30
    - (see also external parameter names)
  - nib editor, 442
    - changed by outlet, 454
  - tuples, 109
- last, 103, 238
- lastIndex, 103, 239
- launch
  - nib, 561
  - process of an app, 429
- layer, configuring in the nib, 467
- lazy
  - initialization, 83
  - instance properties, 135
  - loading of views, 446
  - sequence, 288
- Leaks instrument, 546
- leaks, memory, 314, 544, 545, 654, 660
- let, 7, 73, 158
- Library, 442

- lifetime, 7, 12
  - (see also scope)
- lifetime events, 620
- lightweight generics, 250, 734
- line, 3
  - breakpoints, 517
- linking, 424
- literals
  - array, 233
  - dictionary, 251
  - expressible by, 204
  - logging, 512
  - numeric, 88
  - string, 96
    - multiline, 97
    - raw, 97
- live issues, 506
- LLDB, 522
- loading a nib, 438, 444
- local variables, 73
- Locale, 587
- localization, 548-553
  - creating, 548
  - editing, 551
  - exporting, 550
  - importing, 552
  - testing, 553
- LocalizedError, 298
- Logger, 514
- logging, 513
- logical operators, 87
- looping, 269, 282-287
  - for, 284
  - short-circuiting, 289
  - while, 282
- lowercased, 99

## M

- main
  - attribute, Swift, 430
  - function, Objective-C, 430
  - storyboard, 421, 432
    - app without, 433
  - Swift file, 9, 430
  - view of view controller, 437, 440
    - loaded from nib, 446
- MainActor, 373
- mangling, name, 718
- map, 120, 245

- mapValues, 256
- MARK comments, 499, 507
- Markdown, 477
- marketing icon, 561
- math functions, 94
- max, 240
- Measurement, 594
- MeasurementFormatter, 594
- measurements, formatted, 595
- member center, 539
- members, 13
- memberwise initializer, 154, 504
- memory graph, 545
- memory leaks, 314, 544, 545, 654, 660
- memory management, 314-322, 653-671
  - anonymous functions, 318
  - ARC, 655
  - autorelease pool, 657
  - capture list, 319
  - CTypeRefs, 667
  - collections, 656, 666
  - dangling pointers, 654
  - debugging, 671
  - delegates, 661
  - golden rule, 655
  - graph, 545
  - key-value observing, 664
  - leaks, 314, 545, 654
  - mutable Objective-C classes, 670
  - nilifying unsafe references, 662
  - notifications, 663
  - ownership, 655
  - properties, 659
    - Objective-C, 668
  - protocol references, 321
  - retain cycles, 314, 660
  - retains, unusual, 666
  - timers, 665
  - Unmanaged, 668
  - unowned references, 317, 661
  - unsafe references, 662
  - UnsafePointer, 711
  - weak references, 316, 661
- merging dictionaries, 257
- messages, 5
  - Optionals, 117
  - self, 19
  - sending optionally, 202, 578
- metatype, 191

- methods, 13, 136
  - (see also functions)
  - async, 355
    - Objective-C, 727
  - class, 137
  - enums, 150
  - external parameter names, 721
  - factory, 189
  - inheritance, 163
  - instance, 16, 137
    - secret life, 138
  - mutating, 151, 155, 158
  - Objective-C, 721
  - omitting type name, 146
  - optional, 201, 577
  - overriding, 165
    - extensions, 221
    - polymorphism, 179
    - preventing, 167, 308
  - selectors, 67
  - static, 137
    - vs. class, 177
  - structs, 155
  - test, 525
  - where clauses, 226
- min, 240
- minimap, 442, 508
- Mirror, 309
- Model–View–Controller, 687
- Model–View–Presenter, 689
- modifiers, 692
- modules, 9, 14, 425
  - privacy, 308
- multiple selection, 500
- multithreading, 344
  - (see also concurrency)
- mutable Objective-C classes, 603
  - NSCopying, 670
- mutating
  - instance, 39, 158
  - methods, 151, 155, 158
- MVC, 687

## N

- name mangling, 718
- namespaces, 13, 141, 156, 221
  - Objective-C, 715
- navigating code, 506
- Navigator pane, 399

- nested
  - arrays, 237
  - scopes, 299
  - types, 14, 126, 141
- NeXTStep, 438
- nib
  - editor, 438
  - files, 421, 437–469
    - dependent on device type, 494
    - launch, 561
    - loading, 444
    - localizing, 549
  - objects, 440
  - owner, 451
- nib-based instantiation, 438
  - additional configuration, 466
- nib-loading mechanism, 444
- nil, 115
  - Objective-C collections, 603
  - signaling failure, 121
  - signaling no data, 122, 131
  - unwrapping, 116
- nil-coalescing operator, 281
- nil-targeted actions, 640
- nilifying unsafe references, 662
- nonisolated, 388
- nonnull, 733
- nonobjc, 718
- Notification, 621
- Notification.Name, 622
  - forming from string, 628
- NotificationCenter, 621
- notifications, 622
  - Combine framework, 627, 683
  - posting, 628
  - registering, 623
  - retain cycles, 663
  - structured concurrency, 627
  - unregistering, 625, 663
- NSArray, 249, 598
- NSAttributedString, 586
- NSCoder, 608
- NSCoding, 204
- NSCopying, 576, 670
- NSCountedSet, 602
- NSDecimalNumber, 591
- NSDictionary, 257, 600
- NSError, 291
- NSErrorPointer, 726



- NSHashTable, 666
- NSKeyedArchiver, 593, 608
- NSLog, 513
- NSMapTable, 666
- NSMutableArray, 249, 598
- NSMutableDictionary, 258, 600
- NSMutableOrderedSet, 601
- NSMutableSet, 601
- NSMutableString, 584
- NSNotFound, 583
- NSNull, 603
- NSNumber, 590
- NSObject, 163, 616-618
  - comparison, 597
  - equality, 595
  - hashability, 596
- NSObjectProtocol, 616
- NSOrderedSet, 601
- NSPointerArray, 666
- NSRange, 581
- NSRegularExpression, 585
- NSSet, 601
- NSString, 101, 584
- NSValue, 592
- NS\_ENUM, 703
- NS\_OPTIONS, 705
- NS\_SWIFT\_NAME, 722
- nullable, 733
- numbers, formatted, 592
- numeric
  - literals, 88
  - types
    - C, 90, 702
    - Swift, 88
- Numerics package, 95

## O

- objc, 68, 201, 230, 308, 321, 611, 703, 717
- ObjcBool, 702
- objcMembers, 718
- object types, 125-178
  - comparison, 192
  - declaration, 125
  - definition over multiple files, 222
  - extensions, 221
  - flavors, 6
  - generic, 209
    - extensions, 225
  - initializers, 127

- methods, 136
- nested, 141
- Objective-C, 716
  - passing or assigning, 191
  - polymorphism, 188
  - printing, 187
  - properties, 134
  - reference vs. value, 157
  - references to, 187
    - Objective-C, 715
  - scope, 125
  - subscripts, 139
  - umbrella types, 227
- Objective-C, 701-735
  - (see also bridged types)
  - accessors, 80, 609
  - categories, 574
  - class factory methods, 726
  - collections, 602-604, 734
  - comparison, 597
  - equality, 595
  - hashability, 596
  - header files, 735
  - id, 227, 716
  - immutable vs. mutable classes, 603
  - initializers, 725
  - instance variables, 609
  - lightweight generics, 250, 734
  - methods, 721
    - async, 727
    - internal parameter names, 723
    - overloading, 724
    - renamification, 721
    - variadic parameters, 724
  - namespaces, 715
  - object references, 715
  - object types, 716
  - Optionals, 121
  - properties, 609
  - protocols, 576
  - selectors, 728
  - subscripts, 598-602
  - Swift
    - class member exposure, 717
    - invisible features, 716
    - target, bilingual, 735
    - translating app into, 737
- objects, 4
  - (see also object types)

- communication between, 673
  - (see also communication)
  - graphing, 544
  - same, 231
- Objects library, 442
- ObservableObject, 697
- observers, setter, 82
- octal numbers, 88
- opaque types, 339
- open, 306
- operator syntax, 5, 311
- operators, 310-313
  - arithmetic, 92
    - custom, 312
  - bitwise, 93, 261
    - (see also option sets)
  - Boolean, 87
  - Combine framework, 683
  - comparison, 95
  - compound assignment, 94
  - creating, 312
  - declaration, 311
  - equality, 95
    - custom, 323
  - identity, 231
  - interval, 106
  - nil-coalescing, 281
  - overriding, 312
  - precedence, 94, 311
  - ternary, 281
  - unwrap, 113, 117
- Optimization Level build setting, 415
- optimizing, 543
- option sets, 261, 706
  - empty, 263
- optional
  - message sending, 202, 578
  - methods, 201, 577
  - properties, 201
  - unwrap operator, 117
- Optional chains, 117
- Optionals, 111-123
  - array of, 234, 247
  - casting, 185
  - chain, 117
  - comparison, 120
  - creating, 111
  - declaration, 112
  - deferred initialization, 122, 131
  - double-wrapped, 201, 238
  - empty, 115
  - enum, 145, 205
  - equality, 120
  - flatMap, 120
  - implicitly unwrapped, 114, 733
  - initialization, 115
  - map, 120
  - messages to, 117
  - nil, 115
  - Objective-C, 121
  - properties, 131
  - type, 111
    - testing, 185
  - unwrapping, 113, 116, 271, 275, 281, 283, 304
    - wrapping, 112
- OptionSet, 261, 706
- OrderedDictionary, 266
- OrderedSet, 263
- organization identifier, 396
- Organizer window, 555
- orientation of interface, 564
- OSLog, 514
- outlet collections, 460
- outlets, 449
  - creating, 457
  - deleting, 457
  - key-value coding, 612
  - misconfiguring, 455
- output, 25
- overflow, 94
- overlay, Swift, 581, 719
- overloading, 32
  - Objective-C, 724
- overriding, 165
  - extensions, 221
  - initializers, 171
  - polymorphism, 179
  - preventing, 167, 308
- overscroll, 499
- owner
  - memory management, 655
  - nib, 451

## P

- packages, 425
  - adding, 425
  - collections, 426

- creating, 427
  - documenting, 479
  - manifest, 428
  - resources, 428
  - sharing, 429
- pane, editor, 406
  - assistant, 407
- parameter list, 26
  - anonymous function, 44
  - omitting, 48
- parameters, 25
  - default values, 33
  - external names, 30
    - initializers, 127
    - methods, 721
    - subscripts, 139
  - functions as, 41
  - ignoring, 35
  - internal names, 27
  - modifiable, 36
  - property wrappers, 335
  - variadic, 34
- parentheses
  - calling a function, 27
  - coercion, 89
  - declaring a function, 26
  - instantiating an object type, 15, 35, 127
  - order of operations, 88, 94
  - signifying Void, 29, 111
  - tuples, 108
- partial range, 108, 237, 238, 252, 275
- patterns, switch statement, 274
- persistence (see lifetime)
- persisting references, 315
- pipeline
  - Combine framework, 680
  - SwiftUI binding, 697
- placeholders
  - code, 502
  - generic, 205
    - (see also generics)
  - nib editor (see proxy objects)
- pointee, 38, 709
- pointer-to-void, 709
- pointers, 37, 160, 716, 731
  - C, 708
  - dangling, 654
  - generic, 709
  - raw, 709
- polymorphism, 178
  - generics, 214
  - protocol extensions, 223
  - Self, 188
- pool, autorelease, 657
- popFirst and popLast, 241
- Portal, 539
- posting a notification, 622
- precedence, 311
- precondition, 303
- prefix, 104, 238, 245
- presenter, 689
- previews, video, 563
- print, 3, 34, 196, 512
  - (see also logging)
- privacy, 20, 305-309
- private, 306
- product name, 396
- production certificate, 556
- profile (see provisioning profile)
- profiling, 543
- project, 395
  - file, 409
  - folder, 408, 435
  - renaming, 435
  - templates, 395, 492
    - backward compatible, 492
  - window, 398
- Project navigator, 399, 506
- projected value, 334
- properties, 13, 71, 134
  - (see also variables)
  - accessors, 610
  - binding, 694
  - class, 72, 134
  - communication through, 673
  - computed, 79
    - (see also variables, computed)
  - property wrappers, 81, 332
  - self, 135
  - dynamic, 330, 645
  - enums, 149
  - initialization, 129, 135
    - classes, 168
    - computed, 78
    - deferred, 122, 131
    - lazy, 85
  - inspectable, 468
  - instance, 16, 72, 134

- memory management, 659
- Objective-C, 609
  - memory management, 668
- omitting type name, 146
- Optional, 131
- optional, 201
- overriding, 176
- private, 22
- releasing, 660
- state, 692
- static, 72, 134
  - enum, 156
  - initialization, 84
  - struct, 156
  - vs. class, 178
- structs, 154
- property list, 604
  - target (see Info.plist)
- property wrappers, 81, 332
  - initializing, 333
  - projected value, 334
  - Published, 685
  - State, 693
  - wrapped value, 332
- protocols, 193-205, 576
  - adopter, 208
  - adopting, 194
  - associated type, 208
    - chaining, 215
    - constraining, 218
  - casting, 197
  - class, 199
  - composition, 198
  - conditional conformance, 227
  - conforming to, 194
  - declaration, 197
  - delegate, 633
  - documentation, 577
  - extensions, 222, 575
    - constraining associated type, 225
    - invisible to Objective-C, 633
  - generic, 208
    - constraining associated type, 218
  - implicitly required initializers, 203
  - informal, 580
  - memory management, 321
  - Objective-C, 576
  - optional members, 201, 578
  - synthesizing, 323
  - testing type, 197
  - provisioning profile, 538
    - development, 541
    - distribution, 557
    - universal, 541
  - proxy objects, 441, 451
  - public, 306
  - Published, 685
  - Publisher, 681
  - pull requests, 498
  - pyramid of doom, 272, 304

## Q

  - query events, 620
  - question mark, 112, 119, 184, 202, 275, 281
  - Quick Help, 405, 476
  - Quick Look a variable, 521
  - quotes, 96

## R

  - random, 95
  - randomElement, 243
  - randomSample, 243
  - Range, 106
  - ranges, 106
    - coercion to NSRange, 582
    - indexing with, 107, 236
    - iterating in reverse, 313
    - partial, 108, 237, 238, 252, 275
    - string, 101, 582
  - raw pointer, 709
  - raw value, 143
  - RawRepresentable, 144
  - read-only variables, 79
  - Real, 95
  - recursion, 40
  - recursive
    - initializers, 132
    - references, 162
  - reduce, 248
  - refactoring, 503
  - reference types, 157
    - memory management, 314
  - references, 6, 71
    - functions, 63
    - getting, 676
    - object types, 187
      - Objective-C, 715
    - persisting, 315

- recursive, 162
- same object, 160, 231
- strong, 315
- unowned, 317, 661
- unsafe, 662
- weak, 316, 661
- registering
  - app, 542
  - device, 540, 542
  - for a notification, 623
  - for key–value observing, 643
- regular expressions, 585
- Related Items menu, 405
- release, 655
- releasing a property, 660
- remove, 106, 241
- removeFirst and removeLast, 241
- removeSubrange, 108
- removeValue, 254
- renamification, 721
- renaming a project, 434
- replaceSubrange, 107
- replacing, 509
- Report navigator, 403, 529
- required initializers, 175, 189, 203
- reserved words, 22
- resolution, screen, 493
- resolving a generic, 206, 212
- resources, 421
  - app bundle, 422
  - asset catalog, 423
  - dependent on build type, 490
  - dependent on device type, 493
  - Swift package, 428
- responder chain, 639
- responds, 578
- Result, 341, 352
- result builders, 341
- result of a function, 25
  - ignoring, 28
- retain, 655
  - count, 654
  - cycles, 314, 660
    - anonymous functions, 318
    - key–value observing, 664
    - notifications, 663
    - timers, 665
  - unusual, 666
- rethrows, 297
- return, 26
  - function from function, 54
  - omitting, 27, 49
  - type
    - anonymous function, 44
    - function, 26
- reverse generics, 339
- reversed, 107, 242
- root
  - class, 162
  - view controller, 432
- router, 688
- run, 4, 397
  - device, 537
  - Simulator, 510
- runtime issue breakpoint, 519

## S

- sample code, Apple, 484
- scalars, 6, 590, 702
- Scanner, 585
- scene
  - delegate, 432
  - dock, 440
  - storyboard, 440
  - window, 431, 492
- Scheme pop-up menu, 417
- schemes, 416
  - renaming, 435
- scientific notation, 89
- scope, 12
  - exiting early, 288
  - nested, 299
  - object types, 125
  - variable, 71
- screen resolution, 493
- screencasts, 563
- screenshots, 532, 562
- SDKs, 418, 424
  - older, 492
- searching
  - arrays, 239
  - code, 509
  - documentation, 472
  - symbols, 482
- selection, multiple, 500
- Selector, 727
- selectors, 67, 727
- self, 19

- capture list, 61
- escaping closures, 60, 320
- escaping functions, 159
- initializers, 131, 170
- instance methods, 20, 126
- polymorphism, 180
- property initialization, 135
- static/class methods, 126
- type name with, 191
- type of, 187
- Self, 187, 208, 217, 224
- semicolon, 3
- Sendable, 390
- sequence
  - array initializer, 233
  - asynchronous, 368
  - character, 102
  - cycling through, 284
  - enumerating with index, 109, 285
  - function, 287
  - generating, 284
  - lazy, 288
  - range indexing, 107
  - striding, 286
  - transforming, 286
- Sequence, 284
- serialization, 604
- Set, 258
- sets, 258-263, 601
  - declaration, 259
  - equality, 260
  - hashable elements, 258
    - NSObject, 596
  - initializers, 259
  - literals, 259
  - mutating, 260
  - operations, 260
  - option sets, 261, 706
  - ordered, 263, 601
  - sampling, 259
  - transformations, 259
  - unordered, 259
- setter, 78
  - Objective-C, 609, 611
  - observers, 82
- shared application instance, 432
- short-circuiting, 289
- shuffle, 243
- side effects, 28
- signature of a function, 30
- signing an app, 538
  - automatic, 539
  - manual, 541
- Simulator, 510
- singleton, 84
- Size inspector, 405, 444
- slice, 236
- snippets
  - creating, 503
  - Snippets library, 503
- some, 339
- sort, 242
- SortDescriptor, 599
- sorted, 242
- Source Control navigator, 400, 496
- Source Control preferences and menu, 495
- specializing a generic, 206, 212
- splatting, 35
- split, 104, 242
- square brackets, 139, 233, 251
- stack, call, 288, 403, 520
- startIndex, 105, 239
- starts, 240
- State, 334, 693
- state of an instance, 19
- statement, 3
- static
  - members, 16
  - methods, 137
    - vs. class methods, 177
  - properties, 72, 134
    - enum, 156
    - initialization, 84
    - struct, 156
    - vs. class properties, 178
- stepping, 523
- stored variables, 78
- storyboard files, 421
  - (see also main storyboard)
  - compiled, 419
  - dependent on device type, 494
  - editing, 438
  - entry point, 441
  - launch, 561
- stride, 286
- String, 96
- String.Index, 105
- stringly typed, 706

- strings, 96-108
  - attributed, 586
  - C strings, 712
  - characters, 102
  - coercion, 100
  - comparison, 99
  - concatenating, 99
  - constants, global, 706
  - drawing, 586
  - equality, 99
  - format, 513
  - indexing, 105, 107
  - initializers, 100
  - interpolation, 98, 196
    - custom, 337
  - length, 100, 102
  - literals, 96
    - multiline, 97
    - raw, 97
  - modifying, 107
  - notification names, 628
  - range, 101, 582
  - searching, 101
  - substrings, 101-108, 585
  - trimming, 245
  - Unicode, 100
- strong references, 315
- structs, 153-156
  - (see also object types)
  - bridged to Objective-C classes, 592, 718
  - C structs, 592, 707
  - initializers, 153
    - extensions, 222
  - methods, 155
  - omitting type name, 146
  - properties, 154
  - static properties, 156
  - subscripts, 155
  - vs. classes, 156
- structured concurrency (see concurrency)
- styled text, 586
- subclass, 162
- subclassing
  - Cocoa, 571, 620
  - preventing, 164, 308
  - UILabel, 573
  - UIView, 572, 620
  - UIViewController, 572, 621
- Subscriber, 681
- subscripting, 105, 107, 236, 253
  - Objective-C, 598-602
- subscripts, 139
  - classes, 167
  - enums, 152
  - overriding, 167
  - structs, 155
- subsorting, 242
- substitution principle, 178
- Substring, 104
- subview, 440
- suffix, 104, 238
- super, 167
  - initializers, 171
- superclass, 162
- superview, 440
- supported interface orientations, 564
- swapAt, 243
- swapping variables, 109
- Swift, 3-322
  - header, 15
  - history, xv
  - Objective-C bilingual target, 735
  - overlay (Foundation), 581, 719
- Swift Algorithms package, 238, 243
- Swift Collections package, 241, 263
- Swift Numerics package, 95
- SwiftUI, xvii, 334, 340, 438, 690-699
  - bindings, 694
  - Combine framework, 697
  - modifiers, 692
  - result builders, 691
  - state properties, 692
  - visibility by instantiation, 691
- switch, 273, 704
- swizzling, 645
- Symbol navigator, 400, 506
- symbolic breakpoint, 519
- symbols, searching for, 482
- syntax checking, 505
- synthesizing protocols, 323
- system version, 491

## T

- tabs, 407
- target, 411
  - bilingual, 735
  - deployment, 490
  - framework, 425

- test, 525
- Targeted Device Families build setting, 490
- target-action, 636
- Task, 356
- team, 537
- templates
  - file, 424
  - project, 395
    - backward compatible, 492
- ternary operator, 281
- Test Failure breakpoint, 530
- Test navigator, 402, 528
- testable, 527
- TestFlight, 559
- tests, 524-536
  - asynchronous, 526
  - bundle, 527
  - classes, 525
  - failure, expected, 526
  - interface, 531
  - methods, 525
  - performance, 530
  - repeated, 526
  - report, 535
  - screenshots, 532
  - skipping, 525
  - target, 525
  - test plans, 533
  - unit, 527
- thinning an app, 558
- threads, 344
  - (see also concurrency)
- throw, 291
- throws, 293
- Time Profiler instrument, 547
- timers, 629
  - Combine framework, 630
  - retain cycles, 665
  - structured concurrency, 631
- times, 587
- top level, 9, 15
  - (see also global)
- top-level objects (nib), 440
- trailing closures, 48
- trimming, 245
- true, 85
- try, 295
- tuples, 108
- tweaking the APIs, 122, 133, 733

- type
  - checking, suppressing, 230
  - constraints, 210
    - multiple, 217
  - eraser, 257
  - function, 41
  - instance vs. variable, 179
  - name, omitting, 142
  - of instance, testing, 184
  - opaque, 339
  - Optional, 111
  - placeholders, 205
    - (see also generics)
  - references, 187
  - variable, 7, 74
- Type, 191
- type alias, 44, 110
- type(of:), 187
- type-over completions, 499
- typecasting (see casting)
- types, 125
  - (see also object types)

## U

- UDID, 538
- UI tests, 524
- UIAction, 638
- UIApplication, 432
- UIApplicationMain, 431
- UIBackgroundTaskIdentifier, 76
- UIControl, 461, 636
- UILabel, 573
- UIPickerView, 635
- UIResponder, 639
- UISceneSession, 432, 492
- UIView, 572, 620
  - (see also views)
- UIViewController, 572, 621
  - (see also view controller)
- UIWindowScene, 432
- umbrella types, 227
- underflow, 94
- underscore
  - argument label, 31
  - assignment to, 28, 109
  - mop-up switch case, 274
  - parameter name, 35, 64
    - anonymous function, 47
  - property wrapper instance, 334



- Unicode, 96
- UnicodeScalar, 101
- unique an array, 259
- Unit, 594
- unit tests, 524
- universal app, 490
- universal provisioning profile, 541
- unknown default, 704
- Unmanaged, 668
- unowned references, 317, 661
- unregistering
  - for a notification, 625, 663
  - for key-value observing, 644, 664
- unsafe references, 662
- UnsafeContinuation, 360
- UnsafeMutablePointer, 37, 708
- UnsafeMutableRawPointer, 709
- UnsafePointer, 708
  - memory management, 711
- UnsafeRawPointer, 709
  - casting to CTypeRef, 731
- unwrapping an Optional, 113
- updateValue, 254
- uppercased, 99
- URL, 586
- User Defined Runtime Attributes, 467
- user events, 620
- UserDefaults, 156, 678
  - nonproperty-list types in, 608
- UTF-8, UTF-16, UTF-32, 100

## V

- value types, 157
  - memory management, 321
- values (dictionary), 251
- var, 7, 73, 158
- variables, 6, 71-85
  - coercion, 90
  - computed, 78
  - declaration, 6, 73
    - initialization, 77
    - initialization, computed, 77
  - façade, 80
  - functions as value of, 41
  - global, 9, 71
    - initialization, 84
  - initialization, 6
    - Optional, 115
  - lazy, 83

- lifetime, 7, 71
- local, 73
- read-only, 79
- scope, 71
- setter observers, 82
- stored, 78
- swapping, 109
- type, 7, 74
  - vs. instance type, 179
- variables list, 403, 521
- variadic parameters, 34
  - Objective-C, 724
- version control, 495
- version string, 564
- video previews, 563
- view controller, 437, 440, 446
  - initial, 432, 441, 445
- view debugging, 522
- views, 437
  - drawing, 572
- visibility, 12
  - (see also scope)
  - by instantiation, 674
  - by relationship, 677
  - through instance property, 673
- Void, 29, 111
- void, 709

## W

- warnings, compiler, 4
  - additional unknown values, 277, 704
  - code will never be executed, 27
  - custom, 402
  - result of call is unused, 28
  - switch must be exhaustive, 704
  - trailing closure is confusable, 288
- weak references, 316, 661
- weak-strong dance, 319
- where, 217, 225, 276, 285
- while, 282
- while case, 283
- while let, 283
- wildcard provisioning profile, 541
- willSet, 82
- window tabs, 407
- withUnsafePointer, 709
- wrapped value, 332
- wrappers, property, 81, 332

## X

XC wildcard provisioning profile, 541

xcloc bundle, 550

Xcode, 395-567

(see also nib editor)

xib files, 421

editing, 441

xliff files, 548

## Z

zip, 252

zombies, 671

## About the Author

---

**Matt Neuburg** started programming computers in 1968, when he was 14 years old, as a member of a literally underground high school club, which met once a week to do timesharing on a bank of PDP-10s by way of primitive teletype machines. He also occasionally used Princeton University's IBM-360/67, but gave it up in frustration when one day he dropped his punch cards. He majored in Greek at Swarthmore College, and received his PhD from Cornell University in 1981, writing his doctoral dissertation (about Aeschylus) on a mainframe. He proceeded to teach Classical languages, literature, and culture at many well-known institutions of higher learning, most of which now disavow knowledge of his existence, and to publish numerous scholarly articles unlikely to interest anyone. Meanwhile he obtained an Apple IIc and became hopelessly hooked on computers again, migrating to a Macintosh in 1990. He wrote some educational and utility freeware, became an early regular contributor to the online journal *TidBITS*, and in 1995 left academe to edit *MacTech* magazine. In August 1996 he became a freelancer, which means he has been looking for work ever since. He is the author of *Frontier: The Definitive Guide*, *REALbasic: The Definitive Guide*, and *AppleScript: The Definitive Guide*, as well as *Programming iOS 14* (all for O'Reilly Media).

## Colophon

---

The animal on the cover of *iOS 15 Programming Fundamentals with Swift* is a harp seal (*Pagophilus groenlandicus*), a scientific name that translates to “ice-lover from Greenland.” These animals are native to the northern Atlantic and Arctic Oceans, and spend most of their time in the water, only going onto ice packs to give birth and molt. As earless (“true”) seals, their streamlined bodies and energy-efficient swimming style make them well-equipped for aquatic life. While eared seal species like sea lions are powerful swimmers, they are considered semiaquatic because they mate and rest on land.

The harp seal has silvery-gray fur, with a large black marking on its back that resembles a harp or wishbone. They grow to be 5–6 feet long, and weigh 300–400 pounds as adults. Due to their cold habitat, they have a thick coat of blubber for insulation. A harp seal's diet is very varied, including several species of fish and crustaceans. They can remain underwater for an average of 16 minutes to hunt for food and are able to dive several hundred feet.

Harp seal pups are born without any protective fat, but are kept warm by their white coat, which absorbs heat from the sun. After nursing for 12 days, the seal pups are abandoned, having tripled their weight due to their mother's high-fat milk. In the subsequent weeks until they are able to swim off the ice, the pups are very vulnerable

to predators and will lose nearly half of their weight. Those that survive reach maturity after 4–8 years (depending on their sex) and have an average lifespan of 35 years.

Harp seals are hunted commercially off the coasts of Canada, Norway, Russia, and Greenland for their meat, oil, and fur. Though some of these governments have regulations and enforce hunting quotas, it is believed that the number of animals killed every year is underreported. Public outcry and efforts by conservationists have resulted in a decline in market demand for seal pelts and other products, however.

Many of the animals on O'Reilly covers are endangered; all of them are important to the world.

The cover illustration is by Karen Montgomery, based on a black and white engraving from Wood's *Animate Creation*. The cover fonts are Gilroy Semibold and Guardian Sans. The text font is Adobe Minion Pro; the heading font is Adobe Myriad Condensed; and the code font is Dalton Maag's Ubuntu Mono.

The O'Reilly logo is displayed in white, bold, sans-serif capital letters. The background of the entire advertisement is a vibrant red-to-orange gradient, overlaid with several large, semi-transparent, overlapping circles in varying shades of red and orange, creating a dynamic, abstract pattern.

O'REILLY®

## There's much more where this came from.

Experience books, videos, live online training courses, and more from O'Reilly and our 200+ partners—all in one place.

Learn more at [oreilly.com/online-learning](http://oreilly.com/online-learning)